

SITE DATA SUMMARY TABLE LOTS 1 & 2

ZONING:	MTC McKinNEY TOWN CENTER DISTRICT
EXISTING USE:	PARKING LOT/GARAGE
PROPOSED USE:	RETAIL / OFFICE
LOT AREA:	LOT 1 11,840 SF / 0.272 AC LOT 2 11,540 SF / 0.265 AC
BUILDING HEIGHT:	3 STORIES
NUMBER OF BLDGS.	2
TOTAL BLDG. SQ. FOOTAGE:	36,000 SQ. FT. MAX.
PARKING REQUIRED	NO PARKING REQUIRED FOR NON-RESIDENTIAL USES FOR McKinNEY TOWN CENTER DEVELOPMENT CODE
PARKING PROVIDED	VIA NEW PARKING GARAGE (HANDICAP PARKING) (7)
LOT COVERAGE/BLDG FOOTPRINT FLOOR TO AREA RATIO	51% (12,000 SQ. FT.) 1.54:1
LANDSCAPE DATA	INTERIOR LANDSCAPING 7,485 SQ. FT. IMPERVIOUS AREA: 16,895 SQ. FT.

SITE DATA SUMMARY TABLE LOT 3



ZONING:	MTC McKinNEY TOWN CENTER DISTRICT
EXISTING USE:	PARKING LOT
PROPOSED USE:	PARKING GARAGE
LOT AREA:	27,711 SF / 0.638 AC
BUILDING HEIGHT:	50' 6"
NUMBER OF BLDGS.	1
TOTAL BLDG. SQ. FOOTAGE:	129,025 SQ. FT. MAX.
PARKING REQUIRED	NO PARKING REQUIRED FOR NON-RESIDENTIAL USES FOR McKinNEY TOWN CENTER DEVELOPMENT CODE
PARKING PROVIDED	TOTAL PARKING PROVIDED (HANDICAP PARKING) 310 (7)
LOT COVERAGE/BLDG FOOTPRINT FLOOR TO AREA RATIO	93% (25,805 SQ. FT.) 4.66:1
LANDSCAPE DATA	INTERIOR LANDSCAPING 1,512 SQ. FT. IMPERVIOUS AREA: 26,199 SQ. FT.

NOTES

- ALL DIMENSIONS ARE TO BACK OF CURB UNLESS NOTED OTHERWISE.
- NORTH BUILD TO LINE SHALL BE THE HERNDON ROW AND THE SOUTH BUILD TO LINE SHALL BE THE FUTURE LOT LINE


CITY OF McKinNEY SITE PLAN NOTES

- THE SANITATION CONTAINER SCREENING WALLS WILL BE BRICK MASONRY, STONE MASONRY, OR OTHER ARCHITECTURAL MASONRY FINISH, INCLUDING A METAL GATE, PRIMED AND PAINTED, AND THE SANITATION CONTAINER SCREENING WALLS, GATE AND PAD SITE WILL BE CONSTRUCTED IN ACCORDANCE WITH THE CITY OF McKinNEY DESIGN SPECIFICATIONS.
- MECHANICAL AND HEATING AND AIR CONDITIONING EQUIPMENT IN NON-RESIDENTIAL USES SHALL BE SCREENED FROM VIEW FROM THE PUBLIC RIGHT-OF-WAY AND FROM ADJACENT RESIDENTIAL PROPERTIES.
- THE LIGHTING FOR THE SUBJECT PROPERTY WILL BE CONSTRUCTED IN CONFORMANCE WITH CHAPTER 58 OF THE CITY OF McKinNEY CODE OF ORDINANCES.



LEGEND

- 5" 3,000 PSI CONCRETE PAVEMENT WITH 6" LIME TREATED SUB-BASE AND #3 BARS @ 24" O.C.E.W.
- 4" REINFORCED 4,000 PSI CONCRETE PAVEMENT
- R RADIUS
- BFR BARRIER FREE RAMP
- SW SIDE WALK
- BUILDING ENTRANCE
- LSCP. LANDSCAPE AREA



SITE PLAN FOR CHESTNUT COMMONS PARKING GARAGE MCKINNEY, TX

BEING 1.19 ACRES OUT OF THE WILLIAM DAVIS SURVEY ABSTRACT NO. A-248 CITY OF MCKINNEY, COLLIN COUNTY TEXAS DATE 8/3/2017

RECEIVED
By Planning Department at 8:03 am, Aug 10, 2017

CHESTNUT COMMONS PARKING GARAGE

SITE PLAN

Scale: SEE GRAPHIC SCALE

Designed by:	CDR
Drawn by:	CDR
Checked by:	CHB
Date:	8/3/2017
Project No.:	020007-011

OWNER: VIRGINIA@S LLC 11520 N. CENTRAL EXPY, STE 138 DALLAS, TX 75243-6607 (469) 424-5900 EMAIL: Kim.Sanchez@tsag.biz (Authorized Representative)	OWNER: SP2 301 E VIRGINIA LLC 2000 N. McDonald Street, Suite 100 McKinney TX 75071 (469) 424-5900 EMAIL: Kim.Sanchez@tsag.biz	APPLICANT: SANCHEZ AND ASSOCIATES, LLC. 2000 N. McDonald Street, Suite 100 McKinney TX 75071 PH: (469) 424-5900 EMAIL: chris.blevins@thesanchezgroup.biz	ENGINEER: SANCHEZ AND ASSOCIATES, LLC. 2000 N. McDonald Street, Suite 100 McKinney TX 75071 PH: (469) 424-5900 EMAIL: chris.blevins@thesanchezgroup.biz
--	---	--	---

Master Planning Civil Engineering Land Development
SANCHEZ & ASSOCIATES
 2000 N. McDonald Street, Suite 100
 McKinney, TX 75071
 Tel 469 424 5900
 Fax 214 544 5200
 Certificate of Registration No. F-5866

Project: C:\Users\jls\OneDrive\Documents\Projects\0118_Parking_Garage\Map_Auto\Kxaraga-FP_Hatch_XEmit
 Wed 09 Aug 2017 11:11am
 Printed by: scrommond
 Images: S & A Logo.Bg