LAND USE ASSUMPTIONS 2018-2019



Unique by nature.

CONTENTS



01

/ Purpose and Overview

05

/ Ultimate Projections

02

/ Study Process

06

/10-Year Growth Assumptions

03

/ Service Area Maps

07

/ Appendix

04

/ Baseline Data

PURPOSE AND OVERVIEW

To accurately determine the costs associated with providing infrastructure services to new and existing development, a study must be conducted to determine the type, amount, and location of existing development and expected growth. This study is called the Land Use Assumptions (LUA), and is the first step in the impact fee update process. Impact fees are levied against new development to pay for the off-site construction or expansion of infrastructure that is necessitated by the additional impact caused by the new development.

As defined by Chapter 395 of the Texas Local Government Code, impact fees are "a charge or assessment imposed by a political subdivision against new development in order to generate revenue for funding or recouping the costs of capital improvements or facility expansions necessitated by and attributable to the new development", and that "a political subdivision imposing an impact fee shall update the land use assumptions and capital improvements plan at least every five years".



STUDY PROCESS

This report documents the practical approach that was taken to determine Land Use Assumptions. The residential and non-residential growth projections formulated in this report were performed using reasonable and generally accepted forecasting and planning principles. The following data and procedures were used in developing this report:

Study Data

- Existing land uses and non-residential square footages (source: Collin Central Appraisal District).
- Existing zoning map and development regulations (source: City of McKinney).
- ONE McKinney 2040 Comprehensive Plan - Future Land Use Plan (source: City of McKinney).
- Historical population information (source: City of McKinney, U.S. Census Bureau).
- Texas Population Projections 2010 to 2050 (source: Texas Demographic Center)
- Proposals for residential and nonresidential developments that have been approved by the City but not yet constructed (source: City of McKinney).

Primary Steps

- Update service area boundaries in accordance with State Law requirements.
- Determine baseline conditions for 2019 population and non-residential square footage
- 3. Project the ultimate buildout population and non-residential square footage.
- 4. Project population and non-residential square footage growth for the next ten years.



SERVICE AREA MAPS

What is a Service Area?

As defined by Local Government Code Chapter 395, a "service area" may include all or part of the land within the political subdivision or its ETJ to be served by the capital improvements or facilities expansions specified in the Capital Improvements Plan, except roadway facilities and storm water, drainage, and flood control facilities.

For roadway facilities, a service area is limited to an area within the corporate boundaries of the political subdivision and shall not exceed 6 miles. Roadway service area boundaries generally follow existing and future major thoroughfares. Also, roadway service areas represent areas of similar traffic generation characteristics and help to maintain efficiencies in accounting and administration of roadway impact fees.

Exhibit "A" shows the 2019 Roadway Service Area Map. The 2019 Roadway Service Area Map includes the same 13 Service Areas that the City


of McKinney recognized during the 2012-2013 Impact Fee Update. Slight changes have been made to align service area boundaries with newly constructed roadways and the Master Thoroughfare Plan that was adopted in 2018 as part of the ONE McKinney 2040 Comprehensive Plan.

Exhibit "B" shows the 2019 Utility Service Area Map. Minor changes have been made to reflect changes in the ETJ boundary that have taken effect since the last impact fee update that was completed in 2012-2013.

For the purpose of further analysis and geographic specificity, sub-service areas were created to assist with the classification of existing population and non-residential square footages, and distribution of future projections. The subservice areas are smaller boundary entities that nest within their larger service area counterparts.

"Roadway service areas represent areas of similar traffic generation characteristics"





BASELINE DATA



Population

The baseline population in McKinney (including ETJ) as of January 1, 2019 has been estimated at 193,012.

Table 1 shows the population history for McKinney and its ETJ from the 2010 U.S. Census through the estimate for January 1, 2019. Using the official 2010 U.S. Census population as starting point, City Planning Staff estimated a population figure each year based on an analysis of building permit data for the previous years as well as on commonly accepted assumptions for occupancy rates and household sizes.

Table 1 illustrates that McKinney has been experiencing continual residential growth over the last nine years. This general trend of population growth is expected to continue throughout the ten year forecast of this study.

McKinney's population estimate was spatially distributed among the thirteen roadway service areas. To do this, City building permit data was used in conjunction with data from the 2010 Census to determine the location of McKinney's population. This permit data was subsequently converted into population using a "persons per dwelling unit figure" for single-family and multi-family housing types that is annually updated. For single-family, the average household size used is 3.08*. For multi-family, the average household size used is 2.17*.

YEAR	POPULATION	% GROWTH
2010	135,038	-
2011	137,406	1.8%
2012	141,330	2.9%
2013	145,511	3.0%
2014	153,807	5.7%
2015	159,100	3.4%
2016	166,569	4.7%
2017	174,141	4.5%
2018	184,420	5.9%
2019	193,012	4.7%

TABLE 1: POPULATION HISTORY

"McKinney has been experiencing continual residential growth over the last nine years"

Non-Residential Square Footages

It is also necessary to establish a baseline figure for the square footage of non-residential uses currently in McKinney. For roadway impact fees, building square footage is the most common independent variable for the estimation of non-residential vehicle trips generated in the Institute of Transportation Engineers (ITE) Trip Generation Manual. Building square footage is closely tied to trip generation and is known at the time of assessment for an impact fee for a proposed development.

The building square footages were categorized into three commonly used land use classifications. Each classification has unique trip making characteristics.

Basic: Higher impact land uses that generate goods and services that are typically used and sold outside of McKinney, such as manufacturing, construction, transportation, warehousing, and other industrial uses.

Service: Land uses that provide personal and professional services, such as government facilities, schools, medical offices, and other professional offices.

Retail: Land uses where the retail sale of goods primarily serves households, and whose location choice is oriented towards a local market. Examples include restaurants, grocery, and clothing stores.

Baseline square footage of Basic, Service, and Retail uses are determined using data from Collin County Appraisal District (CAD). Collin CAD provides land use and square footage data for all existing non-residential uses within McKinney and its ETJ. Using this data, a summary table of all non-residential use categories within each service area was created. These figures act as the baseline conditions for non-residential square footages.

SERVICE	RESIDENTIAL		NON-RESIDENTIAL SQUARE FEET		
AREA	Population	Dwelling Units	Basic	Service	Retail
Α	306	115	23,500	0	81,515
В	2,834	973	0	0	16,699
С	8,429	2,959	227,746	632,125	278,982
D	11,213	3,343	0	3,104,234	1,255,451
E	3,905	1,204	3,624,114	478,284	1,754,956
F	1,485	556	212,216	27,295	263,232
G	50,272	17,987	899,720	1,889,230	2,428,620
Н	29,944	12,197	581,141	1,933,505	2,627,061
I	39,502	13,959	352,879	2,397,595	1,433,682
J	24,011	10,072	1,649,518	2,754,401	3,513,500
K	20,558	7,651	5,125,000	2,871,086	2,325,009
L	182	75	561,885	499,422	82,826
М	370	164	66,320	14,572	0
TOTAL	193,012	71,255	13,324,039	16,601,750	16,061,533

TABLE 2: BASELINE CONDITIONS

ULTIMATE BUILDOUT PROJECTIONS



Overview

An ultimate buildout projection is needed to determine the potential for additional growth that is available in the undeveloped areas of the city and ETJ. The ultimate buildout projection is broken into the same sub-categories as the baseline data (population, dwelling units, basic, service, and retail). The baseline data was used as the developed areas, and the undeveloped areas were broken into the two following categories:

Zoning Applications

Staff analyzed the zoning districts for all parcels within city limits that were considered undeveloped*. Base zoning districts were given an associated land use category (single-family, multi-family, basic, service, or retail). The Planned Development (PD) districts were reviewed and assigned one or more land use categories. In instances where multiple land uses existed in one zoning, the anticipated acreage of the different uses were applied. The land use acreages for each of these zonings were then multiplied by standard metrics from nearby existing conditions to determine the extent of additional growth that is possible. The standard metrics includes an average persons per acre for single-family and multifamily developments, as well as a typical floor-area-ratio (FAR) for non-residential uses. The districts from the ONE McKinney 2040 Comprehensive Plan's Preferred Scenario were utilized to derive a geographic and market specific approach in determining the existing condition metrics.

Future Land Use Plan Applications

Undeveloped areas located within the ETJ but outside the city limits are not subject to the City's zoning regulations. The Future Land Use Plan (FLUP) will be used to consider an appropriate land use at the time of development in the future. The ultimate buildout projection for the area within the ETJ but outside of the current city limits is calculated based on an analysis of the FLUP. Additionally, areas within city limits that are zoned "AG - Agricultural District" are anticipated to rezone and develop in the future and therefore will also adhere to FLUP designated land uses. The areas where the FLUP is applied were categorized by the Placetypes outlined in the ONE McKinney 2040 Comprehensive Plan. The Placetype acreages were multiplied using a calculator that determines anticipated population and square footages for non-residential uses. Since Placetypes are not land-use-specific, the calculator applies anticipated percentages to determine the associated acreage of a Placetype that will fall into one of the land use categories (residential, basic, service, retail).

SERVICE	RESIDENTIAL		NON-RESIDENTIAL SQUARE FEET		
AREA	Population	Dwelling Units	Basic	Service	Retail
Α	46,188	17,743	9,419,802	12,772,114	4,609,915
В	25,032	8,233	51,707	245,645	369,503
С	57,987	19,538	227,746	2,158,784	4,397,073
D	66,423	23,628	917,483	8,690,336	8,077,829
E	32,533	11,449	11,542,472	3,242,892	6,352,282
F	13,811	4,668	998,038	908,095	1,841,789
G	52,046	18,687	1,157,424	2,184,560	4,653,668
Н	39,582	16,242	641,152	7,115,049	4,131,473
I	46,593	16,581	808,120	3,663,775	4,102,982
J	28,292	11,771	2,180,080	6,881,683	5,658,617
K	24,126	9,048	7,823,668	4,434,426	2,966,485
L	300	114	9,239,373	3,235,736	420,080
М	957	362	4,152,840	1,076,720	229,602
TOTAL	433,869	158,064	49,159,907	56,609,815	47,811,298

TABLE 3: BUILDOUT CONDITIONS

$$\begin{bmatrix} \text{Existing} \\ \text{Population} \end{bmatrix} + \begin{bmatrix} \text{Zoning} \\ \text{Applications} \end{bmatrix} + \begin{bmatrix} \text{FLUP} \\ \text{Applications} \end{bmatrix} = \begin{bmatrix} \text{Ultimate} \\ \text{Buildout} \end{bmatrix}$$

"An ultimate buildout projection is needed to determine the potential for additional growth"

10-YEAR GROWTH ASSUMPTIONS

This study considers the years 2019-2029. Acknowledging that the parameters of the study (city limits, Master Thoroughfare Plan, Comprehensive Plan, zoning maps, existing development, etc.) are changing constantly, this study is based on conditions as they were on January 1, 2019.

Population Projections

The following methods were used in projecting the population of McKinney in 2029. An explanation of why these methods were chosen follows their description.

Gompertz Method

The Gompertz growth curve is an extrapolation method that generally fits the growth pattern of McKinney over the last few years. It assumes that, during the total growth period of a geographic area, the growth is slow in the beginning, then increases exponentially for a period of time, and then tapers off as the population approaches an upper growth limit. Using the ultimate population (433,869) from the ultimate buildout projections as the upper growth limit, a Gompertz curve has been plotted and used in part to project the population in 2029.

Ratio Method

Projections for larger geographic areas (i.e. counties or regions) are more reliable than projections for smaller areas (i.e. cities) since a larger population base is less likely to exhibit short term variations. For this reason, the ratio

method has also been utilized. This method operates under the assumptions that if a relationship between a city's population and its larger geographic area has a generally fixed ratio, the population of the city can be related and projected based on the population projection of the larger area. Eight variations of the ratio method were tested for their ability to project McKinney's population over the next ten years. From these methods, the two best performing were chosen, McKinney's share of Collin County's growth, and Collin County's population rate of change.

The Texas Demographic Center's Population Projections Program produces projections for the state, and all counties in the state by age, sex and race/ethnicity. These projections contain the anticipated population for Collin County for every year from 2010 to 2050. Using the ratio methods described above, and for the purposes of the Land Use Assumptions, McKinney's population was projected out to 2029.




EXHIBIT C: PROJECTED POPULATION GROWTH

Similar to previous iterations of Land Use Assumptions, in projecting the population for McKinney it is assumed that using a combination of the Ratio and Gompertz method will perform best. The Ratio projection methods are a simplified extension of existing or predicted population trends. Gompertz is a logarithmic curve that recalculates new projections as new data points (updated yearly populations) are added. The combination of these methods help to provide a balanced approach for population projections.

In deriving the 2029 population, a weighted average was used between the three population projections (Collin County's Growth Share, Collin County's Population Rate of Change, and Gompertz) for the two methods. The average divides the weight of the projections by method, allotting 50% of the weight to the Ratio Method, and 50% to Gompertz. From this average, a population of 262,084 was calculated for McKinney in 2029; a growth of 69,073 from the 2019 population of 193,012.*

Once the population was projected for the ten year window, distribution was completed using the spatial data generated during the buildout potential calculation. The existing level of developed area in a sub-service area was calculated as well as the sub-service area's remaining growth potential. Then, using common Planning practices the sub-service area's buildout percent was structured to reflect conditions that area likely to exist in 2029. These incremental percentage increases generate additional population, and are influenced by the sub-service areas buildout potential and location.



10-YEAR GROWTH ASSUMPTIONS

Non-Residential Projections

To forecast the amount of growth in Basic, Service, and Retail land use categories over the ten year period of the study, a combination of methods were utilized. The previous ten years of non-residential square footages were analyzed on a service area basis to identify existing trends. The most consistent and noticeable trend were the land use categories relationship's with population. By analyzing the amount of Basic, Service, and Retail square feet per person for the last ten years, the following trends were identified:

Basic: It is assumed that as McKinney's population increases, the amount of Basic square footage per person will decrease. While total square feet of Basic has increased, the general trend for the past ten years showed a decrease in square feet per person. An average of the ten year median, and a ten year trend were used to determine a square foot per person growth over the next ten years. An additional 4,230,559 square feet of Basic is expected by 2029.

Service: It is assumed that as McKinney's population increases, the amount of Service square footage per person will remain the same. The general trend for the past five years showed a slight decrease in square feet per person. A five year median was used to determine a square

foot per person growth over the next ten years. An additional 6,160,065 square feet of Service is expected by 2029.

Retail: It is assumed that as McKinney's population increases, the amount of Retail square footage per person will slightly increase. The general trend for the past ten years showed a general increase in square feet per person. An average of the ten year median, and a ten year trend were used to determine a square foot per person growth over the next ten years. An additional 6,136,024 square feet of Retail is expected by 2029.

Once the square footages were projected for the ten year window, distribution was completed using the spatial data generated during the buildout determination process. The existing level of developed area in a sub-service area was calculated as well as the sub-service area's remaining non-residential growth potential. Then, using common Planning practices the subservice area's buildout percent was structured to reflect conditions that area likely to exist in 2029. These changes in percent generate additional square footages for the three land uses, and are influenced by the sub-service areas buildout potential.





SERVICE	RESIDENTIAL		NON-RESIDENTIAL SQUARE FEET		
AREA	Population	Dwelling Units	Basic	Service	Retail
Α	0	0	0	0	0
В	21,871	6,959	10,071	207,903	86,236
С	6,945	2,312	0	726,068	438,993
D	17,370	6,277	59,635	700,061	830,401
E	2,506	873	2,482,408	199,736	725,194
F	713	118	19,891	71,783	212,738
G	1,130	435	30,630	69,408	719,260
Н	8,439	3,495	14,932	1,806,746	787,669
I	4,218	1,608	112,104	252,841	1,199,668
J	4,112	1,390	227,006	1,733,118	774,630
K	1,700	639	504,952	247,260	331,012
L	0	0	597,354	113,513	16,437
М	69 23		171,577	31,628	13,786
TOTAL	69,073	24,128	4,230,559	6,160,065	6,136,024

TABLE 4: PROJECTED GROWTH


SERVICE	RESIDENTIAL		NON-RESIDENTIAL SQUARE FEET		
AREA	Population	Dwelling Units	Basic	Service	Retail
Α	306	115	23,500	0	81,515
В	24,705	7,932	10,071	207,903	102,935
С	15,374	5,271	227,746	1,358,193	717,975
D	28,583	9,620	59,635	3,804,295	2,085,852
E	6,411	2,077	6,106,522	678,020	2,480,149
F	2,198	674	232,107	99,078	475,970
G	51,402	18,422	930,350	1,958,638	3,147,880
Н	38,383	15,692	596,073	3,740,251	3,414,730
I	43,720	15,567	464,983	2,650,436	2,633,350
J	28,123	11,462	1,876,524	4,487,519	4,288,131
K	22,258	8,290	5,629,951	3,118,347	2,656,021
L	182	75	1,159,239	612,935	99,263
М	439	187	237,897	46,200	13,786
TOTAL	262,084	95,383	17,554,598	22,761,815	22,197,558


TABLE 5: 2029 BASELINE CONDITIONS







2029 POPULATION DISTRIBUTION






SUBSERVICE AREAS







2019 ROADWAY IMPACT FEE UPDATE



October 2020

Prepared for the City of McKinney

Prepared by:

Kimley-Horn and Associates, Inc.

801 Cherry Street, Unit 11, Suite 1300

Fort Worth, TX 76102

Phone 817 335 6511

TBPE Firm Registration Number: F-928

JEFFREY A. WHITACRE

10/7/2020

JEFFREY A. WHITACRE

102469

CENSE SONAL

Project Number: 061269201

© Kimley-Horn and Associates, Inc.





Table of Contents

EXECL	JTIVE SUMMARY4	
l.	INTRODUCTION11	
II.	LAND USE ASSUMPTIONS	
III.	ROADWAY IMPACT FEE ROADWAY IMPROVEMENTS PLAN	
1. 2. 3. 4. 5. 6.	METHODOLOGY FOR ROADWAY IMPACT FEES A. Service Areas	32 33 33
V.	F. Service Unit Calculation	
	C. Financial Component of Impact Fee Determination	
VI.	SAMPLE CALCULATIONS	
VII.	ADOPTION AND ADMINISTRATION OF ROADWAY IMPACT FEES	
VIII.	CONCLUSION73	
IX.	APPENDICES	





LIST OF EXHIBITS

1	Service Areas	15
2	10-Year Roadway Impact Fee Roadway Improvements Plan	26
LIS	T OF TABLES	
1	Residential and Non-Residential Projections for the City of McKinney	16
2	10-Year Roadway Impact Fee Roadway Improvements Plan	
_	Service Area A	18
	Service Area B	
	Service Area C	
	Service Area D	
	Service Area E	
	Service Area F	
	Service Area G	22
	Service Area H	22
	Service Area I	23
	Service Area J	23
	Service Area K	24
	Service Area L	24
	Service Area M	25
3A	Service Volumes for Proposed Facilities	29
3B	Service Volumes for Existing Facilities	29
4	Construction Cost Pay Items	33
5	10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections	
	Service Area A	35
	Service Area B	35
	Service Area C	36
	Service Area D	37
	Service Area E	38
	Service Area F	38
	Service Area G	39
	Service Area H	39
	Service Area I	40
	Service Area J	40
	Service Area K	41
	Service Area L	41
	Service Area M	
6	Maximum Trip Lengths by Service Area	45
7	Transportation Demand Factor Calculations	
	Service Area C Examples	
	Service Area I Examples	46
8.	10-Year Growth Projections	
9	Maximum Assessable Roadway Impact Fee Calculation	48-50





10	Maximum Assessable Roadway Impact Fee	54
11	Land Use/Vehicle-Mile Equivalency Table (LUVMET)	
	Service Area A	
	Service Area B	58
	Service Area C	
	Service Area D	59
	Service Area E	
	Service Area F	62
	Service Area G	63
	Service Area H	
	Service Area I	
	Service Area J	66
	Service Area K	67
	Service Area L	68
	Service Area M	69
12	Land Use Descriptions	70





EXECUTIVE SUMMARY

Introduction

Impact Fees are a mechanism for funding the public infrastructure necessitated by new development. Across the country, they are used to fund police and fire facilities, parks, schools, roads, and utilities. In Texas, the legislature has allowed their use for water, wastewater, roadway, and drainage facilities. In 2003, the City began exploring Water, Wastewater, and Roadway Impact Fees as a funding tool for infrastructure needs as a result of significant growth in the City of McKinney.

In the most basic terms, impact fees are meant to recover the incremental cost of the impact of each new unit of development creating new infrastructure needs. In the case of Roadway Impact Fees, the infrastructure need is the increased capacity on arterial and thoroughfare roadways that serve the overall transportation system. The purpose of the 2019 Roadway Impact Fee Update is to identify the fee per unit of new development necessary to fund these improvements in accordance with the enabling legislation, Chapter 395 of the Texas Local Government Code.

Impact Fees are a mathematical calculation that determines a maximum impact fee that would be equivalent for growth paying for growth. The Maximum Roadway Impact Fee per Service Unit for Roadway Facilities is considered an appropriate measure of the impacts generated by a new unit of development on the City's Master Thoroughfare Plan. An impact fee program is anticipated to be designed so that it is predictable for both the development community and City.

An impact fee program is transparent. This report describes in detail how the fee is calculated and how the Capital Improvements Advisory Committee (CIAC) monitors the Impact Fee program. An impact fee program is flexible in that funds can be used on priority projects and not just on projects adjacent to a specific development. An impact fee program is consistent with other City goals and objectives for growth. For example, the actual collection rate set by Council may be determined to be less than the Maximum Roadway Impact Fee to achieve and be in alignment with other City goals and objectives for growth.





Impact Fee Basics

Roadway Impact Fees are determined by several key variables, each described below in greater detail.

Impact Fee Study

The 2019 Roadway Impact Fee Update was completed to determine the maximum impact fee per unit of new development chargeable as allowed by the state law. This determination is not a recommendation; the actual fee amount ultimately assessed is at the discretion of the McKinney City Council, so long as it does not exceed the maximum assessable fee allowed by law. The study looks at a period of 10 years to project new growth and corresponding capacity needs, as required by state law. The study and corresponding maximum fees must be restudied at least every five years. However, the study can be updated at any time to accommodate significant changes in any of the key variables of the impact fee equation.

Service Areas

A Service Area is a geographic area within which a unique maximum impact fee is determined. All fees collected within the Service Area must be spent on eligible improvements within the same Service Area. For Roadway Impact Fees, the Service Area may not exceed 6 miles. In McKinney, this results in the creation of thirteen (13) separate Service Areas. A map of the Service Areas can be found on Page 15. It is to be noted that Service Area A and F were assumed to be no fee Service Areas.

In defining the Service Area boundaries, the project team considered the corporate boundary, required size limit, adjacent land uses, highway facilities, and topography. The Service Areas used in the 2019 Roadway Impact Fee Update are approximately the same as in the previous impact fee update with some minor modifications to accommodate recent annexations and roadway realignments. Since each Service Area has a unique maximum impact fee, the per-unit maximum fee for an identical land use will vary from one Service Area to the next.





Land Use Assumptions

The Impact Fee determination is required to be based on the projected growth and corresponding capacity needs in a 10-year window. This study considers the years 2019-2029. Acknowledging that the parameters of the study (city limits, Master Thoroughfare Plan, Comprehensive Plan, zoning maps, existing development, etc.) are changing constantly, this study is based on conditions as they were in January 2019.

One of the key elements in the determination of the impact fee is the amount of new development anticipated over 10 years. The residential and non-residential growth projections were performed using reasonable and generally accepted forecasting and planning principles by City of McKinney staff in a separate report titled 2019 Land Use Assumptions.

Roadway Impact Fee Roadway Improvements Plan

The Roadway Impact Fee Roadway Improvements Plan (RIF RIP) is distinct and separate from the City's traditional Capital Improvements Program (CIP). The RIF RIP is a list of projects eligible for funding through impact fees. The City's Master Thoroughfare Plan is the ultimate plan for the infrastructure within the City Limits. Only capacity improvements still needed to build out the City's Master Thoroughfare Plan to accommodate the expected growth within the next 10-years are included in the RIF RIP. Capacity improvements may include the addition of lanes, intersection improvements, or the extension of a new road. Resurfacing or other maintenance activities do not qualify as capacity improvements under impact fee law in Texas and cannot be funded with Roadway Impact Fees.

The cost of the RIF RIP is one of the fundamental factors in the calculation of the per-unit maximum impact fee. The RIF RIP's cost was calculated through systematic evaluation of each eligible project. In determining project limits, the team identified roadway segments with uniform need. For Example, Hardin Boulevard has a portion with one third of a six-lane divided facility built north of Wilmeth Road, while approximately 3,590' south of the future Bloomdale Road extension, Wilmeth Road has two thirds of a six-lane divided facility built. These were split as two separate projects based on uniform need. Developing unit costs based on input from local staff, uniform costs were determined for the major items of work, additional construction items, and project delivery costs. Section III provides a listing of the 10-Year RIF RIP by service area in Tables 2.A – 2.M and a city-wide map of the RIF RIP in Exhibit 2.





Finally, detailed cost projections by project can be found in Appendix A. It should be noted that these cost projections are based on conceptual level planning and are subject to refinement upon final design. Only those projects listed in the RIF RIP are eligible to utilize impact fee funds.

Only the costs associated with providing the additional capacity at an anticipated level of service D necessitated by 10 years of growth can be used to calculate the maximum impact fee. To calculate the maximum impact fee, the total cost of the RIF RIP at build-out was reduced to account for (1) the portion of new capacity that will address existing needs, and (2) the portion of new capacity that will not be necessitated until beyond the 10-year growth window. A ratio that compares 10 years' demand for capacity to the net supply of capacity (total new capacity in the RIF RIP minus existing needs) can be calculated. That ratio, which may not exceed 100%, is then applied to the cost of the net capacity supplied. The result is a determination of the costs attributable to the next 10 years' growth, which is then used to calculate the maximum impact fee in accordance with state law. The result is known as the recoverable cost of the RIF RIP. The projected recoverable cost to construct infrastructure needed through 2029 by service area are:

Service Area	Recoverable Cost of RIP and Financing
А	\$0
В	\$10,479,185
С	\$43,752,749
D	\$141,971,941
E	\$39,294,334
F	\$0
G	\$8,942,328
Н	\$11,297,580
I	\$23,188,757
J	\$8,633,827
K	\$10,208,369
L	\$3,868,782
M	\$731,486





A portion of the remainder can be assessed as the planning window extends beyond 2029 and as the impact fees are updated in the future.

Service Unit

The "service unit" is a measure of consumption or use of the capital facilities by new development. In other words, it is the unit of measure used in the 2019 Roadway Impact Fee Update to quantify the supply and demand for roads in the City. For transportation purposes, the service unit is defined as a vehicle-mile. A vehicle-mile is the capacity consumed in a single lane in the PM peak hour by a vehicle making a trip one mile in length. The PM Peak is used as the basis for transportation planning and the estimation of trips caused by new development.

For each type of development, the City of McKinney uses the Land Use/Vehicle-Mile Equivalency Table (LUVMET) to determine the number of service units. Based on the City's 10-year growth projections and associated demand (consumption) values the vehicle-miles of demand in each service area are:

Service	Total Vehicle-Miles of
Area	Demand over Ten Years
А	0
В	9,578
С	15,582
D	41,299
E	17,845
F	0
G	7,742
Н	31,324
I	18,332
J	24,864
K	8,530
L	1,893
M	304





Impact Fee Calculation

In the simplest terms, the maximum impact fee allowable by law is calculated by dividing the recoverable cost of the RIF RIP by the number of new service units of development. In accordance with state law, both the cost of the RIF RIP and the number of new service units of development used in the equation are based on the growth and corresponding capacity needs projected to occur within a 10-year window. This calculation is performed for each service area individually; each service area has a stand-alone RIF RIP and 10-year growth projection.

In practice, there are many factors that complicate this calculation. The maximum impact fee allowable by law for each service area is calculated in Table 10. A detailed discussion of the calculation is found on Page 48, and is walked through in Table 9.

Collection and Use of Roadway Impact Fees

Roadway Impact Fees are assessed when a final plat is recorded. The assessment defines the impact of each unit at the time of platting, according to land use, and may not exceed the maximum impact fee allowed by law. An existing plat would be assessed at the adoption of the ordinance and would be exempt from impact fees for one year. Roadway Impact Fees are collected when a building permit is issued. Therefore, funds are not collected until development-impacts are introduced to the transportation system. Funds collected within a service area can be used only within the same service area. Finally, fees must be utilized within 10 years of collection in the designated service area or must be refunded with interest. Fees should be utilized in a first in, first out basis.

Adoption Process

Chapter 395 of the Texas Local Government Code stipulates a specific process for the adoption of Roadway Impact Fees. A Capital Improvements Advisory Committee (CIAC) is required to review the Land Use Assumptions and RIF RIP used in calculating the maximum fee, and to provide the Committee's findings for consideration by the City Council. The CIAC also reviews the Roadway Impact Fee ordinance and provides its findings to the City Council. The composition of the CIAC (Planning and Zoning Commission in McKinney) is required to have one representative of the building and development communities. The City Council then conducts a public hearing on the Land Use Assumptions, RIF RIP, and Impact Fee Ordinance. A public hearing is required for the 2019 Roadway Impact Fee Update.





Following policy adoption, the CIAC is tasked with advising the City Council of the need to update the Land Use Assumptions or the RIF RIP at any time within five years of adoption. Finally, the CIAC oversees the proper administration of the Impact Fee, once in place, and advises the Council as necessary.

2019 Roadway Impact Fee Update Results

Below is the comparison of the maximum assessable impact fee per service unit (Vehicle-Mile) for the 2012-2013 and 2019 Roadway Impact Fee Updates:

Service	2019 Maximum Fee Per Service Unit	2012–2013 Maximum Fee Per Service
Area	(Per Vehicle-Mile)	Unit (Per Vehicle-Mile)
А	\$0	\$0
В	\$1,094	\$861
С	\$2,808	\$1,500
D	\$3,438	\$1,711
E	\$2,202	\$2,082
F	\$0	\$0
G	\$1,155	\$635
Н	\$361	\$393
I	\$1,265	\$755
J	\$347	\$824
K	\$1,197	\$1,182
L	\$2,044	\$1,320
М	\$2,406	\$0





I. INTRODUCTION

Chapter 395 of the Texas Local Government Code describes the procedure political subdivisions must follow to create and implement impact fees. Chapter 395 defines an Impact Fee as "a charge or assessment imposed by a political subdivision against new development in order to generate revenue for funding or recouping the costs of roadway improvements or facility expansions necessitated by and attributable to the new development."

The City has retained Kimley-Horn and Associates, Inc. to provide professional transportation engineering services for the update of their Rodway Impact Fees. This report includes details of the Roadway Impact Fee calculation methodology in accordance with Chapter 395, the applicable Land Use Assumptions, development of the RIF RIP, and the Land Use Equivalency Table.

This report references two of the basic inputs to the Roadway Impact Fee:

- 1) Land Use Assumptions (Pg. 13)
- 2) Roadway Impact Fee Roadway Improvements Plan (RIF RIP) (Pg. 17)

Information from these Land Use Assumptions and RIF RIP are used extensively throughout the remainder of the report.

There is a detailed discussion of the methodology for the computation of impact fees. This discussion is broken into three components:

- 1) Methodology for Roadway Impact Fees (Pg. 27)
- 2) Roadway Impact Fee Calculation (Pg. 48)
- 3) Plan for the Roadway Impact Fee Credit (Pg. 50)





The components of the Methodology for Roadway Impact Fees include development of:

- Service Areas (Pg. 27)
- Service Units (Pg. 27)
- Cost Per Service Unit (Pg. 30)
- RIF RIP Costing Methodology (Pg. 30)
- Summary of RIF RIP Costs (Pg. 34)
- Service Unit Calculation (Pg. 42)

The Roadway Impact Fee is then calculated as:

- Maximum Assessable Impact Fee Per Service Unit (Pg. 48)
- Service Unit Demand Per Unit of Development (Pg. 55)

The final section of the report is the Conclusion, which presents the findings of the updated analysis and summarizes the report.





II. LAND USE ASSUMPTIONS

A. Purpose and Overview

In order to assess an impact fee, Land Use Assumptions must be developed to provide the basis for residential and non-residential growth projections within a political subdivision. As defined by Chapter 395 of the Texas Local Government Code, these assumptions include a description of changes in land uses, densities, and population in the service area. The land use assumptions used in this report were developed by City of McKinney staff and are presented in a separate report titled 2019 Land Use Assumptions. These land use assumptions were adopted by City Council on September 17, 2019.

The residential and non-residential estimates and projections were compiled in accordance with the following categories:

Units: Number of dwelling units.

Population: Number of people, based on person per dwelling unit factor.

Employment: Square feet of building area based on three (3) different classifications. Each

classification has unique trip making characteristics.

<u>Retail</u>: Land use activities which provide for the retail sale of goods which primarily serve households and whose location choice is oriented toward the household sector, such as grocery stores and restaurants.

<u>Service</u>: Land use activities which provide personal and professional services, such as government and other professional offices.

<u>Basic</u>: Land use activities that produce goods and services such as those which are exported outside of the local economy, such as manufacturing, construction, transportation, wholesale, trade, warehousing, and other industrial uses.






The above categories are used in the development of the assumptions for impact fees; however, expanded classifications used in the assessment of impact fees are found in the Land Use / Vehicle-Mile Equivalency Table (Pg. 57 - 69).

B. Roadway Impact Fee Service Areas

The geographic boundaries of the proposed impact fee service areas for transportation facilities are shown in Exhibit 1. The City of McKinney is currently divided into thirteen (13) service areas, each based upon a six (6) mile limit as required by Chapter 395. For roadway facilities, the service areas are limited to those areas within the current corporate limits. Therefore, areas within the extraterritorial jurisdiction (ETJ) are excluded from this study.

At locations where service area boundaries follow a thoroughfare facility, the proposed boundary is intended to follow the centerline of the roadway. In cases where a service area boundary follows the City Limits, only those portions of the facility within the City Limits are included in the service area.







C. Land Use Assumptions Summary

Table 1 summarizes the residential and non-residential 10-year growth projections within the City of McKinney for 2019 and 2029. The previously referenced *2019 Land Use Assumptions* is the source for this data.

Table 1. Residential and Non-Residential Projections for the City of McKinney

Service		Resident		Non-R	esidential Squa	re Feet
Area	Year	Population	Dwelling Units	Basic	Service	Retail
А	2019	306	115	23,500	0	81,515
A	2029	306	115	23,500	0	81,515
В	2019	2,834	973	0	0	16,699
Б	2029	24,705	7,932	10,071	207,903	102,935
С	2019	8,429	2,959	227,746	632,125	278,982
C	2029	15,374	5,271	227,746	1,358,193	717,975
D	2019	11,213	3,343	0	3,104,234	1,255,451
D	2029	28,583	9,620	59,635	3,804,295	2,085,852
Е	2019	3,905	1,204	3,624,114	478,284	1,754,956
E.	2029	6,411	2,077	6,106,522	678,020	2,480,149
F	2019	1,485	556	212,216	27,295	263,232
Г	2029	2,198	674	232,107	99,078	475,970
G	2019	50,272	17,987	899,720	1,889,230	2,428,620
G	2029	51,402	18,422	930,350	1,958,638	3,147,880
Н	2019	29,944	12,197	581,141	1,933,505	2,627,061
П	2029	38,383	15,692	596,073	3,740,251	3,414,730
ı	2019	39,502	13,959	352,879	2,397,595	1,433,682
l	2029	43,720	15,567	464,983	2,650,436	2,633,350
J	2019	24,011	10,072	1,649,518	2,754,401	3,513,500
J	2029	28,123	11,462	1,876,524	4,487,519	4,288,131
K	2019	20,558	7,651	5,125,000	2,871,086	2,325,009
K	2029	22,258	8,290	5,629,951	3,118,347	2,656,021
	2019	182	75	561,885	499,422	82,826
L	2029	182	75	1,159,239	612,935	99,263
М	2019	370	164	66,320	14,572	0
	2029	439	187	237,897	46,200	13,786
Sub-Total – 202	-	69,073	24,129	4,230,560	6,160,065	6,136,024





III. ROADWAY IMPACT FEE ROADWAY IMPROVEMENTS PLAN

The City has identified the transportation projects needed to accommodate the projected growth within the City. The City's Master Thoroughfare Plan is the ultimate plan for the infrastructure within the City Limits. Only capacity improvements still needed to build out the City's Master Thoroughfare Plan to accommodate the expected growth within the next 10-years are included in the RIF RIP. The RIF RIP consists of 4 categories of projects. They are as follows:

- New Any future roadway identified by the City to be included in the RIP.
- Widening Existing roadways not currently built to the ultimate classification in the Master Thoroughfare Plan and must be completely reconstructed.
- Partial Widening Existing roadways that only have a portion of the ultimate classification cross section to be built.
- Previously Completed Completed projects with excess capacity available to serve new growth that the City contributed to financially.

The RIF RIP includes roadway facilities as well as major intersection improvements. All the roadway facilities identified are included in the currently adopted Master Thoroughfare Plan.

Major intersection improvements were based on direction from City of McKinney staff. Improvements were categorized as follows:

- Signal New signal.
- Interchange Signals Assumes new signals at each frontage road intersection of the interchange.
- Signal Mod Signal modification to an existing signal due to construction of a new roadway approach or a future signal modification identified by the City.
- Intersection Improvement Assumes addition of turn lanes.
- Roundabout Roundabout construction.
- Under Construction Intersection with ongoing improvements identified by the City.





All intersection improvement recommendations are recommended to undergo a design level evaluation before implementation to ensure the most appropriate improvements are made. In the case where a design level evaluation determines improvements contrary to the RIF RIP, such as turn lane improvements in place of a signal, the RIF RIP cost allocated to the intersection may still be applied to the alternate improvements. The intersection improvement costs were based on standard costs for each improvement and no engineering was done when assuming these costs, unless cost projections were provided by the City.

The proposed RIF RIP is listed in Tables 2.A – 2.M and mapped in Exhibit 2 (Individual SA RIP Maps in Appendix). The tables show the length of each project as well as the facility's Master Thoroughfare Plan classification. The RIF RIP was developed in conjunction with input from City of McKinney staff and represents projects that will be needed to accommodate the growth projected in the 2019 Land Use Assumptions.

Table 2.A. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area A

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	A-1, C-1	M6D	UNNAMED 5 (1)	635' W OF STONEBRIDGE DR TO CR 168	0.63	50%
A	A-2, D-1	M6D	UNNAMED 5 (3)	CR 168 TO 1,560' E OF CR 168	0.30	50%
	A-3	G4D	STONEBRIDGE DR (1)	2,635' N OF UNNAMED 5 TO UNNAMED 5	0.50	50%

Note: The 10-Year Roadway Impact Fee RIP is not in a prioritized order.

Table 2.B. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area B

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	B-1, D-2	M6D	UNNAMED 5 (4)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD	0.43	50%
	B-2	G6D	HARDIN BLVD (1)	CR 204 TO CR 206	0.08	50%
В	B-3	G6D	HARDIN BLVD (2)	1,670' N OF OLYMPIC TO 730' S OF OLYMPIC	0.45	50%
ь	B-4	G6D	HARDIN BLVD (3)	1,940' N OF UNNAMED 5 TO UNNAMED 5	0.37	100%
	1	Inter-	Signal	HARDIN BLVD & OLYMPIC		50%
	3	section	Signal	HARDIN BLVD & UNNAMED 5		50%





Table 2.C. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area C

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	A-1, C-1	M6D	UNNAMED 5 (1)	635' W OF STONEBRIDGE DR TO CR 168	0.63	50%
	C-2	M6D	UNNAMED 5 (2)	RIDGE RD TO 1,505' E OF RIDGE RD	0.29	50%
	C-3	G6D	LAUD HOWELL PKWY (1)	695' W OF CUSTER RD TO CUSTER RD	0.13	50%
	C-4	G6D	LAUD HOWELL PKWY (2)	CUSTER RD TO 1,225' E OF CUSTER RD	0.23	100%
	C-5	G6D	LAUD HOWELL PKWY (3)	1,225' E OF CUSTER RD TO 2,070' E OF CUSTER RD	0.16	50%
	C-6	G6D	LAUD HOWELL PKWY (4)	840' E OF STONEBRIDGE DR TO 2,905' E OF STONEBRIDGE DR	0.39	50%
	C-7	G6D	LAUD HOWELL PKWY (5)	1,985' W OF RIDGE RD TO 1,230' E OF RIDGE RD	0.61	50%
	C-8	P6D	BLOOMDALE RD (1)	CUSTER RD TO 1,310' E OF CUSTER RD	0.25	100%
	C-9	P6D	BLOOMDALE RD (2)	1,310' E OF CUSTER RD TO 2,030' W OF STONEBRIDGE DR	0.40	50%
	C-10	P6D	BLOOMDALE RD (3)	2,030' W OF STONEBRIDGE DR TO 3,245' E OF STONEBRIDGE DR	1.00	100%
	C-11	P6D	BLOOMDALE RD (4)	3,245' E OF STONEBRIDGE DR TO 695' W OF RIDGE RD	0.26	50%
	C-12	P6D	BLOOMDALE RD (5)	695' W OF RIDGE RD TO RIDGE RD	0.13	100%
	C-13	P6D(2/3)	BLOOMDALE RD (6)	3,400' W OF LAKE FOREST DR TO LAKE FOREST DR	0.64	50%
	C-14	G4D	WILMETH RD (1)	3,725' W OF STONEBRIDGE DR TO 815' E OF STONEBRIDGE DR	0.86	100%
	C-15	G4D	WILMETH RD (2)	815' E OF STONEBRIDGE DR TO 995' W OF RIDGE RD	0.63	50%
	C-16	G4D(1/2)	WILMETH RD (3)	RIDGE RD TO 585' E OF RIDGE RD	0.11	100%
	C-17	G4D(1/2)	WILMETH RD (4)	1,095' E OF RIDGE RD TO 1,365' E OF RIDGE RD	0.05	100%
	C-18	P6D	CUSTER RD (1)	1,855' N OF LAUD HOWELL PKWY TO LAUD HOWELL PKWY	0.35	50%
	C-19	P6D	CUSTER RD (2)	LAUD HOWELL PKWY TO 2,775 N OF BLOOMDALE RD	0.53	100%
	C-20	P6D	CUSTER RD (3)	2,655 N OF BLOOMDALE RD TO 375' N OF WILMETH RD	1.19	50%
	C-21	G4D	STONEBRIDGE DR (2)	UNNAMED 5 TO 1,280' S OF UNNAMED 5	0.24	100%
C	C-22	G4D	STONEBRIDGE DR (3)	1,570' S OF LAUD HOWELL PKWY TO 280' S OF WILMETH RD	1.51	100%
	C-23	G4D	STONEBRIDGE DR (4)	280' S OF WILMETH RD TO 1,195' S OF WILMETH RD	0.17	50%
	C-24	G4D	STONEBRIDGE DR (5)	1,195' S OF WILMETH RD TO 5,555' S OF WILMETH RD	0.83	100%
	C-25	G4D	STONEBRIDGE DR (6)	580' N OF US HIGHWAY 380 TO US HIGHWAY 380	0.11	100%
	C-26	M6D	RIDGE RD (1)	UNNAMED 5 TO 1,485' S OF UNNAMED 5	0.28	50%
	C-27	M6D	RIDGE RD (2)	LAUD HOWELL PKWY TO BAXTER WELL RD	0.59	100%
	C-28	M6D	RIDGE RD (3)	BAXTER WELL RD TO 2,160' S OF BLOOMDALE RD	0.83	50%
	C-29	M6D	RIDGE RD (4)	1,590' N OF WILMETH RD TO WILMETH RD	0.30	50%
	C-30	M6D(1/3)	RIDGE RD (5)	WILMETH RD TO 2,280' S OF WILMETH RD	0.43	100%
	C-31	M6D(1/3)	RIDGE RD (6)	1,860' N OF US HIGHWAY 380 TO 1,390' N OF US HIGHWAY 380	0.09	50%
	C-32	M6D(1/3)	RIDGE RD (7)	775' N OF US HIGHWAY 380 TO US HIGHWAY 380	0.15	100%
	C-33	M6D(1/3)	LAKE FOREST DR (2)	BLOOMDALE RD TO WILMETH RD	1.02	50%
	C-34, D-22	M6D(1/3)	LAKE FOREST DR (3)	WILMETH RD TO US HIGHWAY 380	0.98	50%
	2		Signal	RIDGE RD & UNNAMED 5		25%
	4		Signal	LAUD HOWELL PKWY & CUSTER RD		75%
	5		Signal	LAUD HOWELL PKWY & RIDGE RD		50%
	12		Intersection Improvement	CUSTER RD & BLOOMDALE RD		50%
	13	u	Signal	BLOOMDALE RD & STONEBRIDGE DR		100%
	14	ctic	Signal	BLOOMDALE RD & RIDGE RD		50%
	15	Intersection	Signal	BLOOMDALE RD & LAKE FOREST DR		25%
	23		Signal	STONEBRIDGE DR & WILMETH RD		100%
	24		Signal	WILMETH RD & RIDGEKNOLL AVE		100%
	25		Roundabout	LAKE FOREST DR & WILMETH RD		50%
	33		Signal Mod	US HIGHWAY 380 & STONEBRIDGE DR		50%
	34		Signal	US HIGHWAY 380 & FOREST RIDGE LN		50%
	35		Signal	US HIGHWAY 380 & AUBURN HILLS PKWY		50%





Table 2.D. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area D

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	A-2, D-1	M6D	UNNAMED 5 (3)	CR 168 TO 1,560' E OF CR 168	0.30	50%
	B-1, D-2	M6D	UNNAMED 5 (4)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD	0.43	50%
	D-3	G6D	LAUD HOWELL PKWY (6)	LAKE FOREST DR TO 1860' E OF HARDIN BLVD	2.65	100%
	D-4	G6D	LAUD HOWELL PKWY (7)	4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY	0.74	100%
	D-5	G6D(1/3)	LAUD HOWELL PKWY (8)	240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75	0.38	100%
	D-6	G4D	TRINITY FALLS PKWY (1)	HARDIN BLVD TO 1,910' E OF HARDIN BLVD	0.36	100%
	D-7	G4D	TRINITY FALLS PKWY (2)	1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD	0.14	50%
	D-8	G4D	TRINITY FALLS PKWY (3)	COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY	0.34	50%
	D-9	G4D	TRINITY FALLS PKWY (4)	LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY	0.42	100%
	D-10	M6D(1/3)	TRINITY FALLS PKWY (5)	4,275' N OF WESTON RD TO LAUD HOWELL PKWY	1.05	100%
	D-11	P6D	BLOOMDALE RD (7)	1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	0.34	50%
	D-12	P6D	BLOOMDALE RD (8)	1,485' E OF CR 1006 TO 1,215' W OF CR 1007	0.29	100%
	D-13	P6D	BLOOMDALE RD (9)	1,225' W OF CR 1007 TO CR 1007	0.23	50%
	D-14	P6D(2/3)	BLOOMDALE RD (10)	CR 1007 TO HARDIN BLVD	0.37	100%
	D-15	P6D(1/3)	BLOOMDALE RD (11)	HARDIN BLVD TO COMMUNITY AVE	0.49	100%
	D-16	G4D	WILMETH RD (5)	LAKE FOREST DR TO UNNAMED A	0.90	50%
	D-17	G4D	WILMETH RD (6)	UNNAMED A TO 825' E OF UNNAMED A	0.16	100%
	D-18	G4D(1/2)	WILMETH RD (7)	825' E OF TAYLOR-BURK DR TO 1,380' E OF TAYLOR-BURK DR	0.11	100%
	D-19	G4D	WILMETH RD (8)	1,380' E OF TAYLOR-BURK DR TO HARDIN BLVD	0.42	50%
	D-20	M6D(1/3)	WILMETH RD (9)	HARDIN BLVD TO US HIGHWAY 75	1.16	100%
	D-21	G6D	LAKE FOREST DR (1)	LAUD HOWELL PKWY TO 3,200' S OF LAUD HOWELL PKWY	0.61	50%
	C-34, D-22	· · · / ·	LAKE FOREST DR (3)	WILMETH RD TO US HIGHWAY 380	0.98	50%
	D-23	G4D	UNNAMED A (1)	5,785' N OF LAUD HOWELL PKWY TO 2,710' S OF LAUD	1.61	100%
	D-24 D-25	G4D G4D	UNNAMED A (2)	2,710' S OF LAUD HOWELL PKWY TO BLOOMDALE RD	0.49	50%
	D-25 D-26		UNNAMED A (4)	1,105' N OF WILMETH RD TO WILMETH RD	0.21	50%
D		M4D	UNNAMED A (4)	WILMETH RD TO HARDIN BLVD		100%
D D	D-27 D-28	M4D G6D	TAYLOR-BURK DR (1)	HARDIN BLVD TO SKYLINE DR	0.28	100% 50%
	D-28 D-29	G6D	HARDIN BLVD (4) HARDIN BLVD (5)	UNNAMED 5 TO 1,550' S OF UNNAMED 5 1,545' S OF UNNAMED 5 TO TRINITY FALLS PKWY	1.38	100%
	D-29 D-30	G6D	HARDIN BLVD (6)	TRINITY FALLS PKWY TO 1,815' S OF TRINITY FALLS PKWY	0.34	50%
	D-30 D-31	G6D	HARDIN BLVD (7)	1,815' S OF TRINITY FALLS PKWY TO 1,190' S OF BLOOMDALE	0.34	100%
	D-31 D-32	G6D(1/3)	HARDIN BLVD (8)	1,190' S OF BLOOMDALE RD TO 3,590' S OF BLOOMDALE RD	0.30	100%
	D-32 D-33	G6D(2/3)	HARDIN BLVD (9)	3,590' S OF BLOOMDALE RD TO WILMETH RD	0.43	50%
	D-33 D-34	G6D(1/3)	HARDIN BLVD (10)	WILMETH RD TO US HIGHWAY 380	1.23	100%
	D-35	G4D	COMMUNITY AVE (1)	TRINITY FALLS PKWY TO 1,275' S OF TRINITY FALLS PKWY	0.24	100%
	D-36	G4D(1/2)	COMMUNITY AVE (2)	1,275' S OF TRINITY FALLS PKWY TO BLOOMDALE RD	0.50	100%
	D-37	M4U(1/2)	COMMUNITY AVE (3)	BLOOMDALE RD TO 2,305' S OF BLOOMDALE RD	0.44	100%
	3	1110(1/2)	Signal	HARDIN BLVD & UNNAMED 5	0	50%
	6		Signal	LAUD HOWELL PKWY & LAKE FOREST DR		50%
	7		Signal	LAUD HOWELL PKWY & UNNAMED A		100%
	8		Signal	LAUD HOWELL PKWY & HARDIN BLVD		100%
	9		Signal	HARDIN BLVD & TRINITY FALLS PKWY		75%
	10		Roundabout	TRINITY FALLS PKWY & COMMUNITY AVE		50%
	11	uo	Interchange Signals	US HIGHWAY 75 & LAUD HOWELL PKWY		50%
	16	ecti.	Signal	BLOOMDALE RD & UNNAMED A		25%
	17	Intersection	Signal	BLOOMDALE RD & HARDIN BLVD		100%
	18	Int	Signal	BLOOMDALE RD & COMMUNITY AVE		100%
	19	⊣ [–] ⊦	Interchange Signals	US HIGHWAY 75 & BLOOMDALE RD		50%
	25] [Roundabout	LAKE FOREST DR & WILMETH RD		50%
	26] [Roundabout	WILMETH RD & UNNAMED A		75%
	27		Roundabout	HARDIN BLVD & WILMETH RD		75%
	32	Ī	Roundabout	HARDIN BLVD & TAYLOR-BURK DR		100%
	36		Under Construction	US HIGHWAY 380 & HARDIN BLVD		50%





Table 2.E. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area E

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	E-1	P6D(1/3)	BLOOMDALE RD (12)	US HIGHWAY 75 TO REDBUD BLVD	0.48	100%
	E-2	P6D(2/3)	BLOOMDALE RD (13)	REDBUD BLVD TO AIRPORT DR	0.51	100%
	E-3	M6D(1/3)	WILMETH RD (10)	US HIGHWAY 75 TO 2,570' E OF REDBUD BLVD	0.78	100%
	E-4	M6D(2/3)	WILMETH RD (11)	2,570' E OF REDBUD BLVD TO STATE HIGHWAY 5	0.41	100%
	E-5	M6D	WILMETH RD (12)	STATE HIGHWAY 5 TO 2,100' E OF SH 5	0.40	100%
	E-6	M6D	WILMETH RD (13)	2,100' E OF SH 5 TO 980' W OF AIRPORT DR	0.25	100%
	E-7	M6D	WILMETH RD (14)	980' W OF AIRPORT DR TO 235' E OF AIRPORT DR	0.23	50%
	E-8	M6D	WILMETH RD (15)	1,150' W OF FM 2933 TO 400' E OF FM 2933	0.29	50%
	E-9	M4D	REDBUD BLVD (1)	BLOOMDALE RD TO 2,930' S OF BLOOMDALE RD	0.55	100%
	E-10	M4D(1/2)	REDBUD BLVD (2)	2,930' S OF BLOOMDALE RD TO WILMETH RD	0.31	100%
	E-11	M6D	LAUD HOWELL PKWY (9)	US HIGHWAY 75 TO 2,620' S OF US HIGHWAY 75	0.50	50%
	E-12	M6D	LAUD HOWELL PKWY (10)	2,620' S OF US HIGHWAY 75 TO BLOOMDALE RD	0.31	100%
	E-13	P6D	LAUD HOWELL PKWY (11)	BLOOMDALE RD TO STATE HIGHWAY 5	0.16	100%
	E-14	M6D	STATE HIGHWAY 5 (1)	4,700' N OF AIRPORT DR TO 3,995' N OF AIRPORT DR	0.13	50%
	E-15	M6D	STATE HIGHWAY 5 (2)	1,915' N OF AIRPORT DR TO US HIGHWAY 380	2.27	100%
E	E-16	P6D	AIRPORT DR (1)	STATE HIGHWAY 5 TO 4,070 S OF STATE HIGHWAY 5	0.77	100%
	E-17	P6D	AIRPORT DR (2)	WILMETH RD TO WOODLAWN RD (N)	0.53	100%
	E-18	P6D	AIRPORT DR (3)	WOODLAWN RD (N) TO WOODLAWN RD (S)	0.29	100%
	E-19	P6D	AIRPORT DR (4)	WOODLAWN RD (S) TO US HIGHWAY 380	0.73	100%
	E-20	P6D(1/3)	UNNAMED C (1)	410' E OF STATE HIGHWAY 5 TO 3,010' E OF STATE HIGHWAY 5	0.49	100%
	E-21	P6D	UNNAMED C (2)	WILMETH RD TO 2,615' S OF WILMETH RD	0.50	50%
	11		Interchange Signals	US HIGHWAY 75 & LAUD HOWELL PKWY		50%
	19		Interchange Signals	US HIGHWAY 75 & BLOOMDALE RD		50%
	20		Signal	BLOOMDALE RD & REDBUD BLVD		100%
	21	Intersection	Signal	LAUD HOWELL PKWY & BLOOMDALE RD		100%
	22	ect	Signal Mod	STATE HIGHWAY 5 & LAUD HOWELL PKWY		100%
	28	ters	Signal	WILMETH RD & REDBUD BLVD		100%
	29	Int	Signal Mod	STATE HIGHWAY 5 & WILMETH RD		100%
	30		Signal	AIRPORT DR & WILMETH RD		50%
	31] [Signal	UNNAMED C & WILMETH RD		50%
	41		Signal Mod	US HIGHWAY 380 & AIRPORT DR		50%

Table 2.F. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area F

No Impact Fee Eligible Roadway Projects





Table 2.G. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area G

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	G-1	M6D(1/3)	VIRGINIA PKWY (1)	COIT RD TO 500' W OF INDEPENDENCE PKWY	0.90	100%
	G-2	M6D(1/3)	VIRGINIA PKWY (2)	500' W OF INDEPENDENCE PKWY TO 325' E OF FORKHORN DR	0.33	50%
	G-3	M6D(1/3)	VIRGINIA PKWY (3)	325' E OF FORKHORN DR TO 935' W OF VIRGINIA HILLS DR	0.28	50%
	G-4	M6D(1/3)	VIRGINIA PKWY (4)	935' W OF VIRGINIA HILLS DR TO CUSTER RD	0.51	100%
	G-5	M6D(1/3)	VIRGINIA PKWY (5)	CUSTER RD TO 410' E OF DANBURY RD	0.49	100%
	G-6	M6D(1/6)	VIRGINIA PKWY (6)	410' E OF DANBURY RD TO VIRGINIA PARKLANDS BLVD	0.39	100%
	G-7	M6D(1/3)	WESTRIDGE BLVD (1)	COIT RD TO 1,635' E OF COIT RD	0.31	50%
	G-8	M6D(1/3)	WESTRIDGE BLVD (2)	1,635' E OF COIT RD TO 2,720' E OF INDEPENDENCE PKWY	1.22	100%
	G-9	M6D(1/3)	WESTRIDGE BLVD (3)	2,720' E OF INDEPENDENCE PKWY TO CUSTER RD	0.50	50%
	H-1, G-10	G6D(1/3)	ELDORADO PKWY (1)	CUSTER RD TO RIDGE RD	2.05	50%
	G-11	M6D(1/3)	COIT RD (1)	US HIGHWAY 380 TO 2,610' S OF VIRGINIA PKWY	1.53	50%
	G-12	M6D(1/3)	COIT RD (2)	WESTRIDGE BLVD TO 2,595' S OF WESTRIDGE BLVD	0.49	50%
	G-13	M6D(1/3)	INDEPENDENCE PKWY (1)	2,380' S OF US HIGHWAY 380 TO 4,465' S OF US HIGHWAY 380	0.39	100%
	G-14	M6D(1/3)	INDEPENDENCE PKWY (2)	VIRGINIA PKWY TO 2,690' S OF WESTRIDGE BLVD	1.52	100%
G	G-15	P6D	CUSTER RD (4)	US HIGHWAY 380 TO WESTRIDGE BLVD	2.03	100%
G	G-16	P6D	CUSTER RD (5)	WESTRIDGE BLVD TO ELDORADO PKWY	1.02	100%
	G-17, I-8	G4D	RIDGE RD (8)	US HIGHWAY 380 TO CREEKSIDE DR	1.30	50%
	33		Signal Mod	US HIGHWAY 380 & STONEBRIDGE DR		50%
	34		Signal	US HIGHWAY 380 & FOREST RIDGE LN		50%
	37		Signa1	STONEBRIDGE DR & LACIMA DR		100%
	38] [Signal	RIDGE RD & HABERSHAM WAY		50%
	43	u	Signal	INDEPENDENCE PKWY & VIRGINIA PKWY		50%
	44	Intersection	Under Construction	VIRGINIA PKWY & RIDGE RD		50%
	47	ısec	Signal	INDEPENDENCE PKWY & WESTRIDGE BLVD		100%
	48	nte	Under Construction	CUSTER RD & WESTRIDGE BLVD		75%
	49		Roundabout	STONEBRIDGE DR & GLEN OAKS DR		100%
	50		Roundabout	RIDGE RD & GLEN OAKS DR		50%
	55		Signal	STONEBRIDGE DR & ALMA DR		100%
	56		Signal	RIDGE RD & RUSH CREEK RD		50%
	57		Signal	RIDGE RD & BERKSHIRE RD		50%

Table 2.H. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area H

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	H-1, G-10	G6D(1/3)	ELDORADO PKWY (1)	CUSTER RD TO RIDGE RD	2.05	50%
	H-2	M4D(1/2)	SILVERADO TRL (1)	CUSTER RD TO BURNETT DR	0.37	100%
	H-3	M4D	SILVERADO TRL (2)	ALMA DR TO ALFALFA DR	0.22	100%
	H-4	P6D(1/3)	STACY RD (1)	CUSTER RD TO RIDGE RD	2.03	100%
	H-5	P6D	CUSTER RD (6)	ELDORADO PKWY TO STONEBRIDGE DR	0.39	100%
	H-6	G4D	ALMA DR (1)	805' S OF BEAVER CREEK DR TO SILVERADO TRL	0.37	100%
	H-7	M6D(1/3)	ALMA DR (2)	SILVERADO TRL TO STACY RD	0.50	100%
Н	H-8, I-9	M6D(1/3)	RIDGE RD (9)	MCKINNEY RANCH PKWY TO STACY RD	0.69	50%
	H-9	M6D(1/3)	MCKINNEY RANCH PKWY (1)	RIDGE RD TO STACY RD	0.77	100%
	65		Signal	CUSTER RD & SILVERADO TRL		50%
	66	ion	Signal	MCKINNEY RANCH PKWY & SILVERADO TRL		100%
	71	ecti	Signal	STACY RD & MCKINNEY RANCH PKWY		100%
	75	Intersection	Signal	CUSTER RD & PARADISE DR		50%
	76		Signal	STACY RD & COLLIN MCKINNEY PKWY		50%
	77		Signal	ALMA DR & HENNEMAN WAY		100%





Table 2.I. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area I

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	I-1	M6D	VIRGINIA PKWY (7)	1035' E OF RIDGE RD TO 1355' W OF HARDIN BLVD	1.43	100%
	I-2	M6D	VIRGINIA PKWY (8)	1355' W OF HARDIN BLVD TO HARDIN BLVD	0.26	100%
	I-3	G6D(1/3)	ELDORADO PKWY (2)	RIDGE RD TO HARDIN BLVD	2.07	100%
	I-4	M6D(1/3)	MCKINNEY RANCH PKWY (2)	RIDGE RD TO HARDIN BLVD	1.80	100%
	I-5	G4D	COLLIN MCKINNEY PKWY (2)	LAKE FOREST DR TO COTTONWOOD CREEK	0.31	100%
	I-6	G4D(1/2)	COLLIN MCKINNEY PKWY (3)	COTTONWOOD CREEK TO 1110' E OF TINA DR	0.55	100%
	I-7	G4D	COLLIN MCKINNEY PKWY (4)	1110' E OF TINA TO HARDIN BLVD	0.19	100%
	G-17, I-8	G4D	RIDGE RD (8)	US HIGHWAY 380 TO CREEKSIDE DR	1.30	50%
	H-8, I-9	M6D(1/3)	RIDGE RD (9)	MCKINNEY RANCH PKWY TO STACY RD	0.69	50%
	I-10, J-6	G6D(1/3)	HARDIN BLVD (11)	US HIGHWAY 380 TO VIRGINIA PKWY	1.58	50%
	I-11, J-7	G6D(1/3)	HARDIN BLVD (12)	VIRGINIA PKWY TO MCKINNEY RANCH PKWY	2.64	50%
	35		Signal	US HIGHWAY 380 & AUBURN HILLS PKWY		50%
	36		Under Construction	US HIGHWAY 380 & HARDIN BLVD		25%
I	38		Signal	RIDGE RD & HABERSHAM WAY		50%
	44		Under Construction	VIRGINIA PKWY & RIDGE RD		50%
	45		Signal	VIRGINIA PKWY & JOPLIN DR		100%
	46		Signal	VIRGINIA PKWY & VILLAGE DR		100%
	50	ion	Roundabout	RIDGE RD & GLEN OAKS DR		50%
	51	Intersection	Roundabout	LAKE FOREST DR & GLEN OAKS DR		100%
	56	ters	Signal	RIDGE RD & RUSH CREEK RD		50%
	57	In	Signal	RIDGE RD & BERKSHIRE RD		50%
	58		Signal	HARDIN BLVD & MAVERICK TRL		50%
	59	- - -	Signal	ELDORADO PKWY & WOODSON DR		100%
	60		Signal	ELDORADO PKWY & HIGHLANDS DR		100%
	72		Signal	LAKE FOREST DR & COLLIN MCKINNEY PKWY		100%
	73		Signal	HARDIN BLVD & COLLIN MCKINNEY PKWY		50%
	76		Signal	STACY RD & COLLIN MCKINNEY PKWY		50%

Table 2.J. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area J

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	J-1	M4D	WHITE AVE (1)	HARDIN BLVD TO BOIS D'ARC RD	0.17	100%
	J-2	M4D	WHITE AVE (2)	BOIS D'ARC RD TO COMMUNITY AVE	0.93	100%
	J-3	M6D	VIRGINIA PKWY (9)	HARDIN BLVD TO US HIGHWAY 75	1.60	100%
	J-4	G6D(1/3)	ELDORADO PKWY (3)	710' E OF US HIGHWAY 75 TO 1,180' E OF BARRANCA WAY	1.08	100%
	J-5	M3U	COLLIN MCKINNEY PKWY (5)	2,100' E OF HARDIN BLVD TO MCKINNEY RANCH PKWY	0.33	100%
	I-10, J-6	G6D(1/3)	HARDIN BLVD (11)	US HIGHWAY 380 TO VIRGINIA PKWY	1.58	50%
	I-11, J-7	G6D(1/3)	HARDIN BLVD (12)	VIRGINIA PKWY TO MCKINNEY RANCH PKWY	2.64	50%
	J-8	M4D	MEDICAL CENTER DR	STATE HIGHWAY 121 TO 1,685' S OF STATE HIGHWAY 121	0.32	100%
	J-9, K-7	M6D	STATE HIGHWAY 5 (4)	640' S OF HARRY MCKILLOP BLVD / FM 546 TO STATE	0.47	50%
J	J-10, K-8	M4D	STATE HIGHWAY 5 (5)	STATE HIGHWAY 121 TO 3,525' S OF STATE HIGHWAY 121	0.67	50%
J	J-11	M4D	STATE HIGHWAY 5 (6)	3,525' S OF STATE HIGHWAY 121 TO 4,520' S OF STATE	0.19	50%
	36		Under Construction	US HIGHWAY 380 & HARDIN BLVD		25%
	39		Signal	WHITE AVE & JORDAN RD		100%
	58	п	Signal	HARDIN BLVD & MAVERICK TRL		50%
	61	tio	Intersection Improvements	ELDORADO PKWY & CRAIG DR		100%
	62	rsec	Signal	STATE HIGHWAY 5 & STEWART RD		50%
	67	Intersection	Signal	MCKINNEY RANCH PKWY & COLLIN MCKINNEY PKWY		100%
	68		Signal	COLLIN MCKINNEY PKWY & CRAIG DR		100%
	69		Signal	STATE HIGHWAY 5 & ENTERPRISE DR		50%
	73		Signal	HARDIN BLVD & COLLIN MCKINNEY PKWY		50%





Table 2.K. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area K

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	K-1	2UO	VIRGINIA STREET	225' W OF AIRPORT DR TO AIRPORT DR	0.04	100%
	K-2	G6D(1/3)	ELDORADO PKWY (4)	1,180' E OF BARRANCA WAY TO STATE HIGHWAY 5	0.40	100%
	K-3	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (1)	STATE HIGHWAY 121 TO AIRPORT DR	1.46	100%
	K-4, L-1	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (2)	AIRPORT DR TO 980' E OF AIRPORT DR	0.19	50%
	K-5, L-2	P6D	HARRY MCKILLOP BLVD / FM 546 (3)	975' E OF AIRPORT DR TO 510' W OF HARRY MCKILLOP BLVD / FM 546 (N)	0.60	50%
	K-6	M6D	STATE HIGHWAY 5 (3)	INDUSTRIAL BLVD TO 640' S OF HARRY MCKILLOP BLVD /	0.40	100%
	J-9, K-7	M6D	STATE HIGHWAY 5 (4)	640' S OF HARRY MCKILLOP BLVD / FM 546 TO STATE	0.47	50%
K	J-10, K-8	M4D	STATE HIGHWAY 5 (5)	STATE HIGHWAY 121 TO 3,525' S OF STATE HIGHWAY 121	0.67	50%
	K-9, L-6	P6D(1/3)	AIRPORT DR (5)	US HIGHWAY 380 TO 470' N OF HARRY MCKILLOP BLVD / FM	2.63	50%
	K-10, L-7	P6D	AIRPORT DR (6)	470' N OF HARRY MCKILLOP BLVD / FM 546 TO HARRY	0.09	50%
	40		Signal	STATE HIGHWAY 5 & SMITH ST		100%
	41		Signal Mod	US HIGHWAY 380 & AIRPORT DR		50%
	52	ion	Roundabout	WILSON CREEK PKWY & PARK VIEW AVE		100%
	53	ect	Signal	WILSON CREEK PKWY & COLLEGE ST		100%
	54	Intersection	Signal	AIRPORT DR & ELM ST		50%
	62		Signal	STATE HIGHWAY 5 & STEWART RD		50%
	63		Signal	HARRY MCKILLOP BLVD / FM 546 & AIRPORT DR		75%
	69		Signal	STATE HIGHWAY 5 & ENTERPRISE DR		50%

Table 2.L. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area L


Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	K-4, L-1	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (2)	AIRPORT DR TO 980' E OF AIRPORT DR	0.19	50%
	K-5, L-2	P6D	HARRY MCKILLOP BLVD / FM 546 (3)	975' E OF AIRPORT DR TO 510' W OF HARRY MCKILLOP BLVD / FM 546 (N)	0.60	50%
	L-3	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (1)	510' W OF HARRY MCKILLOP BLVD / FM 546 (N) TO 1,335' E OF HARRY MCKILLOP BLVD / FM 546 (N)	0.35	100%
	L-4	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (2)	3,480' W OF UNNAMED D TO UNNAMED D	0.66	100%
	L-5	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (1)	HARRY MCKILLOP BLVD / FM 546 (S) TO 1,865' E OF HARRY MCKILLOP BLVD / FM 546 (S)	0.35	100%
	K-9, L-6	P6D(1/3)	AIRPORT DR (5)	US HIGHWAY 380 TO 470' N OF HARRY MCKILLOP BLVD / FM 546	2.63	50%
L	K-10, L-7	P6D	AIRPORT DR (6)	470' N OF HARRY MCKILLOP BLVD / FM 546 TO HARRY MCKILLOP BLVD / FM 546	0.09	50%
	L-8	P6D	UNNAMED C (3)	US HIGHWAY 380 TO 2,435' S OF US HIGHWAY 380	0.46	100%
	L-9, M-5	P6D	UNNAMED C (4)	2,525' N OF HARRY MCKILLOP BLVD / FM 546 TO 1,230' N OF HARRY MCKILLOP BLVD / FM 546	0.25	50%
	L-10, M-6	P6D	UNNAMED C (5)	HARRY MCKILLOP BLVD / FM 546 (N) TO 705' S OF HARRY MCKILLOP BLVD / FM 546 (S)	0.87	50%
	41		Signal Mod	US HIGHWAY 380 & AIRPORT DR		50%
	42	Ę	Signal	US HIGHWAY 380 & UNNAMED C		50%
	54	ctio	Signal	AIRPORT DR & ELM ST		50%
	63	Intersection	Signal	HARRY MCKILLOP BLVD / FM 546 & AIRPORT DR		75%
	70		Signal	HARRY MCKILLOP BLVD / FM 546 (S) & HARRY MCKILLOP BLVD / FM 546 (N)		100%
	74		Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (S)		50%





Table 2.M. 10-Year Roadway Impact Fee Roadway Improvements Plan – Service Area M

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area
	M-1	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (2)	110' E OF UNNAMED C TO 300' E OF UNNAMED C	0.04	50%
	M-2	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (3)	1,700' N OF HARRY MCKILLOP BLVD / FM 546 TO 2,050' N OF HARRY MCKILLOP BLVD / FM 546	0.07	50%
	M-3	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (4)	405' N OF HARRY MCKILLOP BLVD / FM 546 TO 675' N OF HARRY MCKILLOP BLVD / FM 546	0.05	50%
M	M-4	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (3)	UNNAMED C TO 695' E OF UNNAMED C	0.13	100%
	L-9, M-5	P6D	UNNAMED C (4)	2,525' N OF HARRY MCKILLOP BLVD / FM 546 TO 1,230' N OF HARRY MCKILLOP BLVD / FM 546	0.25	50%
	L-10, M-6	P6D	UNNAMED C (5)	HARRY MCKILLOP BLVD / FM 546 (N) TO 705' S OF HARRY MCKILLOP BLVD / FM 546 (S)	0.87	50%
	64	Inter-	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (N)		50%
	74	section	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (S)		50%







IV. METHODOLOGY FOR ROADWAY IMPACT FEES

A. Service Areas

The thirteen (13) service areas used in the 2019 Roadway Impact Fee Update are shown in the previously referenced Exhibit 1. These service areas cover the entire corporate boundary of the City of McKinney. Chapter 395 of the Texas Local Government Code specifies that "the service area is limited to an area within the corporate boundaries of the political subdivision and shall not exceed six (6) miles." The service areas in the 2019 Roadway Impact Fee Update are approximately the same as in the previous impact fee update (adopted in 2013) with some minor modifications to accommodate recent annexations and the realignment of roadways that were formerly used as boundaries.

B. Service Units

The "service unit" is a measure of consumption or use of the capital facilities by new development. In other words, it is the unit of measure used in the 2019 Roadway Impact Fee Update to quantify the supply and demand for roads in the City. For transportation purposes, the service unit is defined as a vehicle-mile. Below is the definition for vehicle-mile.

<u>Vehicle-Mile</u>: The capacity consumed in a single lane in the PM peak hour by a vehicle making a trip one mile in length. The PM Peak is used as the basis for transportation planning and the estimation of trips caused by new development.

<u>Total Vehicle-Miles of Supply</u>: Based on the total length (miles), number of lanes, and capacity (vehicles per hour) provided by the Master Thoroughfare Plan (see Appendix B).

<u>Total Vehicle-Miles of Demand</u>: Based on the 10-year growth projections (Pg. 47). The demand is equal to PM Trip Rate (trips) * Trip Length (miles).

The capacity values used in the 2019 Roadway Impact Fee Update are based upon generally accepted thoroughfare capacity criteria. Tables 3A and 3B show the service volumes as a function of the facility classification and type.





For "Partial Widening" projects, no existing volume was assumed and only the additional capacity of the new lanes were assumed for the calculation of impact fees, unless a previous contribution from the City existed. If this was the case, the existing volume was accounted for along with the ultimate cross section.





Table 3A. Service Volumes for Proposed Facilities

(used in Appendix B – Roadway Impact Fee RIP Service Units of Supply)

Droposed			Hourly Vehicle-Mile
Proposed Crass Section	Facility Classification	Median Configuration	Capacity per Lane-Mile of
Cross Section			Roadway Facility
G6D	Greenway Arterial	Divided	700
P6D	Principal Arterial	Divided	780
M6D	Major Arterial	Divided	700
G4D	Greenway Arterial	Divided	700
M4D	Minor Arterial	Divided	700
M4U	Minor Arterial	Undivided	525
M3U	Minor Arterial	Undivided	550
2UO	Town Thoroughfare	Undivided	500

Table 3B. Service Volumes for Existing Facilities

(used in Appendix C – Existing Roadway Facilities Inventory)

Roadway Type	Description	Hourly Vehicle-Mile Capacity per Lane-Mile of Roadway Facility
2UG	Rural Two-lane Undivided Cross-Section (i.e., gravel, dirt, etc.)	150
2U	Two-lane Undivided	475
2UO	Two-lane Undivided One-way	475
3U	Three-lane Undivided (TWLTL)	525
4U	Four-lane Undivided	525
4D	Four-lane Divided	700
5U	Five-lane Undivided (TWLTL)	625
5D	Five-lane Divided	700
6D	Six-lane Divided	780





C. Cost Per Service Unit

A fundamental step in the impact fee process is to establish the cost for each service unit. In the case of the Roadway Impact Fee, this is the cost for each vehicle-mile of travel. Thus, it is the cost to construct a roadway (lane-mile) needed to accommodate a vehicle-mile of travel. The cost per service unit is calculated for each service area based on the roadway projects within that service area.

The second component of the cost per service unit is the determination of the number of service units in each service area. This number is the measure of the growth in transportation demand that is projected to occur in the ten-year period. Chapter 395 requires that Impact Fees be assessed only to pay for growth projected to occur in the city limits within the next ten-years. As noted earlier, the units of demand are vehicle-miles of travel.

D. Roadway Impact Fee RIP Costing Methodology

All of the project costs for a facility which serves the overall transportation system are eligible to be included in the RIF RIP. Chapter 395 of the Texas Local Government Code specifies that the allowable costs are "...including and limited to the:

- 1. Construction contract price;
- 2. Surveying and engineering fees;
- 3. Land acquisition costs, including land purchases, court awards and costs, attorney's fees, and expert witness fees; and
- 4. Fees actually paid or contracted to be paid to an independent qualified engineer or financial consultant preparing or updating the Roadway Improvements Plan who is not an employee of the political subdivision."

The engineer's opinion of the probable costs of the projects in the RIF RIP is based, in part, on the calculation of a unit cost of construction. This means that a cost per linear foot of roadway is calculated based on an average price for the various components of roadway construction. This allows the probable cost to be determined by the type of facility being constructed, the number of lanes, and the length of the project. The cost for location specific items such as bridges, drainage structures, railroad crossings, or any other special






components are added to each project, as appropriate. In addition, projects in which the City has contributed a portion, or all, of the project costs have been included in the RIP as lump sum projects. For future projects on the state highway system, a separate costing methodology was utilized that incorporated design criteria and unit prices unique to state highway projects. Based upon discussions with City of McKinney staff, it was determined that on average, 50% of TxDOT projects would be funded by the City. The following is a detailed description of the costing worksheet/ methodology for the Roadway Impact Fee RIP.

1. Overview of Roadway Impact Fee RIP Costing Worksheets

For each project a specific costing worksheet was developed (see Appendix A). Each worksheet contains project information, construction pay items, construction component allowances, and a summary of costs and allowances. An example of the costing sheets can be seen below.

City of McKinney

Kimley-Hom and Associates, Inc.



specific project

used for any future Capital Improvement Planning within the City of McKinney

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a





2. Project Information

In order to correctly estimate the cost of a roadway project, several attributes are first identified:

- <u>Project Number</u> Identifies which Service Area the project is in with a corresponding number. The corresponding number does not represent any prioritizations and is used only to identify projects. For example, Project E-7 is in Service Area E and is the 7th project on the list.
- Name A unique identifier for each project.
- Limits Represents the beginning and ending location for each project.
- Impact Fee Class The costing class to be used in the analysis. The impact fee class provides the width and depth for the various elements in the facility cross section. The construction costs are variable, based on the proposed Master Thoroughfare Plan classification of the roadway. Additional classifications are utilized in cases where a portion of the facility currently exists, and the road is only to be widened. The following notations are used for these projects:
 - o "(1/6)" for future six-lane facilities where one additional lane is needed;
 - o "(1/3)" for future six-lane facilities where two additional lanes are needed;
 - o "(1/2)" for facilities where half the facility still needs to be constructed;
 - o "(2/3)" for future six-lane facilities where four additional lanes are needed.
- <u>Thoroughfare Class</u> The ultimate classification according to the Master Thoroughfare Plan.
- <u>Description</u> Describes the type of project identified. Includes; New, Widening, Partial Widening, and Previously Completed. Other specialized situations are noted such as previous City contributions.
- <u>Length (ft)</u> The distance measured in feet that is used to cost out the project.
- <u>Service Area(s)</u> Represents the service area where the project is located. Multiple service areas will be listed if the project lies along a service area boundary.





3. Construction Cost Pay Items

A typical roadway project consists of a number of costs, including the following: planning, survey, design engineering, permitting, right-of way acquisition, construction, and inspection. While the construction cost component of a project may actually consist of approximately 100 various pay items, a simplified approach was used for developing the conceptual level project costs. The pay items for both City and TxDOT roads are shown in Table 4.

Table 4. Construction Cost Pay Items

City Pay Items	TxDOT Pay Items
Unclassified Street Excavation	 Unclassified Street Excavation
 Lime Treated Subgrade 	 Lime Treated Subgrade
Concrete Pavement	 HMAC Underlayment
Top Soil	Concrete Pavement
 Curb and Gutter 	Top Soil
Turn Lanes and Median Openings	Curb and Gutter
Moisture Conditioning	Turn Lanes and Median Openings

4. Construction Component Allowances

A percentage of the paving construction cost is allotted for various major construction component allowances, as appropriate. These allowances include traffic control, pavement markings, drainage, water/sewer adjustments, turf/erosion control, and illumination. If the project type is "New," traffic control was set to 1% and water/sewer adjustments were set to 0%. If the project is a "Partial Widening" drainage, water/sewer adjustments, and illumination were set to 0%. It is to be noted that this percentage is taken from the roadway construction cost.

An allotment of 5% was given for mobilization and site preparation based on the paving and allowance subtotal. In addition, contingency of 15% was given based on the construction cost total.





Lump sum dollar allowances are provided for special drainage structures and railroad crossings. The dollar amount for the drainage structure is based on project type and crossing length and has a minimum amount of \$250,000. An allotment of \$500,000 for railroad crossings were assumed.

5. RIP Allowances

To determine the total Impact Fee project cost, 20% of the construction with contingency cost is added for engineering, surveying, and testing. An additional allowance is given for right-of-way (ROW)/easement acquisition. New projects assumed a 35% allotment, Widening projects assumed a 20% allotment, and Partial Widenings assumed none. Additionally, City project cost contributions from 2008-2012 and from 2012-2019 were included, if applicable.

6. Impact Fee Project Cost

The Impact Fee Project Cost Total is then the Roadway Construction Items, Major Construction Component Allowances, and RIP Allowances. Based upon discussions with City of McKinney staff, TxDOT projects were included with a projected contribution of fifty percent (50%) of the total project. In addition, some projects have been included based on cost estimates from the City.

E. Summary of Roadway Impact Fee RIP Costs

Tables 5.A – 5.M are the 10-Year RIF RIP project lists for each service area with planning level project costs. Individual project cost worksheets can be seen in Appendix A, Conceptual Level Project Cost Projections. It should be noted that these tables reflect only conceptual-level opinions or assumptions regarding the portions of future project costs that are potentially recoverable through impact fees. Actual project costs are likely to change with time and are dependent on market and economic conditions that cannot be predicted.

The RIF RIP establishes the list of projects for which Impact Fees may be utilized. Projects not included in the RIF RIP are not eligible to receive impact fee funding. The cost projections utilized in this study should not be utilized for the City's construction CIP.





Table 5.A – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area A

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area	Total Project Cost	Cost in Service Area	
	A-1, C-1	M6D	UNNAMED 5 (1)	635' W OF STONEBRIDGE DR TO CR 168	0.63	50%	\$ 7,715,900	\$ 3,857,950	
	A-2, D-1	M6D	UNNAMED 5 (3)	CR 168 TO 1,560' E OF CR 168	0.30	50%	\$ 7,517,500	\$ 3,758,750	
A	A-3	G4D	STONEBRIDGE DR (1)	2,635' N OF UNNAMED 5 TO UNNAMED 5	0.50	50%	\$ 4,679,450	\$ 2,339,725	
				Servi	ce Area	Project	Cost Subtotal	\$ 9,956,425	
	Roadway Impact Fee Undate Cost (Per Service Area)								

Total Cost in SERVICE AREA A \$ 9,968,1

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

Table 5.B – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area B

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area	Total Project Cost	Cost in Service Area		
	B-1, D-2	M6D	UNNAMED 5 (4)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD	0.43	50%	\$ 4,904,200	\$ 2,452,100		
	B-2	G6D	HARDIN BLVD (1)	CR 204 TO CR 206	0.08	50%	\$ 877,800	\$ 438,900		
	B-3	G6D	HARDIN BLVD (2)	1,670' N OF OLYMPIC TO 730' S OF OLYMPIC	0.45	50%	\$ 4,837,000	\$ 2,418,500		
- D	B-4	G6D	HARDIN BLVD (3)	1,940' N OF UNNAMED 5 TO UNNAMED 5	0.37	100%	\$ 4,090,450	\$ 4,090,450		
В	1	Inter-	Signal	HARDIN BLVD & OLYMPIC		50%	\$ 300,000	\$ 150,000		
	3	section	Signal	HARDIN BLVD & UNNAMED 5		50%	\$ 300,000	\$ 150,000		
				Servi	ce Area	Project	Cost Subtotal	\$ 9,699,950		
	Roadway Impact Fee Update Cost (Per Service Area) \$									

Total Cost in SERVICE AREA B \$ 9,711,6

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.





Table 5.C – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area C

Service	Proj. #	Class	Roadway	Limits	Length	% In Service		Cost in Service
Area	1103.	CALIS	Atoma may	Zamiko	(mi)	Area	Cost	Area
	A-1, C-1	M6D	UNNAMED 5 (1)	635' W OF STONEBRIDGE DR TO CR 168	0.63	50%	\$ 7,715,900	\$ 3,857,950
	C-2	M6D	UNNAMED 5 (2)	RIDGE RD TO 1,505' E OF RIDGE RD	0.29	50%	\$ 3,137,400	\$ 1,568,700
	C-3	G6D	LAUD HOWELL PKWY (1)	695' W OF CUSTER RD TO CUSTER RD	0.13	50%	\$ 665,000	\$ 332,500
	C-4	G6D	LAUD HOWELL PKWY (2)	CUSTER RD TO 1,225' E OF CUSTER RD	0.23	100%	\$ 1,171,800	\$ 1,171,800
	C-5	G6D	LAUD HOWELL PKWY (3)	1,225' E OF CUSTER RD TO 2,070' E OF CUSTER RD	0.16	50%	\$ 808,500	\$ 404,250
	C-6	G6D	LAUD HOWELL PKWY (4)	840' E OF STONEBRIDGE DR TO 2,905' E OF STONEBRIDGE DR	0.39	50%	\$ 2,859,500	\$ 1,429,750
	C-7	G6D	LAUD HOWELL PKWY (5)	1,985' W OF RIDGE RD TO 1,230' E OF RIDGE RD	0.61	50%	\$ 3,073,000	\$ 1,536,500
	C-8	P6D	BLOOMDALE RD (1)	CUSTER RD TO 1,310' E OF CUSTER RD	0.25	100%	\$ 3,179,400	\$ 3,179,400
	C-9	P6D	BLOOMDALE RD (2)	1,310' E OF CUSTER RD TO 2,030' W OF STONEBRIDGE DR	0.40	50%	\$ 4,838,400	\$ 2,419,200
	C-10	P6D	BLOOMDALE RD (3)	2,030' W OF STONEBRIDGE DR TO 3,245' E OF STONEBRIDGE DR	1.00	100%	\$ 13,314,000	\$ 13,314,000
	C-11	P6D	BLOOMDALE RD (4)	3,245' E OF STONEBRIDGE DR TO 695' W OF RIDGE RD	0.26	50%	\$ 3,292,800	\$ 1,646,400
	C-12	P6D	BLOOMDALE RD (5)	695' W OF RIDGE RD TO RIDGE RD	0.13	100%	\$ 1,453,200	\$ 1,453,200
	C-13	P6D(2/3)	BLOOMDALE RD (6)	3,400' W OF LAKE FOREST DR TO LAKE FOREST DR	0.64	50%	\$ 4,650,800	\$ 2,325,400
	C-14	G4D	WILMETH RD (1)	3,725' W OF STONEBRIDGE DR TO 815' E OF STONEBRIDGE DR	0.86	100%	\$ 8,845,850	\$ 8,845,850
	C-15	G4D	WILMETH RD (2)	815' E OF STONEBRIDGE DR TO 995' W OF RIDGE RD	0.63	50%	\$ 6,200,600	\$ 3,100,300
	C-16	G4D(1/2)	WILMETH RD (3)	RIDGE RD TO 585' E OF RIDGE RD	0.11	100%	\$ 1,593,000	\$ 1,593,000
	C-17	G4D(1/2)	WILMETH RD (4)	1,095' E OF RIDGE RD TO 1,365' E OF RIDGE RD	0.05	100%	\$ 708,000	\$ 708,000
	C-18	P6D	CUSTER RD (1)	1,855' N OF LAUD HOWELL PKWY TO LAUD HOWELL PKWY	0.35	50%	\$ 1,834,000	\$ 917,000
	C-19	P6D	CUSTER RD (2)	LAUD HOWELL PKWY TO 2,775 N OF BLOOMDALE RD	0.53	100%	\$ 2,869,825	\$ 2,869,825
	C-20	P6D	CUSTER RD (3)	2,655 N OF BLOOMDALE RD TO 375' N OF WILMETH RD	1.19	50%	\$ 8,071,300	\$ 4,035,650
	C-21	G4D	STONEBRIDGE DR (2)	UNNAMED 5 TO 1,280' S OF UNNAMED 5	0.24	100%	\$ 2,763,650	\$ 2,763,650
	C-22	G4D	STONEBRIDGE DR (3)	1,570' S OF LAUD HOWELL PKWY TO 280' S OF WILMETH RD	1.51	100%	\$ 14,194,900	\$ 14,194,900
	C-23	G4D	STONEBRIDGE DR (4)	280' S OF WILMETH RD TO 1,195' S OF WILMETH RD	0.17	50%	\$ 2,117,300	\$ 1,058,650
	C-24	G4D	STONEBRIDGE DR (5)	1,195' S OF WILMETH RD TO 5,555' S OF WILMETH RD	0.83	100%	\$ 8,232,050	\$ 8,232,050
C	C-25	G4D	STONEBRIDGE DR (6)	580' N OF US HIGHWAY 380 TO US HIGHWAY 380	0.11	100%	\$ 1,030,750	\$ 1,030,750
	C-26	M6D	RIDGE RD (1)	UNNAMED 5 TO 1,485' S OF UNNAMED 5	0.28	50%	\$ 3,095,400	\$ 1,547,700
	C-27	M6D	RIDGE RD (2)	LAUD HOWELL PKWY TO BAXTER WELL RD	0.59	100%	\$ 7,267,950	\$ 7,267,950
	C-28	M6D	RIDGE RD (3)	BAXTER WELL RD TO 2,160' S OF BLOOMDALE RD	0.83	50%	\$ 9,144,800	\$ 4,572,400
	C-29	M6D	RIDGE RD (4)	1,590' N OF WILMETH RD TO WILMETH RD	0.30	50%	\$ 3,756,200	\$ 1,878,100
	C-30	M6D(1/3)	RIDGE RD (5)	WILMETH RD TO 2,280' S OF WILMETH RD	0.43	100%	\$ 7,411,200	\$ 7,411,200
	C-31	M6D(1/3)	RIDGE RD (6)	1,860' N OF US HIGHWAY 380 TO 1,390' N OF US HIGHWAY 380	0.09	50%	\$ 1,455,000	\$ 727,500
	C-32	M6D(1/3)	RIDGE RD (7)	775' N OF US HIGHWAY 380 TO US HIGHWAY 380	0.15	100%	\$ 2,857,200	\$ 2,857,200
	C-33	M6D(1/3)	LAKE FOREST DR (2)	BLOOMDALE RD TO WILMETH RD	1.02	50%	\$ 5,008,981	\$ 2,504,491
	C-34, D-22	M6D(1/3)	LAKE FOREST DR (3)	WILMETH RD TO US HIGHWAY 380	0.98	50%	\$ 2,350,800	\$ 1,175,400
	2		Signal	RIDGE RD & UNNAMED 5		25%	\$ 300,000	\$ 75,000
	4] [Signal	LAUD HOWELL PKWY & CUSTER RD		75%	\$ 300,000	\$ 225,000
	5] [Signal	LAUD HOWELL PKWY & RIDGE RD		50%	\$ 300,000	\$ 150,000
	12	l l	Intersection Improvement	CUSTER RD & BLOOMDALE RD		50%	\$ 150,000	\$ 75,000
	13	l l	Signal	BLOOMDALE RD & STONEBRIDGE DR		100%	\$ 300,000	\$ 300,000
	14	l l	Signal	BLOOMDALE RD & RIDGE RD		50%	\$ 300,000	\$ 150,000
	15	Intersection	Signal	BLOOMDALE RD & LAKE FOREST DR		25%	\$ 300,000	\$ 75,000
[23] [Signal	STONEBRIDGE DR & WILMETH RD		100%	\$ 300,000	\$ 300,000
	24] [Signal	WILMETH RD & RIDGEKNOLL AVE		100%	\$ 300,000	\$ 300,000
	25] [Roundabout	LAKE FOREST DR & WILMETH RD		50%	\$ 1,830,000	\$ 915,000
	33] [Signal Mod	US HIGHWAY 380 & STONEBRIDGE DR		50%	\$ 150,000	\$ 75,000
	34	[Signal	US HIGHWAY 380 & FOREST RIDGE LN		50%	\$ 300,000	\$ 150,000
	35		Signal	US HIGHWAY 380 & AUBURN HILLS PKWY		50%	\$ 300,000	\$ 150,000
[Servi	ce Area	Project	Cost Subtotal	\$ 116,870,616
				Roadway Impact Fee U	pdate Co	st (Per S	Service Area)	\$ 11,692

Total Cost in SERVICE AREA C \$ 116,882,308

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.





Table 5.D – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area D

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area	Total Project Cost	Cost in Service Area
	A-2, D-1	M6D	UNNAMED 5 (3)	CR 168 TO 1,560' E OF CR 168	0.30	50%	\$ 7,517,500	\$ 3,758,750
	B-1, D-2	M6D	UNNAMED 5 (4)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD	0.43	50%	\$ 4,904,200	\$ 2,452,100
	D-3	G6D	LAUD HOWELL PKWY (6)	LAKE FOREST DR TO 1860' E OF HARDIN BLVD	2.65	100%	\$ 39,497,100	\$ 39,497,100
	D-4	G6D	LAUD HOWELL PKWY (7)	4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY FALLS	0.74	100%	\$ 8,774,550	\$ 8,774,550
	D-5	G6D(1/3)	LAUD HOWELL PKWY (8)	240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75	0.38	100%	\$ 2,220,027	\$ 2,220,027
	D-6	G4D	TRINITY FALLS PKWY (1)	HARDIN BLVD TO 1,910' E OF HARDIN BLVD	0.36	100%	\$ 3,243,800	\$ 3,243,800
	D-7	G4D	TRINITY FALLS PKWY (2)	1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD	0.14	50%	\$ 1,300,600	\$ 650,300
	D-8	G4D	TRINITY FALLS PKWY (3)	COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY	0.34	50%	\$ 5,976,800	\$ 2,988,400
	D-9	G4D	TRINITY FALLS PKWY (4)	LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY	0.42	100%	\$ 8,418,050	\$ 8,418,050
	D-10	M6D(1/3)	TRINITY FALLS PKWY (5)	4,275' N OF WESTON RD TO LAUD HOWELL PKWY	1.05	100%	\$ 7,622,400	\$ 7,622,400
	D-11	P6D	BLOOMDALE RD (7)	1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	0.34	50%	\$ 3,799,600	\$ 1,899,800
	D-12	P6D	BLOOMDALE RD (8)	1,485' E OF CR 1006 TO 1,215' W OF CR 1007	0.29	100%	\$ 3,206,000	\$ 3,206,000
	D-13	P6D	BLOOMDALE RD (9)	1,225' W OF CR 1007 TO CR 1007	0.23	50%	\$ 3,001,600	\$ 1,500,800
	D-14	P6D(2/3)	BLOOMDALE RD (10)	CR 1007 TO HARDIN BLVD	0.37	100%	\$ 5,885,810	\$ 5,885,810
	D-15	P6D(1/3)	BLOOMDALE RD (11)	HARDIN BLVD TO COMMUNITY AVE	0.49	100%	\$ 5,165,390	\$ 5,165,390
	D-16	G4D	WILMETH RD (5)	LAKE FOREST DR TO UNNAMED A	0.90	50%	\$ 10,991,050	\$ 5,495,525
	D-17	G4D	WILMETH RD (6)	UNNAMED A TO 825' E OF UNNAMED A	0.16	100%	\$ 1,401,400	\$ 1,401,400
	D-18 D-19	G4D(1/2) G4D	WILMETH RD (7) WILMETH RD (8)	825' E OF TAYLOR-BURK DR TO 1,380' E OF TAYLOR-BURK DR 1,380' E OF TAYLOR-BURK DR TO HARDIN BLVD	0.11	100%	\$ 411,600 \$ 3,803,800	\$ 411,600 \$ 1,901,900
	D-19 D-20	M6D(1/3)	WILMETH RD (8) WILMETH RD (9)	HARDIN BLVD TO US HIGHWAY 75	1.16	100%	\$ 3,803,800	\$ 1,901,900
	D-20 D-21	G6D	LAKE FOREST DR (1)	LAUD HOWELL PKWY TO 3,200' S OF LAUD HOWELL PKWY	0.61	50%	\$ 6,448,400	\$ 2,799,600
	C-34, D-22	M6D(1/3)	LAKE FOREST DR (1) LAKE FOREST DR (3)	WILMETH RD TO US HIGHWAY 380	0.61	50%	\$ 2,350,800	\$ 3,224,200 \$ 1,175,400
	D-23	G4D	UNNAMED A (1)	5,785' N OF LAUD HOWELL PKWY TO 2,710' S OF LAUD HOWELL	1.61	100%	\$ 17,435,950	\$ 17,435,950
	D-23 D-24	G4D G4D	UNNAMED A (1)	2,710' S OF LAUD HOWELL PKWY TO BLOOMDALE RD	0.49	50%	\$ 4,598,850	\$ 2,299,425
1	D-24 D-25	G4D	UNNAMED A (2)	1,105' N OF WILMETH RD TO WILMETH RD	0.49	50%	\$ 1,876,000	\$ 938,000
	D-26	M4D	UNNAMED A (4)	WILMETH RD TO HARDIN BLVD	0.75	100%	\$ 5,969,050	\$ 5,969,050
	D-27	M4D	TAYLOR-BURK DR (1)	HARDIN BLVD TO SKYLINE DR	0.28	100%	\$ 2,038,250	\$ 2,038,250
D	D-28	G6D	HARDIN BLVD (4)	UNNAMED 5 TO 1,550' S OF UNNAMED 5	0.29	50%	\$ 3,267,400	\$ 1,633,700
	D-29	G6D	HARDIN BLVD (5)	1,545' S OF UNNAMED 5 TO TRINITY FALLS PKWY	1.38	100%	\$ 21,290,800	\$ 21,290,800
l i	D-30	G6D	HARDIN BLVD (6)	TRINITY FALLS PKWY TO 1,815' S OF TRINITY FALLS PKWY	0.34	50%	\$ 4,102,000	\$ 2,051,000
	D-31	G6D	HARDIN BLVD (7)	1,815' S OF TRINITY FALLS PKWY TO 1,190' S OF BLOOMDALE RD	0.36	100%	\$ 4,538,400	\$ 4,538,400
	D-32	G6D(1/3)	HARDIN BLVD (8)	1,190' S OF BLOOMDALE RD TO 3,590' S OF BLOOMDALE RD	0.45	100%	\$ 1,070,400	\$ 1,070,400
	D-33	G6D(2/3)	HARDIN BLVD (9)	3,590' S OF BLOOMDALE RD TO WILMETH RD	0.33	50%	\$ 2,249,800	\$ 1,124,900
	D-34	G6D(1/3)	HARDIN BLVD (10)	WILMETH RD TO US HIGHWAY 380	1.23	100%	\$ 2,904,000	\$ 2,904,000
	D-35	G4D	COMMUNITY AVE (1)	TRINITY FALLS PKWY TO 1,275' S OF TRINITY FALLS PKWY	0.24	100%	\$ 2,164,400	\$ 2,164,400
	D-36	G4D(1/2)	COMMUNITY AVE (2)	1,275' S OF TRINITY FALLS PKWY TO BLOOMDALE RD	0.50	100%	\$ 1,960,000	\$ 1,960,000
	D-37	M4U(1/2)	COMMUNITY AVE (3)	BLOOMDALE RD TO 2,305' S OF BLOOMDALE RD	0.44	100%	\$ 1,174,600	\$ 1,174,600
	3		Signal	HARDIN BLVD & UNNAMED 5		50%	\$ 300,000	\$ 150,000
	6		Signal	LAUD HOWELL PKWY & LAKE FOREST DR		50%	\$ 300,000	\$ 150,000
	7		Signal	LAUD HOWELL PKWY & UNNAMED A		100%	\$ 300,000	\$ 300,000
	8		Signal	LAUD HOWELL PKWY & HARDIN BLVD		100%	\$ 300,000	\$ 300,000
	9		Signal	HARDIN BLVD & TRINITY FALLS PKWY		75%	\$ 300,000	\$ 225,000
	10	-	Roundabout	TRINITY FALLS PKWY & COMMUNITY AVE US HIGHWAY 75 & LAUD HOWELL PKWY		50% 50%	\$ 200,000 \$ 600,000	\$ 100,000 \$ 300,000
	16	-	Interchange Signals Signal	BLOOMDALE RD & UNNAMED A		25%	\$ 300,000	\$ 300,000
1	17	Intersection	Signal	BLOOMDALE RD & UNNAMED A BLOOMDALE RD & HARDIN BLVD		100%	\$ 300,000	\$ 300,000
	18		Signal	BLOOMDALE RD & COMMUNITY AVE		100%	\$ 300,000	\$ 300,000
1	19		Interchange Signals	US HIGHWAY 75 & BLOOMDALE RD		50%	\$ 600,000	\$ 300,000
	25		Roundabout	LAKE FOREST DR & WILMETH RD		50%	\$ 1,830,000	\$ 915,000
	26		Roundabout	WILMETH RD & UNNAMED A		75%	\$ 200,000	\$ 150,000
	27		Roundabout	HARDIN BLVD & WILMETH RD		75%	\$ 2,100,000	\$ 1,575,000
	32		Roundabout	HARDIN BLVD & TAYLOR-BURK DR		100%	\$ 1,200,000	\$ 1,200,000
	36		Under Construction	US HIGHWAY 380 & HARDIN BLVD		50%	\$ 780,682	\$ 390,341
				Servi	ce Area	Project (Cost Subtotal	\$ 189,016,118
			<u> </u>	Roadway Impact Fee U _I		-		\$ 11,692

Total Cost in SERVICE AREA D \$ 189,027,810

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.





Table 5.E – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area E

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area	Total P		Cost in Service Area
	E-1	P6D(1/3)	BLOOMDALE RD (12)	US HIGHWAY 75 TO REDBUD BLVD	0.48	100%	\$ 9:	55,200	\$ 955,200
	E-2	P6D(2/3)	BLOOMDALE RD (13)	REDBUD BLVD TO AIRPORT DR	0.51	100%	\$ 3,3	61,400	\$ 3,361,400
	E-3	M6D(1/3)	WILMETH RD (10)	US HIGHWAY 75 TO 2,570 E OF REDBUD BLVD	0.78	100%	\$ 1,9	35,600	\$ 1,935,600
	E-4	M6D(2/3)	WILMETH RD (11)	2,570' E OF REDBUD BLVD TO STATE HIGHWAY 5	0.41	100%	\$ 2,6	08,200	\$ 2,608,200
	E-5	M6D	WILMETH RD (12)	STATE HIGHWAY 5 TO 2,100' E OF SH 5	0.40	100%	\$ 5,0	68,500	\$ 5,068,500
	E-6	M6D	WILMETH RD (13)	2,100' E OF SH 5 TO 980' W OF AIRPORT DR	0.25	100%	\$ 2,8	04,200	\$ 2,804,200
	E-7	M6D	WILMETH RD (14)	980' W OF AIRPORT DR TO 235' E OF AIRPORT DR	0.23	50%	\$ 3,4	17,400	\$ 1,708,700
	E-8	M6D	WILMETH RD (15)	1,150' W OF FM 2933 TO 400' E OF FM 2933	0.29	50%	\$ 3,2	29,800	\$ 1,614,900
	E-9	M4D	REDBUD BLVD (1)	BLOOMDALE RD TO 2,930' S OF BLOOMDALE RD	0.55	100%	\$ 6:	50,000	\$ 650,000
	E-10	M4D(1/2)	REDBUD BLVD (2)	2,930' S OF BLOOMDALE RD TO WILMETH RD	0.31	100%	\$ 8:	52,600	\$ 852,600
	E-11	M6D	LAUD HOWELL PKWY (9)	US HIGHWAY 75 TO 2,620' S OF US HIGHWAY 75	0.50	50%	\$ 3,9	09,500	\$ 1,954,750
	E-12	M6D	LAUD HOWELL PKWY (10)	2,620' S OF US HIGHWAY 75 TO BLOOMDALE RD	0.31	100%	\$ 1,8	76,700	\$ 1,876,700
	E-13	P6D	LAUD HOWELL PKWY (11)	BLOOMDALE RD TO STATE HIGHWAY 5	0.16	100%	\$ 8	61,000	\$ 861,000
	E-14	M6D	STATE HIGHWAY 5 (1)	4,700' N OF AIRPORT DR TO 3,995' N OF AIRPORT DR	0.13	50%	\$ 6	95,100	\$ 347,550
	E-15	M6D	STATE HIGHWAY 5 (2)	1,915' N OF AIRPORT DR TO US HIGHWAY 380	2.27	100%	\$ 13,9	94,400	\$ 13,994,400
	E-16	P6D	AIRPORT DR (1)	STATE HIGHWAY 5 TO 4,070 S OF STATE HIGHWAY 5	0.77	100%	\$ 9,3	79,050	\$ 9,379,050
E	E-17	P6D	AIRPORT DR (2)	WILMETH RD TO WOODLAWN RD (N)	0.53	100%	\$ 6,5	82,850	\$ 6,582,850
	E-18	P6D	AIRPORT DR (3)	WOODLAWN RD (N) TO WOODLAWN RD (S)	0.29	100%	\$ 3,6	48,400	\$ 3,648,400
	E-19	P6D	AIRPORT DR (4)	WOODLAWN RD (S) TO US HIGHWAY 380	0.73	100%	\$ 8,9	52,800	\$ 8,952,800
	E-20	P6D(1/3)	UNNAMED C (1)	410' E OF STATE HIGHWAY 5 TO 3,010' E OF STATE HIGHWAY 5	0.49	100%	\$ 9	86,400	\$ 986,400
	E-21	P6D	UNNAMED C (2)	WILMETH RD TO 2,615' S OF WILMETH RD	0.50	50%	\$ 2,8	06,300	\$ 1,403,150
	11		Interchange Signals	US HIGHWAY 75 & LAUD HOWELL PKWY		50%	\$ 60	000,000	\$ 300,000
	19		Interchange Signals	US HIGHWAY 75 & BLOOMDALE RD		50%	\$ 60	000,000	\$ 300,000
	20		Signal	BLOOMDALE RD & REDBUD BLVD		100%	\$ 30	000,000	\$ 300,000
	21		Signal	LAUD HOWELL PKWY & BLOOMDALE RD		100%	\$ 30	000,000	\$ 300,000
	22	Intersection	Signal Mod	STATE HIGHWAY 5 & LAUD HOWELL PKWY		100%	\$ 1:	50,000	\$ 150,000
	28	mersection	Signal	WILMETH RD & REDBUD BLVD		100%	\$ 30	000,000	\$ 300,000
	29		Signal Mod	STATE HIGHWAY 5 & WILMETH RD		100%	\$ 1:	50,000	\$ 150,000
	30		Signal	AIRPORT DR & WILMETH RD		50%	\$ 30	000,000	\$ 150,000
	31		Signal	UNNAMED C & WILMETH RD		50%	\$ 30	000,000	\$ 150,000
	41		Signal Mod	US HIGHWAY 380 & AIRPORT DR		50%	\$ 1:	50,000	\$ 75,000
				Servi	ce Area	Project (Cost Sul	btotal	\$ 73,721,350
				Roadway Impact Fee U	pdate Co	st (Per S	Service .	Area)	\$ 11,692

Total Cost in SERVICE AREA E \$ 73,733,042

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

Table 5.F – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area F

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area	Total Project Cost	Cost in Service Area
				No Impact Fee Eligible Roadway Projects				
F								
	Service Area Project Cost Subtotal \$							
	Roadway Impact Fee Update Cost (Per Service Area)							

Total Cost in SERVICE AREA F \$ 11,692

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.





Table 5.G – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area G

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area		al Project Cost	Cost in Service Area
	G-1	M6D(1/3)	VIRGINIA PKWY (1)	COIT RD TO 500' W OF INDEPENDENCE PKWY	0.90	100%	\$	2,158,800	\$ 2,158,800
	G-2	M6D(1/3)	VIRGINIA PKWY (2)	500' W OF INDEPENDENCE PKWY TO 325' E OF FORKHORN DR	0.33	50%	\$	794,400	\$ 397,200
	G-3	M6D(1/3)	VIRGINIA PKWY (3)	325' E OF FORKHORN DR TO 935' W OF VIRGINIA HILLS DR	0.28	50%	\$	913,196	\$ 456,598
	G-4	M6D(1/3)	VIRGINIA PKWY (4)	935' W OF VIRGINIA HILLS DR TO CUSTER RD	0.51	100%	\$	1,661,863	\$ 1,661,863
	G-5	M6D(1/3)	VIRGINIA PKWY (5)	CUSTER RD TO 410' E OF DANBURY RD	0.49	100%	\$	1,182,000	\$ 1,182,000
	G-6	M6D(1/6)	VIRGINIA PKWY (6)	410' E OF DANBURY RD TO VIRGINIA PARKLANDS BLVD	0.39	100%	\$	392,400	\$ 392,400
	G-7	M6D(1/3)	WESTRIDGE BLVD (1)	COIT RD TO 1,635' E OF COIT RD	0.31	50%	\$	745,200	\$ 372,600
	G-8	M6D(1/3)	WESTRIDGE BLVD (2)	1,635' E OF COIT RD TO 2,720' E OF INDEPENDENCE PKWY	1.22	100%	\$	2,931,600	\$ 2,931,600
	G-9	M6D(1/3)	WESTRIDGE BLVD (3)	2,720' E OF INDEPENDENCE PKWY TO CUSTER RD	0.50	50%	\$	1,192,800	\$ 596,400
	H-1, G-10	G6D(1/3)	ELDORADO PKWY (1)	CUSTER RD TO RIDGE RD	2.05	50%	\$	5,202,000	\$ 2,601,000
	G-11	M6D(1/3)	COIT RD (1)	US HIGHWAY 380 TO 2,610' S OF VIRGINIA PKWY	1.53	50%	\$	3,681,600	\$ 1,840,800
	G-12	M6D(1/3)	COIT RD (2)	WESTRIDGE BLVD TO 2,595' S OF WESTRIDGE BLVD	0.49	50%	\$	1,184,400	\$ 592,200
	G-13	M6D(1/3)	INDEPENDENCE PKWY (1)	2,380' S OF US HIGHWAY 380 TO 4,465' S OF US HIGHWAY 380	0.39	100%	\$	951,600	\$ 951,600
	G-14	M6D(1/3)	INDEPENDENCE PKWY (2)	VIRGINIA PKWY TO 2,690' S OF WESTRIDGE BLVD	1.52	100%	\$	3,666,000	\$ 3,666,000
	G-15	P6D	CUSTER RD (4)	US HIGHWAY 380 TO WESTRIDGE BLVD	2.03	100%	\$	3,260,945	\$ 3,260,945
G	G-16	P6D	CUSTER RD (5)	WESTRIDGE BLVD TO ELDORADO PKWY	1.02	100%	\$	1,476,398	\$ 1,476,398
G	G-17, I-8	G4D	RIDGE RD (8)	US HIGHWAY 380 TO CREEKSIDE DR	1.30	50%	\$	550,813	\$ 275,407
	33		Signal Mod	US HIGHWAY 380 & STONEBRIDGE DR		50%	\$	150,000	\$ 75,000
	34		Signal	US HIGHWAY 380 & FOREST RIDGE LN		50%	\$	300,000	\$ 150,000
	37		Signal	STONEBRIDGE DR & LACIMA DR		100%	\$	300,000	\$ 300,000
	38		Signal	RIDGE RD & HABERSHAM WAY		50%	\$	343,000	\$ 171,500
	43		Signal	INDEPENDENCE PKWY & VIRGINIA PKWY		50%	\$	80,000	\$ 40,000
	44		Under Construction	VIRGINIA PKWY & RIDGE RD		50%	\$	390,341	\$ 195,171
	47	Intersection	Signal	INDEPENDENCE PKWY & WESTRIDGE BLVD		100%	\$	300,000	\$ 300,000
	48		Under Construction	CUSTER RD & WESTRIDGE BLVD		75%	\$	390,341	\$ 292,756
	49		Roundabout	STONEBRIDGE DR & GLEN OAKS DR		100%	\$	1,950,000	\$ 1,950,000
	50		Roundabout	RIDGE RD & GLEN OAKS DR		50%	\$	2,640,000	\$ 1,320,000
	55		Signal	STONEBRIDGE DR & ALMA DR		100%	\$	300,000	\$ 300,000
	56		Signal	RIDGE RD & RUSH CREEK RD		50%	\$	300,000	\$ 150,000
	57		Signal	RIDGE RD & BERKSHIRE RD		50%	\$	300,000	\$ 150,000
								Subtotal	\$ 30,208,237
				Roadway Impact Fee U	pdate Co	ost (Per S	Servi	ce Area)	\$ 11,692

Total Cost in SERVICE AREA G \$ 30,219,929

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

Table 5.H – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area H

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area	Total Project Cost	Cost in Service Area		
	H-1, G-10	G6D(1/3)	ELDORADO PKWY (1)	CUSTER RD TO RIDGE RD	2.05	50%	\$ 5,202,000	\$ 2,601,000		
	H-2	M4D(1/2)	SILVERADO TRL (1)	CUSTER RD TO BURNETT DR	0.37	100%	\$ 2,746,293	\$ 2,746,293		
	H-3	M4D	SILVERADO TRL (2)	ALMA DR TO ALFALFA DR	0.22	100%	\$ 141,088	\$ 141,088		
	H-4	P6D(1/3)	STACY RD (1)	CUSTER RD TO RIDGE RD	2.03	100%	\$ 4,479,991	\$ 4,479,991		
	H-5	P6D	CUSTER RD (6)	ELDORADO PKWY TO STONEBRIDGE DR	0.39	100%	\$ 622,725	\$ 622,725		
	H-6	G4D	ALMA DR (1)	805' S OF BEAVER CREEK DR TO SILVERADO TRL	0.37	100%	\$ 239,850	\$ 239,850		
	H-7	M6D(1/3)	ALMA DR (2)	SILVERADO TRL TO STACY RD	0.50	100%	\$ 1,522,102	\$ 1,522,102		
н	H-8, I-9	M6D(1/3)	RIDGE RD (9)	MCKINNEY RANCH PKWY TO STACY RD	0.69	50%	\$ 1,662,000	\$ 831,000		
11	H-9	M6D(1/3)	MCKINNEY RANCH PKWY (1)	RIDGE RD TO STACY RD	0.77	100%	\$ 1,857,600	\$ 1,857,600		
	65		Signal	CUSTER RD & SILVERADO TRL		50%	\$ 300,000	\$ 150,000		
	66		Signal	MCKINNEY RANCH PKWY & SILVERADO TRL		100%	\$ 300,000	\$ 300,000		
	71	Intersection	Signal	STACY RD & MCKINNEY RANCH PKWY		100%	\$ 300,000	\$ 300,000		
	75	Hitersection	Signal	CUSTER RD & PARADISE DR		50%	\$ 300,000	\$ 150,000		
	76		Signal	STACY RD & COLLIN MCKINNEY PKWY		50%	\$ 300,000	\$ 150,000		
	77		Signal	ALMA DR & HENNEMAN WAY		100%	\$ 300,000	\$ 300,000		
				Serv	ice Area	Project	Cost Subtotal	\$ 16,391,649		
	Roadway Impact Fee Update Cost (Per Service Area) \$									

Total Cost in SERVICE AREA H \$ 16,403,341

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.





Table 5.I – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area I

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area		l Project Cost	Cost in Service Area
	I-1	M6D	VIRGINIA PKWY (7)	1035' E OF RIDGE RD TO 1355' W OF HARDIN BLVD	1.43	100%	\$ 2	2,567,378	\$ 2,567,378
	I-2	M6D	VIRGINIA PKWY (8)	1355' W OF HARDIN BLVD TO HARDIN BLVD	0.26	100%	\$	531,979	\$ 531,979
	I-3	G6D(1/3)	ELDORADO PKWY (2)	RIDGE RD TO HARDIN BLVD	2.07	100%	\$ 4	4,857,600	\$ 4,857,600
	I-4	M6D(1/3)	MCKINNEY RANCH PKWY (2)	RIDGE RD TO HARDIN BLVD	1.80	100%	\$ 4	4,338,000	\$ 4,338,000
	I-5	G4D	COLLIN MCKINNEY PKWY (2)	LAKE FOREST DR TO COTTONWOOD CREEK	0.31	100%	\$ 1	1,777,105	\$ 1,777,105
	I-6	G4D(1/2)	COLLIN MCKINNEY PKWY (3)	COTTONWOOD CREEK TO 1110' E OF TINA DR	0.55	100%	\$ 3	3,221,002	\$ 3,221,002
	I-7	G4D	COLLIN MCKINNEY PKWY (4)	1110' E OF TINA TO HARDIN BLVD	0.19	100%	\$ 1	1,101,893	\$ 1,101,893
	G-17, I-8	G4D	RIDGE RD (8)	US HIGHWAY 380 TO CREEKSIDE DR	1.30	50%	\$	550,813	\$ 275,407
	H-8, I-9	M6D(1/3)	RIDGE RD (9)	MCKINNEY RANCH PKWY TO STACY RD	0.69	50%	\$ 1	1,662,000	\$ 831,000
	I-10, J-6	G6D(1/3)	HARDIN BLVD (11)	US HIGHWAY 380 TO VIRGINIA PKWY	1.58	50%	\$ 13	3,584,097	\$ 6,792,049
	I-11, J-7	G6D(1/3)	HARDIN BLVD (12)	VIRGINIA PKWY TO MCKINNEY RANCH PKWY	2.64	50%	\$ 6	5,208,800	\$ 3,104,400
	35		Signal	US HIGHWAY 380 & AUBURN HILLS PKWY		50%	\$	300,000	\$ 150,000
	36		Under Construction	US HIGHWAY 380 & HARDIN BLVD		25%	\$	780,682	\$ 195,171
	38		Signal	RIDGE RD & HABERSHAM WAY		50%	\$	343,000	\$ 171,500
I	44		Under Construction	VIRGINIA PKWY & RIDGE RD		50%	\$	390,341	\$ 195,171
	45		Signal	VIRGINIA PKWY & JOPLIN DR		100%	\$	300,000	\$ 300,000
	46		Signal	VIRGINIA PKWY & VILLAGE DR		100%	\$	300,000	\$ 300,000
	50		Roundabout	RIDGE RD & GLEN OAKS DR		50%	\$ 2	2,640,000	\$ 1,320,000
	51	Intersection	Roundabout	LAKE FOREST DR & GLEN OAKS DR		100%	\$ 1	1,900,000	\$ 1,900,000
	56	mersection	Signal	RIDGE RD & RUSH CREEK RD		50%	\$	300,000	\$ 150,000
	57		Signal	RIDGE RD & BERKSHIRE RD		50%	\$	300,000	\$ 150,000
	58		Signal	HARDIN BLVD & MAVERICK TRL		50%	\$	300,000	\$ 150,000
	59		Signal	ELDORADO PKWY & WOODSON DR		100%	\$	300,000	\$ 300,000
	60		Signal	ELDORADO PKWY & HIGHLANDS DR		100%	\$	300,000	\$ 300,000
	72		Signal	LAKE FOREST DR & COLLIN MCKINNEY PKWY		100%	\$	300,000	\$ 300,000
	73		Signal	HARDIN BLVD & COLLIN MCKINNEY PKWY		50%	\$	300,000	\$ 150,000
	76		Signal	STACY RD & COLLIN MCKINNEY PKWY		50%	\$	300,000	\$ 150,000
	Service Area Project Cost Subtotal								
				Roadway Impact Fee	Update Co	ost (Per S	Servic	e Area)	\$ 11,692

Total Cost in SERVICE AREA I \$ 35,591,345

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

Table 5.J – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area J

J-2 M4D	Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area		al Project Cost	Cost	in Service Area
J-3 M6D		J-1	M4D	WHITE AVE (1)	HARDIN BLVD TO BOIS D'ARC RD	0.17	100%	\$	981,328	\$	981,328
J-4 G6D(1/3) ELDORADO PKWY (3) 710° E OF US HIGHWAY 75 TO 1,180° E OF BARRANCA WAY 1.08 100% \$ 4,047,600 \$ 4,047		J-2	M4D	WHITE AVE (2)	BOIS D'ARC RD TO COMMUNITY AVE	0.93	100%	\$	213,991	\$	213,991
J-5 M3U COLLIN MCKINNEY PKWY (5) 2,100° E OF HARDIN BLVD TO MCKINNEY RANCH PKWY 0.33 100% \$ 1,953,000 \$ 1,9		J-3	M6D	VIRGINIA PKWY (9)	HARDIN BLVD TO US HIGHWAY 75	1.60	100%	\$	3,267,873	\$	3,267,873
I-10, I-6 G6D(I/3)		J-4	G6D(1/3)	ELDORADO PKWY (3)	710' E OF US HIGHWAY 75 TO 1,180' E OF BARRANCA WAY	1.08	100%	\$	4,047,600	\$	4,047,600
1-11, 1-7 G6D(1/3) HARDIN BLVD (12) VIRGINIA PKWY TO MCKINNEY RANCH PKWY 2,64 50% \$ 6,208,800 \$ 3,10		J-5	M3U	COLLIN MCKINNEY PKWY (5)	2,100' E OF HARDIN BLVD TO MCKINNEY RANCH PKWY	0.33	100%	\$	1,953,000	\$	1,953,000
J-8		I-10, J-6	G6D(1/3)	HARDIN BLVD (11)	US HIGHWAY 380 TO VIRGINIA PKWY	1.58	50%	\$ 1	13,584,097	\$	6,792,049
J-9, K-7 M6D		I-11, J-7	G6D(1/3)	HARDIN BLVD (12)	VIRGINIA PKWY TO MCKINNEY RANCH PKWY	2.64	50%	\$	6,208,800	\$	3,104,400
J-10, K-8		J-8	M4D	MEDICAL CENTER DR	STATE HIGHWAY 121 TO 1,685' S OF STATE HIGHWAY 121	0.32	100%	\$	2,240,000	\$	2,240,000
J-11 M4D STATE HIGHWAY 5 (6) 3,525 S OF STATE HIGHWAY 121 TO 4,520 S OF STATE HIGHWAY 0.19 50% \$ 627,900 \$ 3 36 Under Construction US HIGHWAY 380 & HARDIN BLVD 2.5% \$ 780,682 \$ 1 1 1 1 1 1 1 1 1		J-9, K-7	M6D	STATE HIGHWAY 5 (4)	640' S OF HARRY MCKILLOP BLVD / FM 546 TO STATE HIGHWAY	0.47	50%	\$	4,647,300	\$	2,323,650
36		J-10, K-8	M4D	STATE HIGHWAY 5 (5)	STATE HIGHWAY 121 TO 3,525' S OF STATE HIGHWAY 121	0.67	50%	\$	2,223,200	\$	1,111,600
Signal WHITE AVE & JORDAN RD 100% \$ 300,000 \$ 3		J-11	M4D	STATE HIGHWAY 5 (6)	3,525' S OF STATE HIGHWAY 121 TO 4,520' S OF STATE HIGHWAY	0.19	50%	\$	627,900	\$	313,950
Signal	,	36		Under Construction	US HIGHWAY 380 & HARDIN BLVD		25%	\$	780,682	\$	195,171
Intersection Improvements ELDORADO PKWY & CRAIG DR 100% \$ 150,000 \$ 1		39		Signal	WHITE AVE & JORDAN RD		100%	\$	300,000	\$	300,000
62 Intersection Signal STATE HIGHWAY 5 & STEWART RD 50% \$ 300,000 \$ 1 67 Signal MCKINNEY RANCH PKWY & COLLIN MCKINNEY PKWY 100% \$ 300,000 \$ 3 68 Signal COLLIN MCKINNEY PKWY & CRAIG DR 100% \$ 300,000 \$ 3 69 Signal STATE HIGHWAY 5 & ENTERPRISE DR 50% \$ 300,000 \$ 1 73 Signal HARDIN BLVD & COLLIN MCKINNEY PKWY 50% \$ 300,000 \$ 1 Service Area Project Cost Subtotal \$ 28,19		58		Signal	HARDIN BLVD & MAVERICK TRL		50%	\$	300,000	\$	150,000
67 Signal MCKINNEY RANCH PKWY & COLLIN MCKINNEY PKWY 100% \$ 300,000 \$ 3 68 Signal COLLIN MCKINNEY PKWY & CRAIG DR 100% \$ 300,000 \$ 3 69 Signal STATE HIGHWAY 5 & ENTERPRISE DR 50% \$ 300,000 \$ 1 73 Signal HARDIN BLVD & COLLIN MCKINNEY PKWY 50% \$ 300,000 \$ 1 Service Area Project Cost Subtotal		61		Intersection Improvements	ELDORADO PKWY & CRAIG DR		100%	\$	150,000	\$	150,000
68 Signal COLLIN MCKINNEY PKWY & CRAIG DR 100% \$ 300,000 \$ 3 69 Signal STATE HIGHWAY 5 & ENTERPRISE DR 50% \$ 300,000 \$ 1 73 Signal HARDIN BLVD & COLLIN MCKINNEY PKWY 50% \$ 300,000 \$ 1 Service Area Project Cost Subtotal \$ 28,19		62	Intersection	Signal	STATE HIGHWAY 5 & STEWART RD		50%	\$		\$	150,000
69 Signal STATE HIGHWAY 5 & ENTERPRISE DR 50% \$ 300,000 \$ 1 73 Signal HARDIN BLVD & COLLIN MCKINNEY PKWY 50% \$ 300,000 \$ 1 Service Area Project Cost Subtotal \$ 28,19		67		Signal	MCKINNEY RANCH PKWY & COLLIN MCKINNEY PKWY		100%	\$	300,000	\$	300,000
73 Signal HARDIN BLVD & COLLIN MCKINNEY PKWY 50% \$ 300,000 \$ 1. Service Area Project Cost Subtotal \$ 28,19		68		Signal	COLLIN MCKINNEY PKWY & CRAIG DR		100%	\$	300,000	\$	300,000
Service Area Project Cost Subtotal \$ 28,19		69		Signal	STATE HIGHWAY 5 & ENTERPRISE DR		50%	\$	300,000	\$	150,000
		73		Signal	HARDIN BLVD & COLLIN MCKINNEY PKWY		50%	\$	300,000	\$	150,000
Roadway Impact Fee Update Cost (Per Service Area) \$ 1					Servi	ce Area	Project (Cost	Subtotal	\$:	28,194,611
					Roadway Impact Fee Up	pdate Co	st (Per S	Servi	ce Area)	\$	11,692

Total Cost in SERVICE AREA J \$ 28,206,303

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.





Table 5.K – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area K

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area		al Project Cost	Cost in Service Area
	K-1	2UO	VIRGINIA STREET	225' W OF AIRPORT DR TO AIRPORT DR	0.04	100%	\$	779,650	\$ 779,650
	K-2	G6D(1/3)	ELDORADO PKWY (4)	1,180' E OF BARRANCA WAY TO STATE HIGHWAY 5	0.40	100%	\$	1,699,200	\$ 1,699,200
	K-3	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (1)	STATE HIGHWAY 121 TO AIRPORT DR	1.46	100%	\$	1,839,600	, , , , , , , , , , , , , , , , , , , ,
	K-4, L-1	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (2)	AIRPORT DR TO 980' E OF AIRPORT DR	0.19	50%	\$	234,600	\$ 117,300
	K-5, L-2	P6D	HARRY MCKILLOP BLVD / FM 546 (3)	975' E OF AIRPORT DR TO 510' W OF HARRY MCKILLOP BLVD / FM 546 (N)	0.60	50%	\$	3,267,400	\$ 1,633,700
	K-6	M6D	STATE HIGHWAY 5 (3)	INDUSTRIAL BLVD TO 640' S OF HARRY MCKILLOP BLVD / FM 546	0.40	100%	\$	2,064,300	\$ 2,064,300
	J-9, K-7	M6D	STATE HIGHWAY 5 (4)	640' S OF HARRY MCKILLOP BLVD / FM 546 TO STATE HIGHWAY 121	0.47	50%	\$	4,647,300	\$ 2,323,650
	J-10, K-8	M4D	STATE HIGHWAY 5 (5)	STATE HIGHWAY 121 TO 3,525' S OF STATE HIGHWAY 121	0.67	50%	\$	2,223,200	\$ 1,111,600
K	K-9, L-6	P6D(1/3)	AIRPORT DR (5)	US HIGHWAY 380 TO 470' N OF HARRY MCKILLOP BLVD / FM 546	2.63	50%	\$	6,322,800	\$ 3,161,400
	K-10, L-7	P6D	AIRPORT DR (6)	470' N OF HARRY MCKILLOP BLVD / FM 546 TO HARRY MCKILLOP BLVD / FM 546	0.09	50%	\$	2,925,200	\$ 1,462,600
	40		Signal	STATE HIGHWAY 5 & SMITH ST		100%	\$	300,000	\$ 300,000
	41		Signal Mod	US HIGHWAY 380 & AIRPORT DR		50%	\$	150,000	\$ 75,000
	52		Roundabout	WILSON CREEK PKWY & PARK VIEW AVE		100%	\$	1,820,000	\$ 1,820,000
	53	Intersection	Signal	WILSON CREEK PKWY & COLLEGE ST		100%	\$	300,000	\$ 300,000
	54	mersection	Signal	AIRPORT DR & ELM ST		50%	\$	300,000	\$ 150,000
	62		Signal	STATE HIGHWAY 5 & STEWART RD		50%	\$	300,000	\$ 150,000
	63		Signal	HARRY MCKILLOP BLVD / FM 546 & AIRPORT DR		75%	\$	300,000	\$ 225,000
	69		Signal	STATE HIGHWAY 5 & ENTERPRISE DR		50%	\$	300,000	\$ 150,000
				Servi	ce Area	Project	Cost	Subtotal	\$ 19,363,000
				Roadway Impact Fee Up	date Co	st (Per S	Servi	ice Area)	\$ 11,692

Total Cost in SERVICE AREA K \$ 19,374,692

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

Table 5.L – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area L

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area		l Project Cost	Cost in Service Area
	K-4, L-1	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (2)	AIRPORT DR TO 980' E OF AIRPORT DR	0.19	50%	\$	234,600	\$ 117,300
	K-5, L-2	P6D	HARRY MCKILLOP BLVD / FM 546 (3)	975' E OF AIRPORT DR TO 510' W OF HARRY MCKILLOP BLVD / FM 546 (N)	0.60	50%	\$ 3	,267,400	\$ 1,633,700
	L-3	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (1)	510' W OF HARRY MCKILLOP BLVD / FM 546 (N) TO 1,335' E OF HARRY MCKILLOP BLVD / FM 546 (N)	0.35	100%	\$ 2	2,153,725	\$ 2,153,725
	L-4	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (2)	3,480' W OF UNNAMED D TO UNNAMED D	0.66	100%	\$ 3	,843,225	\$ 3,843,225
	L-5	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (1)	HARRY MCKILLOP BLVD / FM 546 (S) TO 1,865' E OF HARRY MCKILLOP BLVD / FM 546 (S)	0.35	100%	\$ 2	2,166,900	\$ 2,166,900
	K-9, L-6	P6D(1/3)	AIRPORT DR (5)	US HIGHWAY 380 TO 470' N OF HARRY MCKILLOP BLVD / FM 546	2.63	50%	\$ 6	5,322,800	\$ 3,161,400
	K-10, L-7	P6D	AIRPORT DR (6)	470' N OF HARRY MCKILLOP BLVD / FM 546 TO HARRY MCKILLOP BLVD / FM 546	0.09	50%	\$ 2	2,925,200	\$ 1,462,600
	L-8	P6D	UNNAMED C (3)	US HIGHWAY 380 TO 2,435' S OF US HIGHWAY 380	0.46	100%	\$ 5	,807,850	\$ 5,807,850
L	L-9, M-5	P6D	UNNAMED C (4)	2,525' N OF HARRY MCKILLOP BLVD / FM 546 TO 1,230' N OF HARRY MCKILLOP BLVD / FM 546	0.25	50%	\$ 2	2,830,300	\$ 1,415,150
	L-10, M-6	P6D	UNNAMED C (5)	HARRY MCKILLOP BLVD / FM 546 (N) TO 705' S OF HARRY MCKILLOP BLVD / FM 546 (S)	0.87	50%	\$ 10	,002,150	\$ 5,001,075
	41		Signal Mod	US HIGHWAY 380 & AIRPORT DR		50%	\$	150,000	\$ 75,000
	42		Signal	US HIGHWAY 380 & UNNAMED C		50%	\$	300,000	\$ 150,000
	54		Signal	AIRPORT DR & ELM ST		50%	\$	300,000	\$ 150,000
	63	Intersection	Signal	HARRY MCKILLOP BLVD / FM 546 & AIRPORT DR		75%	\$	300,000	\$ 225,000
	70		Signal	HARRY MCKILLOP BLVD / FM 546 (S) & HARRY MCKILLOP BLVD / FM 546 (N)		100%	\$	300,000	\$ 300,000
	74		Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (S)		50%	\$	300,000	\$ 150,000
				Servi	ce Area	Project (Cost S	Subtotal	\$ 27,812,925
				Roadway Impact Fee Up	date Co	st (Per S	Servic	e Area)	\$ 11,692

Total Cost in SERVICE AREA L \$ 27,824,617

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.





Table 5.M – 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Projections – Service Area M

Service Area	Proj. #	Class	Roadway	Limits	Length (mi)	% In Service Area	Total Project Cost	Cost in Service Area
	M-1	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (2)	110' E OF UNNAMED C TO 300' E OF UNNAMED C	0.04	50%	\$ 196,075	\$ 98,038
	M-2	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (3)	1,700' N OF HARRY MCKILLOP BLVD / FM 546 TO 2,050' N OF HARRY MCKILLOP BLVD / FM 546	0.07	50%	\$ 361,150	\$ 180,575
	M-3	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (4)	405' N OF HARRY MCKILLOP BLVD / FM 546 TO 675' N OF HARRY MCKILLOP BLVD / FM 546	0.05	50%	\$ 279,000	\$ 139,500
	M-4	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (3)	UNNAMED C TO 695' E OF UNNAMED C	0.13	100%	\$ 719,975	\$ 719,975
M	L-9, M-5	P6D	UNNAMED C (4)	2,525' N OF HARRY MCKILLOP BLVD / FM 546 TO 1,230' N OF HARRY MCKILLOP BLVD / FM 546	0.25	50%	2830300	\$ 1,415,150
	L-10, M-6	P6D	UNNAMED C (5)	HARRY MCKILLOP BLVD / FM 546 (N) TO 705' S OF HARRY MCKILLOP BLVD / FM 546 (S)	0.87	50%	\$ 10,002,150	\$ 5,001,075
	64	Inter-	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (N)		50%	\$ 300,000	\$ 150,000
	74	section	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (S)		50%	\$ 300,000	\$ 150,000
				Servi	ce Area	Project (Cost Subtotal	\$ 7,854,313
				Roadway Impact Fee Ur	date Co	st (Per S	Service Area)	\$ 11.692

Total Cost in SERVICE AREA M \$ 7,866,005

- a. These planning level cost projections have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Projects within the City of McKinney.
- b. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

F. Service Unit Calculation

The basic service unit for the computation of McKinney's RIF is the vehicle-mile of travel during the afternoon peak-hour (as explained on Pg. 27). To determine the cost per service unit, it is necessary to project the growth in vehicle-miles of travel for the service areas for the ten-year period.

The growth in vehicle-miles from 2019 to 2029 is based upon projected changes in residential units and non-residential growth for the period. To determine this growth, estimates of residential units, basic, service, and retail square footages for 2019 were made by the City, along with growth projections for each of these demographic statistics through 2029. The 2019 Land Use Assumptions details the growth estimates used for impact fee determination.

The population and non-residential square footage statistics in the Land Use Assumptions provides the "independent variables" that are used to calculate the existing (2019) and projected (2029) transportation service units used to establish the roadway impact fee maximum rates within each service area. The roadway demand service units (vehicle-miles) for each service area are the sum of the vehicle-miles "generated" by each category of land use in the service area.





For the purposes of impact fees, all developed and developable land is categorized as either residential or non-residential. For residential land uses, the existing and projected number of dwelling units are estimated. The number of dwelling units in each service area is multiplied by a *transportation demand factor* (discussed in more detail below) to compute the vehicle-miles of travel that occur during the afternoon peak hour. This factor indicates the average amount of demand created by the residential land uses in the service area.

For non-residential land uses, the process is similar. The Land Use Assumptions section of this report provides the existing and projected number of building square footages for three (3) categories of non-residential uses – basic, service, and retail. These categories correspond to an aggregation of other specific land use categories based on the North American Industrial Classification System (NAICS).

Building square footage is the most common independent variable for the estimation of non-residential trips in the *Institute of Transportation Engineers (ITE) Trip Generation Manual*, 10th *Edition*. This characteristic is more appropriate than the number of employees, because building square footage is tied more closely to trip generation and is known at the time of application for any development that would require the assessment of an impact fee.

The existing and projected land use assumptions for the dwelling units and the square footage of basic, service, and retail land uses provide the basis for the projected increase in vehicle-miles of travel. As noted earlier, a *transportation demand factor* is applied to these values and then summed to calculate the total peak hour vehicle-miles of demand for each service area.

The transportation demand factors are aggregate rates derived from two sources – the ITE Trip Generation Manual, 10th Edition and information from the National Household Travel Survey (NHTS) performed by the Federal Highway Administration (FHWA).

The ITE Trip Generation Manual, 10th Edition provides the number of trips that are produced or attracted to the land use for each dwelling unit, square foot of building, or other corresponding unit. For the retail category of land uses, the rate is adjusted to account for the fact that a percentage of retail trips are made by people who would otherwise be





traveling past that particular establishment anyway, such as a trip between work and home. These trips are called pass-by trips, and since the travel demand is accounted for in the land use calculations relative to the primary trip, it is necessary to discount the retail trip generation rates to avoid double counting trips.

The next component of the *transportation demand factor* accounts for the length of each trip. The average trip length for each category is based on the region-wide travel characteristics survey conducted by NHTS and other generally accepted planning principles.

The computation of the *transportation demand factor* is based on the following equation:

$$TDF = T * (1 - P_b) * L_{Max}$$

$$Where...L_{Max} = min (L * OD or SA_L)$$

Variables:

TDF = Transportation Demand Factor,

T = Trip Rate (peak hour trips / unit),

P_b = Pass-By Discount (% of trips),

L = Average Trip Length (miles),

 L_{Max} = Maximum Trip Length (miles),

OD = Origin-Destination Reduction (50%); and

SA_L = Max Service Area Trip Length (see Table 6)

The maximum trip length, for land uses which are characterized by longer average trip lengths (primarily residential uses), has been limited to a length based on the nature of the roadway network within the service area, along with consideration of the existing City boundaries. Although Chapter 395 of the Texas Local Government Code allows for a service area diameter of six (6) miles, the City of McKinney has set service area boundaries in anticipation of the ultimate corporate limits. Therefore, the individual service areas have different trip characteristics. In order to account for these differences, the values shown in Table 6 were used for calculation of the *transportation demand factor* for each service area.





Table 6. Maximum Trip Lengths by Service Area

Service Area	Max. Trip Length (mi)	Service Area	Max. Trip Length (mi)
А	0.50	Н	4.65
В	1.30	I	6.00
С	4.00	J	6.00
D	6.00	K	5.30
E	4.80	L	3.50
F	0.00	M	1.50
G	6.00		

The adjustment made to the average trip length statistic in the computation of the maximum trip length is the origin-destination reduction. This adjustment is made because the RIF is charged to both the origin and destination end of the trip. For example, impact fee methodology will account for a trip from home to work within McKinney to both residential and non-residential land uses. To avoid counting these trips twice as both residential and non-residential trips, a 50% origin-destination (OD) reduction factor is applied. Therefore, only half of the trip length is assessed to each land use, and the total trip is only counted once.





Tables 7A and 7B show the derivation of the *Transportation Demand Factor* for the residential land uses and the three (3) non-residential land use categories in Service Areas C and I. The values utilized for all variables shown in the *transportation demand factor* equation are also shown in the table.

Table 7.A. Transportation Demand Factor Calculations – SA C Examples

Variable	Single Family	Basic	Service	Retail
T	0.99	0.63	1.15	3.81
Pb	0%	0%	0%	34%
L _{Max} *	4.00	4.00	4.00	2.80
TDF	3.96	2.52	4.60	7.03

Table 7.B. Transportation Demand Factor Calculations – SA I Examples

Variable	Single Family	Basic	Service	Retail
T	0.99	0.63	1.15	3.81
P _b	0%	0%	0%	34%
L _{Max} *	4.90	5.01	6.00	2.80
TDF	4.85	3.16	6.90	7.03

The application of the demographic projections and the *transportation demand factors* are presented in the 10-Year Growth Projections in Table 8. This table shows the total vehiclemiles by service area for the years 2019 and 2029. These estimates and projections lead to the Vehicle-Miles of Travel for the 10-year period.





Table 8. 10-Year Growth Projections

Year 2019

SERVICE	RESIDE	NTIAL VEHICL	E-MILES	S		SQUARE FEET	ı	TRANS	. DEMAND FA	ACTOR ⁵	NON-	RESIDENTIA	L VEHICLE-N	IILES ⁹	TOTAL
AREA	POPULATION ¹	DWELLING UNITS ¹	TDF ²	VEHICLE MILES ³	BASIC	SERVICE	RETAIL	BASIC ⁶	SERVICE ⁷	RETAIL ⁸	BASIC	SERVICE	RETAIL	TOTAL	VEHICLE MILES ¹⁰
Α	306	115	0.50	58	23,500	0	81,515	0.32	0.58	1.26	8	0	103	111	169
В	2,834	973	1.29	1,255	0	0	16,699	0.82	1.50	3.26	0	0	54	54	1,309
С	8,429	2,959	3.96	11,718	227,746	632,125	278,982	2.52	4.60	7.03	574	2,908	1,961	5,443	17,161
D	11,213	3,343	4.85	16,214	0	3,104,234	1,255,451	3.16	6.90	7.03	0	21,419	8,826	30,245	46,459
Е	3,905	1,204	4.75	5,719	3,624,114	478,284	1,754,956	3.02	5.52	7.03	10,945	2,640	12,337	25,922	31,641
F	1,485	556	0.00	0	212,216	27,295	263,232	0.00	0.00	0.00	0	0	0	0	0
G	50,272	17,987	4.85	87,237	899,720	1,889,230	2,428,620	3.16	6.90	7.03	2,843	13,036	17,073	32,952	120,189
Н	29,944	12,197	4.60	56,106	581,141	1,933,505	2,627,061	2.93	5.35	7.03	1,703	10,344	18,468	30,515	86,621
ı	39,502	13,959	4.85	67,701	352,879	2,397,595	1,433,682	3.16	6.90	7.03	1,115	16,543	10,079	27,737	95,438
J	24,011	10,072	4.85	48,849	1,649,518	2,754,401	3,513,500	3.16	6.90	7.03	5,212	19,005	24,700	48,917	97,766
K	20,558	7,651	4.85	37,107	5,125,000	2,871,086	2,325,009	3.16	6.10	7.03	16,195	17,514	16,345	50,054	87,161
L	182	75	3.47	260	561,885	499,422	82,826	2.21	4.03	7.03	1,242	2,013	582	3,837	4,097
М	370	164	1.49	244	66,320	14,572	0	0.95	1.73	3.77	63	25	0	88	332
Totals	193,011	71,255		332,468	13,324,039	16,601,749	16,061,533				39,900	105.447	110,528	255,875	588,343

Year 2029

SERVICE	RESIDE	NTIAL VEHICL	E-MILES	S		SQUARE FEET		TRANS	. DEMAND F	ACTOR ⁵	NON-	RESIDENTIA	L VEHICLE-N	IILES ⁹	TOTAL
AREA	POPULATION ¹	DWELLING UNITS ¹	TDF ²	VEHICLE MILES ³	BASIC	SERVICE	RETAIL	BASIC ⁶	SERVICE ⁷	RETAIL ⁸	BASIC	SERVICE	RETAIL	TOTAL	VEHICLE MILES ¹⁰
Α	306	115	0.50	58	23,500	0	81,515	0.32	0.58	1.26	8	0	103	111	169
В	24,705	7,932	1.29	10,232	10,071	207,903	102,935	0.82	1.50	3.26	8	312	336	656	10,888
С	15,374	5,271	3.96	20,873	227,746	1,358,193	717,975	2.52	4.60	7.03	574	6,248	5,047	11,869	32,742
D	28,583	9,620	4.85	46,657	59,635	3,804,295	2,085,852	3.16	6.90	7.03	188	26,250	14,664	41,102	87,759
E	6,411	2,077	4.75	9,866	6,106,522	678,020	2,480,150	3.02	5.52	7.03	18,442	3,743	17,435	39,620	49,486
F	2,198	674	0.00	0	232,107	99,078	475,970	0.00	0.00	0.00	0	0	0	0	0
G	51,402	18,422	4.85	89,347	930,350	1,958,638	3,147,880	3.16	6.90	7.03	2,940	13,515	22,130	38,585	127,932
н	38,383	15,692	4.60	72,183	596,073	3,740,251	3,414,730	2.93	5.35	7.03	1,746	20,010	24,006	45,762	117,945
I	43,720	15,567	4.85	75,500	464,983	2,650,436	2,633,350	3.16	6.90	7.03	1,469	18,288	18,512	38,269	113,769
J	28,123	11,462	4.85	55,591	1,876,524	4,487,519	4,288,130	3.16	6.90	7.03	5,930	30,964	30,146	67,040	122,631
K	22,258	8,290	4.85	40,207	5,629,952	3,118,346	2,656,021	3.16	6.10	7.03	17,791	19,022	18,672	55,485	95,692
L	182	75	3.47	260	1,159,239	612,935	99,263	2.21	4.03	7.03	2,562	2,470	698	5,730	5,990
М	439	187	1.49	279	237,897	46,200	13,786	0.95	1.73	3.77	226	80	52	358	637
Totals	262,084	95,384		421,053	17,554,599	22,761,814	22,197,557				51,884	140,902	151,801	344,587	765,640

VEHICLE-MILES OF INCREASE (2019 - 2029)¹¹

SERVICE AREA	VEH-MILES
Α	0
В	9,578
С	15,582
D	41,299
E	17,845
F	0
G	7,742
Н	31,324
I	18,332
J	24,864
K	8,530
L	1,893
М	304
Total	177,293

Notes

- ¹ From 2019 *Land Use Assumptions* Report
- ² Transportation Demand Factor for each Service Area (from LUVMET) using Single Family Detached Housing land use and *trip generation rate*
- ³ Calculated by multiplying TDF by the number of dwelling units
- ⁴ From 2019 Land Use Assumptions Report
- 5 Trip generation rate and Transportation Demand Factors from LUVMET for each land use
- $^{\rm 6}$ 'Basic' corresponds to General Light Industrial land use and $\it trip\ generation\ rate$
- ⁷ 'Service' corresponds to General Office land use and *trip generation rate*
- ⁸ 'Retail' corresponds to Shopping Center land use and *trip generation rate*
- ⁹ Calculated by multiplying Transportation Demand Factor by the number of thousand square feet for each land use
- $^{\rm 10}$ Residential plus non-residential vehicle-mile totals for each Service Area
- ¹¹ Total Vehicle-Miles (2019) subtracted from Total Vehicle Miles (2029)





V. ROADWAY IMPACT FEE CALCULATION

A. Maximum Assessable Impact Fee Per Service Unit

This section presents the maximum assessable impact fee rate calculated for each service area. The maximum assessable impact fee is the sum of the eligible RIF RIP costs for the service area divided by the growth in travel attributable to new development projected to occur within the 10-year period. A majority of the components of this calculation have been described and presented in previous sections of this report. The purpose of this section is to document the computation for each service area and to demonstrate that the guidelines provided by Chapter 395 of the Texas Local Government Code have been addressed.

Table 9 illustrates the computation of the maximum assessable impact fee computed for each service area. Each row in the table is numbered to simplify explanation of the calculation.

Table 9. Maximum Assessable Roadway Impact Fee Computation

Line	Title	Description
	Total Vehicle-Miles of	The total number of vehicle-miles added to the service area based on
1	Capacity Added by the	the capacity, length, and number of lanes in each project (from
	RIF RIP	Appendix B – RIF RIP Units of Supply)

Each project identified in the RIP will add a certain amount of capacity to the City's roadway network based on its length and classification. This line displays the total amount added within each service area.

2	Total Vehicle-Miles of Existing Demand	A measure of the amount of traffic currently using the roadway facilities upon which capacity is being added. (from Appendix B – RIF RIP Units of Supply)
---	---	---

A number of facilities identified in the RIF RIP have traffic currently utilizing a portion of their existing capacity. This line displays the total amount of capacity along these facilities currently being used by existing traffic.

3	Total Vehicle-Miles of Existing Deficiencies	Number of vehicle-miles of travel that are not accommodated by the existing roadway system (from Appendix C – Existing Facilities Inventory)
---	---	--

In order to ensure that existing deficiencies on the City's roadway network are not recoverable through impact fees, this line is based on the entire roadway network within the service area. Any roadway within the service area that is deficient – even those not identified on the Impact Fee RIP – will have these additional trips removed from the calculation.





4	Net Amount of Vehicle-	A measurement of the amount of vehicle-miles added by the RIP that
4	Miles of Capacity Added	will not be utilized by existing demand (Line 1 – Line 2 – Line 3)

This calculation identifies the portion of the Impact Fee RIP (in vehicle-miles) that may be recoverable through the collection of impact fees.

5	Total Cost of the RIP within the Service Area	The total cost of the projects within each service area (from Table 5: 10-Year Roadway Impact Fee RIP with Conceptual Level Cost Opinions)
---	---	--

This line simply identifies the total cost of all of the projects identified in each service area.

6	Cost of Net Capacity Supplied	The total RIP cost (Line 5) prorated by the ratio of Net Capacity Added (Line 4) to Total Capacity Added (Line 1). [(Line 4 / Line 1) * (Line 5)]
---	----------------------------------	---

Using the ratio of vehicle-miles added by the Impact Fee RIP available to serve future growth to the total vehicle-miles added, the total cost of the Impact Fee RIP is reduced to the amount available for future growth (i.e. excluding existing usage and deficiencies).

7	Cost to Meet Existing	The difference between the Total Cost of the RIP (Line 5) and the
/	Needs and Usage	Cost of the Net Capacity supplied (Line 6). (Line 5 – Line 6)

This line is provided for information purposes only – it is to present the portion of the total cost of the Impact Fee RIP that is required to meet existing demand.

	Total Vehicle-Miles of	Based upon the growth projection provided in the Land Use
8	New Demand over Ten	Assumptions, an estimate of the number of new vehicle-miles within
	Years	the service area over the next ten years. (from Table 8)

This line presents the amount of growth (in vehicle-miles) projected to occur within each service area over the next ten years.

9	Percent of Capacity Added Attributable to	The result of dividing Total Vehicle-Miles of New Demand (Line 8) by the Net Amount of Capacity Added (Line 4), limited to 100% (Line
	New Growth	10). This calculation is required by Chapter 395 to ensure capacity
10	Chapter 395 Check	added is attributable to new growth.

In order to ensure that the vehicle-miles added by the RIF RIP do not exceed the amount needed to accommodate growth beyond the ten-year window, a comparison of the two values is performed. If the amount of vehicle-miles added by the RIF RIP exceeds the growth projected to occur in the next ten years, the RIF RIP cost is reduced accordingly.

Ī		Cost of Capacity Added	The result of multiplying the Cost of Net Capacity Added (Line 6) by
	11	Attributable to New	the Percent of Capacity Added Attributable to New Growth, limited
		Growth	to 100% (Line 9).

This value is the total Impact Fee RIP project costs (excluding financial costs) that may be recovered through impact fees. This line is determined considering the limitations to impact fees required by the Texas legislature.





B. Plan for the Roadway Impact Fee Credit

Chapter 395 of the Texas Local Government Code requires the RIF RIP to contain specific enumeration of a plan for awarding the impact fee credit. Section 395.014 of the Code requires:

- (A) a credit for the portion of ad valorem tax and utility service revenues generated by new service units during the program period that is used for the payment of improvements, including the payment of debt, that are included in the capital improvements plan; or
- (B) In the alternative, a credit equal to 50 percent of the total projected cost of implementing the Capital Improvements Plan..."

The plan following 395.014(T)(A) is summarized, as prepared by NewGen Strategies & Solutions, Inc., in Appendix D and E, Plan for Awarding the Roadway Impact Fee Credit. The following table summarizes the portions of Table 9 that utilize this credit calculation.

Table 9 (Cont'd). Maximum Assessable Roadway Impact Fee Computation

Line	Title	Description
12	Financing Costs	(from Appendix D – Plan for Awarding the Roadway Impact Fee Credit)
13	Existing Fund Balance	(from Appendix D – Plan for Awarding the Roadway Impact Fee Credit)
14	Interest Earnings	(from Appendix D – Plan for Awarding the Roadway Impact Fee Credit)
15	Cost of the RIP and Financing Attributable to New Growth	The sum of the Cost of Capacity Added Attributable to New Growth, Financing Costs, and Interest Earnings. (Line 11 + Line 12 + Line 13+Line 14)
16	Pre-Credit Maximum Fee Per Service Unit	Found by dividing the Cost of the RIP and Financing Attributable to New Growth (Line 15) by the Total Vehicle-Miles of New Demand Over Ten Years (Line 8). (Line 15 / Line 8)
17	Credit for Ad Valorem Taxes	A credit for the portion of ad valorem taxes projected to be generated by the new service units, as per Section 395.014 of the Local Government Code. (from Appendix D – Plan for Awarding the Roadway Impact Fee Credit)
18	Recoverable Cost of RIP and Financing	The difference between the Cost of the RIP and Financing Attributable to New Growth (Line 15) and the Credit for Ad Valorem Taxes (Line 17). (Line 15 + Line 17)
19	Maximum Assessable Fee Per Service Unit	Found by dividing the Recoverable Cost of the RIP and Financing (Line 18) by the Total Vehicle-Miles of New Demand Over Ten Years (Line 8). (Line 18 / Line 8)





C. Financial Component of Impact Fee Determination

The impact fee determination method employed by NewGen Strategies and Solutions, LLC is developed through a financial based model, which fully recognizes the requirements of Chapter 395, including the recognition of cash and/or debt financing, interest earnings, fund balances, and applicable credits associated with the use of ad valorem taxes. In developing the components of the financial model several assumptions must be made, including the following:

- Financing
 - o Method of financing (i.e. cash or debt financing)
 - The level of financing (e.g. 100% debt)
 - Cost of financing
 - Debt repayment structure
- Timing and Level of Expenditures and Revenues
- Interest Earnings
- Annual Vehicle Mile Growth
- Portion of Ad Valorem Tax Revenue Used to Fund Impact Fee Roadway Improvements

The assumptions employed in the maximum assessable impact fee determination provide a reasonable basis for forecasting; however, it must be emphasized that these assumptions may not necessarily reflect actual future conditions. To address this, Chapter 395 requires the monitoring of impact fees through the Capital Improvements Advisory Committee and allows for the option to update or revise impact fees to reflect the actual implementation of the impact fee program.

Once the cost of capacity added that is attributable to growth (Table 10 - line 11) is determined, it must then be decided how the cost will be financed: cash and/or debt. For any previously funded projects, whether partially funded or in full, actual costs of capital have been included. Based on discussions with City staff, unless specific funding has already been determined, it is assumed that the City will debt finance 50% of the future project costs, and the remaining 50% with cash.





For debt financing, the cost of financing is based on the City staff estimates of future debt costs for bonds issued with 20-year terms, as shown in Appendix E. Debt service payments for each future debt issue are assumed to remain constant over the issue's term.

Currently, the exact timing and annual level of cash capital expenditures over the forecast period is indeterminate; therefore, it is assumed that capital expenditures will occur in equal amounts over the 10-year program period. It is also assumed that for debt-financed capital projects, the City will expend debt proceeds over a 3-year timeframe. For the calculation of the maximum assessable impact fee, debt is assumed to be issued in equal amounts for each year. In order to recognize the full amount of debt to be issued for the cost of capacity added that is attributable to growth during the 10-year period, a portion of years 8, 9, and 10 are assumed to be spent in the final 3 years.

Because debt is issued over 20-year terms and impact fees developed herein are to be charged over a 10-year period, sufficient fund balance must be generated to meet the future debt service obligations. Fund balances were identified for each service area as a potential source for the current Impact Fee CIP. Because of the generation of the fund balance, excess monies will be available for interest earnings.

Chapter 395 states that interest earnings are funds of the impact fee account and are to be held to the same restrictions as impact fee revenues. Therefore, in order to recognize that interest earnings are used to fund only impact fee eligible improvements, interest earnings are credited against the costs recoverable through impact fees. It should be noted that Chapter 395 does not require the upfront recognition of interest earnings in the impact fee determination; however, in an effort to acknowledge the time value of the impact fee payers' monies, interest earnings have been credited. Interest is assumed to be earned at an annual rate of 2% per City staff.

As with the timing and level of the capital expenditures over the 10-year forecast, the timing and annual level of vehicle mile growth over the 10-year program period is indeterminate at the present time. As such, it is assumed that vehicle mile growth will be consistent over the 10-year forecast.





Chapter 395 requires a plan for awarding either a credit for the portion of ad valorem tax and/or utility service revenues generated by new vehicle miles during the program period that are used for payment of improvements that are included in the Roadway Impact Fee CIP. As an alternative, a credit equal to 50% of the total cost of implementing the Roadway Impact Fee CIP may be used. The City has elected to pursue the determination of a credit for the portion of ad valorem tax revenues generated by new vehicle miles during the program period that are used for payment of improvements that are included in the Roadway Impact Fee CIP. It should be noted that the credit is not a determination to recognize the total ad valorem tax revenue generated by new vehicle miles, but is only a credit for the portion of ad valorem tax revenue that is used for payment of improvements that are included in the Roadway Impact Fee CIP. Theoretically, the credit determination could be zero (\$0) if the City does not utilize any of the new vehicle mile ad valorem tax revenue to fund improvements that are included in the Roadway Impact Fee CIP. However, to be conservative and recognize potential cash flow issues that can occur with the funding of major capital improvement projects, it is assumed that the debt-funded projects (50% of the improvement costs included in the Roadway Impact Fee CIP but not otherwise funded) could potentially be funded by ad valorem tax revenue.

Since payments made through ad valorem tax revenue will consist of not only the revenue generated by new vehicle miles in the defined service area, but also existing property owners throughout the City, the portion attributable to the new vehicle miles in the defined service area must be isolated, as illustrated in the credit calculation in Appendix E.





Table 10. Maximum Assessable Roadway Impact Fee

	SERVICE AREA:	A	В	C	D	E	F	G	Н	I	J	K	L	M
1	TOTAL VEH-MI OF CAPACITY ADDED BY THE RIP (FROM RIP UNITS OF SUPPLY, APPENDIX B)	2,653	3,570	43,092	59,041	36,038	0	29,072	19,076	22,925	12,550	10,297	14,785	3,565
2	TOTAL VEH-MI OF EXISTING DEMAND (FROM RIP UNITS OF SUPPLY, APPENDIX B)	0	27	2,321	1,923	3,602	0	10,520	7,085	6,301	7,106	3,061	2	0
3	TOTAL VEH-MI OF EXISTING DEFICIENCIES (FROM EXISTING FACILITIES INVENTORY, APPENDIX C)	0	0	55	663	427	0	0	113	507	1,163	1,972	302	0
4	NET AMOUNT OF VEH-MI OF CAPACITY ADDED (LINE 1 - LINE 2 - LINE 3)	2,653	3,543	40,716	56,455	32,009	0	18,552	11,878	16,117	4,281	5,264	14,481	3,565
5	TOTAL COST OF THE RIP WITHIN SERVICE A REA (FROM TABLE 4)	\$ 9,968,117	\$ 9,711,642	\$ 116,882,308	\$ 189,027,810	\$ 73,733,042	\$ 11,692	\$ 30,219,929	\$ 16,403,341	\$ 35,591,345	\$ 28,206,303	\$ 19,374,692	\$ 27,824,617	\$ 7,866,005
6	COST OF NET CAPACITY SUPPLIED (LINE 4 / LINE 1) * (LINE 5)	\$ 9,968,117	\$ 9,638,193	\$ 110,437,669	\$ 180,748,378	\$ 65,489,787	\$ -	\$ 19,284,539	\$ 10,213,823	\$ 25,021,841	\$ 9,621,608	\$ 9,904,669	\$ 27,252,504	\$ 7,866,005
7	COST TO MEET EXISTING NEEDS AND USAGE (LINE 5 - LINE 6)	\$ -	\$ 73,449	\$ 6,444,639	\$ 8,279,432	\$ 8,243,255	\$ 11,692	\$ 10,935,390	\$ 6,189,518	\$ 10,569,504	\$ 18,584,695	\$ 9,470,023	\$ 572,113	\$ -
8	TOTAL VEH-MI OF NEW DEMAND OVER TEN YEARS (FROM TABLE 8 and Land Use Assumptions)	0	9,578	15,582	41,299	17,845	0	7,742	31,324	18,332	24,864	8,530	1,893	304
9	PERCENT OF CAPACITY ADDED ATTRIBUTABLE TO GROWTH (LINE 8 / LINE 4)	0.0%	270.3%	38.2%	73.1%	55.7%	0.0%	41.7%	263.7%	113.7%	580.7%	162.0%	13.0%	8.5%
10	IF LINE 8 > LINE 4, REDUCE LINE 9 TO 100%, OTHERWISE NO CHANGE	0.0%	100.0%	38.2%	73.1%	55.7%	0.0%	41.7%	100.0%	100.0%	100.0%	100.0%	13.0%	8.5%
11	COST OF CAPACITY ADDED ATTRIBUTABLE TO GROWTH (LINE 6 * LINE 10)	\$ -	\$ 9,638,193	\$ 42,187,190	\$ 132,127,064	\$ 36,477,811	\$ -	\$ 8,041,653	\$ 10,213,823	\$ 25,021,841	\$ 9,621,608	\$ 9,904,669	\$ 3,542,826	\$ 668,610
12	FINANCING COSTS (FROM APPENDIX D)	\$ -	\$ 2,272,855	\$ 9,640,068	\$ 32,193,283	\$ 8,560,746	\$ -	\$ 2,552,974	\$ 2,942,747	\$ 7,106,451	\$ 2,915,731	\$ 2,590,329	\$ 829,021	\$ 157,670
13	EXISTING FUND BALANCE (FROM APPENDIX D)	\$ -	\$ -	\$ (1,784,813)	\$ (131,981)	\$ (129,689)	\$ -	\$ (448,086)	\$ (293,933)	\$ (5,189,258)	\$ (2,179,356)	\$ (779,111)	\$ (5,532)	\$ -
14	INTEREST EARNINGS (FROM APPENDIX D)	\$ -	\$ (1,349,526)	\$ (5,688,458)	\$ (17,212,335)	\$ (5,036,323)	\$ -	\$ (1,137,019)	\$ (1,231,934)	\$ (3,301,274)	\$ (1,467,153)	\$ (1,427,017)	\$ (491,577)	\$ (94,613)
15	COST OF RIP AND FINANCING ATTRIBUTABLE TO GROWTH (LINE 11 + LINE 12 + LINE 13 + LINE 14)	\$ -	\$ 10,561,522	\$ 44,353,987	\$ 146,976,031	\$ 39,872,546	\$ -	\$ 9,009,522	\$ 11,630,704	\$ 23,637,760	\$ 8,890,830	\$ 10,288,870	\$ 3,874,737	\$ 731,667
16	PRE-CREDIT MAX FEE PER SERVICE UNIT (\$ PER VEH-MI) (LINE 15 / LINE 8)	\$ -	\$ 1,103	\$ 2,846	\$ 3,559	\$ 2,234	\$ -	\$ 1,164	\$ 371	\$ 1,289	\$ 358	\$ 1,206	\$ 2,047	\$ 2,407
17	CREDIT FOR AD VALOREM TAXES (FROM APPENDIX D)	\$ -	\$ (82,337)	\$ (601,239)	\$ (5,004,090)	\$ (578,212)	\$ -	\$ (67,194)	\$ (333,123)	\$ (449,003)	\$ (257,003)	\$ (80,502)	\$ (5,956)	\$ (181)
18	RECOVERABLE COST OF RIP AND FINANCING (LINE 15 + LINE 17)	\$ -	\$ 10,479,185	\$ 43,752,749	\$ 141,971,941	\$ 39,294,334	\$ -	\$ 8,942,328	\$ 11,297,580	\$ 23,188,757	\$ 8,633,827	\$ 10,208,369	\$ 3,868,782	\$ 731,486
19	MAX ASSESSABLE FEE PER SERVICE UNIT (\$ PER VEH-MI) (LINE 18 / LINE 8)	\$ -	\$1,094	\$2,808	\$3,438	\$2,202	\$ -	\$1,155	\$361	\$1,265	\$347	\$1,197	\$2,044	\$2,406

54





D. Service Unit Demand Per Unit of Development

The Roadway Impact Fee is determined by multiplying the impact fee rate by the number of service units projected for the proposed development. For this purpose, the City utilizes the Land Use/Vehicle-Mile Equivalency Table (LUVMET), presented in Table 11. This table lists the predominant land uses that may occur within the City of McKinney. For each land use, the development unit that defines the development's magnitude with respect to transportation demand is shown. Although every possible use cannot be anticipated, the majority of local uses are found in this table. If the exact use is not listed, one similar in trip-making characteristics can serve as a reasonable proxy. The individual land uses are grouped into categories, such as residential, office, commercial, industrial, and institutional.

The trip rates presented for each land use is a fundamental component of the LUVMET. The trip rate is the average number of trips generated during the afternoon peak hour by each land use per development unit. The next column in Table 11, if applicable to the land use, presents the number of trips to and from certain land uses reduced by pass-by trips, as previously discussed.

The definitive source of the trip generation and pass-by statistics is the *ITE Trip Generation Manual*, 10th Edition, the latest edition. This manual utilizes trip generation studies for a variety of land uses throughout the United States, and is the standard used by traffic engineers and transportation planners for traffic impact analysis, site design, and transportation planning.

To convert vehicle trips to vehicle-miles, it is necessary to multiply trips by trip length. The trip length values are based on land use, as explained in Chapter IV, section F – Service Unit Calculation.





The remaining column in the LUVMET shows the vehicle-miles per development unit. This number is the product of the trip rate and the maximum trip length. This number, previously referred to as the *Transportation Demand Factor*, is used in the impact fee to compute the number of service units attributed to each land use category. The number of service units is multiplied by the impact fee rate (established by City ordinance) in order to determine the impact fee for a development.

E. Land Use Descriptions

In the process of assessing and collecting roadway impact fees within the City of McKinney, there are instances in which questions have arisen as to the appropriate application of the Land Use / Vehicle-Mile Equivalency Table (LUVMET) when the type of land use may seem to fit into multiple categories. Table 12 provides the City with a more detailed description of the various land uses for the *ITE Trip Generation Manual*, 10th Edition for a reference.

The LUVMET represents the travel demand factors for the most common utilized trip characteristics; however, the formula for the travel demand factor outlined on page 44 could be utilized for new land uses based upon the trip generation rates in a Traffic Impact Analysis that has been approved by the City of McKinney and follows best practices for trip generation as outlined by the ITE Trip Generation Handbook.

For "Flex Space" and similar types of developments which may provide more than one of the land uses provided in these tables, it is recommended that the City request that each land use on site be broken out and individual square footages be provided.





Table 11.A. Service Area A - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Land Use Category	ITELand Use Code	Development Unit	Trip Gen Rate (PM)		Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - A	Veh-Mi Per Dev- Unit SA - A
PORT AND TERMINAL										0.50	
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	0.50	0.94
INDUSTRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	0.50	0.32
Industrial Park	130	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	0.50	0.20
Warehousing Mini-Warehouse	150 151	1,000 SF GFA 1,000 SF GFA	0.19 0.17			0.19	10.02	50%	5.01	0.50	0.10
RESIDENTIAL	131	1,000 SI GI A	0.17			0.17	10.02	3070	5.01	0.50	0.09
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	0.50	0.50
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	0.50	0.28
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	0.50	0.22
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	0.50	0.18
Vertical Mixed Use Mobile Home Park / Manufactured Housing	231 240	Dwelling Unit Dwelling Unit	0.36			0.36	9.79 9.79	50%	4.90 4.90	0.50	0.18
Senior Adult Housing	252	Dwelling Unit	0.46			0.26	9.79	50%	4.90	0.50	0.23
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	0.50	0.09
Assisted Living	254	Beds	0.26			0.26	9.79	50%	4.90	0.50	0.13
LODGING											
Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	0.50	0.30
Motel / Other Lodging Facilities	320	Rooms	0.38	<u> </u>		0.38	6.43	50%	3.22	0.50	0.19
RECREATIONAL	420	I I - 1	201	***************************************		2.01	7.96	500/	2.02	0.50	1.46
Golf Course Miniature Golf Course	430 431	Holes Holes	2.91 0.33			2.91 0.33	7.86 7.86	50%	3.93 3.93	0.50	1.46 0.17
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	0.50	0.63
Multiplex Movie Theater	445	Screens	13.73			13.73	15.77	50%	7.89	0.50	6.87
Ice Skating Rink	465	1,000 SF GFA	1.33			1.33	7.86	50%	3.93	0.50	0.67
Racquet / Tennis Club	491	Courts	3.82			3.82	7.86	50%	3.93	0.50	1.91
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	0.50	1.16
INSTITUTIONAL											
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	0.50	0.09
High School (9-12) Junior / Community College	530 540	Students Students	0.14 0.11			0.14	3.49 10.44	50%	1.75 5.22	0.50	0.07
University / College	550	Students	0.15			0.15	10.44	50%	5.22	0.50	0.08
Church	560	1,000 SF GFA	0.49			0.49	8.31	50%	4.16	0.50	0.25
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	0.50	3.12
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	0.50	0.95
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	0.50	0.11
Clinic Animal Hospital / Veterinary Clinic	630 640	1,000 SF GFA 1,000 SF GFA	3.28	30%	В	3.28 2.47	9.85 9.85	50%	4.93 4.93	0.50	1.64
OFFICE	040	1,000 51 GI 11	3.33	3070	Б	2.77	7.03	3070	4.73	0.50	1.24
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	0.50	0.58
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	0.50	0.30
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	0.50	0.86
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46	9.85	50%	4.93	0.50	1.73
Office Park	750	1,000 SF GFA	1.07	1		1.07	14.65	50%	7.33	0.50	0.54
COMMERCIAL Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	0.50	0.97
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	0.50	1.40
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.87	4.45	0.50	2.23	0.50	1.44
Quick Lubrication Vehicle Shop	941	Servicing Positions	4.85	40%	В	2.91	4.45	50%	2.23	0.50	1.46
Automobile Care Center	942	1,000 SF GLA	3.11	40%	В	1.87	4.45	50%	2.23	0.50	0.94
Gasoline / Service Station w/ Convenience Market	945	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.50	3.08
Self-Service Car Wash	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.50	1.66
Dining Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	0.50	2.19
High Turnover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	0.50	2.79
Fast Food Restaurant	934	1,000 SF GFA	32.67	50%	A	16.34	5.64	50%	2.82	0.50	8.17
Coffee / Donut Shop	937	1,000 SF GFA	43.38	70%	В	13.01	5.64	50%	2.82	0.50	6.51
Other Retail											
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	C	3.38	5.60	50%	2.80	0.50	1.69
Garden Center (Nursery) Shopping Center	817 820	1,000 SF GFA 1,000 SF GLA	6.94 3.81	30% 34%	B A	4.86 2.51	5.60 5.60	50%	2.80	0.50	2.43 1.26
Supermarket	820 850	1,000 SF GLA 1,000 SF GFA	9.24	36%	A	5.91	5.60	50%	2.80	0.50	2.96
Home Improvement Superstore	862	1,000 SF GFA	2.33	42%	A	1.35	5.60	50%	2.80	0.50	0.68
Toy / Children's Superstore	864	1,000 SF GFA	5.00	30%	В	3.50	5.60	50%	2.80	0.50	1.75
Pharmacy / Drugstore	881	1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	0.50	2.63
SERVICES											
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	0.50	3.64
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	0.50	8.83
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	0.50	0.51

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.B. Service Area B - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Table TT.B. Service Area	р - La	IIU USE / VEI	HUIC-	IVIII	LYL	ui v ali	city la	avit	(LU)	IVIL I	/
Land Use Category	ITELand Use Code	Development Unit	Trip Gen Rate (PM)	Pass- by Rate	Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - B	Veh-Mi Per Dev- Unit SA - B
										1.30	
PORT AND TERMINAL											
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	1.30	2.43
INDUSTRIAL	110	1,000 00 001	0.62			0.62	10.02	500/	501	1.20	0.02
General Light Industrial	110 130	1,000 SF GFA 1,000 SF GFA	0.63			0.63	10.02 10.02	50%	5.01	1.30	0.82
Industrial Park Warehousing	150	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	1.30	0.32
Mini-Warehouse	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	1.30	0.22
RESIDENTIAL		.,									
Single-Family Detached Housing	210	Dwelling Unit	0.99	***************************************		0.99	9.79	50%	4.90	1.30	1.29
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	1.30	0.73
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	1.30	0.57
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	1.30	0.47
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	1.30	0.47
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	1.30	0.60
Senior Adult Housing	252 253	Dwelling Unit	0.26			0.26	9.79 9.79	50%	4.90	1.30	0.34
Congregate Care Facility Assisted Living	253	Dwelling Unit Beds	0.18			0.18	9.79	50%	4.90 4.90	1.30	0.23
LODGING	2,74	Dous	0.20			0.20	2.12	50/0	7.70	1.50	0.34
Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	1.30	0.78
Motel / Other Lodging Facilities	320	Rooms	0.38			0.38	6.43	50%	3.22	1.30	0.49
RECREATIONAL											
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	1.30	3.78
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	1.30	0.43
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	1.30	1.63
Multiplex Movie Theater	445	Screens	13.73	***************************************		13.73	15.77	50%	7.89	1.30	17.85
Ice Skating Rink	465	1,000 SF GFA	1.33			1.33	7.86	50%	3.93	1.30	1.73
Racquet / Tennis Club	491	Courts	3.82			3.82	7.86	50%	3.93	1.30	4.97
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	1.30	3.00
INSTITUTIONAL Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.30	0.22
High School (9-12)	530	Students	0.17			0.17	3.49	50%	1.75	1.30	0.18
Junior / Community College	540	Students	0.11			0.11	10.44	50%	5.22	1.30	0.14
University / College	550	Students	0.15			0.15	10.44	50%	5.22	1.30	0.20
Church	560	1,000 SF GFA	0.49			0.49	8.31	50%	4.16	1.30	0.64
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.30	8.10
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	1.30	2.46
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	1.30	0.29
Clinic	630	1,000 SF GFA	3.28			3.28	9.85	50%	4.93	1.30	4.26
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	1.30	3.21
OFFICE	710	1 000 00 001					11.55	500/	7.00	1.00	1.50
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	1.30	1.50
Corporate Headquarters Building Single Tenant Office Building	714 715	1,000 SF GFA 1,000 SF GFA	0.60 1.71			0.60	14.65 14.65	50%	7.33 7.33	1.30	2.22
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46	9.85	50%	4.93	1.30	4.50
Office Park	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	1.30	1.39
COMMERCIAL		,									
Automobile Related						***************************************				***************************************	
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	1.30	2.52
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	1.30	3.64
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.87	4.45	0.50	2.23	1.30	3.73
Quick Lubrication Vehicle Shop	941	Servicing Positions	4.85	40%	В	2.91	4.45	50%	2.23	1.30	3.78
Automobile Care Center	942	1,000 SF GLA	3.11	40%	В	1.87	4.45	50%	2.23	1.30	2.43
Gasoline / Service Station w/ Convenience Market Self-Service Car Wash	945 947	Vehicle Fueling Positions Stalls	13.99 5.54	56% 40%	A B	6.16 3.32	1.20 1.20	50%	0.60	0.60	3.70 1.99
Dining	747	Stans	3.34	4070	ь	3.32	1.20	3070	0.00	0.00	1.99
Sit-Down Restaurant	931	1.000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	1.30	5.68
High Turnover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	1.30	7.24
Fast Food Restaurant	934	1,000 SF GFA	32.67	50%	A	16.34	5.64	50%	2.82	1.30	21.24
Coffee / Donut Shop	937	1,000 SF GFA	43.38	70%	В	13.01	5.64	50%	2.82	1.30	16.91
Other Retail											
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	1.30	4.39
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	1.30	6.32
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	1.30	3.26
Supermarket	850	1,000 SF GFA	9.24	36%	A	5.91	5.60	50%	2.80	1.30	7.68
Home Improvement Superstore	862	1,000 SF GFA	2.33	42%	A	1.35	5.60	50%	2.80	1.30	1.76
Toy / Children's Superstore Pharmacy / Drugstore	864 881	1,000 SF GFA 1,000 SF GFA	5.00 10.29	30% 49%	B	3.50	5.60	50%	2.80	1.30	4.55
Pharmacy / Drugstore SERVICES	081	1,000 SF GFA	10.29	45%	A	5.25	5.60	<i>3</i> U%	2.80	1.30	6.83
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	1.30	9.46
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	1.30	22.95
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	1.30	1.33
	/10	1,000 51 0171	1.70			Page by D		50/0	J.21	1.50	1.55

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.C. Service Area C - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Table TT.C. Service Area	I C - La	ilia ose / vei	ilicie-	IVIII	e Eqi	uivai	ency i	abit	(LU)	/ IVIL I)
Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)	Pass- by Rate	Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - C	Veh-Mi Per Dev- Unit SA - C
										4.00	
PORT AND TERMINAL											
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	4.00	7.48
INDUSTRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	4.00	2.52
Industrial Park	130	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	4.00	1.60
Warehousing Mini-Warehouse	150 151	1,000 SF GFA 1,000 SF GFA	0.19 0.17			0.19	10.02 10.02	50%	5.01	4.00	0.76
RESIDENTIAL	131	1,000 SF GFA	0.17			0.17	10.02	3070	3.01	4.00	0.06
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	4.00	3.96
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	4.00	2.24
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	4.00	1.76
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.00	1.44
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.00	1.44
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	4.00	1.84
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	4.00	1.04
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	4.00	0.72
Assisted Living	254	Beds	0.26			0.26	9.79	50%	4.90	4.00	1.04
LODGING Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
Motel / Other Lodging Facilities	310	Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
RECREATIONAL	320	KOOHS	0.38			0.38	0.43	30%	3.22	3.22	1.22
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	3.93	11.44
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.93	1.30
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	3.93	4.91
Multiplex Movie Theater	445	Screens	13.73			13.73	15.77	50%	7.89	4.00	54.92
Ice Skating Rink	465	1,000 SF GFA	1.33			1.33	7.86	50%	3.93	3.93	5.23
Racquet / Tennis Club	491	Courts	3.82	*******************************		3.82	7.86	50%	3.93	3.93	15.01
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	3.93	9.08
INSTITUTIONAL											
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
High School (9-12)	530	Students	0.14			0.14	3.49	50%	1.75	1.75	0.25
Junior / Community College	540	Students	0.11			0.11	10.44	50%	5.22	4.00	0.44
University / College	550	Students	0.15			0.15	10.44	50%	5.22	4.00	0.60
Church	560	1,000 SF GFA	0.49	4.40/	- D	0.49	8.31	50%	4.16	4.00	1.96
Day Care Center MEDICAL	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	4.00	7.56
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	4.00	0.88
Clinic	630	1,000 SF GFA	3.28			3.28	9.85	50%	4.93	4.00	13.12
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	4.00	9.88
OFFICE		,									
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	4.00	4.60
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	4.00	2.40
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	4.00	6.84
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46	9.85	50%	4.93	4.00	13.84
Office Park	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	4.00	4.28
COMMERCIAL											
Automobile Related	040	1,000 CE CE 4	2.42	200/	P	1.04	5.00	500/	2.00	2.00	F 12
New and Used Car Sales Automobile Parts Sales	840 843	1,000 SF GFA 1,000 SF GFA	2.43 4.91	20%	В	1.94 2.80	5.60 4.45	50%	2.80	2.80	5.43 6.24
Tire Store	843	1,000 SF GFA 1,000 SF GFA	3.98	28%	A A	2.80	4.45	0.50	2.23	2.23	6.40
Ouick Lubrication Vehicle Shop	941	Servicing Positions	4.85	40%	B	2.91	4.45	50%	2.23	2.23	6.49
Automobile Care Center	942	1,000 SF GLA	3.11	40%	В	1.87	4.45	50%	2.23	2.23	4.17
Gasoline / Service Station w/ Convenience Market	945	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.60	1.99
Dining											
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	2.82	12.32
High Turnover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	2.82	15.71
Fast Food Restaurant	934	1,000 SF GFA	32.67	50%	A	16.34	5.64	50%	2.82	2.82	46.08
Coffee / Donut Shop	937	1,000 SF GFA	43.38	70%	В	13.01	5.64	50%	2.82	2.82	36.69
Other Retail	01.5	1,000 65 654	4.00	2001		2.20	5.00	5001	200	200	0.15
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	C	3.38	5.60	50%	2.80	2.80	9.46
Garden Center (Nursery) Shopping Center	817 820	1,000 SF GFA 1,000 SF GLA	6.94 3.81	30%	B A	4.86 2.51	5.60 5.60	50%	2.80	2.80	7.03
Snopping Center Supermarket	850	1,000 SF GLA 1,000 SF GFA	9.24	36%	A	5.91	5.60	50%	2.80	2.80	16.55
Home Improvement Superstore	862	1,000 SF GFA	2.33	42%	A	1.35	5.60	50%	2.80	2.80	3.78
Toy / Children's Superstore	864	1,000 SF GFA	5.00	30%	В	3.50	5.60	50%	2.80	2.80	9.80
Pharmacy / Drugstore	881	1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	2.80	14.70
SERVICES											
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	2.23	16.23
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	2.23	39.36
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	3.21	3.27
	_	_	_	**		Doce by D		_	_		

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.D. Service Area D - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Land Use Category	ITELand Use Code	Development Unit	Trip Gen Rate (PM)		Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - D	Veh-Mi Per Dev- Unit SA - D
PORT AND TERMINAL											
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	5.01	9.37
INDUSTRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	5.01	3.16
Industrial Park Warehousing	130 150	1,000 SF GFA 1,000 SF GFA	0.40			0.40	10.02 10.02	50%	5.01	5.01	2.00 0.95
Mini-Warehouse	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	5.01	0.85
RESIDENTIAL		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,									
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	4.90	4.85
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	4.90	2.74
Apartment / Multifamily Multifamily Housing (High-Rise)	221 222	Dwelling Unit Dwelling Unit	0.44			0.44	9.79 9.79	50%	4.90 4.90	4.90	2.16
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.90	1.76
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	4.90	2.25
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	4.90	1.27
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	4.90	0.88
Assisted Living	254	Beds	0.26			0.26	9.79	50%	4.90	4.90	1.27
LODGING Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
Motel / Other Lodging Facilities	320	Rooms	0.38			0.38	6.43	50%	3.22	3.22	1.22
RECREATIONAL											
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	3.93	11.44
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.93	1.30
Golf Driving Range	432 445	Driving Positions	1.25			1.25	7.86 15.77	50%	3.93 7.89	3.93	4.91 82.38
Multiplex Movie Theater Ice Skating Rink	445	Screens 1,000 SF GFA	13.73			13.73	7.86	50%	3.93	6.00 3.93	5.23
Racquet / Tennis Club	491	Courts	3.82	***************************************		3.82	7.86	50%	3.93	3.93	15.01
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	3.93	9.08
INSTITUTIONAL											
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
High School (9-12)	530 540	Students	0.14			0.14	3.49 10.44	50%	1.75	1.75	0.25
Junior / Community College University / College	550	Students Students	0.11			0.11	10.44	50%	5.22 5.22	5.22	0.37
Church	560	1,000 SF GFA	0.49			0.49	8.31	50%	4.16	4.16	2.04
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	4.93	9.32
Nursing Home Clinic	620 630	Beds 1,000 SF GFA	0.22 3.28			0.22 3.28	9.85 9.85	50%	4.93 4.93	4.93	1.08
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	4.93	12.18
OFFICE		.,			_						
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	6.00	6.90
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	6.00	3.60
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	6.00	10.26
Medical / Dental Office Office Park	720 750	1,000 SF GFA 1,000 SF GFA	3.46 1.07			3.46 1.07	9.85 14.65	50%	4.93 7.33	4.93 6.00	17.06 6.42
COMMERCIAL	750	1,000 SI GI A	1.07			1.07	14.03	5070	1.55	0.00	0.42
Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	2.80	5.43
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	2.23	6.24
Tire Store	848	1,000 SF GFA	3.98	28%	A B	2.87	4.45 4.45	0.50	2.23	2.23	6.40
Quick Lubrication Vehicle Shop Automobile Care Center	941 942	Servicing Positions 1,000 SF GLA	4.85 3.11	40%	В	2.91 1.87	4.45	50%	2.23	2.23	6.49 4.17
Gasoline / Service Station w/ Convenience Market	945	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.60	1.99
Dining											
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	2.82	12.32
High Turnover (Sit-Down) Restaurant Fast Food Restaurant	932 934	1,000 SF GFA 1,000 SF GFA	9.77 32.67	43% 50%	A A	5.57 16.34	5.64 5.64	50%	2.82	2.82	15.71 46.08
Coffee / Donut Shop	934	1,000 SF GFA	43.38	70%	B	13.01	5.64	50%	2.82	2.82	36.69
Other Retail		-,		. 570			2.01	2370			2.00
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	2.80	9.46
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	2.80	13.61
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	2.80	7.03
Supermarket Home Improvement Superstore	850 862	1,000 SF GFA 1,000 SF GFA	9.24 2.33	36% 42%	A A	5.91 1.35	5.60 5.60	50%	2.80	2.80	16.55 3.78
Toy / Children's Superstore	864	1,000 SF GFA	5.00	30%	A B	3.50	5.60	50%	2.80	2.80	9.80
Pharmacy / Drugstore	881	1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	2.80	14.70
SERVICES											
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	2.23	16.23
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	2.23	39.36
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	3.21	3.27

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.E. Service Area E - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)		Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - E	Veh-Mi Per Dev- Unit SA - E
PORT AND TERMINAL										7.00	
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	4.80	8.98
INDUSTRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	4.80	3.02
Industrial Park	130 150	1,000 SF GFA 1,000 SF GFA	0.40			0.40	10.02 10.02	50%	5.01	4.80	1.92 0.91
Warehousing Mini-Warehouse	151	1,000 SF GFA	0.19			0.19	10.02	50%	5.01	4.80	0.91
RESIDENTIAL		1,000 51 6111	0.17			0.17	10.02	2070	5.01	1.00	0.02
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	4.80	4.75
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	4.80	2.69
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	4.80	2.11
Multifamily Housing (High-Rise) Vertical Mixed Use	222 231	Dwelling Unit Dwelling Unit	0.36			0.36	9.79 9.79	50%	4.90 4.90	4.80	1.73
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.36	9.79	50%	4.90	4.80	2.21
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	4.80	1.25
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	4.80	0.86
Assisted Living	254	Beds	0.26			0.26	9.79	50%	4.90	4.80	1.25
LODGING	210	D-	0.00			0.00	6.42	E00/	2.22	2.22	1.02
Hotel Motel / Other Lodging Facilities	310 320	Rooms Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
RECREATIONAL	320	ROOMS	0.36			0.36	0.43	5070	3.44	<i>عد.د</i>	1.22
Golf Course	430	Holes	2.91		•••••	2.91	7.86	50%	3.93	3.93	11.44
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.93	1.30
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	3.93	4.91
Multiplex Movie Theater	445 465	Screens	13.73			13.73	15.77	50%	7.89 3.93	4.80	65.90
Ice Skating Rink Racquet / Tennis Club	491	1,000 SF GFA Courts	1.33 3.82			3.82	7.86 7.86	50%	3.93	3.93	5.23 15.01
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	3.93	9.08
INSTITUTIONAL		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,									
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
High School (9-12)	530	Students	0.14			0.14	3.49	50%	1.75	1.75	0.25
Junior / Community College	540 550	Students Students	0.11			0.11	10.44 10.44	50%	5.22 5.22	4.80	0.53
University / College Church	560	1,000 SF GFA	0.13			0.13	8.31	50%	4.16	4.16	2.04
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	4.80	9.07
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	4.80	1.06
Clinic Animal Hospital / Veterinary Clinic	630 640	1,000 SF GFA 1,000 SF GFA	3.28	30%	В	3.28 2.47	9.85 9.85	50%	4.93 4.93	4.80	15.74 11.86
OFFICE	040	1,000 31 GFA	5.55	3070	ь	2.47	9.63	3070	4.93	4.00	11.00
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	4.80	5.52
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	4.80	2.88
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	4.80	8.21
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46	9.85	50%	4.93	4.80	16.61
Office Park COMMERCIAL	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	4.80	5.14
Automobile Related		***************************************									
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	2.80	5.43
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	2.23	6.24
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.87	4.45	0.50	2.23	2.23	6.40
Quick Lubrication Vehicle Shop	941 942	Servicing Positions 1,000 SF GLA	4.85 3.11	40%	B B	2.91 1.87	4.45 4.45	50%	2.23	2.23	6.49 4.17
Automobile Care Center Gasoline / Service Station w/ Convenience Market	942	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.60	1.99
Dining											
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	2.82	12.32
High Turnover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	2.82	15.71
Fast Food Restaurant Coffee / Donut Shop	934 937	1,000 SF GFA 1,000 SF GFA	32.67 43.38	50% 70%	A B	16.34 13.01	5.64 5.64	50%	2.82	2.82	46.08 36.69
Other Retail	731	1,000 SF GFA	73.30	7070	D	1.0.01	5.04	5070	2.02	4.04	30.09
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	2.80	9.46
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	2.80	13.61
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	2.80	7.03
Supermarket	850	1,000 SF GFA	9.24	36%	A	5.91	5.60	50%	2.80	2.80	16.55
Home Improvement Superstore Toy / Children's Superstore	862 864	1,000 SF GFA 1,000 SF GFA	2.33 5.00	42% 30%	A B	1.35 3.50	5.60 5.60	50%	2.80	2.80	3.78 9.80
Pharmacy / Drugstore	881	1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	2.80	14.70
SERVICES		,									
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	2.23	16.23
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	2.23	39.36
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	3.21	3.27

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.F. Service Area F - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Table TT.F. Service Area	ı - La	ilu use / vei	IICIE-	IVIII	Lyu	iivait	ency ra	anie	(LU V	/ IVIL I ,	1
Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)	Pass- by Rate	Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - F	Veh-Mi Per Dev- Unit SA - F
										0.00	
PORT AND TERMINAL											
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	0.00	0.00
INDUSTRIAL	110	1 000 00 001	0.62			0.62	10.02	500/	501	0.00	0.00
General Light Industrial	110	1,000 SF GFA 1,000 SF GFA	0.63			0.63	10.02 10.02	50%	5.01	0.00	0.00
Industrial Park Warehousing	150	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	0.00	0.00
Mini-Warehouse	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	0.00	0.00
RESIDENTIAL		.,									
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	0.00	0.00
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	0.00	0.00
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	0.00	0.00
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	0.00	0.00
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	0.00	0.00
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	0.00	0.00
Senior Adult Housing Congregate Care Facility	252 253	Dwelling Unit	0.26			0.26	9.79 9.79	50%	4.90 4.90	0.00	0.00
Assisted Living	253	Dwelling Unit Beds	0.18			0.18	9.79	50%	4.90	0.00	0.00
LODGING	2,74	Dous	0.20	l		0.20	2.12	50/0	7.70	0.00	0.00
Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	0.00	0.00
Motel / Other Lodging Facilities	320	Rooms	0.38			0.38	6.43	50%	3.22	0.00	0.00
RECREATIONAL											
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	0.00	0.00
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	0.00	0.00
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	0.00	0.00
Multiplex Movie Theater	445	Screens	13.73			13.73	15.77	50%	7.89	0.00	0.00
Ice Skating Rink	465	1,000 SF GFA	1.33	**************		1.33	7.86	50%	3.93	0.00	0.00
Racquet / Tennis Club	491	Courts	3.82			3.82	7.86	50%	3.93	0.00	0.00
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	0.00	0.00
INSTITUTIONAL Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	0.00	0.00
High School (9-12)	530	Students	0.17			0.17	3.49	50%	1.75	0.00	0.00
Junior / Community College	540	Students	0.11			0.11	10.44	50%	5.22	0.00	0.00
University / College	550	Students	0.15			0.15	10.44	50%	5.22	0.00	0.00
Church	560	1,000 SF GFA	0.49			0.49	8.31	50%	4.16	0.00	0.00
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	0.00	0.00
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	0.00	0.00
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	0.00	0.00
Clinic	630	1,000 SF GFA	3.28			3.28	9.85	50%	4.93	0.00	0.00
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	0.00	0.00
OFFICE	710	1,000 00 001					11.55	500/	7.00	0.00	0.00
General Office Building	710 714	1,000 SF GFA 1,000 SF GFA	1.15 0.60			1.15 0.60	14.65 14.65	50%	7.33 7.33	0.00	0.00
Corporate Headquarters Building Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	0.00	0.00
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46	9.85	50%	4.93	0.00	0.00
Office Park	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	0.00	0.00
COMMERCIAL											
Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	0.00	0.00
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	0.00	0.00
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.87	4.45	0.50	2.23	0.00	0.00
Quick Lubrication Vehicle Shop	941	Servicing Positions	4.85	40%	В	2.91	4.45	50%	2.23	0.00	0.00
Automobile Care Center Gasoline / Service Station w/ Convenience Market	942 945	1,000 SF GLA	3.11	40%	В	1.87	4.45	50%	2.23	0.00	0.00
Self-Service Car Wash	943	Vehicle Fueling Positions Stalls	13.99 5.54	56% 40%	A B	6.16 3.32	1.20 1.20	50%	0.60	0.00	0.00
Dining	741	Stans	3.54	4070	ь	3.32	1.20	3070	0.00	0.00	0.00
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	0.00	0.00
High Turnover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	0.00	0.00
Fast Food Restaurant	934	1,000 SF GFA	32.67	50%	A	16.34	5.64	50%	2.82	0.00	0.00
Coffee / Donut Shop	937	1,000 SF GFA	43.38	70%	В	13.01	5.64	50%	2.82	0.00	0.00
Other Retail											
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	0.00	0.00
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	0.00	0.00
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	0.00	0.00
Supermarket	850	1,000 SF GFA	9.24	36%	A	5.91	5.60	50%	2.80	0.00	0.00
Home Improvement Superstore	862 864	1,000 SF GFA 1,000 SF GFA	2.33 5.00	42%	A B	1.35	5.60	50%	2.80	0.00	0.00
Toy / Children's Superstore Pharmacy / Drugstore	864	1,000 SF GFA 1,000 SF GFA	10.29	30% 49%	A	3.50 5.25	5.60 5.60	50%	2.80	0.00	0.00
SERVICES	001	1,000 SF GFA	10.27	→ J70	А	3.43	5.00	JU70	2.00	0.00	0.00
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	0.00	0.00
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	0.00	0.00
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	0.00	0.00
		, ,,,,,,,,				Poss by D					

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.G. Service Area G - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Table 11.G. Service Area	<u> </u>	110 030 / 10	111010	IVII	· 4	uivu	iorioy	uvi	~ (LU	v IVIL	٠/
Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)	Pass- by Rate	Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - G	Veh-Mi Per Dev- Unit SA - G
										6.00	
PORT AND TERMINAL											
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	5.01	9.37
INDUSTRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	5.01	3.16
Industrial Park	130	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	5.01	2.00
Warehousing	150	1,000 SF GFA	0.19			0.19	10.02	50%	5.01	5.01	0.95
Mini-Warehouse	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	5.01	0.85
RESIDENTIAL	210	D 11. 11.	0.00			0.00	0.70	500/	4.00	1.00	4.07
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	4.90	4.85
Residentail Condominium / Townhome Apartment / Multifamily	220 221	Dwelling Unit Dwelling Unit	0.56 0.44			0.56	9.79 9.79	50%	4.90	4.90	2.74
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.44			0.36	9.79	50%	4.90	4.90	1.76
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.90	1.76
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	4.90	2.25
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	4.90	1.27
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	4.90	0.88
Assisted Living	254	Beds	0.16			0.16	9.79	50%	4.90	4.90	1.27
LODGING						20		2.370	,0		
Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
Motel / Other Lodging Facilities	320	Rooms	0.38			0.38	6.43	50%	3.22	3.22	1.22
RECREATIONAL											
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	3.93	11.44
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.93	1.30
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	3.93	4.91
Multiplex Movie Theater	445	Screens	13.73			13.73	15.77	50%	7.89	6.00	82.38
Ice Skating Rink	465	1,000 SF GFA	1.33			1.33	7.86	50%	3.93	3.93	5.23
Racquet / Tennis Club	491	Courts	3.82			3.82	7.86	50%	3.93	3.93	15.01
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	3.93	9.08
INSTITUTIONAL											
Primary/Middle School (1-8)	522	Students	0.17	***************************************		0.17	3.49	50%	1.75	1.75	0.30
High School (9-12)	530	Students	0.14			0.14	3.49	50%	1.75	1.75	0.25
Junior / Community College	540	Students	0.11			0.11	10.44	50%	5.22	5.22	0.57
University / College	550	Students	0.15			0.15	10.44	50%	5.22	5.22	0.78
Church	560	1,000 SF GFA	0.49			0.49	8.31	50%	4.16	4.16	2.04
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	4.93	9.32
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	4.93	1.08
Clinic	630	1,000 SF GFA	3.28			3.28	9.85	50%	4.93	4.93	16.17
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	4.93	12.18
OFFICE											
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	6.00	6.90
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	6.00	3.60
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	6.00	10.26
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46	9.85	50%	4.93	4.93	17.06
Office Park	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	6.00	6.42
COMMERCIAL											
Automobile Related	040	1 000 SE CEA	2.42	200/	P	1.04	5.60	500/	2.00	200	5.42
New and Used Car Sales Automobile Parts Sales	840 843	1,000 SF GFA 1,000 SF GFA	2.43 4.91	20% 43%	В	1.94 2.80	5.60 4.45	50%	2.80	2.80	5.43 6.24
Tire Store	843	1,000 SF GFA 1,000 SF GFA	3.98	28%	A A	2.80	4.45	0.50	2.23	2.23	6.40
~~~	941	Servicing Positions	4.85	40%	B	2.91	4.45	50%	2.23	2.23	6.49
Quick Lubrication Vehicle Shop  Automobile Care Center	941	1,000 SF GLA	3.11	40%	В	1.87	4.45	50%	2.23	2.23	4.17
Gasoline / Service Station w/ Convenience Market	942	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	943	Stalls	5.54	40%	B	3.32	1.20	50%	0.60	0.60	1.99
Dining	741	Galls	٠.٠٠	70/0		2.32	1.20	50/0	0.00	0.00	1.99
		1		44%	A	4.37	5.64	50%	2.82	2.82	12.32
	931	1.000 SF GFA	7.80					20/0			
Sit-Down Restaurant	931 932	1,000 SF GFA 1,000 SF GFA	7.80 9.77				~~~~	50%		2,82	15.71
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant	931 932 934	1,000 SF GFA	7.80 9.77 32.67	43%	Α	5.57	5.64 5.64	50% 50%	2.82	2.82	15.71 46.08
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant	932 934	1,000 SF GFA 1,000 SF GFA	9.77 32.67	43%	A A	5.57 16.34	5.64 5.64		2.82 2.82	2.82	46.08
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43% 50%	Α	5.57	5.64	50%	2.82		
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop	932 934	1,000 SF GFA 1,000 SF GFA	9.77 32.67	43% 50%	A A	5.57 16.34	5.64 5.64	50%	2.82 2.82	2.82	46.08
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail	932 934 937	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38	43% 50% 70%	A A B	5.57 16.34 13.01	5.64 5.64 5.64	50% 50%	2.82 2.82 2.82	2.82	46.08 36.69
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Garden Center (Nursery)	932 934 937 815	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83	43% 50% 70% 30%	A A B	5.57 16.34 13.01 3.38	5.64 5.64 5.64 5.60	50% 50%	2.82 2.82 2.82 2.82	2.82 2.82 2.80	46.08 36.69 9.46
Sit-Down Restaurant   High Tumover (Sit-Down) Restaurant   Fast Food Restaurant   Coffee / Donut Shop   Other Retail   Free-Standing Retail Store	932 934 937 815 817	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94	43% 50% 70% 30% 30%	A A B C B	5.57 16.34 13.01 3.38 4.86	5.64 5.64 5.64 5.60 5.60	50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80	2.82 2.82 2.80 2.80	46.08 36.69 9.46 13.61
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Carden Center (Nursery) Shopping Center	932 934 937 815 817 820	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81	43% 50% 70% 30% 30% 34%	A A B C B A	5.57 16.34 13.01 3.38 4.86 2.51	5.64 5.64 5.64 5.60 5.60 5.60	50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80	2.82 2.82 2.80 2.80 2.80	46.08 36.69 9.46 13.61 7.03
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Carden Center (Nursery) Shopping Center Supermarket	932 934 937 815 817 820 850	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GIA 1,000 SF GIA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24	43% 50% 70% 30% 30% 34% 36%	A B C B A A	5.57 16.34 13.01 3.38 4.86 2.51 5.91	5.64 5.64 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80	2.82 2.82 2.80 2.80 2.80 2.80	9.46 13.61 7.03 16.55
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Carden Center (Nursery) Shopping Center Supermarket Home Improvement Superstore	932 934 937 815 817 820 850	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GIA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24 2.33	43% 50% 70% 30% 30% 34% 36% 42%	A B C B A A A	5.57 16.34 13.01 3.38 4.86 2.51 5.91 1.35	5.64 5.64 5.64 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	2.82 2.82 2.80 2.80 2.80 2.80 2.80	9.46 13.61 7.03 16.55 3.78
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Carden Center (Nursery) Shopping Center Supermarket Home Improvement Superstore Toy / Children's Superstore	932 934 937 815 817 820 850 862	1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24 2.33 5.00	43% 50% 70% 30% 30% 34% 36% 42% 30%	A B C B A A A B B	5.57 16.34 13.01 3.38 4.86 2.51 5.91 1.35 3.50	5.64 5.64 5.64 5.60 5.60 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	2.82 2.82 2.80 2.80 2.80 2.80 2.80 2.80	9.46 13.61 7.03 16.55 3.78 9.80
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Carden Center (Nursery) Shopping Center Supermarket Home Improvement Superstore Toy / Children's Superstore Pharmacy / Drugstore	932 934 937 815 817 820 850 862	1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24 2.33 5.00	43% 50% 70% 30% 30% 34% 36% 42% 30%	A B C B A A A B B	5.57 16.34 13.01 3.38 4.86 2.51 5.91 1.35 3.50	5.64 5.64 5.64 5.60 5.60 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	2.82 2.82 2.80 2.80 2.80 2.80 2.80 2.80	9.46 13.61 7.03 16.55 3.78 9.80
Sit-Down Restaurant   High Tumover (Sit-Down) Restaurant   Fast Food Restaurant   Coffee / Donut Shop   Other Retail   Free-Standing Retail Store   Garden Center (Nursery)   Shopping Center   Supermarket   Home Improvement Superstore   Toy / Children's Superstore   Pharmacy / Drugstore   SERVICES	932 934 937 815 817 820 850 862 864 881	1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24 2.33 5.00 10.29	43% 50% 70% 30% 30% 34% 36% 42% 30% 49%	A A B C B A A A A A A A B A	5.57 16.34 13.01 3.38 4.86 2.51 5.91 1.35 3.50 5.25	5.64 5.64 5.64 5.60 5.60 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	2.82 2.82 2.80 2.80 2.80 2.80 2.80 2.80	9.46 13.61 7.03 16.55 3.78 9.80 14.70

A: ITE Trip Generation Handbook 3rd Edition (September 2017)
B: Estimated by Kimley-Horn based on ITE rates for similar categories

B: Estimated by Kimley-Horn based on ITE rates for similar categories
C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.H. Service Area H - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Table 11.H. Service Area	П - La	iliu use / ve	ilicie.	-17111	e cqi	uivai	ency i	abit	(LU	/ IVIL I	)
Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)	Pass- by Rate	Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - H	Veh-Mi Per Dev- Unit SA - H
										4.65	
PORT AND TERMINAL											
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	4.65	8.70
INDUSTRIAL	110	1 000 00 001	0.62			0.62	10.02	500/	501	1	2.02
General Light Industrial	110	1,000 SF GFA 1,000 SF GFA	0.63			0.63	10.02 10.02	50%	5.01	4.65 4.65	2.93
Industrial Park Warehousing	150	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	4.65	0.88
Mini-Warehouse	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	4.65	0.79
RESIDENTIAL		.,									,
Single-Family Detached Housing	210	Dwelling Unit	0.99	***************************************		0.99	9.79	50%	4.90	4.65	4.60
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	4.65	2.60
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	4.65	2.05
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.65	1.67
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.65	1.67
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	4.65	2.14
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	4.65	1.21
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79 9.79	50%	4.90 4.90	4.65	0.84
Assisted Living LODGING	254	Beds	0.26			0.26	7.19	JU%	4.90	4.65	1.21
Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
Motel / Other Lodging Facilities	320	Rooms	0.38			0.38	6.43	50%	3.22	3.22	1.22
RECREATIONAL	520	ACOIII)	0.50			0.50	5.75	20/0	J.22	2.22	1,22
Golf Course	430	Holes	2.91	***************************************		2.91	7.86	50%	3.93	3.93	11.44
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.93	1.30
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	3.93	4.91
Multiplex Movie Theater	445	Screens	13.73			13.73	15.77	50%	7.89	4.65	63.84
Ice Skating Rink	465	1,000 SF GFA	1.33			1.33	7.86	50%	3.93	3.93	5.23
Racquet / Tennis Club	491	Courts	3.82			3.82	7.86	50%	3.93	3.93	15.01
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	3.93	9.08
INSTITUTIONAL				***************************************							
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
High School (9-12)	530	Students	0.14			0.14	3.49	50%	1.75	1.75	0.25
Junior / Community College	540	Students	0.11			0.11	10.44	50%	5.22	4.65	0.51
University / College	550	Students	0.15			0.15	10.44	50%	5.22	4.65	0.70
Church	560	1,000 SF GFA	0.49	4.40/	- D	0.49	8.31	50%	4.16	4.16	2.04
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
MEDICAL	610	D- J-	1.00			1.00	0.95	50%	4.93	1.65	8.79
Hospital Nursing Home	610 620	Beds Beds	1.89 0.22			1.89 0.22	9.85 9.85	50%	4.93	4.65 4.65	1.02
Clinic	630	1,000 SF GFA	3.28			3.28	9.85	50%	4.93	4.65	15.25
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	4.65	11.49
OFFICE		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,									
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	4.65	5.35
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	4.65	2.79
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	4.65	7.95
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46	9.85	50%	4.93	4.65	16.09
Office Park	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	4.65	4.98
COMMERCIAL											
Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	2.80	5.43
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	2.23	6.24
Tire Store Ouick Lubrication Vehicle Shop	848 941	1,000 SF GFA	3.98 4.85	28%	A B	2.87	4.45 4.45	0.50	2.23	2.23	6.40
Automobile Care Center	941	Servicing Positions 1,000 SF GLA	3.11	40%	В	1.87	4.45 4.45	50%	2.23	2.23	6.49 4.17
Gasoline / Service Station w/ Convenience Market	942	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	947	Stalls	5.54	40%	B	3.32	1.20	50%	0.60	0.60	1.99
Dining						2.02	20	2070	2.00	5.00	
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	2.82	12.32
High Turnover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	2.82	15.71
Fast Food Restaurant	934	1,000 SF GFA	32.67	50%	A	16.34	5.64	50%	2.82	2.82	46.08
Coffee / Donut Shop	937	1,000 SF GFA	43.38	70%	В	13.01	5.64	50%	2.82	2.82	36.69
Other Retail											
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	2.80	9.46
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	2.80	13.61
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	2.80	7.03
Supermarket	850	1,000 SF GFA	9.24	36%	A	5.91	5.60	50%	2.80	2.80	16.55
Home Improvement Superstore	862	1,000 SF GFA	2.33	42%	A	1.35	5.60	50%	2.80	2.80	3.78
Toy / Children's Superstore Pharmacy / Drugstore	864	1,000 SF GFA	5.00	30%	B	3.50	5.60	50%	2.80	2.80	9.80
Pharmacy / Drugstore   SERVICES	881	1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	2.80	14.70
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	2.23	16.23
Drive-In Bank	911	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	2.23	39.36
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	3.21	3.27
1 CISORAL DELYBEC	210	1,000 SF UFA	1.43			Poss by D		JU70	J.Z1	J.21	3.41

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.I. Service Area I - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Table 11.1. Service Area		iu use / vei	Trip Gen					Adj.	Adj. Trip	Max Trip	Veh-Mi Per Dev-
Land Use Category	ITE Land Use Code	Development Unit	Rate (PM)	by Rate	Pass-by Source	Trip Rate	Trip Length (mi)	For O-D	Length (mi)	Length (mi) SA - I	Unit SA - I
DODE AND SEDAMIA										6.00	
PORT AND TERMINAL Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	5.01	9.37
INDUSTRIAL	030	1,000 51 G/1	1.07			1.07	10.02	3070	5.01	3.01	7.51
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	5.01	3.16
Industrial Park	130	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	5.01	2.00
Warehousing	150	1,000 SF GFA	0.19			0.19	10.02	50%	5.01	5.01	0.95
Mini-Warehouse RESIDENTIAL	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	5.01	0.85
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	4.90	4.85
Residentail Condominium/ Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	4.90	2.74
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	4.90	2.16
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.90	1.76
Vertical Mixed Use  Mobile Home Park / Manufactured Housing	231	Dwelling Unit Dwelling Unit	0.36			0.36	9.79 9.79	50%	4.90	4.90 4.90	1.76 2.25
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	4.90	1.27
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	4.90	0.88
Assisted Living	254	Beds	0.26			0.26	9.79	50%	4.90	4.90	1.27
LODGING	2:-		0			0			2	2	
Hotel Motel / Other Lodging Facilities	310	Rooms	0.60		ļ	0.60	6.43	50%	3.22	3.22	1.93
Motel / Other Lodging Facilities RECREATIONAL	320	Rooms	0.38			0.38	6.43	50%	3.22	3.22	1.22
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	3.93	11.44
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.93	1.30
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	3.93	4.91
Multiplex Movie Theater	445	Screens	13.73			13.73	15.77	50%	7.89	6.00	82.38
Ice Skating Rink Racquet / Tennis Club	465 491	1,000 SF GFA Courts	1.33 3.82			1.33 3.82	7.86 7.86	50%	3.93	3.93 3.93	5.23
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	3.93	9.08
INSTITUTIONAL	.,.	1,000 001									
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
High School (9-12)	530	Students	0.14			0.14	3.49	50%	1.75	1.75	0.25
Junior / Community College	540	Students	0.11			0.11	10.44	50%	5.22	5.22	0.57
University / College Church	550 560	Students 1,000 SF GFA	0.15			0.15	10.44 8.31	50% 50%	5.22 4.16	5.22 4.16	0.78 2.04
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	4.93	9.32
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	4.93	1.08
Clinic   Animal Hospital / Veterinary Clinic	630 640	1,000 SF GFA 1,000 SF GFA	3.28 3.53	30%	В	3.28 2.47	9.85 9.85	50% 50%	4.93 4.93	4.93 4.93	16.17 12.18
OFFICE	040	1,000 SF GFA	3.33	3070	ь	2.47	9.63	30%	4.93	4.93	12.10
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	6.00	6.90
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	6.00	3.60
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	6.00	10.26
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46 1.07	9.85	50%	4.93	4.93	17.06
Office Park COMMERCIAL	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	6.00	6.42
Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	2.80	5.43
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	2.23	6.24
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.87	4.45	0.50	2.23	2.23	6.40
Quick Lubrication Vehicle Shop  Automobile Care Center	941 942	Servicing Positions 1,000 SF GLA	4.85 3.11	40% 40%	B B	2.91	4.45 4.45	50% 50%	2.23	2.23	6.49 4.17
Gasoline / Service Station w/ Convenience Market	942	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.60	1.99
Dining											
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	2.82	12.32
High Turnover (Sit-Down) Restaurant Fast Food Restaurant	932 934	1,000 SF GFA 1,000 SF GFA	9.77 32.67	43% 50%	A A	5.57 16.34	5.64 5.64	50% 50%	2.82	2.82 2.82	15.71 46.08
Coffee / Donut Shop	934	1,000 SF GFA	43.38	70%	B	13.01	5.64	50%	2.82	2.82	36.69
Other Retail		-,		. 570			2.01	2.370			2
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	2.80	9.46
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	2.80	13.61
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	2.80	7.03
Supermarket   Home Improvement Superstore	850 862	1,000 SF GFA 1,000 SF GFA	9.24 2.33	36% 42%	A	5.91 1.35	5.60 5.60	50% 50%	2.80	2.80 2.80	16.55 3.78
Toy / Children's Superstore	864	1,000 SF GFA	5.00	30%	B	3.50	5.60	50%	2.80	2.80	9.80
Pharmacy / Drugstore	881	1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	2.80	14.70
SERVICES											
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	2.23	16.23
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	2.23	39.36
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	3.21	3.27

A: ITE Trip Generation Handbook 3rd Edition (September 2017)
B: Estimated by Kimley-Horn based on ITE rates for similar categories
C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.J. Service Area J - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)		Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - J	Veh-Mi Per Dev- Unit SA - J
PORT AND TERMINAL										0.00	
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	5.01	9.37
INDUSTRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	5.01	3.16
Industrial Park	130 150	1,000 SF GFA 1,000 SF GFA	0.40			0.40	10.02 10.02	50%	5.01	5.01	2.00 0.95
Warehousing   Mini-Warehouse	151	1,000 SF GFA	0.19			0.19	10.02	50%	5.01	5.01	0.93
RESIDENTIAL		1,000 51 5111	0.17			0.17	10.02	5070	5.01	5.01	0.05
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	4.90	4.85
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	4.90	2.74
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	4.90	2.16
Multifamily Housing (High-Rise)  Vertical Mixed Use	222 231	Dwelling Unit Dwelling Unit	0.36			0.36	9.79 9.79	50%	4.90 4.90	4.90	1.76
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.36	9.79	50%	4.90	4.90	2.25
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	4.90	1.27
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	4.90	0.88
Assisted Living	254	Beds	0.26			0.26	9.79	50%	4.90	4.90	1.27
LODGING	210	Po	0.60			0.60	6.42	500/	2 22	2 22	1.02
Hotel   Motel / Other Lodging Facilities	310 320	Rooms Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
RECREATIONAL	320	ROOMS	0.36			0.36	0.43	5070	3.44	<i>عد.د</i>	1.22
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	3.93	11.44
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.93	1.30
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	3.93	4.91
Multiplex Movie Theater	445 465	Screens	13.73			13.73	15.77	50%	7.89 3.93	6.00	82.38
Ice Skating Rink   Racquet / Tennis Club	491	1,000 SF GFA Courts	1.33 3.82			3.82	7.86 7.86	50%	3.93	3.93	5.23 15.01
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	3.93	9.08
INSTITUTIONAL		.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,									7.00
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
High School (9-12)	530	Students	0.14			0.14	3.49	50%	1.75	1.75	0.25
Junior / Community College	540 550	Students Students	0.11			0.11	10.44 10.44	50%	5.22 5.22	5.22	0.57
University / College Church	560	1,000 SF GFA	0.13			0.13	8.31	50%	4.16	4.16	2.04
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	4.93	9.32
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	4.93	1.08
Clinic Animal Hospital / Veterinary Clinic	630 640	1,000 SF GFA 1,000 SF GFA	3.28	30%	В	3.28 2.47	9.85 9.85	50%	4.93 4.93	4.93	16.17 12.18
OFFICE	0.0	1,000 51 5111	5.55	5070	-	2.17	7.00	5070	,5	,5	12.10
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	6.00	6.90
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	6.00	3.60
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	6.00	10.26
Medical / Dental Office Office Park	720 750	1,000 SF GFA 1,000 SF GFA	3.46 1.07			3.46 1.07	9.85 14.65	50%	4.93 7.33	4.93 6.00	17.06 6.42
COMMERCIAL	750	1,000 SF GFA	1.07			1.07	14.00	3070	1.55	0.00	0.42
Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	2.80	5.43
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	2.23	6.24
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.87	4.45	0.50	2.23	2.23	6.40
Quick Lubrication Vehicle Shop  Automobile Care Center	941 942	Servicing Positions 1,000 SF GLA	4.85 3.11	40%	B B	2.91 1.87	4.45 4.45	50%	2.23	2.23	6.49 4.17
Gasoline / Service Station w/ Convenience Market	945	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.60	1.99
Dining											
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	2.82	12.32
High Turnover (Sit-Down) Restaurant Fast Food Restaurant	932 934	1,000 SF GFA 1,000 SF GFA	9.77 32.67	43% 50%	A	5.57 16.34	5.64 5.64	50%	2.82	2.82	15.71 46.08
Coffee / Donut Shop	934	1,000 SF GFA	43.38	70%	A B	13.01	5.64	50%	2.82	2.82	36.69
Other Retail		-,		. 570			2.01	2.370			2 3.07
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	2.80	9.46
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	2.80	13.61
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	2.80	7.03
Supermarket   Home Improvement Superstore	850 862	1,000 SF GFA 1,000 SF GFA	9.24 2.33	36% 42%	A A	5.91 1.35	5.60 5.60	50%	2.80	2.80	16.55 3.78
Toy / Children's Superstore	862	1,000 SF GFA 1,000 SF GFA	5.00	30%	A B	3.50	5.60	50%	2.80	2.80	9.80
Pharmacy / Drugstore	881	1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	2.80	14.70
SERVICES											
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	2.23	16.23
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	2.23	39.36
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	3.21	3.27

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.K. Service Area K - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Table TT.N. Service Area	. Lu	0007 70			4	J. VU	· - · · · · y	avi	J (LU	4 : VIL	٠,
Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)	Pass- by Rate	Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - K	Veh-Mi Per Dev- Unit SA - K
										5.30	
PORT AND TERMINAL											
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	5.01	9.37
INDUS TRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	5.01	3.16
Industrial Park	130	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	5.01	2.00
Warehousing	150	1,000 SF GFA	0.19			0.19	10.02	50%	5.01	5.01	0.95
Mini-Warehouse RESIDENTIAL	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	5.01	0.85
Single-Family Detached Housing	210	Dwelling Unit	0.99	***************************************		0.99	9.79	50%	4.90	4.90	4.85
Residentail Condominium/ Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	4.90	2.74
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	4.90	2.16
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.90	1.76
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	4.90	1.76
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	4.90	2.25
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	4.90	1.27
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	4.90	0.88
Assisted Living	254	Beds	0.26			0.26	9.79	50%	4.90	4.90	1.27
LODGING											
Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
Motel / Other Lodging Facilities	320	Rooms	0.38			0.38	6.43	50%	3.22	3.22	1.22
RECREATIONAL											
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	3.93	11.44
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.93	1.30
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	3.93	4.91
Multiplex Movie Theater	445	Screens	13.73			13.73	15.77	50%	7.89	5.30	72.77
Ice Skating Rink	465	1,000 SF GFA	1.33			1.33	7.86	50%	3.93	3.93	5.23
Racquet / Tennis Club	491 495	Courts 1,000 SF GFA	3.82 2.31			3.82 2.31	7.86 7.86	50% 50%	3.93 3.93	3.93 3.93	15.01 9.08
Health / Recreational Clubs and Facilities INSTITUTIONAL	493	1,000 SF GFA	2.31			2.31	7.80	30%	3.93	3.93	9.08
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
High School (9-12)	530	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
Junior / Community College	540	Students	0.14			0.11	10.44	50%	5.22	5.22	0.23
University / College	550	Students	0.15			0.15	10.44	50%	5.22	5.22	0.78
Church	560	1,000 SF GFA	0.49			0.49	8.31	50%	4.16	4.16	2.04
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	4.93	9.32
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	4.93	1.08
Clinic	630	1,000 SF GFA	3.28			3.28	9.85	50%	4.93	4.93	16.17
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	4.93	12.18
OFFICE											
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	5.30	6.10
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	5.30	3.18
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	5.30	9.06
Medical / Dental Office	720	1,000 SF GFA	3.46	-		3.46	9.85	50%	4.93	4.93	17.06
Office Park	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	5.30	5.67
COMMERCIAL Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	2.80	5.43
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.80	2.80	6.24
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.80	4.45	0.50	2.23	2.23	6.40
Quick Lubrication Vehicle Shop	941	Servicing Positions	4.85	40%	В	2.91	4.45	50%	2.23	2.23	6.49
Automobile Care Center	942	1,000 SF GLA	3.11	40%	В	1.87	4.45	50%	2.23	2.23	4.17
Gasoline / Service Station w/ Convenience Market	945	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.60	1.99
Dining	<u> </u>										
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	2.82	12.32
High Tumover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	2.82	15.71
Fast Food Restaurant	934	1,000 SF GFA	32.67	50%	A	16.34	5.64	50%	2.82	2.82	46.08
Coffee / Donut Shop	937	1,000 SF GFA	43.38	70%	В	13.01	5.64	50%	2.82	2.82	36.69
Other Retail											
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	2.80	9.46
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	2.80	13.61
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	2.80	7.03
Supermarket	850	1,000 SF GFA	9.24	36%	A	5.91	5.60	50%	2.80	2.80	16.55
	862	1,000 SF GFA	2.33 5.00	42%	A	1.35	5.60	50%	2.80	2.80	3.78
Home Improvement Superstore				30%	В	3.50	5.60	50%	2.80	2.80	9.80
Toy / Children's Superstore	864	1,000 SF GFA						EC	3.00		14.70
Toy / Children's Superstore Pharmacy / Drugstore		1,000 SF GFA 1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	2.80	14.70
Toy / Children's Superstore Pharmacy / Drugstore SERVICES	864 881	1,000 SF GFA	10.29	49%	A	5.25	5.60			2.80	
Toy / Children's Superstore   Pharmacy / Drugstore   SERVICES   Walk-In Bank	864 881 911	1,000 SF GFA 1,000 SF GFA	10.29	49% 40%	A B	5.25 7.28	5.60 4.45	50%	2.23	2.80	16.23
Toy / Children's Superstore Pharmacy / Drugstore SERVICES	864 881	1,000 SF GFA	10.29	49%	A	5.25	5.60			2.80	





Table 11.L. Service Area L - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)		Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - L	Veh-Mi
PORT AND TERMINAL										3.50	
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	3.50	6.55
INDUSTRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	3.50	2.21
Industrial Park Warehousing	130 150	1,000 SF GFA 1,000 SF GFA	0.40			0.40	10.02	50%	5.01	3.50 3.50	1.40 0.67
Mini-Warehouse	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	3.50	0.60
RESIDENTIAL											
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	3.50	3.47
Residentail Condominium / Townhome Apartment / Multifamily	220 221	Dwelling Unit Dwelling Unit	0.56 0.44			0.56	9.79 9.79	50%	4.90 4.90	3.50 3.50	1.96 1.54
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	3.50	1.26
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	3.50	1.26
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	3.50	1.61
Senior Adult Housing  Congregate Care Facility	252 253	Dwelling Unit Dwelling Unit	0.26			0.26	9.79 9.79	50%	4.90 4.90	3.50	0.91
Assisted Living	253	Beds	0.18			0.18	9.79	50%	4.90	3.50	0.63
LODGING											
Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	3.22	1.93
Motel / Other Lodging Facilities RECREATIONAL	320	Rooms	0.38			0.38	6.43	50%	3.22	3.22	1.22
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	3.50	10.19
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	3.50	1.16
Golf Driving Range	432	Driving Positions	1.25			1.25	7.86	50%	3.93	3.50	4.38
Multiplex Movie Theater   Ice Skating Rink	445 465	Screens 1,000 SF GFA	13.73			13.73	15.77 7.86	50%	7.89 3.93	3.50	48.06 4.66
Racquet / Tennis Club	491	Courts	3.82			3.82	7.86	50%	3.93	3.50 3.50	13.37
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	3.50	8.09
INSTITUTIONAL											
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.75	0.30
High School (9-12) Junior / Community College	530 540	Students Students	0.14 0.11			0.14	3.49 10.44	50%	1.75 5.22	1.75 3.50	0.25
University / College	550	Students	0.15			0.15	10.44	50%	5.22	3.50	0.53
Church	560	1,000 SF GFA	0.49			0.49	8.31	50%	4.16	3.50	1.72
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.75	10.90
MEDICAL	610	D-1-	1.90			1.90	9.85	50%	4.93	2.50	6.62
Hospital Nursing Home	610 620	Beds Beds	1.89 0.22			1.89 0.22	9.85	50%	4.93	3.50 3.50	6.62 0.77
Clinic	630	1,000 SF GFA	3.28			3.28	9.85	50%	4.93	3.50	11.48
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	3.50	8.65
OFFICE	710	1 000 GE GEA	1.15			1.15	14.65	500/	7.22	2.50	4.02
General Office Building  Corporate Headquarters Building	710 714	1,000 SF GFA 1,000 SF GFA	1.15 0.60			1.15 0.60	14.65 14.65	50%	7.33 7.33	3.50 3.50	4.03 2.10
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	3.50	5.99
Medical / Dental Office	720	1,000 SF GFA	3.46			3.46	9.85	50%	4.93	3.50	12.11
Office Park	750	1,000 SF GFA	1.07			1.07	14.65	50%	7.33	3.50	3.75
COMMERCIAL Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	2.80	5.43
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	2.23	6.24
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.87	4.45	0.50	2.23	2.23	6.40
Quick Lubrication Vehicle Shop  Automobile Care Center	941 942	Servicing Positions 1,000 SF GLA	4.85 3.11	40%	B B	2.91 1.87	4.45 4.45	50%	2.23	2.23	6.49 4.17
Gasoline / Service Station w/ Convenience Market	945	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash Dining	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.60	1.99
Sit-Down Restaurant	931	1,000 SF GFA	7.80	44%	A	4.37	5.64	50%	2.82	2.82	12.32
High Turnover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	2.82	15.71
Fast Food Restaurant	934	1,000 SF GFA	32.67	50%	A	16.34	5.64	50%	2.82	2.82	46.08
Coffee / Donut Shop Other Retail	937	1,000 SF GFA	43.38	70%	В	13.01	5.64	50%	2.82	2.82	36.69
Free-Standing Retail Store	815	1,000 SF GFA	4.83	30%	С	3.38	5.60	50%	2.80	2.80	9.46
Garden Center (Nursery)	817	1,000 SF GFA	6.94	30%	В	4.86	5.60	50%	2.80	2.80	13.61
Shopping Center	820	1,000 SF GLA	3.81	34%	A	2.51	5.60	50%	2.80	2.80	7.03
Supermarket	850	1,000 SF GFA	9.24	36%	A	5.91	5.60	50%	2.80	2.80	16.55
Home Improvement Superstore  Toy / Children's Superstore	862 864	1,000 SF GFA 1,000 SF GFA	2.33 5.00	42% 30%	A B	1.35 3.50	5.60 5.60	50%	2.80	2.80 2.80	3.78 9.80
Pharmacy / Drugstore	881	1,000 SF GFA	10.29	49%	A	5.25	5.60	50%	2.80	2.80	14.70
SERVICES											
Walk-In Bank	911	1,000 SF GFA	12.13	40%	В	7.28	4.45	50%	2.23	2.23	16.23
Drive-In Bank	912	Drive-in Lanes	27.15	35%	A	17.65	4.45	50%	2.23	2.23	39.36
Personal Service	918	1,000 SF GFA	1.45	30%	В	1.02	6.41	50%	3.21	3.21	3.27

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





Table 11.M. Service Area M - Land Use / Vehicle-Mile Equivalency Table (LUVMET)

	I IVI - Lo	and Use / Ve	HILLIE	-IVII	ie cy	uiva	iency i	abi	e (LU	VIVILI	)
Land Use Category	ITE Land Use Code	Development Unit	Trip Gen Rate (PM)	Pass- by Rate	Pass-by Source	Trip Rate	Trip Length (mi)	Adj. For O-D	Adj. Trip Length (mi)	Max Trip Length (mi) SA - M	Veh-Mi Per Dev- Unit SA - M
										1.50	
PORT AND TERMINAL											
Truck Terminal	030	1,000 SF GFA	1.87			1.87	10.02	50%	5.01	1.50	2.81
INDUSTRIAL											
General Light Industrial	110	1,000 SF GFA	0.63			0.63	10.02	50%	5.01	1.50	0.95
Industrial Park	130	1,000 SF GFA	0.40			0.40	10.02	50%	5.01	1.50	0.60
Warehousing	150	1,000 SF GFA	0.19			0.19	10.02	50%	5.01	1.50	0.29
Mini-Warehouse RESIDENTIAL	151	1,000 SF GFA	0.17			0.17	10.02	50%	5.01	1.50	0.26
Single-Family Detached Housing	210	Dwelling Unit	0.99			0.99	9.79	50%	4.90	1.50	1.49
Residentail Condominium / Townhome	220	Dwelling Unit	0.56			0.56	9.79	50%	4.90	1.50	0.84
Apartment / Multifamily	221	Dwelling Unit	0.44			0.44	9.79	50%	4.90	1.50	0.66
Multifamily Housing (High-Rise)	222	Dwelling Unit	0.36			0.36	9.79	50%	4.90	1.50	0.54
Vertical Mixed Use	231	Dwelling Unit	0.36			0.36	9.79	50%	4.90	1.50	0.54
Mobile Home Park / Manufactured Housing	240	Dwelling Unit	0.46			0.46	9.79	50%	4.90	1.50	0.69
Senior Adult Housing	252	Dwelling Unit	0.26			0.26	9.79	50%	4.90	1.50	0.39
Congregate Care Facility	253	Dwelling Unit	0.18			0.18	9.79	50%	4.90	1.50	0.27
Assisted Living	254	Beds	0.26			0.26	9.79	50%	4.90	1.50	0.39
LODGING											
Hotel	310	Rooms	0.60			0.60	6.43	50%	3.22	1.50	0.90
Motel / Other Lodging Facilities	320	Rooms	0.38			0.38	6.43	50%	3.22	1.50	0.57
RECREATIONAL											
Golf Course	430	Holes	2.91			2.91	7.86	50%	3.93	1.50	4.37
Miniature Golf Course	431	Holes	0.33			0.33	7.86	50%	3.93	1.50	0.50
Golf Driving Range	432 445	Driving Positions	1.25			1.25	7.86 15.77	50%	3.93 7.89	1.50	1.88
Multiplex Movie Theater  Ice Skating Rink	465	Screens 1,000 SF GFA	13.73			13.73	7.86	50%	3.93	1.50	2.00
Racquet / Tennis Club	491	Courts	3.82			3.82	7.86	50%	3.93	1.50	5.73
Health / Recreational Clubs and Facilities	495	1,000 SF GFA	2.31			2.31	7.86	50%	3.93	1.50	3.47
INSTITUTIONAL	493	1,000 SF GFA	2.31			2.31	7.80	3070	3.93	1.30	3.47
Primary/Middle School (1-8)	522	Students	0.17			0.17	3.49	50%	1.75	1.50	0.26
High School (9-12)	530	Students	0.14			0.14	3.49	50%	1.75	1.50	0.21
Junior / Community College	540	Students	0.11			0.11	10.44	50%	5.22	1.50	0.17
University / College	550	Students	0.15			0.15	10.44	50%	5.22	1.50	0.23
Church	560	1,000 SF GFA	0.49			0.49	8.31	50%	4.16	1.50	0.74
Day Care Center	565	1,000 SF GFA	11.12	44%	В	6.23	3.49	50%	1.75	1.50	9.35
MEDICAL											
Hospital	610	Beds	1.89			1.89	9.85	50%	4.93	1.50	2.84
Nursing Home	620	Beds	0.22			0.22	9.85	50%	4.93	1.50	0.33
Clinic	630	1,000 SF GFA	3.28			3.28	9.85	50%	4.93	1.50	4.92
Animal Hospital / Veterinary Clinic	640	1,000 SF GFA	3.53	30%	В	2.47	9.85	50%	4.93	1.50	3.71
OFFICE											
General Office Building	710	1,000 SF GFA	1.15			1.15	14.65	50%	7.33	1.50	1.73
Corporate Headquarters Building	714	1,000 SF GFA	0.60			0.60	14.65	50%	7.33	1.50	0.90
Single Tenant Office Building	715	1,000 SF GFA	1.71			1.71	14.65	50%	7.33	1.50	2.57
Medical / Dental Office Office Park	720 750	1,000 SF GFA 1,000 SF GFA	3.46 1.07			3.46 1.07	9.85 14.65	50%	4.93 7.33	1.50	5.19 1.61
COMMERCIAL	730	1,000 SF GFA	1.07			1.07	14.03	3070	1.33	1.30	1.01
Automobile Related											
New and Used Car Sales	840	1,000 SF GFA	2.43	20%	В	1.94	5.60	50%	2.80	1.50	2.91
Automobile Parts Sales	843	1,000 SF GFA	4.91	43%	A	2.80	4.45	50%	2.23	1.50	4.20
Tire Store	848	1,000 SF GFA	3.98	28%	A	2.87	4.45	0.50	2.23	1.50	4.31
Quick Lubrication Vehicle Shop	941	Servicing Positions	4.85	40%	В	2.91	4.45	50%	2.23	1.50	4.37
Automobile Care Center	942	1,000 SF GLA	3.11	40%	В	1.87	4.45	50%	2.23	1.50	2.81
Gasoline / Service Station w/ Convenience Market	945	Vehicle Fueling Positions	13.99	56%	A	6.16	1.20	50%	0.60	0.60	3.70
Self-Service Car Wash	947	Stalls	5.54	40%	В	3.32	1.20	50%	0.60	0.60	1.99
Dining			7.80	44%	A	4.37	5.64	50%	2.82	1.50	6.56
Sit-Down Restaurant	931	1,000 SF GFA									
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant	932	1,000 SF GFA	9.77	43%	A	5.57	5.64	50%	2.82	1.50	8.36
Sit-Down Restaurant   High Turnover (Sit-Down) Restaurant   Fast Food Restaurant	932 934	1,000 SF GFA 1,000 SF GFA	9.77 32.67	50%	A	16.34	5.64	50%	2.82 2.82	1.50	24.51
Sit-Down Restaurant High Tumover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop	932	1,000 SF GFA	9.77		**************				2.82		***************************************
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail	932 934 937	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38	50% 70%	A B	16.34 13.01	5.64 5.64	50% 50%	2.82 2.82 2.82	1.50 1.50	24.51 19.52
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store	932 934 937 815	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83	50% 70% 30%	A B C	16.34 13.01 3.38	5.64 5.64 5.60	50% 50%	2.82 2.82 2.82 2.82	1.50 1.50	24.51 19.52 5.07
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Garden Center (Nursery)	932 934 937 815 817	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94	50% 70% 30% 30%	A B C B	16.34 13.01 3.38 4.86	5.64 5.64 5.60 5.60	50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80	1.50 1.50 1.50 1.50	24.51 19.52 5.07 7.29
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Garden Center (Nursery) Shopping Center	932 934 937 815 817 820	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81	50% 70% 30% 30% 34%	A B C B	16.34 13.01 3.38 4.86 2.51	5.64 5.64 5.60 5.60 5.60	50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80	1.50 1.50 1.50 1.50 1.50	24.51 19.52 5.07 7.29 3.77
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Garden Center (Nursery) Shopping Center Supermarket	932 934 937 815 817 820 850	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24	50% 70% 30% 30% 34% 36%	A B C B A A	16.34 13.01 3.38 4.86 2.51 5.91	5.64 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80	1.50 1.50 1.50 1.50 1.50 1.50	24.51 19.52 5.07 7.29 3.77 8.87
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Garden Center (Nursery) Shopping Center Supermarket Home Improvement Superstore	932 934 937 815 817 820 850 862	1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24 2.33	50% 70% 30% 30% 34% 36% 42%	A B C B A A A	16.34 13.01 3.38 4.86 2.51 5.91 1.35	5.64 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	1.50 1.50 1.50 1.50 1.50 1.50 1.50	24.51 19.52 5.07 7.29 3.77 8.87 2.03
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Garden Center (Nursery) Shopping Center Supermarket Home Improvement Superstore Toy / Children's Superstore	932 934 937 815 817 820 850 862 864	1,000 SF GFA	9,77 32.67 43.38 4.83 6.94 3.81 9.24 2.33 5.00	50% 70% 30% 30% 34% 36%	A B C B A A B B	16.34 13.01 3.38 4.86 2.51 5.91 1.35 3.50	5.64 5.60 5.60 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	1.50 1.50 1.50 1.50 1.50 1.50 1.50 1.50	24.51 19.52 5.07 7.29 3.77 8.87 2.03 5.25
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Garden Center (Nursery) Shopping Center Supermarket Home Improvement Superstore	932 934 937 815 817 820 850 862	1,000 SF GFA 1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24 2.33	50% 70% 30% 30% 34% 36% 42% 30%	A B C B A A A	16.34 13.01 3.38 4.86 2.51 5.91 1.35	5.64 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	1.50 1.50 1.50 1.50 1.50 1.50 1.50	24.51 19.52 5.07 7.29 3.77 8.87 2.03
Sit-Down Restaurant   High Turnover (Sit-Down) Restaurant   Fast Food Restaurant   Coffee / Donut Shop	932 934 937 815 817 820 850 862 864	1,000 SF GFA	9,77 32.67 43.38 4.83 6.94 3.81 9.24 2.33 5.00	50% 70% 30% 30% 34% 36% 42% 30%	A B C B A A B B	16.34 13.01 3.38 4.86 2.51 5.91 1.35 3.50	5.64 5.60 5.60 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	1.50 1.50 1.50 1.50 1.50 1.50 1.50 1.50	24.51 19.52 5.07 7.29 3.77 8.87 2.03 5.25
Sit-Down Restaurant High Turnover (Sit-Down) Restaurant Fast Food Restaurant Coffee / Donut Shop Other Retail Free-Standing Retail Store Garden Center (Nursery) Shopping Center Supermarket Home Improvement Superstore Toy / Children's Superstore Pharmacy / Drugstore SERVICES	932 934 937 815 817 820 850 862 864 881	1,000 SF GFA	9.77 32.67 43.38 4.83 6.94 3.81 9.24 2.33 5.00 10.29	50% 70% 30% 30% 34% 36% 42% 30% 49%	A B C B A A A A B A	3.38 4.86 2.51 5.91 1.35 3.50 5.25	5.64 5.60 5.60 5.60 5.60 5.60 5.60 5.60 5.60	50% 50% 50% 50% 50% 50% 50% 50% 50%	2.82 2.82 2.82 2.80 2.80 2.80 2.80 2.80	1.50 1.50 1.50 1.50 1.50 1.50 1.50 1.50	24.51 19.52 5.07 7.29 3.77 8.87 2.03 5.25 7.88

A: ITE Trip Generation Handbook 3rd Edition (September 2017)

B: Estimated by Kimley-Horn based on ITE rates for similar categories C: ITE rate adjusted upward by KHA based on logical relationship to other categories





## Table 12 - Land Use Descriptions

1		
Land Use Category	ITE Land Use Code	Land Use Description
DODE AND WITH SPACE		
PORT AND TERMINAL Truck Terminal	030	Point of good transfer between trucks or between trucks and rail
INDUSTRIAL	0.50	Folia of good transfer between ducks of between ducks and fan
General Light Industrial	110	Emphasis on activities other than manufacturing; typically employing fewer than 500 workers
Industrial Park	130	Area containing a number of industries or related facilities
Warehousing	150	Devoted to storage of materials but may included office and maintenance areas
Mini-Warehouse	151	Facilities with a number of units rented to others for the storage of goods
RESIDENTIAL		
Single-Family Detached Housing	210	Single-family detached homes on individual lots
Residential Condominiumn / Townhome Apartment / Multifamily	220	Single-family ownership units that have at least one other single-family owned unit within the same building  At least 3 rental dwelling units and ten levels (floors), or less, per building
Multifamily Housing (High-Rise)	222	At least 3 femilal dwelling units and more than ten levels (floors) per building
Vertical Mixed Use	231	Mixed-use multifamily housing buildings that have between three and 10 levels (floors) and include non-residential space on the first level
Mobile Home Park / Manufactured Housing	240	Consist of manufactured homes that are sited and installed on permanent foundations
Senior Adult Housing	252	Independent living developments without centralized dining or on-site medical facilities
Congregate Care Facility	253	Independent living developments with centralized amenities such as dining, housekeeping, transportation and organized social/recreational activities
Assisted Living	254	Residential settings that provide either routine general protective oversight or assistance with activities.
LODGING	210	
Hotel	310 320	Lodging facilities that typically have on-site restaurants, lounges, meeting and/or banquet rooms, or other retail shops and services
Motel / Other Lodging Facilities RECREATIONAL	520	Lodging facilities that may have small on-site restaurant or buffet area but little or no meeting space
Golf Course	430	May include municipal courses and private country clubs; may have driving ranges, pro shops, and restaurant/banquet facilities
Miniature Golf Course	430	way include infinity actorises and private county closs; navy nave uriving ranges, pito strops, and restaurant/oranquet inactines.  One or more individual putting courses; category should not be used when part of a larger entertainment center (with batting cages, video game centers, etc)
Golf Driving Range	432	Facilities with driving tees for practice; may provide individual or group lessons; may have prop shop and/or refreshment facilities
Multiplex Movie Theater	445	Movie theater with audience seating, minimum of ten screens, lobby, and refreshment area.
Ice Skating Rink	465	Rinks for ice skating and related sports; may contain spectator areas and refreshment facilities
Racquet / Tennis Club	491	Indoor or outdoor facilities specifically designed for playing tennis
Health / Recreational Clubs and Facilites	495	Privately owned facilities that primarily focus on individual fitness or training, can include facilities such as YMCA's
INSTITUTIONAL		
Primary / Middle School (1-8)	522	Serves students who have not yet entered high school
High School (9-12) Junior / Community College	530 540	Serves students who have completed middle or junior high school Two-year junior, community, or technical colleges
University / College	550	Four-year universities or colleges that may or may not offer graduate programs
Church	560	Churches and houses of worship
Day Care Center	565	Generally includes facilities for care of pre-school aged children, generally includes classrooms, offices, eating areas, and playgrounds
MEDICAL		
Hospital	610	Medical and surgical facilities with overnight accommodations
Nursing Home	620	Rest and convalescent homes with residents who do little or no driving
Clinic	630	Facilities with limited diagnostic and outpatient care
Animal Hospital / Veterinary Clinic OFFICE	640	Facility that specializes in the medical care and treatment of animals
General Office Building	710	Office buildings which house multiple tenants
Corporate Headquarters Building	714	Office building housing corporate headquarters of a single company or organization
Single Tenant Office Building	715	Single tenant office buildings other than corporate headquarters
Medical / Dental Office	720	Multi-tenant building with offices for physicians and/or dentists
Office Park	750	Office buildings (typically low-rise) in a campus setting and served by a common roadway system
COMMERCIAL		
Automobile Related		
New and Used Car Sales	840 843	Car dealerships, typically with automobile servicing and part sales
Automobile Parts Sales Tire Store	843 848	Retail sale of auto parts but no on-site vehicle repair  Primary business is sales and installation of tires; usually do not have large storage or warehouse area
Quick Lubrication Vehicle Shop	941	Primary outsiness is sales and installation of tires; usually do not have large storage or warehouse area  Primary business is to perform oil changes and fluid/filter changes with other repair services not provided
Automobile Care Center	942	Automobile repair and servicing including stereo installations and upholstering
Gasoline / Service Station w/ Convenience Market	945	Gasoline sales with convenience store where the primary business is gasoline sales
Self-Service Car Wash	947	Has stalls for driver to park and wash the vehicle
Dining		
Sit-Down Restaurant	931	Restaurants with turnover rates of one hour or longer; typically require reservations
High Turnover (Sit-Down) Restaurant	932	Restaurants with turnover rates less than one hour; typically includes moderately-priced chain restaurants
Fast Food Restaurant	934 937	High-turnover fast food restaurant for carry-out and eat-in customers with a drive-thru window
Coffee / Donut Shop	937	Coffee and Donut restaurants with drive-through windows, hold long store hours and have limited indoor seating
Other Retail Free-Standing Retail Store	815	Category includes free-standing stores with off-street parking; typically offer a variety of products and services with long store hours
Garden Center (Nursery)	817	Caregory areanes nee-standing stores with on-street paraling, typecany orier a variety of products and services with ong store nours Building with a yard of planting or landscape stock; may have office, storage, shipping or greenhouse facilities
Shopping Center	820	Dunang win a yaru oo panung oo ahiraksape atoek, iniy mare onke, skonge, shipping oo geemiouse nachaks Integrated group of commercial establishments; planning, owned, and managed as a unit
Supermarket	850	Primary business is sale of groceries, food, and household cleaning items; may include photo, pharmacy, video rental, and/or ATM
Home Improvement Superstore	862	Warehouse-type facilities offering a large variety of products and services including lumber, tool, paint, lighting, and fixtures, among other items.
Toy / Children's Superstore	864	Businesses specializing in child-oriented merchandise
Pharmacy / Drugstore	881	Facilities that primarily sell prescription and non-prescription drugs with and without drive-through windows
SERVICES	011	
Walk-In Bank	911 912	Bank without drive-thru lanes Bank with divest bru lanes
Drive-In Bank Pers onal Service	912	Bank with drive-thru lanes Facilities that specialize in personal service such as hair salons
reisonar service	916	r actinies that specialize in personal service such as half satons





## VI. SAMPLE CALCULATIONS

The following section details two (2) examples of maximum assessable Roadway Impact Fee calculations.

Example 1: Development Type - One (1) Unit of Single-Family Housing in Service Area C

	Determine Development Unit and Vehicle-Miles Per Development Unit
Step	From Table 11 [Land Use – Vehicle-Mile Equivalency Table]
1 1	Development Type: 1 Dwelling Unit of Single-Family Detached Housing
•	Number of Development Units: 1 Dwelling Unit
	Veh-Mi Per Development Unit: 3.96
Ston	Determine Maximum Assessable Impact Fee Per Service Unit (Vehicle-Mile)
Step 2	From Table 10, Line 19 [Maximum Assessable Fee Per Service Unit]
	Service Area C: \$2,808
	Determine Maximum Assessable Impact Fee
	Impact Fee = # of Development Units * Veh-Mi Per Dev Unit * Max. Fee Per Service
Step	Unit
3	Impact Fee = 1 * 3.96 * \$2,808
	Impact 1 cc = 1 3.70 \$2,000
	Maximum Assessable Impact Fee = \$11,120

Example 2: Development Type – 50,000 Square Foot Shopping Center in Service Area I

	Determine Development Unit and Vehicle-Miles Per Development Unit
Step	From Table 11 [Land Use – Vehicle-Mile Equivalency Table]
1	Development Type: 50,000 square feet of Home Improvement Store
'	Development Unit: 50 thousand square feet of Gross Floor Area
	Veh-Mi Per Development Unit: 7.03
Step	Determine Maximum Assessable Impact Fee Per Service Unit (Vehicle-Mile)
2	From Table 10, Line 19 [Maximum Assessable Fee Per Service Unit]
	Service Area I: \$1,265
	Determine Maximum Assessable Impact Fee
	Impact Fee = # of Development Units * Veh-Mi Per Dev Unit * Max. Fee Per Service
Step	Unit
3	Impact Fee = 50 * 7.03 * \$1,265
	Impact 1 cc = 30 1.03 \$1,203
	Maximum Assessable Impact Fee = \$444,648





#### VII. ADOPTION AND ADMINISTRATION OF ROADWAY IMPACT FEES

#### A. Adoption Process

Chapter 395 of the Texas Local Government Code stipulates a specific process for the adoption of Roadway Impact Fees. A Capital Improvements Advisory Committee (CIAC) is required to review the Land Use Assumptions and Roadway Impact Fees RIP used in calculating the maximum fee, and to provide the Committee's findings for consideration by the City Council. This CIAC also reviews the calculation and resulting maximum fees and provides its findings to the City Council. The composition of the CIAC (Planning and Zoning Commission in McKinney) is required to have one representative of the building and development communities. The City Council then conducts a public hearing on the Land Use Assumptions, RIF RIP, and Impact Fee Ordinance. A public hearing is required for the 2019 Roadway Impact Fee Update.

Following policy adoption, the CIAC is tasked with advising the City Council of the need to update the Land Use Assumptions or the Roadway Impact Fees RIP at any time within five years of adoption. Finally, the CIAC oversees the proper administration of the Impact Fee, once in place, and advises the Council as necessary.

## B. Collection and Use of Transportation Impact Fees

Roadway Impact Fees are assessed when a final plat is recorded. The assessment defines the impact of each unit at the time of platting, according to land use, and may not exceed the maximum impact fee allowed by law. Roadway Impact Fees are collected when a building permit is issued. Therefore, funds are not collected until development-impacts are introduced to the transportation system. Funds collected within a service area can be used only within the same service area. Finally, fees must be utilized within 10 years of collection, or must be refunded with interest.





## VIII. CONCLUSION

The City of McKinney has established a process to implement the assessment and collection of Roadway Impact Fees through the adoption of an impact fee ordinance that is consistent with Chapter 395 of the Texas Local Government Code.

This report establishes the maximum allowable Roadway Impact Fee that could be assessed by the City of McKinney within each of the thirteen (13) service areas. The maximum assessable roadway impact fees calculated in this report are presented below.

Service	2019–2020 Maximum Fee Per Service	2012–2013 Maximum Fee Per Service
Area	Unit (Per Vehicle-Mile)	Unit (Per Vehicle-Mile)
А	\$0	\$0
В	\$1,094	\$1,861
С	\$2,808	\$1,500
D	\$3,438	\$1,711
E	\$2,202	\$2,082
F	\$0	\$0
G	\$1,155	\$635
Н	\$361	\$393
I	\$1,265	\$755
J	\$347	\$824
K	\$1,197	\$1,182
L	\$2,044	\$1,320
М	\$2,406	\$0

This document serves as a guide to the assessment of Roadway Impact Fees pertaining to future development, and the City's need for roadway improvements to accommodate that growth. Following the public hearing process, the City Council may establish an impact fee amount to be assesses (if any), up to the calculated maximum and establish the Roadway Impact Fee Ordinance accordingly.





In conclusion, it is our opinion that the data and methodology used in this analysis are appropriate and consistent with Chapter 395 of the Texas Local Government Code. Furthermore, the Land Use Assumptions and the proposed Roadway Impact Fee Roadway Improvements Plan are appropriately incorporated into the development of the maximum assessable Roadway Impact Fee.





## IX. APPENDICES


- A. Conceptual Level Project Cost Projections
  - SERVICE AREA A
  - SERVICE AREA B
  - SERVICE AREA C
  - SERVICE AREA D
  - SERVICE AREA E
  - SERVICE AREA G
  - SERVICE AREA H
  - SERVICE AREA I
  - SERVICE AREA J
  - SERVICE AREA K
  - SERVICE AREA L
  - SERVICE AREA M
- B. Roadway Impact Fee RIP Service Units of Supply
- C. Existing Roadway Facilities Inventory
- D. Plan for Awarding the Roadway Impact Fee Credit Summary FROM NEWGEN STRATEGIES & SOLUTIONS, LLC
- E. Plan for Awarding the Roadway Impact Fee Credit Supporting Exhibits

FROM NEWGEN STRATEGIES & SOLUTIONS, LLC





Appendix A – Conceptual Level Project Cost Projections



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

#### Roadway Improvements - Service Area A

	Costing					Percent in		Cost in
#	Class	Project	Limits	T	otal Cost	Service Area	Ser	rvice Area
A-1, C-1	M6D	UNNAMED 5 (1)	635' W OF STONEBRIDGE DR TO CR 168	\$	7,715,900	50%	\$	3,857,950
A-2, D-1	M6D	UNNAMED 5 (3)	CR 168 TO 1,560' E OF CR 168	\$	7,517,500	50%	\$	3,758,750
A-3	G4D	STONEBRIDGE DR (1)	2,635' N OF UNNAMED 5 TO UNNAMED 5	\$	4,679,450	50%	\$	2,339,725
				¢	19 912 850		¢	9 956 425

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

## **City of McKinney**

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. A-1, C-1

Name: UNNAMED 5 (1) This project consists of the

Limits: 635' W OF STONEBRIDGE DR TO CR 168 construction of a new six-lane divided

Impact Fee Class: M6D major arterial.

Thoroughfare Class: Major Arterial

Length (If): 3,315 Service Area(s): A and C

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
109	Unclassified Street Excavation	36,833	су	\$	10.00	\$ 368,333
209	Lime Treated Subgrade (8") (PI<12)	28,730	sy	\$	7.00	\$ 201,110
309	9" Concrete Pavement	27,257	sy	\$	60.00	\$ 1,635,400
409	4" Topsoil	12,892	sy	\$	2.50	\$ 32,229
509	6" Curb & Gutter	13,260	lf	\$	5.00	\$ 66,300
609	Allotment for Turn Lanes and Median Openings	2,023	sy	\$	77.00	\$ 155,774
709	Moisture Conditioning	28,730	sy	\$	8.00	\$ 229,840

Paving Construction Cost Subtotal: \$ 2,688,987

Majo	Major Construction Component Allowances**:								
	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	None Anticipated	1%	\$	26,890				
	Pavement Markings/Markers		3%	\$	80,670				
	Roadway Drainage	Standard Internal System	25%	\$	672,247				
	Special Drainage Structures	Stream Crossing		\$	250,000				
	Water	None Anticipated	0%	\$	-				
	Sewer	None Anticipated	0%	\$	-				
	Establish Turf / Erosion Control		2%	\$	53,780				
	Illumination	Standard Ilumination System	6%	\$	161,339				
	Other:								
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	1,244,925				
		Paving and Allowa	nce Subtotal:	\$	3,933,912				
		Mobilization:	5%	\$	196,696				
		Site Preparation:	5%	\$	196,696				
		Construction C	ost TOTAL:	\$	4,328,000				
		Construction Contingency:	15%	\$	649,200				
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	4,978,000				

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,978,000
Engineering/Survey/Testing:		20%	\$ 995,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,742,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## **City of McKinney**

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. A-2, D-1

Name: UNNAMED 5 (3) This project consists of the

Limits: CR 168 TO 1,560' E OF CR 168 construction of a new six-lane divided

Impact Fee Class: M6D major arterial.

Thoroughfare Class: Major Arterial Length (If): 1,560
Service Area(s): A and D

Roa	adway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost
109	Unclassified Street Excavation	17,333	су	\$	10.00	\$	173,333
209	Lime Treated Subgrade (8") (PI<12)	13,520	sy	\$	7.00	\$	94,640
309	9" Concrete Pavement	12,827	sy	\$	60.00	\$	769,600
409	4" Topsoil	6,067	sy	\$	2.50	\$	15,167
509	6" Curb & Gutter	6,240	lf	\$	5.00	\$	31,200
609	Allotment for Turn Lanes and Median Openings	952	sy	\$	77.00	\$	73,306
709	Moisture Conditioning	13,520	sy	\$	8.00	\$	108,160
	_				• • • • •	$\overline{}$	4 005 400

Paving Construction Cost Subtotal: \$ 1,265,406

Major Construction Component Allowances**:									
Item Description	Notes	Allowance		Item Cost					
√ Traffic Control	None Anticipated	1%	\$	12,654					
√ Pavement Markings/Markers		3%	\$	37,962					
$\sqrt{}$ Roadway Drainage	Standard Internal System	25%	\$	316,351					
√ Special Drainage Structures	Bridge		\$	2,100,000					
Water	None Anticipated	0%	\$	-					
Sewer	None Anticipated	0%	\$	-					
√ Establish Turf / Erosion Control		2%	\$	25,308					
$\sqrt{}$ Illumination	Standard Ilumination System	6%	\$	75,924					
Other:									
**Allowances based on % of Paving Construction	Cost Subtotal Allowa	ince Subtotal:	\$	2,568,200					
	Paving and Allowa	nce Subtotal:	\$	3,833,606					
	Mobilization:	5%	\$	191,680					
	Site Preparation:	5%	\$	191,680					
	Construction C		\$	4,217,000					
	Construction Contingency:			632,550					
	Construction Cost TOTAL W/ CON	TINGENCY:	\$	4,850,000					

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,850,000
Engineering/Survey/Testing:		20%	\$ 970,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,697,500

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection


**Project Information: A-3** Description: Project No. Name: STONEBRIDGE DR (1) This project consists of the Limits: 2,635' N OF UNNAMED 5 TO UNNAMED 5 construction of a new four-lane divided **Impact Fee Class:** G4D greenway arterial. Based on the existing Thoroughfare Class: **Greenway Arterial** City Limits, the western half of the Length (If): 2,635 roadway is not included in the Impact Service Area(s): A, Half Fee RIP.

No.	Item Description	Quantity	Unit	Uni	t Price		Item Cost
107	Unclassified Street Excavation	25,764	су	\$	10.00	\$	257,644
207	Lime Treated Subgrade (8") (PI<12)	19,323	sy	\$	7.00	\$	135,263
307	8" Concrete Pavement	18,152	sy	\$	55.00	\$	998,372
407	4" Topsoil	12,589	sy	\$	2.50	\$	31,474
507	6" Curb & Gutter	10,540	lf	\$	5.00	\$	52,700
607	Allotment for Turn Lanes and Median Openings	1,547	sy	\$	72.00	\$	111,389
707	Moisture Conditioning	19,323	sy	\$	8.00	5	154,587
		Paving Constr	uction C	Cost S	ubtotal:	\$	1,741,429
Majo	r Construction Component Allowances**:	_					
	Item Description Notes			Allo	wance		Item Cost

Мајо	or Construction Component Allowand	es**:			
	Item Description	Notes	Allowance		Item Cost
	Traffic Control	None Anticipated	1%	\$	17,414
	Pavement Markings/Markers		3%	\$	52,243
	Roadway Drainage	Standard Internal System	25%	\$	435,357
	Special Drainage Structures None Anticipated				-
	Water None Anticipated 0%				-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	34,829
	Illumination	Standard Ilumination System	6%	\$	104,486
	Other:				
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$	644,329
<u> </u>		Baring and Allana	0		0.005.750
l		Paving and Allowa			2,385,758
		Mobilization:		*	119,288
		Site Preparation:	5%	\$	119,288
		Construction C		\$	2,625,000
		Construction Contingency:	15%	\$	393,750
	Co	nstruction Cost TOTAL W/ CON	TINGENCY:	\$	3.019.000

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,019,000
Engineering/Survey/Testing:		20%	\$ 603,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,056,650
	\$ 4,679,450		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

#### Roadway Improvements - Service Area B

	Costing					Percent in		Cost in
#	Class	Project	Limits	Т	otal Cost	Service Area	Se	rvice Area
B-1, D-2	M6D	UNNAMED 5 (4)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD	\$	4,904,200	50%	\$	2,452,100
B-2	G6D	HARDIN BLVD (1)	CR 204 TO CR 206	\$	877,800	50%	\$	438,900
B-3	G6D	HARDIN BLVD (2)	1,670' N OF OLYMPIC TO 730' S OF OLYMPIC	\$	4,837,000	50%	\$	2,418,500
B-4	G6D	HARDIN BLVD (3)	1,940' N OF UNNAMED 5 TO UNNAMED 5	\$	4,090,450	100%	\$	4,090,450
1	Inter-	Signal	HARDIN BLVD & OLYMPIC	\$	300,000	50%	\$	150,000
3	section	Signal	HARDIN BLVD & UNNAMED 5	\$	300,000	50%	\$	150,000
		_		\$	15,309,450	•	\$	9,699,950

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

## **City of McKinney**

**Project Information:** 

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

This project consists of the construction

of a new six-lane divided major arterial.

Description: Project No.

UNNAMED 5 (4) Name:

1,050' W OF HARDIN BLVD TO

Limits: 1,200' E OF HARDIN BLVD

**Impact Fee Class:** M6D Thoroughfare Class: Major Arterial Length (If): 2,250

Service Area(s): B and D

Roa	Roadway Construction Cost Projection									
No.	Item Description	Quantity	Unit	Unit Price			Item Cost			
109	Unclassified Street Excavation	25,000	су	\$	10.00	\$	250,000			
209	Lime Treated Subgrade (8") (PI<12)	19,500	sy	\$	7.00	\$	136,500			
309	9" Concrete Pavement	18,500	sy	\$	60.00	\$	1,110,000			
409	4" Topsoil	8,750	sy	\$	2.50	\$	21,875			
509	6" Curb & Gutter	9,000	lf	\$	5.00	\$	45,000			
609	Allotment for Turn Lanes and Median Openings	1,373	sy	\$	77.00	\$	105,729			
709	Moisture Conditioning	19,500	sy	\$	8.00	\$	156,000			

Paving Construction Cost Subtotal: \$ 1,825,104

Maio	Major Construction Component Allowances**:									
maje	Item Description	Notes	Allowance		Item Cost					
	Traffic Control	None Anticipated	1%	\$	18,251					
	Pavement Markings/Markers		3%	\$	54,753					
	Roadway Drainage	Standard Internal System	25%	\$	456,276					
	Special Drainage Structures	None Anticipated		\$	-					
	Water	None Anticipated	0%	\$	-					
	Sewer	None Anticipated	0%	\$	-					
	Establish Turf / Erosion Control		2%	\$	36,502					
	Illumination	Standard Ilumination System	6%	\$	109,506					
	Other:									
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	675,289					
		Paving and Allowa			2,500,393					
		Mobilization:	5%	\$	125,020					
		Site Preparation:	5%	\$	125,020					
		Construction C	ost TOTAL:	\$	2,751,000					
		Construction Contingency:	15%	\$	412,650					
	С	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	3,164,000					

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,164,000
Engineering/Survey/Testing:		20%	\$ 632,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,107,400
	Impact Fee Proj	ect Cost TOTAL:	\$ 4,904,200

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

**Roadway Construction Cost Projection** 

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	B-2				
Name:	HARDIN BLVD (1)	This project consists of	the reconstruction	on of a two-				
Limits:	CR 204 TO CR 206	lane facility to a six-lane divided greenway arterial						
Impact Fee Class:	G6D	Based on the existing City Limits, the eastern half of						
Thoroughfare Class:	Greenway Arterial	the roadway is not inclu	· •					
Length (If):	435	, , , , , , , , , , , , , , , , , , , ,						
Service Area(s):	B, Half							

No.	Item Description		Quantity	Unit	Uni	t Price		Item Cost
116	Unclassified Street Excavation		5,317	су	\$	10.00	\$	53,167
216	Lime Treated Subgrade (8") (PI<12)		3,480	sy	\$	7.00	\$	24,360
316	9" Concrete Pavement		3,287	sy	\$	60.00	\$	197,200
416	4" Topsoil		2,755	sy	\$	2.50	\$	6,888
516	6" Curb & Gutter		1,740	lf	\$	5.00	\$	8,700
616	Allotment for Turn Lanes and Median O	penings	301	sy	\$	77.00	\$	23,148
716	Moisture Conditioning		3,480	sy	\$	8.00	\$	27,840
	Paving Construction Cost Subtotal:							341,302
Majo	Major Construction Component Allowances**:							
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	10,239
	Pavement Markings/Markers					3%	\$	10,239
	Roadway Drainage	Standard Internal Sy	rstem			25%	\$	85,325
	Special Drainage Structures	None Anticipated					\$	-
	Water	Incidental Adjustmer	nts			3%	\$	10,239
	Sewer	Incidental Adjustmer	nts			3%	\$	10,239
	Establish Turf / Erosion Control					2%	\$	6,826
	Illumination	Standard Ilumination	System			6%	\$	20,478
	Other:							
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	ınce S	subtotal:	\$	153,586
	Paving and Allowance Subtotal:							494,888
			Mobi	lization:		5%	\$	24,744
			Site Prep	aration:		5%	\$	24,744
			Construc			OTAL:	\$	545,000
		Constr	uction Conti	ngency:		15%	\$	81,750

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 627,000
Engineering/Survey/Testing:		20%	\$ 125,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 125,400

**Construction Cost TOTAL W/ CONTINGENCY:** 

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

627,000

**Project Information:** 

Kimley-Horn and Associates, Inc.

10/6/2020

# 2019 Roadway Impact Fee Update

Conceptual Level Project Cost Projection

**B-3** Project No. Description:

Name: HARDIN BLVD (2) This project consists of the

Limits: 1,670' N OF OLYMPIC TO 730' S OF OLYMPIC

**Impact Fee Class:** G₆D

Thoroughfare Class: **Greenway Arterial** 

Length (If): 2,400 Service Area(s): B, Half reconstruction of a two-lane facility to a six-lane divided greenway arterial. Based on the existing City Limits, the eastern half of the roadway is not

updated:

included in the Impact Fee RIP.

Roa	Roadway Construction Cost Projection							
No.	Item Description		Quantity	Unit	Unit	t Price		Item Cost
116	Unclassified Street Excavation		29,333	су	\$	10.00	\$	293,333
216	Lime Treated Subgrade (8") (PI<12)		19,200	sy	\$	7.00	\$	134,400
316	9" Concrete Pavement		18,133	sy	\$	60.00	\$	1,088,000
416	6 4" Topsoil		15,200	sy	\$	2.50	\$	38,000
516	6" Curb & Gutter		9,600	lf	\$	5.00	\$	48,000
616	Allotment for Turn Lanes and Median C	penings	1,659	sy	\$	77.00	\$	127,711
716	Moisture Conditioning		19,200	sy	\$	8.00	\$	153,600
		P	aving Const	ruction (	Cost S	ubtotal:	\$	1,883,044
Major Construction Component Allowances**:								
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	56,491
	Pavement Markings/Markers					3%		56,491
	Roadway Drainage	Standard Internal Sy	rstem			25%		470,761
l .	Special Drainage Structures	None Anticipated					\$	-
	Water	Incidental Adjustmer	nts			3%		56,491
	Sewer	Incidental Adjustmer	nts			3%		56,491
	Establish Turf / Erosion Control					2%		37,661
	Illumination	Standard Ilumination	System			6%	\$	112,983
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	ince S	ubtotal:	\$	847,370
			Paving an					2,730,414
Mobilization: 5%							\$	136,521
			Site Prep			5%		136,521
			Construc			OTAL:		3,004,000
			ruction Conti			15%	-	450,600
	Coi	nstruction Cos	t TOTAL W	// CON	TING	ENCY:	\$	3,455,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,455,000
Engineering/Survey/Testing:		20%	\$ 691,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 691,000
	\$ 4,837,000		

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## **City of McKinney**

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc. updated: 10/6/2020

Project Information: Description: Project No. B-4

Name: HARDIN BLVD (3)

Limits: This project consists of a new six-lane divided of a new six-lane divided

Impact Fee Class: G6D

Thoroughfare Class: Greenway Arterial


Length (If): 1,940 Service Area(s): B This project consists of the construction of a new six-lane divided greenway arterial.

Roadway Construction Cost Projection								
No.	No. Item Description			Unit	Un	it Price		Item Cost
116	116 Unclassified Street Excavation			су	\$	10.00	\$	237,111
216	16 Lime Treated Subgrade (8") (PI<12)		15,520	sy	\$	7.00	\$	108,640
316	316 9" Concrete Pavement			sy	\$	60.00	\$	879,467
416	6 4" Topsoil			sy	\$	2.50	\$	30,717
516	6 6" Curb & Gutter		7,760	lf	\$	5.00	\$	38,800
616	Allotment for Turn Lanes and Median Openings		1,341	sy	\$	77.00	\$	103,233
716	716 Moisture Conditioning		15,520	sy	\$	8.00	\$	124,160
Paving Construction Cost Subtotal:						\$	1,522,128	
Majo	Major Construction Component Allowances**:							
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	None Anticipated	<u>.                                      </u>			1%	\$	15,221
	Pavement Markings/Markers					3%	\$	45,664

	Item Description	Notes	Allowance		Item Cost
	raffic Control None Anticipated 1%				15,221
	Pavement Markings/Markers		3%	\$	45,664
	Roadway Drainage	Standard Internal System	25%	\$	380,532
	Special Drainage Structures	None Anticipated		\$	-
	Water	None Anticipated	0%	\$	-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	30,443
	Illumination	Standard Ilumination System	6%	\$	91,328
	Other:				
**Allo	**Allowances based on % of Paving Construction Cost Subtotal Allowance Subtotal:				
	\$	2,085,315			
	\$	104,266			
	\$	104,266			
	\$	2,294,000			
	\$	344,100			
	\$	2,639,000			

Item Description	Notes:	Allowance	Item Cost	
Construction:		-	\$	2,639,000
Engineering/Survey/Testing:		20%	\$	527,800
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$	923,650

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

Roadway Improvements - Service Area C

#	Costing Class	Project	Limits	7	Total Cost	Percent in Service Area	Cost in rvice Area
A-1, C-1	M6D	UNNAMED 5 (1)	635' W OF STONEBRIDGE DR TO CR 168	\$	7,715,900	50%	\$ 3,857,950
C-2	M6D	UNNAMED 5 (2)	RIDGE RD TO 1,505' E OF RIDGE RD	\$	3,137,400	50%	\$ 1,568,700
C-3	G6D	LAUD HOWELL PKWY (1)	695' W OF CUSTER RD TO CUSTER RD	\$	665,000	50%	\$ 332,500
C-4	G6D	LAUD HOWELL PKWY (2)	CUSTER RD TO 1,225' E OF CUSTER RD	\$	1,171,800	100%	\$ 1,171,800
C-5	G6D	LAUD HOWELL PKWY (3)	1,225' E OF CUSTER RD TO 2,070' E OF CUSTER RD	\$	808,500	50%	\$ 404,250
C-6	G6D	LAUD HOWELL PKWY (4)	840' E OF STONEBRIDGE DR TO 2,905' E OF STONEBRIDGE DR	\$	2,859,500	50%	\$ 1,429,750
C-7	G6D	LAUD HOWELL PKWY (5)	1,985' W OF RIDGE RD TO 1,230' E OF RIDGE RD	\$	3,073,000	50%	\$ 1,536,500
C-8	P6D	BLOOMDALE RD (1)	CUSTER RD TO 1,310' E OF CUSTER RD	\$	3,179,400	100%	\$ 3,179,400
C-9	P6D	BLOOMDALE RD (2)	1,310' E OF CUSTER RD TO 2,030' W OF STONEBRIDGE DR	\$	4,838,400	50%	\$ 2,419,200
C-10	P6D	BLOOMDALE RD (3)	2,030' W OF STONEBRIDGE DR TO 3,245' E OF STONEBRIDGE DR	\$	13,314,000	100%	\$ 13,314,000
C-11	P6D	BLOOMDALE RD (4)	3,245' E OF STONEBRIDGE DR TO 695' W OF RIDGE RD	\$	3,292,800	50%	\$ 1,646,400
C-12	P6D	BLOOMDALE RD (5)	695' W OF RIDGE RD TO RIDGE RD	\$	1,453,200	100%	\$ 1,453,200
C-13	P6D(2/3)	BLOOMDALE RD (6)	3,400' W OF LAKE FOREST DR TO LAKE FOREST DR	\$	4,650,800	50%	\$ 2,325,400
C-14	G4D	WILMETH RD (1)	3,725' W OF STONEBRIDGE DR TO 815' E OF STONEBRIDGE DR	\$	8,845,850	100%	\$ 8,845,850
C-15	G4D	WILMETH RD (2)	815' E OF STONEBRIDGE DR TO 995' W OF RIDGE RD	\$	6,200,600	50%	\$ 3,100,300
C-16	G4D(1/2)	WILMETH RD (3)	RIDGE RD TO 585' E OF RIDGE RD	\$	1,593,000	100%	\$ 1,593,000
C-17	G4D(1/2)	WILMETH RD (4)	1,095' E OF RIDGE RD TO 1,365' E OF RIDGE RD	\$	708,000	100%	\$ 708,000
C-18	P6D	CUSTER RD (1)	1,855' N OF LAUD HOWELL PKWY TO LAUD HOWELL PKWY	\$	1,834,000	50%	\$ 917,000
C-19	P6D	CUSTER RD (2)	LAUD HOWELL PKWY TO 2,775 N OF BLOOMDALE RD	\$	2,869,825	100%	\$ 2,869,825
C-20	P6D	CUSTER RD (3)	2,655 N OF BLOOMDALE RD TO 375' N OF WILMETH RD	\$	8,071,300	50%	\$ 4,035,650
C-21	G4D	STONEBRIDGE DR (2)	UNNAMED 5 TO 1,280' S OF UNNAMED 5	\$	2,763,650	100%	\$ 2,763,650
C-22	G4D	STONEBRIDGE DR (3)	1,570' S OF LAUD HOWELL PKWY TO 280' S OF WILMETH RD	\$	14,194,900	100%	\$ 14,194,900
C-23	G4D	STONEBRIDGE DR (4)	280' S OF WILMETH RD TO 1,195' S OF WILMETH RD	\$	2,117,300	50%	\$ 1,058,650
C-24	G4D	STONEBRIDGE DR (5)	1,195' S OF WILMETH RD TO 5,555' S OF WILMETH RD	\$	8,232,050	100%	\$ 8,232,050
C-25	G4D	STONEBRIDGE DR (6)	580' N OF US HIGHWAY 380 TO US HIGHWAY 380	\$	1,030,750	100%	\$ 1,030,750
C-26	M6D	RIDGE RD (1)	UNNAMED 5 TO 1,485' S OF UNNAMED 5	\$	3,095,400	50%	\$ 1,547,700
C-27	M6D	RIDGE RD (2)	LAUD HOWELL PKWY TO BAXTER WELL RD	\$	7,267,950	100%	\$ 7,267,950
C-28	M6D	RIDGE RD (3)	BAXTER WELL RD TO 2,160' S OF BLOOMDALE RD	\$	9,144,800	50%	\$ 4,572,400
C-29	M6D	RIDGE RD (4)	1,590' N OF WILMETH RD TO WILMETH RD	\$	3,756,200	50%	\$ 1,878,100
C-30	M6D(1/3)	RIDGE RD (5)	WILMETH RD TO 2,280' S OF WILMETH RD	\$	7,411,200	100%	\$ 7,411,200
C-31	M6D(1/3)	RIDGE RD (6)	1,860' N OF US HIGHWAY 380 TO 1,390' N OF US HIGHWAY 380	\$	1,455,000	50%	\$ 727,500
C-32	M6D(1/3)	RIDGE RD (7)	775' N OF US HIGHWAY 380 TO US HIGHWAY 380	\$	2,857,200	100%	\$ 2,857,200
C-33	M6D(1/3)	LAKE FOREST DR (2)	BLOOMDALE RD TO WILMETH RD	\$	5,008,981	50%	\$ 2,504,491
C-34, D-22	M6D(1/3)	LAKE FOREST DR (3)	WILMETH RD TO US HIGHWAY 380	\$	2,350,800	50%	\$ 1,175,400
2		Signal	RIDGE RD & UNNAMED 5	\$	300,000	25%	\$ 75,000
4		Signal	LAUD HOWELL PKWY & CUSTER RD	\$	300,000	75%	\$ 225,000
5		Signal	LAUD HOWELL PKWY & RIDGE RD	\$	300,000	50%	\$ 150,000
12		Intersection Improvement	CUSTER RD & BLOOMDALE RD	\$	150,000	50%	\$ 75,000
13	_	Signal	BLOOMDALE RD & STONEBRIDGE DR	\$	300,000	100%	\$ 300,000
14	ctio	Signal	BLOOMDALE RD & RIDGE RD	\$	300,000	50%	\$ 150,000
15	ntersection	Signal	BLOOMDALE RD & LAKE FOREST DR	\$	300,000	25%	\$ 75,000
23	nte	Signal	STONEBRIDGE DR & WILMETH RD	\$	300,000	100%	\$ 300,000
24		Signal	WILMETH RD & RIDGEKNOLL AVE	\$	300,000	100%	\$ 300,000
25		Roundabout	LAKE FOREST DR & WILMETH RD	\$	1,830,000	50%	\$ 915,000
33		Signal Mod	US HIGHWAY 380 & STONEBRIDGE DR	\$	150,000	50%	\$ 75,000
34	1	Signal	US HIGHWAY 380 & FOREST RIDGE LN	\$	300,000	50%	\$ 150,000
35	]	Signal	US HIGHWAY 380 & AUBURN HILLS PKWY	\$	300,000	50%	\$ 150,000
		v		\$	156,098,456		\$ 116,870,616

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. A-1, C-1

Name: UNNAMED 5 (1) This project consists of the

Limits: 635' W OF STONEBRIDGE DR TO CR 168 construction of a new six-lane divided

Impact Fee Class: M6D major arterial.

Thoroughfare Class: Major Arterial

Length (If): 3,315 Service Area(s): A and C

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
109	Unclassified Street Excavation	36,833	су	\$	10.00	\$ 368,333
209	Lime Treated Subgrade (8") (PI<12)	28,730	sy	\$	7.00	\$ 201,110
309	9" Concrete Pavement	27,257	sy	\$	60.00	\$ 1,635,400
409	4" Topsoil	12,892	sy	\$	2.50	\$ 32,229
509	6" Curb & Gutter	13,260	lf	\$	5.00	\$ 66,300
609	Allotment for Turn Lanes and Median Openings	2,023	sy	\$	77.00	\$ 155,774
709	Moisture Conditioning	28,730	sy	\$	8.00	\$ 229,840

Paving Construction Cost Subtotal: \$ 2,688,987

Majo	or Construction Component Allowa	nces**:			
	Item Description	Notes	Allowance		Item Cost
	Traffic Control	None Anticipated	1%	\$	26,890
	Pavement Markings/Markers		3%	\$	80,670
	Roadway Drainage	Standard Internal System	25%	\$	672,247
	Special Drainage Structures	Stream Crossing		\$	250,000
	Water	None Anticipated	0%	\$	-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	53,780
	Illumination	Standard Ilumination System	6%	\$	161,339
	Other:				
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	1,244,925
		Paving and Allowa	nce Subtotal:	\$	3,933,912
		Mobilization:	5%	\$	196,696
		Site Preparation:	5%	\$	196,696
		Construction C	ost TOTAL:	49	4,328,000
		Construction Contingency:	15%	\$	649,200
	C	onstruction Cost TOTAL W/ CON	FINGENCY:	\$	4,978,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,978,000
Engineering/Survey/Testing:		20%	\$ 995,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,742,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

10/6/2020

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information: C-2** Description: Project No. Name: UNNAMED 5 (2) This project consists of the Limits: RIDGE RD TO 1,505' E OF RIDGE RD reconstruction of a two-lane asphalt Impact Fee Class: M6D facility to a six-lane divided major Thoroughfare Class: Major Arterial arterial. Based on the existing City Length (If): 1,505 Limits, the northern half of the roadway Service Area(s): C, Half is not included in the Impact Fee RIP.

Pos	dway Construction Cost Project	ction					
No.	Item Description	CHOII	Quantity	Unit	Un	it Price	Item Cost
109	Unclassified Street Excavation		16,722	СУ	\$	10.00	\$ 167,222
209	Lime Treated Subgrade (8") (PI<12)		13,043	sy	\$	7.00	\$ 91,303
309	9" Concrete Pavement		12,374	sy	\$	60.00	\$ 742,467
409	4" Topsoil		5,853	sy	\$	2.50	\$ 14,632
509	6" Curb & Gutter		6,020	lf	\$	5.00	\$ 30,100
609	Allotment for Turn Lanes and Median O	penings	918	sy	\$	77.00	\$ 70,721
709	Moisture Conditioning	-	13,043	sy	\$	8.00	\$ 104,347
		Р	aving Constr	uction (	Cost S	Subtotal:	\$ 1,220,792
			_				
Majo	r Construction Component Allowanc	es**:					
	Item Description	Notes			Alle	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 36,624
	Pavement Markings/Markers					3%	\$ 36,624
	Roadway Drainage	Standard Internal Sy	stem			25%	\$ 305,198
	Special Drainage Structures	None Anticipated					\$ -
	Water	Incidental Adjustmer	nts			3%	36,624
	Sewer	Incidental Adjustmer	nts			3%	\$ 36,624
	Establish Turf / Erosion Control					2%	\$ 24,416
	Illumination	Standard Ilumination	System			6%	\$ 73,248
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce	Subtotal:	\$ 549,356
			Paving and	d Allowa	nce S	Subtotal:	\$ 1,770,148
			Mobi	lization:		5%	\$ 88,507
			Site Prep	aration:		5%	\$ 88,507
			Construc				\$ 1,948,000
			uction Conti			15%	\$ 292,200
	Cor	nstruction Cos	t TOTAL W	// CON	TING	ENCY:	\$ 2,241,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,241,000
Engineering/Survey/Testing:		20%	\$ 448,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 448,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

C, Half

716 Allotment for Turn Lanes and Median Openings

Service Area(s):

updated: 10/6/2020

Project Information:		Description:	Project No.	C-3
Name:	LAUD HOWELL PKWY (1) 695' W OF CUSTER RD TO	This project consists of lane asphalt facility to a		
Limits:	CUSTER RD	arterial. Based on the ex	cisting City Limits	s, the
Impact Fee Class:	G6D	northern half of the road	dway is not includ	ded in the
Thoroughfare Class:	Greenway Arterial	Impact Fee RIP.		
Length (If):	695			

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	J	nit Price	Item Cost
116	Unclassified Street Excavation	4,247	су	\$	15.00	\$ 63,708
216	Lime Treated Subgrade (8") (PI<12)	5,560	sy	\$	7.00	\$ 38,920
316	4" TY D HMAC Underlayment	5,251	sy	\$	5.00	\$ 26,256
416	9" Concrete Pavement	5,251	sy	\$	60.00	\$ 315,067
516	4" Topsoil	4,402	sy	\$	4.00	\$ 17,607
616	6" Curb & Gutter	2,780	lf	\$	5.00	\$ 13,900

480

Paving Construction Cost Subtotal: \$ 517,243

87.00 \$

41,786

Mai				
Majo	or Construction Component Allov Item Description	Notes	Allowance	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$ 15,517
	Pavement Markings/Markers		3%	\$ 15,517
	Roadway Drainage		25%	\$ 129,311
	Special Drainage Structures	None Anticipated		\$ -
	Water	Incidental Adjustments	3%	\$ 15,517
	Sewer	Incidental Adjustments	3%	\$ 15,517
	Establish Turf / Erosion Control		2%	\$ 10,345
	Illumination	Standard Ilumination System	6%	\$ 31,035
	Other:			
**Allc	wances based on % of Paving Construction	Cost Subtotal Allowa	ance Subtotal:	\$ 232,759
		Paving and Allowa		750,003
		Mobilization:	5%	\$ 37,500
		Site Preparation:	5%	\$ 37,500
		Construction C	ost TOTAL:	\$ 826,000
		Construction Contingency:	15%	\$ 123,900
		Construction Cost TOTAL W/ CON	TINGENCY:	\$ 950,000

Impact Fee Project Cost Summ	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 950,000
Engineering/Survey/Testing:		20%	\$ 190,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 190,000
Impact Fe	ee Project Cost TOTAL (50% City C	ontribution)	\$ 665,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. C-4

Name: LAUD HOWELL PKWY (2) This project consists of the

Limits: CUSTER RD TO 1,225' E OF CUSTER RD reconstruction of a tw

Impact Fee Class: G6D

Thoroughfare Class: Greenway Arterial

Length (If): 1,225 Service Area(s): C reconstruction of a two-lane asphalt facility to a six-lane divided greenway

arterial.

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	it Price	Item Cost
116	Unclassified Street Excavation	7,486	су	\$	15.00	\$ 112,292
216	Lime Treated Subgrade (8") (PI<12)	9,800	sy	\$	7.00	\$ 68,600
316	4" TY D HMAC Underlayment	9,256	sy	\$	5.00	\$ 46,278
416	9" Concrete Pavement	9,256	sy	\$	60.00	\$ 555,333
516	4" Topsoil	7,758	sy	\$	4.00	\$ 31,033
616	6" Curb & Gutter	4,900	lf	\$	5.00	\$ 24,500
716	Allotment for Turn Lanes and Median Openings	847	sy	\$	87.00	\$ 73,652
		Paving Consti	ruction C	ost	Subtotal:	\$ 911,688

		Paving Construction C	Cost Subtotal:	\$ 911,688
Majo	or Construction Component Allowand	es**:		_
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$ 27,351
	Pavement Markings/Markers		3%	\$ 27,351
	Roadway Drainage		25%	\$ 227,922
	Special Drainage Structures	None Anticipated		\$ -
	Water	Incidental Adjustments	3%	\$ 27,351
	Sewer	Incidental Adjustments	3%	\$ 27,351
	Establish Turf / Erosion Control		2%	\$ 18,234
	Illumination	Standard Ilumination System	6%	\$ 54,701
	Other:			
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$ 410,259
		Paving and Allowa	nce Subtotal:	\$ 1,321,947
		Mobilization:	5%	\$ 66,097
		Site Preparation:	5%	\$ 66,097
		Construction C	ost TOTAL:	\$ 1,455,000
		Construction Contingency:	15%	\$ 218,250

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,674,000
Engineering/Survey/Testing:		20%	\$ 334,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 334,800

Construction Cost TOTAL W/ CONTINGENCY:

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

1,674,000

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No. C-5
Name:	LAUD HOWELL PKWY (3) 1,225' E OF CUSTER RD TO 2,070'		This project consists of the reconstruction of a two-lane asphalt
Limits: Impact Fee Class:	E OF CUSTER RD G6D		facility to a six-lane divided greenway arterial. Based on the existing City
Thoroughfare Class: Length (If):	Greenway Arterial 845		Limits, the northern half of the roadway
Service Area(s):	C, Half		is not included in the Impact Fee RIP.

Roa	dway Construction Cost Proj	ection					
No.	Item Description		Quantity	Unit	Un	it Price	Item Cost
116	Unclassified Street Excavation		5,164	су	\$	15.00	\$ 77,458
216	Lime Treated Subgrade (8") (PI<12)		6,760	sy	\$	7.00	\$ 47,320
316	4" TY D HMAC Underlayment		6,384	sy	\$	5.00	\$ 31,922
416	9" Concrete Pavement		6,384	sy	\$	60.00	\$ 383,067
516	4" Topsoil		5,352	sy	\$	4.00	\$ 21,407
616	16 6" Curb & Gutter 3,380 If				\$	5.00	\$ 16,900
716	Allotment for Turn Lanes and Median	Openings	584	sy	\$	87.00	\$ 50,805
		Р	Paving Consti	ruction (	Cost	Subtotal:	\$ 628,878
Majo	r Construction Component Allowar	ces**:					
	Item Description	Notes			All	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 18,866
	Pavement Markings/Markers					3%	\$ 18,866
	Roadway Drainage					25%	\$ 157,220
	Special Drainage Structures	None Anticipated					\$ -
	Water	Incidental Adjustmer	nts			3%	\$ 18,866
	Sewer	Incidental Adjustmer	nts			3%	\$ 18,866
	Establish Turf / Erosion Control					2%	\$ 12,578
	Illumination	Standard Ilumination	System			6%	\$ 37,733
	Other:						
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	nce	Subtotal:	\$ 282,995
							_
			Paving an	d Allowa	nce	Subtotal:	\$ 911,874
			Mobi	lization:		5%	\$ 45,594
			Site Prep	aration:		5%	\$ 45,594
			Construc	ction C	ost	TOTAL:	\$ 1,004,000
		Constr	uction Conti	ngency:		15%	\$ 150,600
	С	onstruction Cos	t TOTAL W	// CON	TING	SENCY:	\$ 1,155,000

Impact Fee Project Cost Summa	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,155,000
Engineering/Survey/Testing:		20%	\$ 231,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 231,000
Impact Fe	e Project Cost TOTAL (50% City C	ontribution)	\$ 808,500

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	C-6
Name:	LAUD HOWELL PKWY (4) 840' E OF STONEBRIDGE DR TO	This project consists o lane asphalt facility to		
Limits: Impact Fee Class:	2,905' E OF STONEBRIDGE DR G6D	arterial. Based on the e	xisting City Lin	nits, the
Thoroughfare Class: Length (If):	Greenway Arterial 2.065	Impact Fee RIP.		
Service Area(s):	C, Half			

Por	adway Canatruction Cost Brais	action					
	adway Construction Cost Proje	CUON	Quantity	Unit	Ur	it Price	Item Cost
116	Unclassified Street Excavation		12.619	су	\$	15.00	\$ 189,292
216	Lime Treated Subgrade (8") (PI<12)		16,520	sy	\$	7.00	\$ 115,640
	4" TY D HMAC Underlayment		15,602	sy	\$	5.00	\$ 78,011
	9" Concrete Pavement		15,602	sy	\$	60.00	\$ 936,133
516	4" Topsoil		13,078	sy	\$	4.00	\$ 52,313
616	6" Curb & Gutter		8,260	lf	\$	5.00	\$ 41,300
716	Allotment for Turn Lanes and Median	Openings	1,427	sy	\$	87.00	\$ 124,156
	Paving Construction Cost Subtotal:						\$ 1,536,845
			_				
Majo	or Construction Component Allowand	ces**:					
	Item Description	Notes			All	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 46,105
	Pavement Markings/Markers					3%	\$ 46,105
	Roadway Drainage					25%	\$ 384,211
	Special Drainage Structures	Bridge					\$ 1,000,000
	Water	Incidental Adjustmer	nts			3%	\$ 46,105
	Sewer	Incidental Adjustmer	nts			3%	\$ 46,105
	Establish Turf / Erosion Control					2%	\$ 30,737
	Illumination	Standard Ilumination	System			6%	\$ 92,211
	Other:						
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce	Subtotal:	\$ 1,691,580
			Paving an	d Allowa	nce	Subtotal:	\$ 3,228,425
			Mobi	lization:		5%	\$ 161,421
			Site Prep	aration:		5%	\$ 161,421
			Construc			TOTAL:	\$ 3,552,000
			ruction Conti			15%	\$ 532,800
	Co	nstruction Cos	st TOTAL W	// CON	TINC	SENCY:	\$ 4,085,000

Impact Fee Project Cost Summ	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,085,000
Engineering/Survey/Testing:		20%	\$ 817,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 817,000
Impact Fe	ee Project Cost TOTAL (50% City C	ontribution)	\$ 2,859,500

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Information</b>	1:	Description:	Project No. C-7
Name:	LAUD HOWELL PKWY (5) 1,985' W OF RIDGE RD TO 1,230' E		This project consists of the reconstruction of a two-lane asphalt
Limits: Impact Fee Class: Thoroughfare Class: Length (If): Service Area(s):	OF RIDGE RD G6D Greenway Arterial 3,215 C, Half		facility to a six-lane divided greenway arterial. Based on the existing City Limits, the northern half of the roadway is not included in the Impact Fee RIP.

Roa	dway Construction Cost Projec	tion					
No.	Item Description		Quantity	Unit	Unit Price		Item Cost
116	Unclassified Street Excavation		19,647	су	\$ 15.00	\$	294,708
216	Lime Treated Subgrade (8") (PI<12)		25,720	sy	\$ 7.00	\$	180,040
316	4" TY D HMAC Underlayment		24,291	sy	\$ 5.00	\$	121,456
416	9" Concrete Pavement		24,291	sy	\$ 60.00	\$	1,457,467
516	4" Topsoil		20,362	sy	\$ 4.00	\$	81,447
	6" Curb & Gutter		12,860	lf	\$ 5.00	\$	64,300
716	Allotment for Turn Lanes and Median O		2,222	sy	\$ 87.00	\$	193,298
	Paving Construction Cost					\$	2,392,715
Maio	or Construction Component Allowance	`\$\$**•	_	_			
11123	Item Description	Notes			Allowance	Π	Item Cost
	Traffic Control	Construction Phase	Fraffic Control		3%	\$	71,781
	Pavement Markings/Markers				3%	\$	71,781
	Roadway Drainage				25%	\$	598,179
	Special Drainage Structures	None Anticipated				\$	-
	Water	Incidental Adjustmen	ts		3%	\$	71,781
	Sewer	Incidental Adjustmen	ts		3%	\$	71,781
	Establish Turf / Erosion Control				2%	\$	47,854
	Illumination	Standard Ilumination	System		6%	\$	143,563
	Other:						
**Allo	wances based on % of Paving Construction Cost Si	ubtotal		Allowa	ınce Subtotal:	\$	1,076,722
						Ļ	- 100 100
			_		nce Subtotal:		3,469,437
				lization:	5%	•	173,472
			Site Prep				173,472
					ost TOTAL:		3,817,000
			ruction Conti			,	572,550
	Co	nstruction Cos	st TOTAL V	W CON	TINGENCY:	\$	4,390,000

Impact Fee Project Cost Summa	ry		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,390,000
Engineering/Survey/Testing:		20%	\$ 878,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 878,000
Impact Fo	ee Project Cost TOTAL (50% City C	ontribution)	\$ 3,073,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. C-8

Name: BLOOMDALE RD (1) This project consists of the

Limits: CUSTER RD TO 1,310' E OF CUSTER RD reconstruction of a two-la

Impact Fee Class: P6D facility to

Thoroughfare Class: Principal Arterial

Length (If): 1,310 Service Area(s): C reconstruction of a two-lane asphalt facility to a six-lane divided principal

arterial.

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
113	Unclassified Street Excavation	14,556	су	\$	10.00	\$ 145,556
213	Lime Treated Subgrade (8") (PI<12)	11,353	sy	\$	7.00	\$ 79,473
313	9" Concrete Pavement	10,771	sy	\$	60.00	\$ 646,267
413	4" Topsoil	5,968	sy	\$	2.50	\$ 14,919
513	6" Curb & Gutter	5,240	lf	\$	5.00	\$ 26,200
613	Allotment for Turn Lanes and Median Openings	799	sy	\$	77.00	\$ 61,558
713	Moisture Conditioning	11,353	sy	\$	8.00	\$ 90,827
	F	Paving Constr	uction C	Cost S	Subtotal:	\$ 1,064,800

Mai	C			_					
Maj	or Construction Component Allowand Item Description	es ::  Notes	Allowance		Item Cost				
	Traffic Control	Construction Phase Traffic Control	3%	\$	31,944				
į	Pavement Markings/Markers	Construction Finance France Control	3%		31,944				
V	Roadway Drainage	Standard Internal System	25%		266,200				
V	Special Drainage Structures	Stream Crossing		\$	250,000				
V	Water	Incidental Adjustments	3%	\$	31,944				
	Sewer	Incidental Adjustments	3%		31,944				
	Establish Turf / Erosion Control	,	2%		21,296				
	Illumination	Standard Ilumination System	6%		63,888				
	Other:	,			,				
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$	729,160				
	, , , , , , , , , , , , , , , ,								
		Paving and Allowa	nce Subtotal:	\$	1,793,959				
		Mobilization:	5%	\$	89,698				
		Site Preparation:	5%	\$	89,698				
		Construction C	ost TOTAL:	\$	1,974,000				
		Construction Contingency:	15%	\$	296,100				
	Col	nstruction Cost TOTAL W/ CON	TINGENCY:	\$	2,271,000				

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,271,000
Engineering/Survey/Testing:		20%	\$ 454,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 454,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information:	Description:	Project No.	C-9

Name: BLOOMDALE RD (2) This project consists of the

1,310' E OF CUSTER RD TO 2,030' reconstruction of a t

Limits: W OF STONEBRIDGE DR

Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 2,105 Service Area(s): C, Half reconstruction of a two-lane asphalt facility to a six-lane divided principal arterial. Based on the existing City Limits, the southern half of the roadway is not included in the Impact Fee RIP.

Da	advisor Construction Cost Brain	antin in						
	adway Construction Cost Projetem Description	ection	Quantity	Unit	Un	it Price		Item Cost
113	Unclassified Street Excavation		23,389	су	\$	10.00	\$	233,889
	Lime Treated Subgrade (8") (PI<12)		18,243	sy	\$	7.00	\$	127,703
313	9" Concrete Pavement		17,308	sy	\$	60.00	\$	1,038,467
413	4" Topsoil		9,589	sy	\$	2.50	\$	23,974
513	6" Curb & Gutter		8,420	lf	\$	5.00	\$	42,100
613	Allotment for Turn Lanes and Median	Openings	1,285	sy	\$	77.00	\$	98,916
713	Moisture Conditioning		18,243	sy	\$	8.00	\$	145,947
		F	Paving Const	ruction (	Cost	Subtotal:	\$	1,710,995
			J				-	
Majo	or Construction Component Allowan	ces**:						
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	51,330
	Pavement Markings/Markers					3%	\$	51,330
	Roadway Drainage	Standard Internal Sy	stem			25%	\$	427,749
	Special Drainage Structures	Stream Crossing					\$	250,000
	Water	Incidental Adjustmer	nts			3%	\$	51,330
	Sewer	Incidental Adjustmer	nts			3%	\$	51,330
	Establish Turf / Erosion Control					2%	\$	34,220
	Illumination	Standard Ilumination	n System			6%	\$	102,660
	Other:							
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce S	Subtotal:	\$	1,019,948
	Paving and Allowance Subtotal:							2,730,942
	Mobilization: 5%						\$	136,547
	Site Preparation: 5%						\$	136,547
	Construction Cost TOTAL:						\$	3,005,000
			ruction Conti			15%	_	450,750
	Construction Cost TOTAL W/ CONTINGENCY:						\$	3,456,000

Impact Fee Project Cost Sumr	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,456,000
Engineering/Survey/Testing:		20%	\$ 691,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 691,200
	Impact Fee P	roject Cost TOTAL:	\$ 4,838,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc. updated: 10/6/2020

2019 Roadway Impact Fee Update

Conceptual Level Project Cost Projection

**Project Information:** C-10 Description: Project No.

BLOOMDALE RD (3) Name: This project consists of the

2,030' W OF STONEBRIDGE DR TO reconstruction of a two-lane asphalt

Limits: 3,245' E OF STONEBRIDGE DR facility to a six-lane divided principal

**Impact Fee Class:** arterial.

Thoroughfare Class: Principal Arterial

Length (If): 5,275 С Service Area(s):

Roa	adway Construction Cost Projection				
No.	Item Description	Quantity	Unit	Unit Price	Item Cost
113	Unclassified Street Excavation	58,611	су	\$ 10.00	\$ 586,111
213	Lime Treated Subgrade (8") (PI<12)	45,717	sy	\$ 7.00	\$ 320,017
313	9" Concrete Pavement	43,372	sy	\$ 60.00	\$ 2,602,333
413	4" Topsoil	24,031	sy	\$ 2.50	\$ 60,076
513	6" Curb & Gutter	21,100	lf	\$ 5.00	\$ 105,500
613	Allotment for Turn Lanes and Median Openings	3,219	sy	\$ 77.00	\$ 247,876
713	Moisture Conditioning	45,717	sy	\$ 8.00	\$ 365,733

Paving Construction Cost Subtotal: \$ 4,287,647

Majo	Major Construction Component Allowances**:									
	Item Description	Notes	Allowance		Item Cost					
	Traffic Control	Construction Phase Traffic Control	3%	\$	128,629					
	Pavement Markings/Markers		3%	\$	128,629					
	Roadway Drainage	Standard Internal System	25%	\$	1,071,912					
	Special Drainage Structures	Bridge		\$	1,300,000					
	Water	Incidental Adjustments	3%	\$	128,629					
	Sewer	Incidental Adjustments	3%	\$	128,629					
	Establish Turf / Erosion Control		2%	\$	85,753					
	Illumination	Standard Ilumination System	6%	\$	257,259					
	Other:									
**Allo	wances based on % of Paving Construction Cost S	ubtotal Allowa	nce Subtotal:	\$	3,229,441					
		Paving and Allowa	nce Subtotal:	\$	7,517,088					
		Mobilization:	5%	\$	375,854					
		Site Preparation:	5%	\$	375,854					
	\$	8,269,000								
	Construction Contingency: 15%									
	Con	struction Cost TOTAL W/ CON	TINGENCY:	\$	9,510,000					
				•						

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 9,510,000
Engineering/Survey/Testing:		20%	\$ 1,902,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 1,902,000
	Impact Fee P	roject Cost TOTAL:	\$ 13,314,000

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

<b>Project Information</b>	n:	Description:	Project No.	C-11			
Name:	BLOOMDALE RD (4) 3,245' E OF STONEBRIDGE DR TO	This project consists of lane asphalt facility to a					
Limits: Impact Fee Class:	695' W OF RIDGE RD P6D	arterial. Based on the existing City Limits, the southern half of the roadway is not included in the					
Thoroughfare Class:	Principal Arterial	Impact Fee RIP.	away io not mor				
Length (If): Service Area(s):	1,365 C, Half						

Roa	adway Construction Cost Pro	ection					
No.	Item Description		Quantity	Unit	Unit	t Price	Item Cost
113	Unclassified Street Excavation		15,167	су	\$	10.00	\$ 151,667
213	Lime Treated Subgrade (8") (PI<12)		11,830	sy	\$	7.00	\$ 82,810
313	9" Concrete Pavement		11,223	sy	\$	60.00	\$ 673,400
413	4" Topsoil		6,218	sy	\$	2.50	\$ 15,546
513	6" Curb & Gutter		5,460	lf	\$	5.00	\$ 27,300
613	Allotment for Turn Lanes and Mediar	Openings	833	sy	\$	77.00	\$ 64,142
713	Moisture Conditioning		11,830	sy	\$	8.00	\$ 94,640
		F	Paving Const	ruction (	Cost S	ubtotal:	\$ 1,109,505
Majo	or Construction Component Allowa	nces**:					
	Item Description	Notes			Allo	wance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 33,285
	Pavement Markings/Markers					3%	\$ 33,285
	Roadway Drainage	Standard Internal Sy	Standard Internal System			25%	\$ 277,376
	Special Drainage Structures	Stream Crossing					\$ 250,000
	Water	Incidental Adjustme	nts			3%	\$ 33,285

√ Traffic Control	Construction Phase Traffic Control	3%	\$	33,285
√ Pavement Markings/Markers		3%	\$	33,285
√ Roadway Drainage	Standard Internal System	25%	\$	277,376
√ Special Drainage Structures	Stream Crossing		\$	250,000
√ Water	Incidental Adjustments	3%	\$	33,285
√ Sewer	Incidental Adjustments	3%	\$	33,285
√ Establish Turf / Erosion Control		2%	\$	22,190
$\sqrt{}$ Illumination	Standard Ilumination System	6%	\$	66,570
Other:				
**Allowances based on % of Paving Construction C	ost Subtotal Allowa	nce Subtotal:	\$	749,277
	Paving and Allowa	naa Cubtatali	\$	1,858,782
	Mobilization:		-	92,939
	Site Preparation:		Ĭ	•
	-	92,939		
	\$	2,045,000		
Construction Contingency: 15%				306,750
	Construction Cost TOTAL W/ CON	TINGENCY:	\$	2,352,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,352,000
Engineering/Survey/Testing:		20%	\$ 470,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 470,400
	Impact Fee Project	Cost TOTAL:	\$ 3,292,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

 Project Information:
 Description:
 Project No.
 C-12

 Name:
 BLOOMDALE RD (5)
 This project consists of the reconstruction of a two-limits:

 Limits:
 695' W OF RIDGE RD TO RIDGE RD lane asphalt facility to a six-lane divided principal

Impact Fee Class: P6D arterial.

Thoroughfare Class: Principal Arterial

Length (If): 695 Service Area(s): C

Roadway Construction Cost Projection							
No.	No. Item Description Quant			Unit	Unit Price		Item Cost
113	Unclassified Street Excavation		7,722	су	\$ 10.00	\$	77,222
213	Lime Treated Subgrade (8") (PI<12)		6,023	sy	\$ 7.00	\$	42,163
313	9" Concrete Pavement		5,714	sy	\$ 60.00	\$	342,867
413	4" Topsoil		3,166	sy	\$ 2.50	\$	7,915
513	6" Curb & Gutter		2,780	lf	\$ 5.00	\$	13,900
613	Allotment for Turn Lanes and Median O	penings	424	sy	\$ 77.00	\$	32,659
713	Moisture Conditioning		6,023	sy	\$ 8.00	\$	48,187
		Р	aving Constr	ruction C	Cost Subtotal:	\$	564,913
Majo	or Construction Component Allowance						
	Item Description	Notes			Allowance		Item Cost
<b>√</b>	Traffic Control	Construction Phase	Traffic Control		3%		16,947
<b>√</b>	Pavement Markings/Markers				3%		16,947
	Roadway Drainage	Standard Internal Sy	rstem		25%		141,228
,	Special Drainage Structures	None Anticipated				\$	-
	Water	Incidental Adjustmer	nts		3%		16,947
	Sewer	Incidental Adjustmer	nts		3%		16,947
	Establish Turf / Erosion Control				2%		11,298
	Illumination	Standard Ilumination	n System		6%	\$	33,895
	Other:				_	<u> </u>	
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	nce Subtotal:	\$	254,211
						ļ.,	
Paving and Allowance Subtotal:							819,123
Mobilization: 5%						40,956	
	Site Preparation: 5%						40,956
Construction Cost TOTAL:							902,000
			uction Conti			<u> </u>	135,300
	Con	struction Cos	t TOTAL W	// CON	TINGENCY:	\$	1,038,000

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,038,000
Engineering/Survey/Testing:		20%	\$ 207,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 207,600
	Impact Fee Pr	oject Cost TOTAL:	\$ 1,453,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### updated:

10/6/2020

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information:** C-13 Description: Project No. Name: **BLOOMDALE RD (6)** This project consists of the 3,400' W OF LAKE FOREST DR TO construction of four additional through Limits: LAKE FOREST DR lanes of the ultimate six-lane divided Impact Fee Class: P6D(2/3) principal arterial. Based on the existing Thoroughfare Class: Principal Arterial City Limits, the northern half of the Length (If): 3,400 roadway is not included in the Impact Service Area(s): C, Half Fee RIP

Roa	dway Construction Cost Projection				
No.	Item Description	Quantity	Unit	Unit Price	Item Cost
115	Unclassified Street Excavation	30,978	су	\$ 10.00	\$ 309,778
215	Lime Treated Subgrade (8") (PI<12)	19,833	sy	\$ 7.00	\$ 138,833
315	9" Concrete Pavement	18,700	sy	\$ 60.00	\$ 1,122,000
415	4" Topsoil	11,522	sy	\$ 2.50	\$ 28,806
515	6" Curb & Gutter	10,200	lf	\$ 5.00	\$ 51,000
615	Allotment for Turn Lanes and Median Openings	2,075	sy	\$ 77.00	\$ 159,769

Paving Construction Cost Subtotal: \$ 1,810,185

	or Construction Component Allowar	Notes	Allowance		Item Cost
	Item Description			_	
ν,	Traffic Control	Construction Phase Traffic Control	3%		54,306
√.	Pavement Markings/Markers		3%	\$	54,306
	Roadway Drainage	Standard Internal System	25%	\$	452,546
	Special Drainage Structures	None Anticipated		\$	-
	Water	Incidental Adjustments	3%	\$	54,306
	Sewer	Incidental Adjustments	3%	\$	54,306
	Establish Turf / Erosion Control		2%	\$	36,204
	Illumination	Standard Ilumination System	6%	\$	108,611
	Other:				
**All	owances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	814,583
		Paving and Allowa	nce Subtotal:	\$	2,624,769
		Mobilization:	5%	\$	131,238
Site Preparation: 5%					131,238
		Construction C	ost TOTAL:	\$	2,888,000
		Construction Contingency:	15%	\$	433,200
	\$	3,322,000			

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,322,000
Engineering/Survey/Testing:		20%	\$ 664,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 664,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information:** C-14 Description: Project No.

Name: WILMETH RD (1) This project consists of the construction

3,725' W OF STONEBRIDGE DR TO of a new four-lane divided greenway Limits:

815' E OF STONEBRIDGE DR arterial.

**Impact Fee Class:** G4D

Thoroughfare Class: **Greenway Arterial** 

Length (If): 4,540 С Service Area(s):

Roadway Construction Cost Projection								
No.	Item Description	Quantity	Unit	Un	it Price		Item Cost	
107	Unclassified Street Excavation	44,391	су	\$	10.00	\$	443,911	
207	Lime Treated Subgrade (8") (PI<12)	33,293	sy	\$	7.00	\$	233,053	
307	8" Concrete Pavement	31,276	sy	\$	55.00	\$	1,720,156	
407	4" Topsoil	21,691	sy	\$	2.50	\$	54,228	
507	6" Curb & Gutter	18,160	lf	\$	5.00	\$	90,800	
607	Allotment for Turn Lanes and Median Openings	2,666	sy	\$	72.00	\$	191,918	
707	Moisture Conditioning	33,293	sy	\$	8.00	\$	266,347	

Paving Construction Cost Subtotal: \$ 3,000,413

Mai	or Construction Component Allow	ancas**•	_		_
iviaj	Item Description	Notes	Allowance	П	Item Cost
	Traffic Control	None Anticipated	1%	\$	30,004
	Pavement Markings/Markers		3%	\$	90,012
	Roadway Drainage	Standard Internal System	25%	\$	750,103
	Special Drainage Structures	Stream Crossing		\$	400,000
	Water	None Anticipated	0%	\$	-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	60,008
	Illumination	Standard Ilumination System	6%	\$	180,025
	Other:				
**Allo	wances based on % of Paving Construction (	Cost Subtotal Allowa	nce Subtotal:	\$	1,510,153
		Paving and Allowa		\$	4,510,565
		Mobilization:	5%	\$	225,528
		Site Preparation:	5%	\$	225,528
		Construction C	ost TOTAL:	\$	4,962,000
		Construction Contingency:	15%	\$	744,300
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	5,707,000

Impact Fee Project Cost Summ	nary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	5,707,000
Engineering/Survey/Testing:		20%	\$	1,141,400
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$	1,997,450
Impact Fee Project Cost TOTAL:				8,845,850

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

<b>Project Informatio</b>	n:	Description:	Project No.	C-15
Name: Limits: Impact Fee Class: Thoroughfare Class: Length (If): Service Area(s):	WILMETH RD (2) 815' E OF STONEBRIDGE DR TO 995' W OF RIDGE RD G4D Greenway Arterial 3,340	This project consists of lane asphalt facility to arterial. Based on the southern half of the ro Impact Fee RIP for the the northern half of the the remaining 1,055' eroadway is not include	a four-lane divi- existing City Lir adway is not ind 2,285' western e roadway is no astern section.	ded greenway nits, the cluded in the section while t included for 775' of this

Roa	adway Construction Cost Projec	ction						
No.	Item Description		Quantity	Unit	Uni	t Price		Item Cost
107	Unclassified Street Excavation		32,658	су	\$	10.00	\$	326,578
207	Lime Treated Subgrade (8") (PI<12)		24,493	sy	\$	7.00	\$	171,453
307	8" Concrete Pavement		23,009	sy	\$	55.00	\$	1,265,489
407	07 4" Topsoil			sy	\$	2.50	\$	39,894
507	6" Curb & Gutter		13,360	lf	\$	5.00	<b>65</b>	66,800
607	Allotment for Turn Lanes and Median O	penings	1,961	sy	\$	72.00	\$	141,191
707	Moisture Conditioning		24,493	sy	\$	8.00	\$	195,947
		P	Paving Const	ruction (	Cost S	ubtotal:	\$	2,207,352
Majo	or Construction Component Allowance							
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	-	66,221
	Pavement Markings/Markers					3%	\$	66,221
	Roadway Drainage	Standard Internal Sy	rstem			25%	\$	551,838
	Special Drainage Structures	Stream Crossing					\$	300,000
	Water	Incidental Adjustmer	nts			3%		66,221
	Sewer	Incidental Adjustmer	nts			3%	-	66,221
	Establish Turf / Erosion Control					2%	\$	44,147
	Illumination	Standard Ilumination	System			6%	\$	132,441
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	ince S	ubtotal:	\$	1,293,308
Paving and Allowance Subtotal:							3,500,660	
	Mobilization: 5%					\$	175,033	
			Site Prep			5%		175,033
			Construc			OTAL:	\$	3,851,000
		Constr	uction Conti	ngency:		15%	\$	577,650
	Construction Cost TOTAL W/ CONTINGENCY:						\$	4,429,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,429,000
Engineering/Survey/Testing:		20%	\$ 885,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 885,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

# 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	C-16
Name:	WILMETH RD (3)	This project is part of	the Ridge Rd pro	oject from US
Limits:	RIDGE RD TO 585' E OF RIDGE RD	380 to Wilmeth Rd wh	nich includes a ro	undabout at
Impact Fee Class:	G4D(1/2)	the Ridge Rd & Wilme	eth Rd intersection	n. The City
Thoroughfare Class:	Greenway Arterial	provided an overall pr	roject cost estima	ate of
Length (If):	585	\$17,700,000. This pro	ject consists of t	he
Service Area(s):	C	construction of two a	dditional lanes o	f the ultimate
		four-lane divided gree	enway arterial. Th	nis project
		accounted for \$1,593,	· · · · · · · · · · · · · · · · · · ·	• •

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 1,593,000
	Impact Fee Project C	ost TOTAL:	\$ 1,593,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	C-17				
Name:	WILMETH RD (4) 1,095' E OF RIDGE RD TO 1,365' E	This project is part of 380 to Wilmeth Rd wh	•	•				
Limits: Impact Fee Class:	OF RIDGE RD G4D(1/2)	the Ridge Rd & Wilmeth Rd intersection. The City						
Thoroughfare Class:	Greenway Arterial	provided an overall project cost estimate of \$17,700,000. This project consists of the construction of two additional lanes of the ultim four-lane divided greenway arterial. This project						
Length (If): Service Area(s):	270 C, Half							
		accounted for \$708,00	•					

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 708,000
	Impact Fee Project C	ost TOTAL:	\$ 708,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

	Project Information	Description:	Project No. C-18
--	---------------------	--------------	------------------

Name: CUSTER RD (1) This project consists of the

1,855' N OF LAUD HOWELL PKWY reconstruction of a two-la

Limits: TO LAUD HOWELL PKWY

Conceptual Level Project Cost Projection

Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 1,855 Service Area(s): C, Half reconstruction of a two-lane asphalt facility to a six-lane divided principal arterial. Based on the existing City Limits, the western half of the roadway is not included in the Impact Fee RIP.

	adway Construction Cost Proje	ection						
No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
113	Unclassified Street Excavation		10,306	су	\$	15.00	\$	154,583
213	3 Lime Treated Subgrade (8") (PI<12)			sy	\$	7.00	\$	112,537
313	4" TY D HMAC Underlayment		15,252	sy	\$	5.00	\$	76,261
413	9" Concrete Pavement		15,252	sy	\$	60.00	\$	915,133
513	4" Topsoil		8,451	sy	\$	4.00	\$	33,802
	6" Curb & Gutter		7,420	lf	\$	5.00	\$	37,100
713	Allotment for Turn Lanes and Median	Openings	1,132	sy	\$	87.00	\$	98,488
		P	Paving Const	ruction (	Cost	Subtotal:	\$	1,427,905
Majo	or Construction Component Allowand	ces**:						
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	42,837
	Pavement Markings/Markers					3%		42,837
	Roadway Drainage					25%	\$	356,976
	Special Drainage Structures	None Anticipated					\$	-
	Water	Incidental Adjustmer	nts			3%	\$	42,837
	Sewer	Incidental Adjustmer	nts			3%		42,837
	Establish Turf / Erosion Control					2%	\$	28,558
	Illumination	Standard Ilumination	System			6%	\$	85,674
	Other:							
**Allo	wances based on % of Paving Construction Cos	t Subtotal	·	Allowa	nce	Subtotal:	\$	642,557
	·		Paving an					2,070,462
	Mobilization: 5%					\$	103,523	
			Site Prep			5%	\$	103,523
			Construc			TOTAL:	\$	2,278,000
	-		uction Conti			15%	-	341,700
							\$	2,620,000

Impact Fee Project Cost Summa	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,620,000
Engineering/Survey/Testing:		20%	\$ 524,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 524,000
Impact Fe	e Project Cost TOTAL (50%	City Contribution)	\$ 1,834,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information:** C-19 **Description:** Project No. CUSTER RD (2) Name: This project consists of the Limits: LAUD HOWELL PKWY TO 2,775 N OF BLOOMDALE RD construction of a new **Impact Fee Class:** P6D alignment of Custer Road to a Thoroughfare Class: Principal Arterial six-lane divided principal Length (If): 2,775 arterial. Service Area(s): С

Roa	ndway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
113	Unclassified Street Excavation	15,417	су	\$	15.00	\$ 231,250
213	Lime Treated Subgrade (8") (PI<12)	24,050	sy	\$	7.00	\$ 168,350
313	4" TY D HMAC Underlayment	22,817	sy	\$	5.00	\$ 114,083
413	9" Concrete Pavement	22,817	sy	\$	60.00	\$ 1,369,000
513	4" Topsoil	12,642	sy	\$	4.00	\$ 50,567
613	6" Curb & Gutter	11,100	lf	\$	5.00	\$ 55,500
713	Allotment for Turn Lanes and Median Openings	1,693	sy	\$	87.00	\$ 147,334
		Paving Constr	uction C	Cost	Subtotal:	\$ 2,136,084

Mai	or Construction Component Allowand	es**:		
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	None Anticipated	1%	\$ 21,361
	Pavement Markings/Markers		3%	\$ 64,083
	Roadway Drainage		25%	\$ 534,021
	Special Drainage Structures	None Anticipated		\$ -
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 42,722
	Illumination	Standard Ilumination System	6%	\$ 128,165
	Other:			
**Allo	wances based on % of Paving Construction Cos	Subtotal Allowa	nce Subtotal:	\$ 790,351
		Paving and Allowa		\$ 2,926,435
		Mobilization:	5%	\$ 146,322
		Site Preparation:	5%	\$ 146,322
		Construction C	ost TOTAL:	\$ 3,220,000
		Construction Contingency:	15%	\$ 483,000
	Co	nstruction Cost TOTAL W/ CON	TINGENCY:	\$ 3.703.000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,703,000
Engineering/Survey/Testing:		20%	\$ 740,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,296,050

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

<b>Project Informatio</b>	n:	Description:	Project No.	C-20			
Name:	CUSTER RD (3) 2,655 N OF BLOOMDALE RD TO	This project consists lane asphalt facility to					
Limits:	375' N OF WILMETH RD	arterial. The City contributed approximately					
Impact Fee Class:	P6D	\$1,080,000 of eligible funds from '12-'19. Based on					
Thoroughfare Class:	Principal Arterial	the existing City Limits, the western half of the					
Length (If):	6,275	roadway is not included in the Impact Fee RIP.					
Service Area(s):	C, Half	roddwdy io not moldd	iou iii tiio iiiipuot	1 00 Km 1			

Roadway Construction Cost Projection								
No.	Item Description	ection	Quantity	Unit	Un	it Price		Item Cost
113	Unclassified Street Excavation		34,861	СУ	\$	15.00	\$	522,917
213	Lime Treated Subgrade (8") (PI<12)		54,383	sy	\$	7.00	\$	380,683
313	4" TY D HMAC Underlayment		51,594	sy	\$	5.00	\$	257,972
413	9" Concrete Pavement		51,594	sy	\$	60.00	\$	3,095,667
513	4" Topsoil		28,586	sy	\$	4.00	\$	114,344
613	6" Curb & Gutter		25,100	lf	\$	5.00	\$	125,500
713	Allotment for Turn Lanes and Median	Openings	3,829	sy	\$	87.00	\$	333,161
		F	Paving Const	ruction (	Cost	Subtotal:	\$	4,830,245
			•					
Maj	or Construction Component Allowan	ces**:						
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	144,907
	Pavement Markings/Markers					3%	\$	144,907
	Roadway Drainage					25%	\$	1,207,561
	Special Drainage Structures	Bridge					\$	1,500,000
	Water	Incidental Adjustme	nts			3%	\$	144,907
	Sewer	Incidental Adjustme	nts			3%	\$	144,907
	Establish Turf / Erosion Control					2%	\$	96,605
	Illumination	Standard Ilumination	n System			6%	\$	289,815
	Other:							
**Allc	wances based on % of Paving Construction Cos	st Subtotal		Allowa	ance S	Subtotal:	\$	3,673,610
			Paving an	d Allowa	ance S	Subtotal:	\$	8,503,855
	Mobilization: 5%					\$	425,193	
			Site Prep	aration:		5%	\$	425,193
			Construc			TOTAL:	\$	9,355,000
			ruction Conti			15%	\$	1,403,250
	C	Construction Cost TOTAL W/ CONTINGENCY:						10,759,000

Impact Fee Project Cost Summ	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 10,759,000
Engineering/Survey/Testing:		20%	\$ 2,151,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 1,080,000
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 2,151,800
Impact F	ee Project Cost TOTAL (50% City C	ontribution)	\$ 8,071,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. C-21

Name: STONEBRIDGE DR (2) This project consists of the

Limits: UNNAMED 5 TO 1,280' S OF UNNAMED 5 construction of a new four-lane divided

Impact Fee Class: G4D greenway arterial.

Thoroughfare Class: Greenway Arterial

Length (If): 1,280 Service Area(s): C

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
107	Unclassified Street Excavation	12,516	су	\$	10.00	\$ 125,156
207	Lime Treated Subgrade (8") (PI<12)	9,387	sy	\$	7.00	\$ 65,707
307	8" Concrete Pavement	8,818	sy	\$	55.00	\$ 484,978
407	4" Topsoil	6,116	sy	\$	2.50	\$ 15,289
507	6" Curb & Gutter	5,120	lf	\$	5.00	\$ 25,600
607	Allotment for Turn Lanes and Median Openings	752	sy	\$	72.00	\$ 54,109
707	Moisture Conditioning	9,387	sy	\$	8.00	\$ 75,093

Paving Construction Cost Subtotal: \$ 845,931

Majo	or Construction Component Allowa	nnces**:				
	Item Description	Notes	Allowance		Item Cost	
	Traffic Control	None Anticipated	1%	\$	8,459	
	Pavement Markings/Markers		3%	\$	25,378	
	Roadway Drainage	Standard Internal System	25%	\$	211,483	
	Special Drainage Structures	Stream Crossing		\$	250,000	
	Water	None Anticipated	0%	\$	-	
	Sewer	None Anticipated	0%	\$	-	
	Establish Turf / Erosion Control		2%	\$	16,919	
	Illumination	Standard Ilumination System	6%	\$	50,756	
	Other:					
**Allo	wances based on % of Paving Construction C	ost Subtotal Allowa	nce Subtotal:	\$	562,995	
		Paving and Allowa	nce Subtotal:	\$	1,408,926	
		Mobilization:	5%	\$	70,446	
		Site Preparation:	5%	\$	70,446	
	Construction Cost TOTAL:					
		Construction Contingency:	15%	\$	232,500	
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	1,783,000	

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,783,000
Engineering/Survey/Testing:		20%	\$ 356,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 624,050

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. C-22

Name: STONEBRIDGE DR (3)

1,570' S OF LAUD HOWELL PKWY

This project consists of the construction of a new four-life construct

1,570' S OF LAUD HOWELL PKWY construction of a new four-lane
Limits: TO 280' S OF WILMETH RD divided greenway arterial.

Impact Fee Class: G4D

Thoroughfare Class: Greenway Arterial

Length (If): 7,995 Service Area(s): C

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
107	Unclassified Street Excavation	78,173	су	\$	10.00	\$ 781,733
207	Lime Treated Subgrade (8") (PI<12)	58,630	sy	\$	7.00	\$ 410,410
307	8" Concrete Pavement	55,077	sy	\$	55.00	\$ 3,029,217
407	4" Topsoil	38,198	sy	\$	2.50	\$ 95,496
507	6" Curb & Gutter	31,980	lf	\$	5.00	\$ 159,900
607	Allotment for Turn Lanes and Median Openings	4,694	sy	\$	72.00	\$ 337,970
707	Moisture Conditioning	58,630	sy	\$	8.00	\$ 469,040

Paving Construction Cost Subtotal: \$ 5,283,766

Majo	or Construction Component Allowance	es**:		
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	None Anticipated	1%	\$ 52,838
	Pavement Markings/Markers		3%	\$ 158,513
	Roadway Drainage	Standard Internal System	25%	\$ 1,320,942
	Special Drainage Structures	None Anticipated		\$ -
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 105,675
	Illumination	Standard Ilumination System	6%	\$ 317,026
	Other:			
**Allo	wances based on % of Paving Construction Cost S	Subtotal Allowa	nce Subtotal:	\$ 1,954,994
		Paving and Allowa	nce Subtotal:	\$ 7,238,760
		Mobilization:	5%	\$ 361,938
		Site Preparation:	5%	\$ 361,938
		Construction C	ost TOTAL:	\$ 7,963,000
		Construction Contingency:	15%	\$ 1,194,450
	Con	struction Cost TOTAL W/ CON	TINGENCY:	\$ 9,158,000
				, -,

Impact Fee Project Cost Summ	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 9,158,000
Engineering/Survey/Testing:		20%	\$ 1,831,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 3,205,300
	Impact Fee Projec	Cost TOTAL:	\$ 14,194,900

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc. updated: 10/6/2020

Conceptual Level Project Cost Projection

Description: Project No. C-23

Name: STONEBRIDGE DR (4)

280' S OF WILMETH RD TO 1,195' S

Limits: OF WILMETH RD

Impact Fee Class: G4D

Project Information:

Thoroughfare Class: Greenway Arterial

Length (If): 915 Service Area(s): C, Half This project consists of the construction of a new four-lane divided greenway arterial. Based on the existing City Limits, the eastern half of the roadway is not included in the Impact Fee RIP.

No.	adway Construction Cost Pro Item Description		Quantity	Unit	Un	it Price		Item Cost
107	Unclassified Street Excavation		8,947	су	\$	10.00	\$	89,467
207	Lime Treated Subgrade (8") (PI<12)		6,710	sy	\$	7.00	\$	46,970
307	8" Concrete Pavement		6,303	sy	\$	55.00	\$	346,683
107	4" Topsoil		4,372	sy	\$	2.50	\$	10,929
507	6" Curb & Gutter		3,660	lf	\$	5.00	\$	18,300
607	Allotment for Turn Lanes and Median	n Openings	537	sy	\$	72.00	\$	38,680
707	Moisture Conditioning		6,710	sy	\$	8.00	\$	53,680
			Paving Const	ruction (	Cost S	Subtotal:	\$	604,709
Иаj	or Construction Component Allowa	nces**:						
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	None Anticipated				1%	\$	6,047
	Pavement Markings/Markers					3%	\$	18,141
	Roadway Drainage	Standard Internal S	ystem			25%	\$	151,177
	Special Drainage Structures	Stream Crossing					\$	250,000
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	12,094
	Illumination	Standard Iluminatio	n System			6%	\$	36,283
	Other:							
'Allc	wances based on % of Paving Construction Co	ost Subtotal		Allowa	nce S	Subtotal:	\$	473,742
			Paving an	d Allowa	nce S	Subtotal:	\$	1,078,451
			Mobi	lization:		5%	\$	53,923
						5%	\$	53,923
			Site Prep	aration:		5 /0	Ψ	00,020
			Site Prep Construc				\$	1,187,000
		Const		ction C	ost			

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,366,000
Engineering/Survey/Testing:		20%	\$ 273,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 478,100
	Impact Fee Project	ct Cost TOTAL:	\$ 2,117,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information:

Description:

Project No.

C-24

Name:
STONEBRIDGE DR (5)
Limits:
1,195' S OF WILMETH RD TO 5,555' S OF WILMETH RD Construction of a new four-lane divided greenway arterial.

Thoroughfare Class: Greenway Arterial

Length (If): 4,360 Service Area(s): C

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
107	Unclassified Street Excavation	42,631	су	\$	10.00	\$ 426,311
207	Lime Treated Subgrade (8") (PI<12)	31,973	sy	\$	7.00	\$ 223,813
307	8" Concrete Pavement	30,036	sy	\$	55.00	\$ 1,651,956
407	4" Topsoil	20,831	sy	\$	2.50	\$ 52,078
507	6" Curb & Gutter	17,440	lf	\$	5.00	\$ 87,200
607	Allotment for Turn Lanes and Median Openings	2,560	sy	\$	72.00	\$ 184,309
707	Moisture Conditioning	31,973	sy	\$	8.00	\$ 255,787
		Paving Constr	uction (	Cost	Subtotal:	\$ 2,881,454

Mai		+-		-	
waj	or Construction Component Allowan Item Description	Notes	Allowance		Item Cost
	<u> </u>	Notes			
	Traffic Control	None Anticipated	1%	\$	28,815
	Pavement Markings/Markers		3%	\$	86,444
	Roadway Drainage	Standard Internal System	25%	\$	720,363
	Special Drainage Structures	Stream Crossing		\$	250,000
	Water	None Anticipated	0%	\$	-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	57,629
	Illumination	Standard Ilumination System	6%	\$	172,887
	Other:				
**Allo	wances based on % of Paving Construction Cos	st Subtotal Allowa	nce Subtotal:	\$	1,316,138
		Paving and Allowa	nce Subtotal:	\$	4,197,591
		Mobilization:	5%	\$	209,880
		Site Preparation:	5%	\$	209,880
		Construction C	ost TOTAL:	\$	4,618,000
		Construction Contingency:	15%	\$	692,700
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	5,311,000

Impact Fee Project Cost Sumi	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 5,311,000
Engineering/Survey/Testing:		20%	\$ 1,062,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,858,850
	Impact Fee Project	ct Cost TOTAL:	\$ 8,232,050

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information:** C-25 Description: Project No. Name: STONEBRIDGE DR (6) This project consists of the

Limits: 580' N OF US HIGHWAY 380 TO US HIGHWAY 380 construction of a new four-lane

**Impact Fee Class:** 

divided greenway arterial.

Thoroughfare Class: **Greenway Arterial** 

Length (If): 580 Service Area(s): С

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Unit I	Price	Item Cost
107	Unclassified Street Excavation	5,671	су	\$	10.00	\$ 56,711
207	Lime Treated Subgrade (8") (PI<12)	4,253	sy	\$	7.00	\$ 29,773
307	8" Concrete Pavement	3,996	sy	\$	55.00	\$ 219,756
407	4" Topsoil	2,771	sy	\$	2.50	\$ 6,928
507	6" Curb & Gutter	2,320	If	\$	5.00	\$ 11,600
607	Allotment for Turn Lanes and Median Openings	341	sy	\$	72.00	\$ 24,518
707	Moisture Conditioning	4,253	sy	\$	8.00	\$ 34,027

Paving Construction Cost Subtotal: \$ 383,313

Majo	or Construction Component Allowan	ces**:			
	Item Description	Notes	Allowance		Item Cost
	Traffic Control	None Anticipated	1%	\$	3,833
	Pavement Markings/Markers		3%	\$	11,499
	Roadway Drainage	Standard Internal System	25%	\$	95,828
	Special Drainage Structures	None Anticipated		\$	-
	Water	None Anticipated	0%	\$	-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	7,666
	Illumination	Standard Ilumination System	6%	\$	22,999
	Other:				
**Allo	wances based on % of Paving Construction Cos	st Subtotal Allowa	nce Subtotal:	\$	141,826
		Paving and Allowa	nce Subtotal:	\$	525,138
		Mobilization:	5%	\$	26,257
		Site Preparation:	5%	\$	26,257
		Construction C	ost TOTAL:	\$	578,000
		Construction Contingency:		-	86,700
	Co	onstruction Cost TOTAL W/ CON	FINGENCY:	\$	665,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 665,000
Engineering/Survey/Testing:		20%	\$ 133,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 232,750

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

<b>Project Informatio</b>	n:	Description:	Project No.	C-26
Name:	RIDGE RD (1) UNNAMED 5 TO 1,485' S OF	This project consists lane asphalt facility to		
Limits: Impact Fee Class:	UNNAMED 5 M6D	arterial. Based on the	e existing City Lir	nits, the
Thoroughfare Class:	Major Arterial	Impact Fee RIP.	saurray io not mo	
Length (If): Service Area(s):	1,485 C, Half			

	adway Construction Cost Projeticem Description	<b>701.011</b>	Quantity	Unit	Un	it Price	Item Cost
109	Unclassified Street Excavation		16,500	CV	\$	10.00	\$ 165,000
209				sy	\$	7.00	\$ 90,090
309	9" Concrete Pavement		12,870 12,210	sy	\$	60.00	\$ 732,600
409	4" Topsoil		5,775	sy	\$	2.50	\$ 14,438
509	6" Curb & Gutter		5,940	lf	\$	5.00	\$ 29,700
609	Allotment for Turn Lanes and Median	Openings	906	sy	\$	77.00	\$ 69,781
709	Moisture Conditioning		12,870	sy	\$	8.00	\$ 102,960
		F	Paving Const	ruction (	Cost S	Subtotal:	\$ 1,204,569
Мајо	or Construction Component Allowan	ces**:					
	Item Description	Notes			Allo	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 36,137
	Pavement Markings/Markers					3%	\$ 36,137
	Roadway Drainage	Standard Internal Sy	/stem			25%	\$ 301,142
	Special Drainage Structures	None Anticipated					\$ -
	Water	Incidental Adjustme	nts			3%	\$ 36,137
	Sewer	Incidental Adjustme	nts			3%	\$ 36,137
	Establish Turf / Erosion Control					2%	\$ 24,091
	Illumination	Standard Ilumination	n System			6%	\$ 72,274
	Other:						
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	ince S	Subtotal:	\$ 542,056
Paving and Allowance Subtotal:						\$ 1,746,625	
	Mobilization: 5%					\$ 87,331	
	Site Preparation: 5%					\$ 87,331	
			Construc	ction C	ost 7	ΓΟΤΑL:	\$ 1,922,000
			ruction Conti			15%	\$ 288,300
	Construction Cost TOTAL W/ CONTINGENCY:					\$ 2,211,000	

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,211,000
Engineering/Survey/Testing:		20%	\$ 442,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 442,200
	Impact Fee Project	Cost TOTAL:	\$ 3,095,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information: C-27** Description: Project No. Name: RIDGE RD (2)

Limits: LAUD HOWELL PKWY TO BAXTER WELL RD

**Impact Fee Class:** 

Thoroughfare Class: Major Arterial

Length (If): 3,110 Service Area(s): С

This project consists of the construction of a new six-lane M6D divided major arterial.

Roa	ndway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost
109	Unclassified Street Excavation	34,556	су	\$	10.00	\$	345,556
209	Lime Treated Subgrade (8") (PI<12)	26,953	sy	\$	7.00	\$	188,673
309	9" Concrete Pavement	25,571	sy	\$	60.00	\$	1,534,267
409	4" Topsoil	12,094	sy	\$	2.50	\$	30,236
509	6" Curb & Gutter	12,440	lf	\$	5.00	\$	62,200
609	Allotment for Turn Lanes and Median Openings	1,898	sy	\$	77.00	\$	146,141
709	Moisture Conditioning	26,953	sy	\$	8.00	\$	215,627
					Culatatala	Φ.	0 500 700

Paving Construction Cost Subtotal: \$ 2,522,700

Maj	or Construction Component Allowan	ices**:		
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	None Anticipated	1%	\$ 25,227
	Pavement Markings/Markers		3%	\$ 75,681
	Roadway Drainage	Standard Internal System	25%	\$ 630,675
	Special Drainage Structures	Stream Crossing		\$ 250,000
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 50,454
	Illumination	Standard Ilumination System	6%	\$ 151,362
	Other:			
**Allo	owances based on % of Paving Construction Cos	st Subtotal Allowa	nce Subtotal:	\$ 1,183,399
		Paving and Allowa	nce Subtotal:	\$ 3,706,098
		Mobilization:	5%	\$ 185,305
		Site Preparation:	5%	\$ 185,305
		Construction C	ost TOTAL:	\$ 4,077,000
		Construction Contingency:	15%	\$ 611,550
	Co	onstruction Cost TOTAL W/ CON	FINGENCY:	\$ 4,689,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,689,000
Engineering/Survey/Testing:		20%	\$ 937,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,641,150

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Information</b>	n:	Description:	Project No.	C-28
Name:	RIDGE RD (3) BAXTER WELL RD TO 2,160' S OF	This project consists of lane asphalt facility to		
Limits: Impact Fee Class: Thoroughfare Class: Length (If):	BLOOMDALE RD M6D Major Arterial 4,390	arterial. Based on the eastern half of the roa Impact Fee RIP for the the western half of the	existing City Lindway is not incless 3,540' northern	nits, the uded in the section while
Service Area(s):	C, Half	the remaining 850' sou	uthern section.	

<b>.</b>	Service Area(s).							
Roa	dway Construction Cost Proje	ction						
	Item Description		Quantity	Unit	Un	it Price		Item Cost
109	Unclassified Street Excavation		48,778	су	\$	10.00	\$	487,778
209	Lime Treated Subgrade (8") (PI<12)		38,047	sy	\$	7.00	\$	266,327
309	9" Concrete Pavement		36,096	sy	\$	60.00	\$	2,165,733
409	4" Topsoil		17,072	sy	\$	2.50	\$	42,681
509	6" Curb & Gutter		17,560	lf	\$	5.00	\$	87,800
	Allotment for Turn Lanes and Median	Openings	2,679	sy	\$	77.00	69	206,289
709	Moisture Conditioning		38,047	sy	\$	8.00	\$	304,373
			Paving Const	ruction (	Cost	Subtotal:	\$	3,560,981
Maja	··· Compatible Comment Allows	**-						
Majo	or Construction Component Allowand Item Description	Notes			ΙΔΙΙ	owance		Item Cost
V	Traffic Control	Construction Phase	Traffic Control		7111	3%	\$	106,829
V	Pavement Markings/Markers	Construction i hase	Traine Control			3%	*	106,829
V	Roadway Drainage	Standard Internal S	vstem			25%	-	890,245
,	Special Drainage Structures	None Anticipated	yotom			2070	\$	
	Water	Incidental Adjustme	nts			3%		106,829
Ì	Sewer	Incidental Adjustme				3%		106,829
Ì	Establish Turf / Erosion Control	niolaentai / tajaetine				2%	\$	71,220
Ì	Illumination	Standard Ilumination	n System			6%	-	213,659
	Other:						•	_::,:::
*Allov	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce s	Subtotal:	\$	1,602,441
	·							
			Paving an	d Allowa	nce S	Subtotal:	\$	5,163,422
	Mobilization: 5%				\$	258,171		
			Site Prep			5%		258,171
			Constru				\$	5,680,000
			truction Conti			15%	_	852,000
	Construction Cost TOTAL W/ CONTINGENCY:					\$	6,532,000	

Impact Fee Project Cost Sumn	nary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	6,532,000
Engineering/Survey/Testing:		20%	\$	1,306,400
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	Existing Alignment	20%	\$	1,306,400
	Impact Fee P	Project Cost TOTAL:	<b>\$</b>	9,144,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

<b>Project Information</b>	n:	Description:	Project No.	C-29
Name:	RIDGE RD (4) 1,590' N OF WILMETH RD TO		s project consists of the onstruction of a two-la	
Limits: Impact Fee Class:	WILMETH RD M6D	faci	lity to a six-lane divide	d major
Thoroughfare Class: Length (If):	Major Arterial 1,590	Lim	its, the western half of ot included in the Impa	the roadway
Service Area(s):	C, Half	15 11	ot included in the impa	act ree KIP.

_		4.						
Roa No.	adway Construction Cost Project   Item Description	ction	Quantity	Unit	Un	it Price		Item Cost
109	Unclassified Street Excavation		17,667	су	\$	10.00	\$	176,667
209	Lime Treated Subgrade (8") (PI<12)		13,780	sy	\$	7.00	\$	96,460
	9" Concrete Pavement		13,073	sy	\$	60.00	\$	784,400
409	4" Topsoil		6,183	sy	\$	2.50	\$	15,458
509	6" Curb & Gutter		6,360	lf	\$	5.00	\$	31,800
609	Allotment for Turn Lanes and Median O	penings	970	sy	\$	77.00	\$	74,715
	Moisture Conditioning		13,780	sy	\$	8.00	\$	110,240
		P	aving Const	ruction (	Cost	Subtotal:	\$	1,289,740
			J					
Majo	or Construction Component Allowance	es**:						
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	38,692
	Pavement Markings/Markers					3%	\$	38,692
	Roadway Drainage	Standard Internal Sy	rstem			25%	\$	322,435
	Special Drainage Structures	Stream Crossing					\$	250,000
	Water	Incidental Adjustmer	nts			3%	\$	38,692
	Sewer	Incidental Adjustmer	nts			3%	\$	38,692
	Establish Turf / Erosion Control					2%	\$	25,795
	Illumination	Standard Ilumination	System			6%	\$	77,384
	Other:							
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	nce	Subtotal:	\$	830,383
			Paving an					2,120,123
				lization:		5%	\$	106,006
			Site Prep			5%	\$	106,006
			Construc					2,333,000
			uction Conti			15%	-	349,950
	Construction Cost TOTAL W/ CONTINGENCY:					\$	2,683,000	

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,683,000
Engineering/Survey/Testing:		20%	\$ 536,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 536,600
	Impact Fee Project (	Cost TOTAL:	\$ 3,756,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

<b>Project Informatio</b>	n:	Description:	Project No.	C-30
Name: Limits: Impact Fee Class: Thoroughfare Class: Length (If):	RIDGE RD (5) WILMETH RD TO 2,280' S OF WILMETH RD M6D(1/3) Major Arterial 2,280	This project is part 380 to Wilmeth Rd the Ridge Rd & Wil provided an overall \$17,700,000. This peligible funds for for project consists of through lanes of the	which includes a remeth Rd intersection I project cost estimate of the ultimate of the construction of	oundabout at on. The City late of or \$6,372,000 of six lanes. This f two additional
Service Area(s):	С	arterial.	e ullimate six-lane	uivided major

	dway Construction Cost Proj		Quantity	Unit	Ur	it Price		Item Cost
111	Unclassified Street Excavation		7,093	су	\$	10.00	\$	70,933
211	Lime Treated Subgrade (8") (PI<12)		6,840	sy	\$	7.00	\$	47,880
311	9" Concrete Pavement		6,333	sy	\$	60.00	\$	380,000
411	4" Topsoil		2,027	sy	\$	2.50	\$	5,067
511	6" Curb & Gutter		4,560	lf	\$	5.00	\$	22,800
611	Allotment for Turn Lanes and Median	Openings	1,391	sy	\$	77.00	\$	107,139
		ı	Paving Const	ruction (	Cost	Subtotal:	\$	633,819
Maio	or Construction Component Allowan	rces**:	_	_	-	_		
maje	Item Description	Notes			All	owance	П	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	19,015
	Pavement Markings/Markers					3%		19,015
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	12,676
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	ance	Subtotal:	\$	50,706
			Paving an				\$	684,524
				lization:		5%	\$	34,226
			Site Prep			5%	-	34,226
			Construc					753,000
			ruction Conti			15%	,	112,950
l	C	onstruction Cos	st TOTAL W	// CON	TINC	SENCY:	\$	866,000

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 866,000
Engineering/Survey/Testing:		20%	\$ 173,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 6,372,000
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 7,411,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

<b>Project Informatio</b>	n:	Description:	Project No.	C-31
Name: Limits: Impact Fee Class: Thoroughfare Class: Length (If): Service Area(s):	RIDGE RD (6) 1,860' N OF US HIGHWAY 380 TO 1,390' N OF US HIGHWAY 380 M6D(1/3) Major Arterial 470 C, Half	This project is part of 380 to Wilmeth Rd with the Ridge Rd & Wilm provided an overall project consists of the arterial.	hich includes a ro eth Rd intersection project cost estimates of the ultimates of construction o	oundabout at on. The City ate of or \$1,239,000 of six lanes. This f two additional
` '		arteriar.		

Roa	adway Construction Cost Proj	ection						
	Item Description	ootion	Quantity	Unit	Uni	it Price		Item Cost
111	Unclassified Street Excavation		1,462	су	\$	10.00	\$	14,622
211	Lime Treated Subgrade (8") (PI<12)		1,410	sy	\$	7.00	\$	9,870
311	9" Concrete Pavement		1,306	sy	\$	60.00	\$	78,333
411	4" Topsoil		418	sy	\$	2.50	\$	1,044
511	6" Curb & Gutter		940	lf	\$	5.00	\$	4,700
611	Allotment for Turn Lanes and Median	Openings	287	sy	\$	77.00	\$	22,086
		F	Paving Const	ruction (	Cost S	Subtotal:	\$	130,656
Majo	or Construction Component Allowan							
	Item Description	Notes			Allo	owance		Item Cost
$\sqrt{}$	Traffic Control	Construction Phase	Traffic Control			3%		3,920
	Pavement Markings/Markers					3%		3,920
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	2,613
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	ance S	Subtotal:	\$	10,452
			Paving an				\$	141,108
				lization:		5%	\$	7,055
			Site Prep			5%	_	7,055
			Construc			OTAL:		156,000
			ruction Conti			15%	-	23,400
	C	onstruction Cos	st TOTAL W	// CON	TING	ENCY:	\$	180,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 180,000
Engineering/Survey/Testing:		20%	\$ 36,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 1,239,000
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 1,455,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No.	C-32
Name: Limits: Impact Fee Class: Thoroughfare Class: Length (If):	RIDGE RD (7) 775' N OF US HIGHWAY 380 TO US HIGHWAY 380 M6D(1/3) Major Arterial 775	This project is part of the to Wilmeth Rd which incl Ridge Rd & Wilmeth Rd i an overall project cost es project accounted for \$2, four of the ultimate six la the construction of two a ultimate six-lane divided	ludes a roundab ntersection. The stimate of \$17,70 ,124,000 of eligib ines. This project additional throug	out at the e City provided 00,000. This ole funds for et consists of
Service Area(s):	C		ajo: artorian	

Roa	adway Construction Cost Pro	iection						
	Item Description	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Quantity	Unit	Uni	t Price		Item Cost
111	Unclassified Street Excavation		2,411	су	\$	10.00	\$	24,111
211	Lime Treated Subgrade (8") (PI<12)		2,325	sy	\$	7.00	\$	16,275
311	9" Concrete Pavement		2,153	sy	\$	60.00	\$	129,167
411	4" Topsoil		689	sy	\$	2.50	\$	1,722
511	6" Curb & Gutter		1,550	lf	\$	5.00	\$	7,750
611	Allotment for Turn Lanes and Mediar	n Openings	473	sy	\$	77.00	\$	36,418
		<u>-</u>	Paving Const	ruction (	Cost S	Subtotal:	\$	215,443
Maio	or Construction Component Allowa	nces**:						
	Item Description	Notes			Allo	wance	П	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	6,463
	Pavement Markings/Markers					3%	\$	6,463
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	Future Bridge Wider	ning				\$	250,000
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	4,309
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Co	ost Subtotal		Allowa	nce S	ubtotal:	\$	267,235
			Danie e e e	-I A II		l. 4 a 4 a l .		400.070
			Paving an	d Allowa lization:			\$	482,678
						5%	\$	24,134
			Site Prep			5%		24,134
		•	Construc				\$	531,000
			struction Conti			15%	\$	79,650
		Construction C	OST IOTAL W	// CON	IING	ENCY:	\$	611,000

Impact Fee Project Cost Summ	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 611,000
Engineering/Survey/Testing:		20%	\$ 122,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 2,124,000
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 2,857,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Informatio</b>	n:	Description:	Project No.	C-33
Name:	LAKE FOREST DR (2)	This project consists o	f the constructi	on of two
Limits:	BLOOMDALE RD TO WILMETH RD	additional through lane	s within the ex	isting median
Impact Fee Class:	M6D(1/3)	of the ultimate six-lane	divided major	arterial. The
Thoroughfare Class:	Major Arterial	City contributed approx	cimately \$2,541	,781 of eligible
Length (If):	5,410	funds from '12-'19. Bas		_
		Limits, the eastern half	of the roadway	/ is not
Service Area(s):	C, Half	included in the Impact	Fee RIP.	

Roa	adway Construction Cost Proje	ection						
No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
111	Unclassified Street Excavation		16,831	су	\$	10.00	\$	168,311
211	Lime Treated Subgrade (8") (PI<12)		16,230	sy	\$	7.00	\$	113,610
311	9" Concrete Pavement		15,028	sy	\$	60.00	\$	901,667
411	4" Topsoil		4,809	sy	\$	2.50	\$	12,022
511	6" Curb & Gutter		10,820	lf	\$	5.00	\$	54,100
611	Allotment for Turn Lanes and Median	Openings	3,302	sy	\$	77.00	\$	254,220
		Р	aving Consti	ruction (	Cost S	Subtotal:	\$	1,503,930
		4.4						
Majo	or Construction Component Allowan							
	Item Description	Notes			Allo	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	-	45,118
	Pavement Markings/Markers					3%		45,118
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
$\checkmark$	Establish Turf / Erosion Control					2%	\$	30,079
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Cos	st Subtotal		Allowa	nce S	Subtotal:	\$	120,314
			Paving and		nce S			1,624,244
				lization:		5%	-	81,212
			Site Prep			5%		81,212
			Construc				\$	1,787,000
			uction Conti			15%		268,050
	Co	nstruction Cos	t TOTAL W	// CON	TING	ENCY:	\$	2,056,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,056,000
Engineering/Survey/Testing:		20%	\$ 411,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 2,541,781
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### updated:

10/6/2020

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information:

Name:

LAKE FOREST DR (3)

Limits:

WILMETH RD TO US HIGHWAY 380

Impact Fee Class:

MoD(1/3)

Description:

Project No. C-34, D-22

This project consists of the construction of two additional through lanes within the existing median of the ultimate six-lane divided major arterial.

Thoroughfare Class: Major Arterial

Length (If): 5,155
Service Area(s): C and D

Roa	adway Construction Cost Pro	jection							
No.	Item Description	Quantity	Unit	Uni	t Price	Item Cost			
111	Unclassified Street Excavation	16,038	су	\$	10.00	\$	160,378		
211	Lime Treated Subgrade (8") (PI<12)	15,465	sy	\$	7.00	\$	108,255		
311	9" Concrete Pavement	14,319	sy	\$	60.00	\$	859,167		
411	4" Topsoil	4,582	sy	\$	2.50	\$	11,456		
511	6" Curb & Gutter	10,310	lf	\$	5.00	\$	51,550		
611	Allotment for Turn Lanes and Median	3,146	sy	\$	77.00	\$	242,237		
	Paving Construction Co				Cost S	t Subtotal: \$ 1,433,04			
Maj	Major Construction Component Allowances**:								
	Item Description	Notes			Allo	Allowance		Item Cost	
	Traffic Control	Construction Phase	Construction Phase Traffic Control			3%	\$		
	Dayamant Markings/Markers							42,991	
	Pavement Markings/Markers					3%		42,991 42,991	
	Roadway Drainage	None Anticipated				3% 0%	\$	,	
	· ·	None Anticipated None Anticipated					\$	,	
	Roadway Drainage	· ·					\$ \$ \$	,	
	Roadway Drainage Special Drainage Structures	None Anticipated				0%	\$ \$ \$ \$	,	
V	Roadway Drainage Special Drainage Structures Water	None Anticipated None Anticipated				0% 0%	\$ \$ \$ \$	,	


**Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal	Allowance Subtotal:		
Paving and Allowa	Paving and Allowance Subtotal:		1,547,686
Mobilization:	5%	\$	77,384
Site Preparation:	5%	\$	77,384
Construction C	ost TOTAL:	\$	1,703,000
Construction Contingency:	15%	\$	255,450
Construction Cost TOTAL W/ CON	FINGENCY:	\$	1,959,000

Impact Fee Project Cost Summary						
Item Description	Notes:	Allowance		Item Cost		
Construction:		-	\$	1,959,000		
Engineering/Survey/Testing:		20%	\$	391,800		
2008 - 2012 City contribution			\$	-		
2012 - 2019 City contribution			\$	-		
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-		
Impact Fee Project Cost TOTAL:				2,350,800		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

Other:



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

Roadway Improvements - Service Area D

	adway Improvements - Service   Costing					Percent in	Cost in		
#	Class	Project	Limits		otal Cost	Service Area	Service Area		
A-2, D-1	M6D	UNNAMED 5 (3)	CR 168 TO 1,560' E OF CR 168	\$	7,517,500	50%	\$	3,758,750	
B-1, D-2	M6D	UNNAMED 5 (4)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD	\$	4,904,200	50%	\$	2,452,100	
D-3	G6D	LAUD HOWELL PKWY (6)	LAKE FOREST DR TO 1860' E OF HARDIN BLVD	\$	39,497,100	100%	\$	39,497,100	
D-4	G6D	LAUD HOWELL PKWY (7)	4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY FALLS PKWY	\$	8,774,550	100%	\$	8,774,550	
D-5	G6D(1/3)	LAUD HOWELL PKWY (8)	240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75	\$	2,220,027	100%	\$	2,220,027	
D-6	G4D	TRINITY FALLS PKWY (1)	HARDIN BLVD TO 1,910' E OF HARDIN BLVD	\$	3,243,800	100%	\$	3,243,800	
D-7	G4D	TRINITY FALLS PKWY (2)	1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD	\$	1,300,600	50%	\$	650,300	
D-8	G4D	TRINITY FALLS PKWY (3)	COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY	\$	5,976,800	50%	\$	2,988,400	
D-9	G4D	TRINITY FALLS PKWY (4)	LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY	\$	8,418,050	100%	\$	8,418,050	
D-10	M6D(1/3)	TRINITY FALLS PKWY (5)	4,275' N OF WESTON RD TO LAUD HOWELL PKWY	\$	7,622,400	100%	\$	7,622,400	
D-11	P6D	BLOOMDALE RD (7)	1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	\$	3,799,600	50%	\$	1,899,800	
D-12	P6D	BLOOMDALE RD (8)	1,485' E OF CR 1006 TO 1,215' W OF CR 1007	\$	3,206,000	100%	\$	3,206,000	
D-13	P6D	BLOOMDALE RD (9)	1,225' W OF CR 1007 TO CR 1007	\$	3,001,600	50%	\$	1,500,800	
D-14	P6D(2/3)	BLOOMDALE RD (10)	CR 1007 TO HARDIN BLVD	\$	5,885,810	100%	\$	5,885,810	
D-15	P6D(1/3)	BLOOMDALE RD (11)	HARDIN BLVD TO COMMUNITY AVE	\$	5,165,390	100%	\$	5,165,390	
D-16	G4D	WILMETH RD (5)	LAKE FOREST DR TO UNNAMED A	\$	10,991,050	50%	\$	5,495,525	
D-17	G4D	WILMETH RD (6)	UNNAMED A TO 825' E OF UNNAMED A	\$	1,401,400	100%	\$	1,401,400	
D-18	G4D(1/2)	WILMETH RD (7)	825' E OF TAYLOR-BURK DR TO 1,380' E OF TAYLOR-BURK DR	\$	411,600	100%	\$	411,600	
D-19	G4D	WILMETH RD (8)	1,380' E OF TAYLOR-BURK DR TO HARDIN BLVD	\$	3,803,800	50%	\$	1,901,900	
D-20	M6D(1/3)	WILMETH RD (9)	HARDIN BLVD TO US HIGHWAY 75	\$	2,799,600	100%	\$	2,799,600	
D-21	G6D	LAKE FOREST DR (1)	LAUD HOWELL PKWY TO 3,200' S OF LAUD HOWELL PKWY	\$	6,448,400	50%	\$	3,224,200	
C-34, D-22	M6D(1/3)	LAKE FOREST DR (3)	WILMETH RD TO US HIGHWAY 380	\$	2,350,800	50%	\$	1,175,400	
D-23	G4D	UNNAMED A (1)	5,785' N OF LAUD HOWELL PKWY TO 2,710' S OF LAUD HOWELL PKWY	\$	17,435,950	100%	\$	17,435,950	
D-24	G4D	UNNAMED A (2)	2,710' S OF LAUD HOWELL PKWY TO BLOOMDALE RD	\$	4,598,850	50%	\$	2,299,425	
D-25	G4D	UNNAMED A (3)	1,105' N OF WILMETH RD TO WILMETH RD	\$	1,876,000	50%	\$	938,000	
D-26	M4D	UNNAMED A (4)	WILMETH RD TO HARDIN BLVD	\$	5,969,050	100%	\$	5,969,050	
D-27	M4D	TAYLOR-BURK DR (1)	HARDIN BLVD TO SKYLINE DR	\$	2,038,250	100%	\$	2,038,250	
D-28	G6D	HARDIN BLVD (4)	UNNAMED 5 TO 1,550' S OF UNNAMED 5	\$	3,267,400	50%	\$	1,633,700	
D-29	G6D	HARDIN BLVD (5)	1,545' S OF UNNAMED 5 TO TRINITY FALLS PKWY	\$	21,290,800	100%	\$	21,290,800	
D-30	G6D	HARDIN BLVD (6)	TRINITY FALLS PKWY TO 1,815' S OF TRINITY FALLS PKWY	\$	4,102,000	50%	\$	2,051,000	
D-31	G6D	HARDIN BLVD (7)	1,815' S OF TRINITY FALLS PKWY TO 1,190' S OF BLOOMDALE RD	\$	4,538,400	100%	\$	4,538,400	
D-32	G6D(1/3)	HARDIN BLVD (8)	1,190' S OF BLOOMDALE RD TO 3,590' S OF BLOOMDALE RD	\$	1,070,400	100%	\$	1,070,400	
D-33	G6D(2/3)	HARDIN BLVD (9)	3,590' S OF BLOOMDALE RD TO WILMETH RD	\$	2,249,800	50%	\$	1,124,900	
D-34	G6D(1/3)	HARDIN BLVD (10)	WILMETH RD TO US HIGHWAY 380	\$	2,904,000	100%	\$	2,904,000	
D-35	G4D	COMMUNITY AVE (1)	TRINITY FALLS PKWY TO 1,275' S OF TRINITY FALLS PKWY	\$	2,164,400	100%	\$	2,164,400	
D-36	G4D(1/2)	COMMUNITY AVE (2)	1,275' S OF TRINITY FALLS PKWY TO BLOOMDALE RD	\$	1,960,000	100%	\$	1,960,000	
D-37	M4U(1/2)	COMMUNITY AVE (3)	BLOOMDALE RD TO 2,305' S OF BLOOMDALE RD	\$	1,174,600	100%	\$	1,174,600	
3		Signal	HARDIN BLVD & UNNAMED 5	\$	300,000	50%	\$	150,000	
6		Signal	LAUD HOWELL PKWY & LAKE FOREST DR	\$	300,000	50%	\$	150,000	
7		Signal	LAUD HOWELL PKWY & UNNAMED A	\$	300,000	100%	\$	300,000	
8		Signal	LAUD HOWELL PKWY & HARDIN BLVD	\$	300,000	100%	\$	300,000	
9		Signal	HARDIN BLVD & TRINITY FALLS PKWY	\$	300,000	75%	\$	225,000	
10		Roundabout	TRINITY FALLS PKWY & COMMUNITY AVE	\$	200,000	50%	\$	100,000	
11	uo	Interchange Signals	US HIGHWAY 75 & LAUD HOWELL PKWY	\$	600,000	50%	\$	300,000	
16	Intersection	Signal	BLOOMDALE RD & UNNAMED A	\$	300,000	25%	\$	75,000	
17	ers	Signal	BLOOMDALE RD & HARDIN BLVD	\$	300,000	100%	\$	300,000	
18	n T	Signal	BLOOMDALE RD & COMMUNITY AVE	\$	300,000	100%	\$	300,000	
19		Interchange Signals	US HIGHWAY 75 & BLOOMDALE RD	\$	600,000	50%	\$	300,000	
25		Roundabout	LAKE FOREST DR & WILMETH RD	\$	1,830,000	50%	\$	915,000	
26		Roundabout	WILMETH RD & UNNAMED A	\$	200,000	75%	\$	150,000	
27		Roundabout	HARDIN BLVD & WILMETH RD	\$	2,100,000	75%	\$	1,575,000	
32	<u> </u>	Roundabout	HARDIN BLVD & TAYLOR-BURK DR	\$	1,200,000	100%	\$	1,200,000	
36		Under Construction	US HIGHWAY 380 & HARDIN BLVD	\$	780,682	50%	\$	390,341	
30		Glider Collstruction	US TIIGHWAT 300 & HANDIN BLVD	\$	225,290,659	30 /0	\$	189,016,118	

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. A-2, D-1

Name: UNNAMED 5 (3) This project consists of the

Limits: CR 168 TO 1,560' E OF CR 168 construction of a new six-lane divided

Impact Fee Class: M6D major arterial.

Thoroughfare Class: Major Arterial Length (If): 1,560
Service Area(s): A and D

Roa	dway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost
109	Unclassified Street Excavation	17,333	су	\$	10.00	\$	173,333
209	Lime Treated Subgrade (8") (PI<12)	13,520	sy	\$	7.00	\$	94,640
309	9" Concrete Pavement	12,827	sy	\$	60.00	\$	769,600
409	4" Topsoil	6,067	sy	\$	2.50	\$	15,167
509	6" Curb & Gutter	6,240	lf	\$	5.00	\$	31,200
609	Allotment for Turn Lanes and Median Openings	952	sy	\$	77.00	\$	73,306
709	Moisture Conditioning	13,520	sy	\$	8.00	\$	108,160
	Paving Construction Cost Subtotal:						1,265,406

Maj	or Construction Component Allowan	ces**:							
	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	None Anticipated	1%	\$	12,654				
	Pavement Markings/Markers		3%	\$	37,962				
	Roadway Drainage	Standard Internal System	25%	\$	316,351				
	Special Drainage Structures	Bridge		\$	2,100,000				
	Water	None Anticipated	0%	\$	-				
	Sewer	None Anticipated	0%	\$	-				
	Establish Turf / Erosion Control		2%	\$	25,308				
	Illumination	Standard Ilumination System	6%	\$	75,924				
	Other:								
**Allo	owances based on % of Paving Construction Cos	st Subtotal Allowa	nce Subtotal:	\$	2,568,200				
		Paving and Allowa	nce Subtotal:	\$	3,833,606				
		Mobilization:	5%	\$	191,680				
		Site Preparation:	5%	\$	191,680				
	Construction Cost TOTAL:								
		Construction Contingency:	15%	\$	632,550				
	Co	onstruction Cost TOTAL W/ CON	FINGENCY:	\$	4,850,000				

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,850,000
Engineering/Survey/Testing:		20%	\$ 970,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,697,500

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

Project Information: Description: Project No. B-1, D-2

Name: UNNAMED 5 (4)

UNNAMED 5 (4) This project consists of the construction 1,050' W OF HARDIN BLVD TO of a new six-lane divided major arterial.

Limits: 1,200' E OF HARDIN BLVD

Impact Fee Class: M6D
Thoroughfare Class: Major Arterial
Length (If): 2,250
Service Area(s): B and D

Roa	adway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost
109	Unclassified Street Excavation	25,000	су	\$	10.00	\$	250,000
209	Lime Treated Subgrade (8") (PI<12)	19,500	sy	\$	7.00	\$	136,500
309	9" Concrete Pavement	18,500	sy	\$	60.00	\$	1,110,000
409	4" Topsoil	8,750	sy	\$	2.50	\$	21,875
509	6" Curb & Gutter	9,000	lf	\$	5.00	\$	45,000
609	Allotment for Turn Lanes and Median Openings	1,373	sy	\$	77.00	\$	105,729
709	Moisture Conditioning	19,500	sy	\$	8.00	\$	156,000
		oving Conet	ruction (	`oct	Subtotale	¢	1 925 104

Paving Construction Cost Subtotal: \$ 1,825,104

Majo	or Construction Component Allow	ances**:				
	Item Description	Notes	Allowance		Item Cost	
	Traffic Control	None Anticipated	1%	\$	18,251	
	Pavement Markings/Markers		3%	\$	54,753	
	Roadway Drainage	Standard Internal System	25%	\$	456,276	
	Special Drainage Structures	None Anticipated		\$	-	
	Water	None Anticipated	0%	\$	-	
	Sewer	None Anticipated	0%	\$	-	
	Establish Turf / Erosion Control		2%	\$	36,502	
	Illumination	Standard Ilumination System	6%	\$	109,506	
	Other:					
**Allo	owances based on % of Paving Construction	Cost Subtotal Allowa	nce Subtotal:	\$	675,289	
		Paving and Allowa	nce Subtotal:	\$	2,500,393	
		Mobilization:	5%	\$	125,020	
		Site Preparation:	5%	\$	125,020	
	Construction Cost TOTAL:					
		Construction Contingency:	15%	\$	412,650	
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	3,164,000	

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,164,000
Engineering/Survey/Testing:		20%	\$ 632,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,107,400
	Impact Fee Proj	ect Cost TOTAL:	\$ 4,904,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-3

Name: LAUD HOWELL PKWY (6)

Limits: LAKE FOREST DR TO 1860' E OF HARDIN BLVD

This project consists of the construction of a new six-later than the construction

Impact Fee Class: G6D

Thoroughfare Class: Greenway Arterial

Length (If): 13,995 Service Area(s): D construction of a new six-lane divided greenway arterial.

Roa	adway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost
116	Unclassified Street Excavation	171,050	су	\$	10.00	\$	1,710,500
216	Lime Treated Subgrade (8") (PI<12)	111,960	sy	\$	7.00	\$	783,720
316	9" Concrete Pavement	105,740	sy	\$	60.00	\$	6,344,400
416	4" Topsoil	88,635	sy	\$	2.50	\$	221,588
516	6" Curb & Gutter	55,980	lf	\$	5.00	\$	279,900
616	Allotment for Turn Lanes and Median Openings	9,672	sy	\$	77.00	\$	744,715
716	Moisture Conditioning	111,960	sy	\$	8.00	\$	895,680
		Paving Constr	uotion (	`~~ <b>*</b>	Cubtotali	¢	10 000 502

Paving Construction Cost Subtotal: \$ 10,980,503

Mai	or Construction Component Allowan	222**		_		
Iviaj	Item Description	Notes	Allowance		Item Cost	
	Traffic Control	None Anticipated	1%	\$	109,805	
	Pavement Markings/Markers		3%	\$	329,415	
	Roadway Drainage	Standard Internal System	25%	\$	2,745,126	
	Special Drainage Structures	Bridge		\$	5,100,000	
	Water	None Anticipated	0%	\$	-	
	Sewer	None Anticipated	0%	\$	-	
	Establish Turf / Erosion Control		2%	\$	219,610	
	Illumination	Standard Ilumination System	6%	\$	658,830	
	Other:					
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	9,162,786	
		Paving and Allowa	nce Subtotal:	\$	20,143,289	
		Mobilization:	5%	\$	1,007,164	
	Site Preparation: 5%					
		Construction C	ost TOTAL:	\$	22,158,000	
		Construction Contingency:	15%	\$	3,323,700	
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	25,482,000	

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 25,482,000
Engineering/Survey/Testing:		20%	\$ 5,096,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 8,918,700

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-4

Name: LAUD HOWELL PKWY (7) This project consists of the construction

4,170' N OF TRINITY FALLS PKWY

of a new six-lane divided greenway

Limits:

TO 240' N OF TRINITY FALLS

arterial.

Impact Fee Class: G6D

Thoroughfare Class: Greenway Arterial

Length (If): 3,930 Service Area(s): D

Roa	adway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost
116	Unclassified Street Excavation	48,033	су	\$	10.00	\$	480,333
216	Lime Treated Subgrade (8") (PI<12)	31,440	sy	\$	7.00	\$	220,080
316	9" Concrete Pavement	29,693	sy	\$	60.00	\$	1,781,600
416	4" Topsoil	24,890	sy	\$	2.50	\$	62,225
516	6" Curb & Gutter	15,720	lf	\$	5.00	\$	78,600
616	Allotment for Turn Lanes and Median Openings	2,716	sy	\$	77.00	\$	209,127
716	Moisture Conditioning	31,440	sy	\$	8.00	\$	251,520
	-				0 1 4 4 1	_	0.000.105

Paving Construction Cost Subtotal: \$ 3,083,485

Maio	or Construction Component Allowa	nnces**:			
THE ST	Item Description	Notes	Allowance	П	Item Cost
	Traffic Control	None Anticipated	1%	\$	30,835
	Pavement Markings/Markers		3%	\$	92,505
	Roadway Drainage	Standard Internal System	25%	\$	770,871
	Special Drainage Structures	Stream Crossing		\$	250,000
	Water	None Anticipated	0%	\$	-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	61,670
	Illumination	Standard Ilumination System	6%	\$	185,009
	Other:				
**Allo	wances based on % of Paving Construction C	cost Subtotal Allowa	nce Subtotal:	\$	1,390,890
-		Devine and Alleur	maa Cubtatali	•	4 474 075
		Paving and Allowa			4,474,375
		Mobilization:			223,719
		Site Preparation:			223,719 <b>4,922,000</b>
		Construction Contingency:		_	738,300
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	5,661,000

Impact Fee Project Cost Summ	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 5,661,000
Engineering/Survey/Testing:		20%	\$ 1,132,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,981,350
	Impact Fee Projec	t Cost TOTAL:	\$ 8,774,550

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

# 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Information</b>	<b>1</b> : D	escription:	Project No.	D-5
Name:	LAUD HOWELL PKWY (8)		This project consi	sts of the
Limits:	240' N OF TRINITY FALLS PKWY TO U	S HIGHWAY 75	construction of tw	o additional
Impact Fee Class:	G6D(1/3)		through lanes with	nin the
Thoroughfare Class:	Greenway Arterial		existing median of	f the ultimate
Length (If):	2,020		six-lane divided gr	
			arterial. The City of	ontributed
			approximately \$1,	320,027 of
Service Area(s):	D		eligible funds fron	n '12-'19.

Roa	adway Construction Cost Proje	ction						
	Item Description	<u> </u>	Quantity	Unit	Un	it Price		Item Cost
117	Unclassified Street Excavation		5,836	су	\$	10.00	\$	58,356
217	Lime Treated Subgrade (8") (PI<12)		5,611	sy	\$	7.00	\$	39,278
317	9" Concrete Pavement		5,162	sy	\$	60.00	\$	309,733
417	4" Topsoil		5,387	sy	\$	2.50	\$	13,467
517	6" Curb & Gutter		4,040	lf	\$	5.00	\$	20,200
617	Allotment for Turn Lanes and Median	Openings	1,396	sy	\$	77.00	\$	107,490
		F	Paving Const	ruction (	Cost S	Subtotal:	\$	548,524
Majo	or Construction Component Allowand	ces**:						
	Item Description	Notes			Allo	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	16,456
	Pavement Markings/Markers					3%	\$	16,456
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	10,970
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	ance S	Subtotal:	\$	43,882
			Paving an					592,405
				lization:		5%	*	29,620
			Site Prep			5%	_	29,620
			Constru					652,000
			ruction Conti			15%		97,800
	С	onstruction Co	st TOTAL V	W CON	TING	SENCY:	\$	750,000

Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	750,000
Engineering/Survey/Testing:		20%	\$	150,000
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	1,320,027
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-
- <b>1</b>	Impact Fee Project		·	2,220,027

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-6

Name: TRINITY FALLS PKWY (1) This project consists of the

Limits: HARDIN BLVD TO 1,910' E OF HARDIN BLVD reconstruction of a two-la

Impact Fee Class: G4D

Thoroughfare Class: Greenway Arterial

Length (If): 1,910 Service Area(s): D reconstruction of a two-lane asphalt facility to a four-lane divided greenway

arterial.

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	it Price	Item Cost
107	Unclassified Street Excavation	18,676	су	\$	10.00	\$ 186,756
207	Lime Treated Subgrade (8") (PI<12)	14,007	sy	\$	7.00	\$ 98,047
307	8" Concrete Pavement	13,158	sy	\$	55.00	\$ 723,678
407	4" Topsoil	9,126	sy	\$	2.50	\$ 22,814
507	6" Curb & Gutter	7,640	lf	\$	5.00	\$ 38,200
607	Allotment for Turn Lanes and Median Openings	1,121	sy	\$	72.00	\$ 80,741
707	Moisture Conditioning	14,007	sy	\$	8.00	\$ 112,053
	F	Paving Constr	ruction C	ost	Subtotal:	\$ 1,262,288
		-				

Major Construction Component Allowances**:							
	Item Description	Notes	Allowance		Item Cost		
	Traffic Control	Construction Phase Traffic Control	3%	\$	37,869		
	Pavement Markings/Markers		3%	\$	37,869		
	Roadway Drainage	Standard Internal System	25%	\$	315,572		
	Special Drainage Structures	None Anticipated		\$	-		
	Water	Incidental Adjustments	3%	\$	37,869		
	Sewer	Incidental Adjustments	3%	\$	37,869		
	Establish Turf / Erosion Control		2%	\$	25,246		
	Illumination	Standard Ilumination System	6%	\$	75,737		
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$	568,030		
		Paving and Allowa	nce Subtotal:	\$	1,830,318		
		Mobilization:	5%	\$	91,516		
		Site Preparation:	5%	\$	91,516		
	Construction Cost TOTAL:						
		Construction Contingency:	15%	\$	302,100		
	Cor	nstruction Cost TOTAL W/ CON	TINGENCY:	\$	2,317,000		

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,317,000
Engineering/Survey/Testing:		20%	\$ 463,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 463,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	D-7
Name:	TRINITY FALLS PKWY (2) 1,910' E OF HARDIN BLVD TO		project consists of the onstruction of a two-land	
Limits: Impact Fee Class:	2,675' E OF HARDIN BLVD G4D	facil	ity to a four-lane divide rial. Based on the existi	d greenway
Thoroughfare Class: Length (If):	Greenway Arterial 765	Limi	its, the nothern half of to tot included in the Impac	he roadway
Service Area(s):	D, Half			

Roa	adway Construction Cost Project	ction						
No.	Item Description		Quantity	Unit	Ur	it Price		Item Cost
107	Unclassified Street Excavation		7,480	су	\$	10.00	\$	74,800
207	Lime Treated Subgrade (8") (PI<12)		5,610	sy	\$	7.00	\$	39,270
307	8" Concrete Pavement		5,270	sy	\$	55.00	\$	289,850
407	4" Topsoil		3,655	sy	\$	2.50	\$	9,138
507	6" Curb & Gutter		3,060	lf	\$	5.00	\$	15,300
	Allotment for Turn Lanes and Median C	penings	449	sy	\$	72.00	\$	32,339
707	Moisture Conditioning		5,610	sy	\$	8.00	\$	44,880
		F	Paving Consti	ruction (	Cost	Subtotal:	\$	505,576
Majo	or Construction Component Allowance							
	Item Description	Notes			All	owance		Item Cost
<b>√</b>	Traffic Control	Construction Phase	Traffic Control			3%		15,167
	Pavement Markings/Markers					3%		15,167
	Roadway Drainage	Standard Internal Sy	rstem .			25%	\$	126,394
	Special Drainage Structures	None Anticipated					\$	-
	Water	Incidental Adjustmer	nts			3%	\$	15,167
	Sewer	Incidental Adjustmer	nts			3%	\$	15,167
	Establish Turf / Erosion Control					2%	\$	10,112
	Illumination	Standard Ilumination	n System			6%	\$	30,335
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce	Subtotal:	\$	227,509
			Paving and					733,085
	Mobilization: 5%					\$	36,654	
			Site Prep	aration:		5%	\$	36,654
			Construc				\$	807,000
			ruction Conti			15%	_	121,050
	Coi	nstruction Cos	st TOTAL W	// CON	TINC	SENCY:	\$	929,000

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 929,000
Engineering/Survey/Testing:		20%	\$ 185,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 185,800
	Impact Fee Project	Cost TOTAL:	\$ 1,300,600

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Project Information: Description: Project No. D-8

Name: TRINITY FALLS PKWY (3)

COMMUNITY AVE TO 2,200' W OF

Limits: LAUD HOWELL PKWY

Impact Fee Class: G4D

Thoroughfare Class: Greenway Arterial

Length (If): 1,820
Service Area(s): D, Half

This project consists of the construction of a new four-lane divided greenway arterial. Based on the existing City Limits, the nothern half of the roadway is not included in the Impact Fee RIP.

Por	adway Construction Cost Projec	ction					
	Item Description	CHOII	Quantity	Unit	Unit Price		Item Cost
107	Unclassified Street Excavation		17.796	СУ	\$ 10.00	\$	177,956
207	Lime Treated Subgrade (8") (PI<12)		13,347	sy	\$ 7.00	\$	93,427
307	8" Concrete Pavement		12,538	sy	\$ 55.00	\$	689,578
407	4" Topsoil		8,696	sy	\$ 2.50	\$	21,739
507	6" Curb & Gutter		7,280	lf	\$ 5.00	\$	36,400
607	Allotment for Turn Lanes and Median O	penings	1,069	sy	\$ 72.00	\$	76,936
	Moisture Conditioning		13,347	sy	\$ 8.00	\$	106,773
		P	aving Const	ruction (	Cost Subtotal:	\$	1,202,809
			J				, ,
Majo	or Construction Component Allowance	es**:					
	Item Description	Notes			Allowance	П	Item Cost
	Traffic Control	None Anticipated			1%	\$	12,028
$\sqrt{}$	Pavement Markings/Markers				3%	\$	36,084
$\sqrt{}$	Roadway Drainage	Standard Internal Sy	stem		25%	\$	300,702
	Special Drainage Structures	Bridge				\$	1,400,000
	Water	None Anticipated			0%	\$	-
	Sewer	None Anticipated			0%	\$	-
	Establish Turf / Erosion Control				2%	\$	24,056
	Illumination	Standard Ilumination	System		6%	\$	72,169
	Other:						
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	nce Subtotal:	\$	1,845,039
			Paving an	d Allowa	nce Subtotal:	\$	3,047,848
	Mobilization: 5%					\$	152,392
			Site Prep	aration:	5%	\$	152,392
	Construction Cost TOTAL:					\$	3,353,000
			uction Conti			-	502,950
	Cor	nstruction Cos	t TOTAL W	// CON	TINGENCY:	\$	3,856,000

Impact Fee Project Cost Summ	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,856,000
Engineering/Survey/Testing:		20%	\$ 771,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,349,600
	Impact Fee Project	t Cost TOTAL:	\$ 5,976,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-9

Name: TRINITY FALLS PKWY (4) This project consists of the construction of a new four-lane divided greenway

Limits: OF LAUD HOWELL PKWY arterial.

or LADD HOWELL PRIVIT

Impact Fee Class: G4D
Thoroughfare Class: Greenway Arterial

Length (If): 2,200 Service Area(s): D

Roa	adway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost
107	Unclassified Street Excavation	21,511	су	\$	10.00	\$	215,111
207	Lime Treated Subgrade (8") (PI<12)	16,133	sy	\$	7.00	\$	112,933
307	8" Concrete Pavement	15,156	sy	\$	55.00	\$	833,556
407	4" Topsoil	10,511	sy	\$	2.50	\$	26,278
507	6" Curb & Gutter	8,800	lf	\$	5.00	\$	44,000
607	Allotment for Turn Lanes and Median Openings	1,292	sy	\$	72.00	\$	93,000
707	Moisture Conditioning	16,133	sy	\$	8.00	\$	129,067
	_					_	

Paving Construction Cost Subtotal: \$ 1,453,944

Mai	Major Construction Component Allowances**:								
IVIAJ	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	None Anticipated	1%	\$	14,539				
	Pavement Markings/Markers	·	3%	\$	43,618				
	Roadway Drainage	Standard Internal System	25%	\$	363,486				
	Special Drainage Structures	Bridge		\$	2,300,000				
	Water	None Anticipated	0%	\$	-				
	Sewer	None Anticipated	0%	\$	-				
	Establish Turf / Erosion Control		2%	\$	29,079				
	Illumination	Standard Ilumination System	6%	\$	87,237				
	Other:								
**Allc	wances based on % of Paving Construction	Cost Subtotal Allowa	nce Subtotal:	\$	2,837,959				
		Paving and Allowa			4,291,904				
		Mobilization:	5%	\$	214,595				
	\$	214,595							
	\$	4,722,000							
		Construction Contingency:	15%	\$	708,300				
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	5,431,000				

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 5,431,000
Engineering/Survey/Testing:		20%	\$ 1,086,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,900,850
	\$ 8,418,050		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No. D-10
Name: Limits: Impact Fee Class:	TRINITY FALLS PKWY (5) 4,275' N OF WESTON RD TO LAUD HOWELL PKWY M6D(1/3)		This section is currently under construction for a four-lane divided section and the City contributed approximately \$5,100,000 of eligible
Thoroughfare Class: Length (If):	Major Arterial 5,530		funds from '12-'19. This project consists of the construction of two additional through lanes within the existing median of the ultimate six-lane divided
Service Area(s):	D		maior arterial.

Ros	adway Construction Cost Pro	iection						
	Item Description	Jection .	Quantity	Unit	Un	it Price		Item Cost
111	Unclassified Street Excavation		17,204	су	\$	10.00	\$	172,044
211	Lime Treated Subgrade (8") (PI<12)		16,590	sy	\$	7.00	\$	116,130
311	9" Concrete Pavement		15,361	sy	\$	60.00	\$	921,667
411	4" Topsoil		4,916	sy	\$	2.50	\$	12,289
511	6" Curb & Gutter		11,060	lf	\$	5.00	\$	55,300
611	Allotment for Turn Lanes and Media	n Openings	3,375	sy	\$	77.00	\$	259,859
		F	Paving Const	ruction (	Cost S	Subtotal:	\$	1,537,289
Majo	or Construction Component Allowa							
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	46,119
	Pavement Markings/Markers					3%		46,119
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	30,746
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction C	ost Subtotal		Allowa	ince S	Subtotal:	\$	122,983
Paving and Allowance Subtotal:							\$	1,660,272
Mobilization: 5%							\$	83,014
Site Preparation: 5%							_	83,014
Construction Cost TOTAL:							\$	1,827,000
			ruction Conti				\$	274,050
	Construction Cost TOTAL W/ CONTINGENCY:							2,102,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,102,000
Engineering/Survey/Testing:		20%	\$ 420,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 5,100,000
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	\$ 7,622,400		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No. D-11			
Name:	BLOOMDALE RD (7) 1,820' W OF TAYLOR-BURK DR TO		This project consists of the reconstruction of a two-lane asphalt			
Limits:	TAYLOR-BURK DR		facility to a six-lane divided principal			
Impact Fee Class:	P6D		arterial. Based on the existing City			
Thoroughfare Class:	Principal Arterial		Limits, the southern half of the roadway			
Length (If):	is not included in the Impact Fee RIP.					
Service Area(s):	D, Half		io not morados in ano impaot i do itii i			

	dway Construction Cost Project	ction						
No.	Item Description		Quantity	Unit	-	it Price		Item Cost
113	Unclassified Street Excavation		20,222	су	\$	10.00	\$	202,222
213	Lime Treated Subgrade (8") (PI<12)		15,773	sy	\$	7.00	\$	110,413
313	9" Concrete Pavement		14,964	sy	\$	60.00	\$	897,867
413	4" Topsoil		8,291	sy	\$	2.50	\$	20,728
	6" Curb & Gutter		7,280	lf	\$	5.00	\$	36,400
613	Allotment for Turn Lanes and Median O	penings	1,111	sy	\$	77.00	\$	85,523
713	Moisture Conditioning		15,773	sy	\$	8.00	\$	126,187
		P	aving Const	ruction (	Cost	Subtotal:	\$	1,479,340
Majo	or Construction Component Allowance	es**:						
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	44,380
	Pavement Markings/Markers					3%	\$	44,380
	Roadway Drainage	Standard Internal Sy	stem			25%	\$	369,835
	Special Drainage Structures	None Anticipated					\$	-
	Water	Incidental Adjustmer	nts			3%	\$	44,380
	Sewer	Incidental Adjustmer	nts			3%	\$	44,380
	Establish Turf / Erosion Control					2%	\$	29,587
	Illumination	Standard Ilumination	System			6%	\$	88,760
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtota <b>l</b>		Allowa	nce	Subtotal:	\$	665,703
			Paving an	d Allowa	nce :	Subtotal:	\$	2,145,043
	Mobilization: 5%						\$	107,252
	Site Preparation: 5%						\$	107,252
	Construction Cost TOTAL:							2,360,000
	-		uction Conti			15%	\$	354,000 <b>2,714,000</b>
	Construction Cost TOTAL W/ CONTINGENCY:							

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,714,000
Engineering/Survey/Testing:		20%	\$ 542,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 542,800
	\$ 3,799,600		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-12

Name: BLOOMDALE RD (8) This project consists of the

Limits: 1,485' E OF CR 1006 TO 1,215' W OF CR 1007 reconstruction of a two-

Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 1,535 Service Area(s): D reconstruction of a two-lane asphalt

facility to a six-lane divided principal

arterial.

Roa	adway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Un	it Price		Item Cost
113	Unclassified Street Excavation	17,056	су	\$	10.00	\$	170,556
213	Lime Treated Subgrade (8") (PI<12)	13,303	sy	\$	7.00	\$	93,123
313	9" Concrete Pavement	12,621	sy	\$	60.00	\$	757,267
413	4" Topsoil	6,993	sy	\$	2.50	\$	17,482
513	6" Curb & Gutter	6,140	lf	\$	5.00	\$	30,700
613	Allotment for Turn Lanes and Median Openings	937	sy	\$	77.00	\$	72,131
713	Moisture Conditioning	13,303	sy	\$	8.00	\$	106,427
Paving Construction Cost Subtotal: \$							

	\$ 1,247,685			
Majo	r Construction Component Allowanc	es**:		
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$ 37,431
$\sqrt{}$	Pavement Markings/Markers		3%	\$ 37,431
$\sqrt{}$	Roadway Drainage	Standard Internal System	25%	\$ 311,921
	Special Drainage Structures	None Anticipated		\$ -
$\sqrt{}$	Water	Incidental Adjustments	3%	\$ 37,431
$\sqrt{}$	Sewer	Incidental Adjustments	3%	\$ 37,431
$\sqrt{}$	Establish Turf / Erosion Control		2%	\$ 24,954
$\sqrt{}$	Illumination	Standard Ilumination System	6%	\$ 74,861
	Other:			
**Allov	vances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$ 561,458
		Paving and Allowa	nce Subtotal:	\$ 1,809,143
	\$ 90,457			
	\$ 90,457			
		Construction C	ost TOTAL:	\$ 1,991,000
		Construction Contingency:	15%	\$ 298,650

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,290,000
Engineering/Survey/Testing:		20%	\$ 458,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 458,000
	Impact Fee P	roject Cost TOTAL:	\$ 3,206,000

**Construction Cost TOTAL W/ CONTINGENCY:** 

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

2,290,000

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Informatio</b>	n:	Description:	Project No.	D-13		
Name:	BLOOMDALE RD (9)	This project consists of the reconstruction of a t				
Limits:	1,225' W OF CR 1007 TO CR 1007	lane asphalt facility to a six-lane divided principal				
Impact Fee Class:	P6D	arterial. Based on the existing City Limits, the northern half of the roadway is not included in the				
Thoroughfare Class:	Principal Arterial					
Length (If):	1,225	Impact Fee RIP.				
Service Area(s):	D, Half	•				

Roa	adway Construction Cost Proje	ction					
No.	Item Description		Quantity	Unit	Unit Price		Item Cost
113	Unclassified Street Excavation		13,611	су	\$ 10.00	\$	136,111
213	Lime Treated Subgrade (8") (PI<12)		10,617	sy	\$ 7.00	\$	74,317
313	9" Concrete Pavement		10,072	sy	\$ 60.00	\$	604,333
413	13 4" Topsoil 5,581			sy	\$ 2.50	\$	13,951
513	13 6" Curb & Gutter 4,900 If		\$ 5.00	\$	24,500		
613	Allotment for Turn Lanes and Median C	penings	748	sy	\$ 77.00	\$	57,564
713	Moisture Conditioning		10,617	sy	\$ 8.00		84,933
		Р	aving Constr	uction C	Cost Subtotal	: \$	995,709
Majo	or Construction Component Allowand						
	Item Description	Notes			Allowance		Item Cost
$\sqrt{}$	Traffic Control	Construction Phase	Traffic Control		3%		29,871
$\sqrt{}$	Pavement Markings/Markers				3%		29,871
$\sqrt{}$	Roadway Drainage	Standard Internal Sy	/stem		25%	<mark>6</mark> \$	248,927
$\sqrt{}$	Special Drainage Structures	Stream Crossing				\$	250,000
$\sqrt{}$	Water	Incidental Adjustme	nts		3%		29,871
$\sqrt{}$	Sewer	Incidental Adjustmen	nts		3%		29,871
$\sqrt{}$	Establish Turf / Erosion Control				2%		19,914
	Illumination	Standard Ilumination	n System		6%	<mark>6</mark> \$	59,743
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce Subtotal	:  \$	698,069
					nce Subtotal		1,693,779
				lization:	5%	_	84,689
			Site Prep		5%		84,689
					ost TOTAL		1,864,000
			uction Conti				279,600
	Construction Cost TOTAL W/ CONTINGENCY: 5						2,144,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,144,000
Engineering/Survey/Testing:		20%	\$ 428,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 428,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Informatio</b>	n:	Description:	Project No.	D-14
Name:	BLOOMDALE RD (10)	The City contributed ap	proximately \$2	,962,610 of
Limits:	CR 1007 TO HARDIN BLVD	eligible funds from '12-	'19 for two of tl	ne six lanes.
Impact Fee Class:	P6D(2/3)	This project consists o	f the constructi	on of four
Thoroughfare Class:	Principal Arterial	additional through lane	es of the ultima	te six-lane
Length (If):	1,965	divided principal arteria		
Service Area(s):	D			

215   Lime Treated Subgrade (8") (PI<12)		ndway Construction Cost Proje	ction						
215   Lime Treated Subgrade (8") (Pl<12)	No.	Item Description		Quantity	Unit	Uni	t Price		Item Cost
315   9" Concrete Pavement   10,808   Sy   \$ 60.00   \$ 648,450	115	Unclassified Street Excavation		17,903	су	\$	10.00	\$	179,033
415   4" Topsoil   6,659   sy   \$ 2.50   \$ 16,648	215	Lime Treated Subgrade (8") (PI<12)		11,463	sy		7.00		80,238
515         6" Curb & Gutter         5,895         If         \$ 5,00         \$ 29,475           615         Allotment for Turn Lanes and Median Openings         1,199         sy         \$ 77.00         \$ 92,337           715         Moisture Conditioning         11,463         sy         \$ 8.00         \$ 91,700           Paving Construction Cost Subtotal:         \$ 1,137,881           Major Construction Component Allowances**:           Item Description         Notes         Allowance         Item Cost           √ Traffic Control         Construction Phase Traffic Control         3%         \$ 34,136           √ Pavement Markings/Markers         Standard Internal System         25%         \$ 284,470           Special Drainage Structures         None Anticipated         \$ 34,136           √ Sewer         Incidental Adjustments         3%         \$ 34,136           √ Establish Turf / Erosion Control         Standard Illumination System         6%         \$ 68,273           √ Illumination Other:         Standard Illumination System         6%         \$ 68,273           **Allowances based on % of Paving Construction Cost Subtotal         Allowance Subtotal:         \$ 1,649,927           * Paving and Allowance Subtotal:         \$ 1,649,927	315	9" Concrete Pavement		10,808	sy	\$	60.00	\$	648,450
Allotment for Turn Lanes and Median Openings	415	5 4" Topsoil 6,659 sy				2.50	\$	16,648	
T15   Moisture Conditioning	515	6" Curb & Gutter		5,895	lf			\$	29,475
Paving Construction Cost Subtotal:       \$ 1,137,881         Major Construction Component Allowances**:       Item Description       Notes       Allowance       Item Cost         √ Traffic Control       Construction Phase Traffic Control       3%       \$ 34,136         √ Pavement Markings/Markers       Construction Phase Traffic Control       3%       \$ 34,136         √ Roadway Drainage       Standard Internal System       25%       \$ 284,470         Special Drainage Structures       None Anticipated       \$ 3%       \$ 34,136         √ Water       Incidental Adjustments       3%       \$ 34,136         √ Establish Turf / Erosion Control       29%       \$ 22,758         √ Illumination       Standard Ilumination System       6%       68,273         Vallowances based on % of Paving Construction Cost Subtotal       Allowance Subtotal:       \$ 1,649,927         Mobilization:       5%       \$ 82,496         Site Preparation:       5%       \$ 82,496         Construction Cost TOTAL:       \$ 1,815,000         Construction Contingency:       15%       \$ 272,250	615	Allotment for Turn Lanes and Median C	)penings	1,199	sy		77.00	\$	92,337
Major Construction Component Allowances**:         Item Description       Notes       Allowance       Item Cost         √ Traffic Control       Construction Phase Traffic Control       3%       \$ 34,136         √ Pavement Markings/Markers       Standard Internal System       25%       \$ 284,470         √ Roadway Drainage       Standard Internal System       25%       \$ 284,470         × Special Drainage Structures       None Anticipated       \$ 3%       \$ 34,136         √ Sewer       Incidental Adjustments       3%       \$ 34,136         √ Establish Turf / Erosion Control       Incidental Adjustments       3%       \$ 34,136         √ Illumination       Standard Ilumination System       6%       \$ 68,273         **Allowances based on % of Paving Construction Cost Subtotal       Allowance Subtotal:       \$ 1,649,927         Mobilization:       5%       \$ 82,496         Site Preparation:       5%       \$ 82,496         Construction Cost TOTAL:       \$ 1,815,000         Construction Contingency:       15%       \$ 272,250	715	Moisture Conditioning		11,463	sy	\$	8.00	\$	91,700
Item Description         Notes         Allowance         Item Cost           √ Traffic Control         Construction Phase Traffic Control         3%         \$ 34,136           √ Pavement Markings/Markers         3%         \$ 34,136           √ Roadway Drainage         Standard Internal System         25%         \$ 284,470           Special Drainage Structures         None Anticipated         \$ 3%         \$ 34,136           √ Water         Incidental Adjustments         3%         \$ 34,136           √ Establish Turf / Erosion Control         Illumination         2%         \$ 22,758           √ Illumination         Standard Illumination System         6%         68,273           **Allowances based on % of Paving Construction Cost Subtotal         Allowance Subtotal:         \$ 1,649,927           Mobilization:         5%         \$ 82,496           Site Preparation:         5%         \$ 82,496           Construction Cost TOTAL:         1,815,000           Construction Contingency:         15%         \$ 272,250			Р	aving Constr	uction C	Cost S	ubtotal:	\$	1,137,881
Item Description         Notes         Allowance         Item Cost           √ Traffic Control         Construction Phase Traffic Control         3%         \$ 34,136           √ Pavement Markings/Markers         3%         \$ 34,136           √ Roadway Drainage         Standard Internal System         25%         \$ 284,470           Special Drainage Structures         None Anticipated         \$ 3%         \$ 34,136           √ Water         Incidental Adjustments         3%         \$ 34,136           √ Establish Turf / Erosion Control         Illumination         2%         \$ 22,758           √ Illumination         Standard Illumination System         6%         68,273           **Allowances based on % of Paving Construction Cost Subtotal         Allowance Subtotal:         \$ 1,649,927           Mobilization:         5%         \$ 82,496           Site Preparation:         5%         \$ 82,496           Construction Cost TOTAL:         1,815,000           Construction Contingency:         15%         \$ 272,250									
√ Traffic Control         Construction Phase Traffic Control         3%         \$ 34,136           √ Pavement Markings/Markers         3%         \$ 34,136           √ Roadway Drainage         Standard Internal System         25%         \$ 284,470           Special Drainage Structures         None Anticipated         \$ 3%         \$ 34,136           √ Water         Incidental Adjustments         3%         \$ 34,136           √ Sewer         Incidental Adjustments         3%         \$ 34,136           √ Establish Turf / Erosion Control         2%         \$ 22,758           √ Illumination         Standard Ilumination System         6%         68,273           Other:         **Allowances based on % of Paving Construction Cost Subtotal         * 512,046           **Allowances based on % of Paving Construction Cost Subtotal         * 1,649,927           Mobilization:         5%         \$ 82,496           Site Preparation:         5%         \$ 82,496           * Construction Cost TOTAL:         * 1,815,000           * 272,250	Majo								
√ Pavement Markings/Markers         3%         \$ 34,136           √ Roadway Drainage         Standard Internal System         25%         \$ 284,470           Special Drainage Structures         None Anticipated         \$ 3%         \$ 34,136           √ Water         Incidental Adjustments         3%         \$ 34,136           √ Sewer         Incidental Adjustments         3%         \$ 34,136           √ Establish Turf / Erosion Control         2%         \$ 22,758           √ Illumination         Standard Ilumination System         6%         \$ 68,273           Other:         **Allowances based on % of Paving Construction Cost Subtotal         * 512,046           Paving and Allowance Subtotal:         \$ 1,649,927           Mobilization:         5%         \$ 82,496           Site Preparation:         5%         \$ 1,815,000           Construction Cost TOTAL:         \$ 1,815,000		Item Description	Notes			Allo	wance		Item Cost
√ Roadway Drainage Special Drainage StructuresStandard Internal System25%\$ 284,470√ Water √ Water √ SewerIncidental Adjustments3%\$ 34,136√ Establish Turf / Erosion Control √ Illumination Other:Standard Ilumination System6%\$ 22,758**Allowances based on % of Paving Construction Cost SubtotalAllowance Subtotal:\$ 1,649,927**Allowances based on % of Paving Construction Cost SubtotalPaving and Allowance Subtotal:\$ 1,649,927Mobilization: Site Preparation:5%\$ 82,496Site Preparation:5%\$ 82,496Construction Cost TOTAL:\$ 1,815,000Construction Contingency:15%\$ 272,250		Traffic Control	Construction Phase	Traffic Control			3%	\$	34,136
Special Drainage Structures  √ Water  √ Sewer  √ Sewer  √ Establish Turf / Erosion Control  √ Illumination Other:  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal  **Allowances Subtotal:  **Allowances S		Pavement Markings/Markers					3%	\$	34,136
√ Water         Incidental Adjustments         3%         \$ 34,136           √ Sewer         Incidental Adjustments         3%         \$ 34,136           √ Establish Turf / Erosion Control         2%         \$ 22,758           √ Illumination         Standard Illumination System         6%         \$ 68,273           **Allowances based on % of Paving Construction Cost Subtotal         Allowance Subtotal:         \$ 1,649,927           Mobilization:         5%         \$ 82,496           Site Preparation:         5%         \$ 82,496           Construction Cost TOTAL:         \$ 1,815,000           Construction Contingency:         15%         \$ 272,250		•	Standard Internal Sy	/stem			25%	\$	284,470
Value   Val		Special Drainage Structures	None Anticipated					\$	-
✓ Establish Turf / Erosion Control ✓ Illumination Other:2% 6%\$ 22,758 6%**Allowances based on % of Paving Construction Cost SubtotalAllowance Subtotal:\$ 512,046Paving and Allowance Subtotal:\$ 1,649,927Mobilization: Site Preparation:5% 5%\$ 82,496Construction Cost TOTAL:\$ 1,815,000Construction Contingency:15%\$ 272,250		Water	Incidental Adjustmen	nts			3%	\$	34,136
√ Illumination Other:Standard Illumination System6%\$ 68,273**Allowances based on % of Paving Construction Cost SubtotalAllowance Subtotal:\$ 512,046Paving and Allowance Subtotal:\$ 1,649,927Mobilization:5%\$ 82,496Site Preparation:5%\$ 82,496Construction Cost TOTAL:\$ 1,815,000Construction Contingency:15%\$ 272,250		Sewer	Incidental Adjustmer	nts					34,136
Other:  **Allowances based on % of Paving Construction Cost Subtotal  Paving and Allowance Subtotal:  Mobilization:  Site Preparation:  Construction Cost TOTAL:  Construction Contingency:  15%  \$ 272,250		Establish Turf / Erosion Control					2%	\$	22,758
**Allowances based on % of Paving Construction Cost Subtotal  Paving and Allowance Subtotal:  Mobilization:  Site Preparation:  Construction Cost TOTAL:  Construction Contingency:  * 512,046  \$ 1,649,927  \$ 82,496  \$ 82,496  \$ 272,250		Illumination	Standard Ilumination	n System			6%	\$	68,273
Paving and Allowance Subtotal:   \$ 1,649,927		Other:							
Mobilization:         5%         \$ 82,496           Site Preparation:         5%         \$ 82,496           Construction Cost TOTAL:         \$ 1,815,000           Construction Contingency:         15%         \$ 272,250	**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce S	ubtotal:	\$	512,046
Mobilization:         5%         \$ 82,496           Site Preparation:         5%         \$ 82,496           Construction Cost TOTAL:         \$ 1,815,000           Construction Contingency:         15%         \$ 272,250									
Site Preparation:         5%         \$ 82,496           Construction Cost TOTAL:         \$ 1,815,000           Construction Contingency:         15%         \$ 272,250				_		nce S		\$	
Construction Cost TOTAL: \$ 1,815,000  Construction Contingency: 15% \$ 272,250								-	
Construction Contingency: 15% \$ 272,250								_	82,496
				Construc	ction C	ost T	OTAL:		1,815,000
Construction Cost TOTAL W/ CONTINGENCY: \$ 2,088,000			Constr	uction Conti	ngency:		15%	\$	272,250
		Co	nstruction Cos	t TOTAL W	// CON	TING	ENCY:	\$	2,088,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,088,000
Engineering/Survey/Testing:		20%	\$ 417,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 2,962,610
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 417,600
	Impact Fee P	roject Cost TOTAL:	\$ 5,885,810

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Informatio</b>	n:	Description:	Project No.	D-15				
Name:	BLOOMDALE RD (11)	The City contributed ap	proximately \$3,	887,390 of				
Limits:	HARDIN BLVD TO COMMUNITY AV	Eeligible funds from '12-'	19 for four of th	ne six lanes.				
Impact Fee Class:	P6D(1/3)	This project consists of the construction of two						
Thoroughfare Class:	Principal Arterial	additional through lane						
Length (If):	2,580	ultimate six-lane divide						
Service Area(s):	D							

Roadway Construction Cost Projection								
No.	Item Description		Quantity	Unit	Uni	it Price		Item Cost
114	Unclassified Street Excavation		8,027	су	\$	10.00	\$	80,267
214	Lime Treated Subgrade (8") (PI<12)		7,740	sy	\$	7.00	\$	54,180
	9" Concrete Pavement		7,167	sy	\$	60.00	\$	430,000
414	4" Topsoil		2,293	sy	\$	2.50	\$	5,733
514	6" Curb & Gutter		5,160	lf	\$	5.00	\$	25,800
614	Allotment for Turn Lanes and Median O	penings	1,574	sy	\$	77.00	\$	121,236
714	Moisture Conditioning		7,740	sy	\$	8.00	\$	61,920
		Р	aving Constr	uction (	Cost S	Subtotal:	\$	779,136
Majo	or Construction Component Allowance							
	Item Description	Notes			Allo	owance		Item Cost
$\sqrt{}$	Traffic Control	Construction Phase	Traffic Control			3%		23,374
	Pavement Markings/Markers					3%		23,374
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	15,583
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtota <b>l</b>		Allowa	nce S	Subtotal:	\$	62,331
			Paving and		nce S			841,467
				lization:		5%	\$	42,073
			Site Prep	aration:		5%	\$	42,073
			Construc					926,000
			uction Conti			15%		138,900
	Con	struction Cos	t TOTAL W	// CON	TING	ENCY:	\$	1,065,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,065,000
Engineering/Survey/Testing:		20%	\$ 213,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 3,887,390
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 5,165,390

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

707 Moisture Conditioning

#### updated:

10/6/2020

201,007

278,960

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

607 Allotment for Turn Lanes and Median Openings

Project Information: **D-16** Description: Project No. Name: WILMETH RD (5) This project consists of the construction of a new Limits: LAKE FOREST DR TO UNNAMED A four-lane divided greenway arterial. Based on the Impact Fee Class: G4D existing City Limits, the northern half of the roadway Thoroughfare Class: **Greenway Arterial** is not included in the Impact Fee RIP. Length (If): 4,755 Service Area(s): D, Half

**Roadway Construction Cost Projection** No. Item Description Quantity Unit **Unit Price Item Cost** 107 Unclassified Street Excavation 46,493 \$ 10.00 \$ 464,933 су 207 Lime Treated Subgrade (8") (PI<12) 34,870 \$ 7.00 \$ 244,090 sy 307 8" Concrete Pavement 32,757 \$ 55.00 \$ 1,801,617 sy 407 4" Topsoil 22,718 \$ 2.50 \$ 56,796 sy 507 6" Curb & Gutter 19,020 lf \$ 5.00 \$ 95,100

2,792

34,870

Paving Construction Cost Subtotal: \$ 3,142,503

72.00

8.00

\$

\$

\$

\$

sy

sy

		Jost Subtotal.	Ψ	3,142,303			
Maj	or Construction Component Allow	ances**:					
	Item Description	Notes	Allowance		Item Cost		
	Traffic Control	None Anticipated	1%	\$	31,425		
	Pavement Markings/Markers		3%	\$	94,275		
	Roadway Drainage	Standard Internal System	25%	\$	785,626		
	Special Drainage Structures	Bridge		\$	1,300,000		
	Water	None Anticipated	0%	\$	-		
<b>l</b> .	Sewer	None Anticipated	0%	\$	-		
$\sqrt{}$	Establish Turf / Erosion Control		2%	\$	62,850		
	Illumination	Standard Ilumination System	6%	\$	188,550		
	Other:						
**Allo	wances based on % of Paving Construction	Cost Subtotal Allowa	nce Subtotal:	\$	2,462,726		
		Paving and Allowa			5,605,229		
		Mobilization:			280,261 280,261		
	Site Preparation: 5%						
	Construction Cost TOTAL:						
		Construction Contingency:	15%	\$	924,900		
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	7,091,000		

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 7,091,000
Engineering/Survey/Testing:		20%	\$ 1,418,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 2,481,850

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-17

Name: WILMETH RD (6) This project consists of the

Limits: UNNAMED A TO 825' E OF UNNAMED A reconstruction of a two-lane asphalt

Impact Fee Class: G4D facility to a four-lane divided greenway

Thoroughfare Class: Greenway Arterial arterial.

Length (If): 825 Service Area(s): D

Roa	adway Construction Cost Proje	ection							
	Item Description		Quantity	Unit	Un	it Price		Item Cost	
107	Unclassified Street Excavation		8,067	су	\$	10.00	\$	80,667	
207	Lime Treated Subgrade (8") (PI<12)		6,050	sy	\$	7.00	\$	42,350	
307	8" Concrete Pavement		5,683	sy	\$	55.00	\$	312,583	
407	4" Topsoil		3,942	sy	\$	2.50	\$	9,854	
507	6" Curb & Gutter		3,300	lf	\$	5.00	\$	16,500	
607	Allotment for Turn Lanes and Median	Openings	484	sy	\$	72.00	\$	34,875	
707	Moisture Conditioning		6,050	sy	\$	8.00	\$	48,400	
		Р	aving Constr	uction C	Cost	Subtotal:	\$	545,229	
Majo	or Construction Component Allowan	ces**:							
	Item Description	Notes			All	owance		Item Cost	
	Traffic Control	Construction Phase	Traffic Control			3%	\$	16,357	
$\checkmark$	Pavement Markings/Markers					3%	\$	16,357	
$\checkmark$	Roadway Drainage	Standard Internal Sy	/stem			25%	\$	136,307	
	Special Drainage Structures	None Anticipated					\$	-	
$\checkmark$	Water	Incidental Adjustme	nts			3%	\$	16,357	
$\checkmark$	Sewer	Incidental Adjustme	nts			3%	\$	16,357	
$\checkmark$	Establish Turf / Erosion Control					2%	\$	10,905	
$\checkmark$	Illumination	Standard Ilumination	System			6%	\$	32,714	
	Other:								
**Allo	wances based on % of Paving Construction Cos	st Subtotal		Allowa	nce (	Subtotal:	\$	245,353	
			Paving and	d Allowa	nce (	Subtotal:	\$	790,582	
			Mobi	lization:		5%	\$	39,529	
			Site Prep	aration:		5%	\$	39,529	
			Construc	ction C	ost	TOTAL:	\$	870,000	
		Constr	uction Conti	ngency:		15%	\$	130,500	
	Co	nstruction Cos	t TOTAL W	Construction Cost TOTAL W/ CONTINGENCY: 5					

Impact Fee Project Cost Sumi	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,001,000
Engineering/Survey/Testing:		20%	\$ 200,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 200,200
	Impact Fee Pro	ject Cost TOTAL:	\$ 1,401,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-18

Name: WILMETH RD (7) This project consists of the

825' E OF TAYLOR-BURK DR TO construction of two additional lanes of

Limits: 1,380' E OF TAYLOR-BURK DR the ultimate four-lane divided greenway

Impact Fee Class: G4D(1/2) arterial.

Thoroughfare Class: Greenway Arterial

Length (If): 555 Service Area(s): D

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
108	Unclassified Street Excavation	2,097	су	\$	10.00	\$ 20,967
208	Lime Treated Subgrade (8") (PI<12)	2,035	sy	\$	7.00	\$ 14,245
308	8" Concrete Pavement	1,912	sy	\$	55.00	\$ 105,142
408	4" Topsoil	709	sy	\$	2.50	\$ 1,773
508	6" Curb & Gutter	1,110	lf	\$	5.00	\$ 5,550
608	Allotment for Turn Lanes and Median Openings	163	sy	\$	72.00	\$ 11,731

Paving Construction Cost Subtotal: \$ 159,407

Majo	Major Construction Component Allowances**:								
	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	Construction Phase Traffic Control	3%	\$	4,782				
	Pavement Markings/Markers		3%	\$	4,782				
	Roadway Drainage	Standard Internal System	25%	\$	39,852				
	Special Drainage Structures	None Anticipated		\$	-				
	Water	Incidental Adjustments	3%	\$	4,782				
	Sewer	Incidental Adjustments	3%	\$	4,782				
	Establish Turf / Erosion Control		2%	\$	3,188				
	Illumination	Standard Ilumination System	6%	\$	9,564				
	Other:								
**Allo	wances based on % of Paving Construction Cos	Subtotal Allowa	nce Subtotal:	\$	71,733				
		Paving and Allowa			231,140				
		Mobilization:			11,557				
		Site Preparation:		_	11,557				
		Construction C			255,000				
		Construction Contingency:	15%	\$	38,250				
	Со	nstruction Cost TOTAL W/ CON	ΓINGENCY:	\$	294,000				

Item Description	Notes:	Allowance	lt	tem Cost
Construction:		-	\$	294,000
Engineering/Survey/Testing:		20%	\$	58,800
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	Existing Alignment	20%	\$	58,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

Project Information	ղ:	Description:	Project No. D-19
Name:	WILMETH RD (8)		This project consists of the
	1,380' E OF TAYLOR-BURK DR TO		reconstruction of a two-lane asphalt
Limits:	HARDIN BLVD		facility to a four-lane divided greenway
Impact Fee Class:	G4D		arterial. Based on the existing City
Thoroughfare Class:	Greenway Arterial		Limits, the northern half of the roadway

Length (If): 2,240 Service Area(s): D, Half

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
107	Unclassified Street Excavation	21,902	су	\$	10.00	\$ 219,022
207	Lime Treated Subgrade (8") (PI<12)	16,427	sy	\$	7.00	\$ 114,987
307	8" Concrete Pavement	15,431	sy	\$	55.00	\$ 848,711
407	4" Topsoil	10,702	sy	\$	2.50	\$ 26,756
507	6" Curb & Gutter	8,960	lf	\$	5.00	\$ 44,800
607	Allotment for Turn Lanes and Median Openings	1,315	sy	\$	72.00	\$ 94,691
707	Moisture Conditioning	16 427	SV	\$	8.00	\$ 131 413

Paving Construction Cost Subtotal: \$ 1,480,380

is not included in the Impact Fee RIP.

Maj	or Construction Component Allov Item Description	vances**:   Notes	Allowance	П	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$	44,411
	Pavement Markings/Markers		3%	\$	44,411
	Roadway Drainage	Standard Internal System	25%	\$	370,095
	Special Drainage Structures	None Anticipated		\$	-
	Water	Incidental Adjustments	3%	\$	44,411
	Sewer	Incidental Adjustments	3%	\$	44,411
	Establish Turf / Erosion Control		2%	\$	29,608
	Illumination	Standard Ilumination System	6%	\$	88,823
	Other:				
**Allo	owances based on % of Paving Construction	Cost Subtotal Allowa	ance Subtotal:	\$	666,171
		Paving and Allowa	ance Subtotal:	\$	2,146,551
		Mobilization:	5%	\$	107,328
		Site Preparation:	5%	\$	107,328
		Construction C	ost TOTAL:	\$	2,362,000
		Construction Contingency:	15%	\$	354,300
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	2,717,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,717,000
Engineering/Survey/Testing:		20%	\$ 543,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 543,400
	Impact Fee Project	Cost TOTAL:	\$ 3,803,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No.	D-20
Name:	WILMETH RD (9)	This project consists of	the construction	on of two
Limits:	HARDIN BLVD TO US HIGHWAY 75	additional through lane	s within the exis	sting median
Impact Fee Class:	M6D(1/3)	of the ultimate six-lane	divided major a	rterial.
Thoroughfare Class:	Major Arterial		•	

Length (If): 6,140 Service Area(s):

Roa	adway Construction Cost Proje	ection						
No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
111	Unclassified Street Excavation		19,102	су	\$	10.00	\$	191,022
211	11 Lime Treated Subgrade (8") (PI<12)		18,420	sy	\$	7.00	\$	128,940
311	311 9" Concrete Pavement		17,056	sy	\$	60.00	\$	1,023,333
411	111 4" Topsoil 5,458 sy		\$	2.50	\$	13,644		
	6" Curb & Gutter		12,280	lf	\$	5.00	\$	61,400
611	Allotment for Turn Lanes and Median (		3,747	sy	\$	77.00	\$	288,523
		Р	aving Constr	uction C	Cost S	Subtotal:	\$	1,706,863
Majo	or Construction Component Allowan							
	Item Description	Notes			Alle	owance		Item Cost
$\sqrt{}$	Traffic Control	Construction Phase	Traffic Control			3%		51,206
	Pavement Markings/Markers					3%		51,206
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	34,137
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce S	Subtotal:	\$	136,549
			Paving and		nce S		\$	1,843,412
				lization:		5%	\$	92,171
			Site Prep			5%	_	92,171
			Construc			ΓΟTAL:	\$	2,028,000
		Constr	uction Conti	ngency:		15%	\$	304,200
						\$	2,333,000	

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,333,000
Engineering/Survey/Testing:		20%	\$ 466,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

Project Information: Description: Project No. D-21

Name: LAKE FOREST DR (1) This project consists of the

LAUD HOWELL PKWY TO 3,200' S reconstruction of a two-l

Limits: OF LAUD HOWELL PKWY

Conceptual Level Project Cost Projection

Impact Fee Class: G6D

Thoroughfare Class: Greenway Arterial

Length (If): 3,200
Service Area(s): D, Half

reconstruction of a two-lane asphalt facility to a six-lane divided greenway arterial. Based on the existing City Limits, the western half of the roadway is not included in the Impact Fee RIP.

Po:	adway Construction Cost Proje	ction						
	Item Description	Clion	Quantity	Unit	Un	it Price		Item Cost
116	Unclassified Street Excavation		39,111	су	\$	10.00	\$	391,111
216	Lime Treated Subgrade (8") (PI<12)		25,600	sy	\$	7.00	\$	179,200
316				\$	60.00	\$	1,450,667	
416				\$	2.50	\$	50,667	
516	6" Curb & Gutter		12,800	lf	\$	5.00	\$	64,000
616	Allotment for Turn Lanes and Median C	penings	2,211	sy	\$	77.00	\$	170,281
716	Moisture Conditioning	-	25,600	sy	\$	8.00	\$	204,800
	-	P	aving Const	ruction (	Cost S	Subtotal:	\$	2,510,726
			•					
Majo	or Construction Component Allowanc	es**:						
	Item Description	Notes			Allo	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	75,322
	Pavement Markings/Markers					3%	\$	75,322
	Roadway Drainage	Standard Internal Sy	rstem			25%	\$	627,681
	Special Drainage Structures	None Anticipated					\$	-
	Water	Incidental Adjustmer	nts			3%	\$	75,322
	Sewer	Incidental Adjustmer	nts			3%	\$	75,322
	Establish Turf / Erosion Control					2%	\$	50,215
	Illumination	Standard Ilumination	System			6%	\$	150,644
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce S	Subtotal:	\$	1,129,827
			Paving an	d Allowa	nce S	Subtotal:	\$	3,640,553
	Mobilization: 5%					\$	182,028	
			Site Prep	aration:		5%	\$	182,028
			Construc	ction C	ost 1	ΓΟΤΑL:	\$	4,005,000
			uction Conti			15%	-	600,750
	Со	nstruction Cos	t TOTAL W	// CON	TING	ENCY:	\$	4,606,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,606,000
Engineering/Survey/Testing:		20%	\$ 921,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 921,200
	Impact Fee Pro	ject Cost TOTAL:	\$ 6,448,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information:

Name:

LAKE FOREST DR (3)

Limits:

WILMETH RD TO US HIGHWAY 380

Impact Fee Class:

MoD(1/3)

Description:

Project No. C-34, D-22

This project consists of the construction of two additional through lanes within the existing median of the ultimate six-lane divided major arterial.

Thoroughfare Class: Major Arterial

Length (If): 5,155
Service Area(s): C and D

Roa	adway Construction Cost Pro	jection						
No.	Item Description		Quantity	Unit	Uni	it Price		Item Cost
111	Unclassified Street Excavation		16,038	су	\$	10.00	\$	160,378
211	Lime Treated Subgrade (8") (PI<12)		15,465	sy	\$	7.00	\$	108,255
311	9" Concrete Pavement		14,319	sy	\$	60.00	\$	859,167
411	4" Topsoil		4,582	sy	\$	2.50	\$	11,456
511	6" Curb & Gutter		10,310	lf	\$	5.00	\$	51,550
611	Allotment for Turn Lanes and Median	n Openings	3,146	sy	\$	77.00	\$	242,237
			Paving Consti	uction (	Cost S	Subtotal:	\$	1,433,042
Maj	or Construction Component Allowa	nces**:						
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	42,991
	Pavement Markings/Markers					3%	\$	42,991
	Roadway Drainage	None Anticipated				0%	\$	-
	Roadway Drainage Special Drainage Structures	None Anticipated None Anticipated				0%	\$ \$	-
	, ,					0% 0%	\$	- - -
	Special Drainage Structures	None Anticipated					\$ \$	- - -
V	Special Drainage Structures Water	None Anticipated None Anticipated				0%	\$ \$ \$	- - - 28,661

**Allowances based on % of Paving Construction Cost Subtotal  **Allowances based on % of Paving Construction Cost Subtotal	Allowance Subtotal:		114,643
Paving and Allowa	nce Subtotal:	\$	1,547,686
Mobilization:	5%	\$	77,384
Site Preparation:	5%	\$	77,384
Construction C	ost TOTAL:	\$	1,703,000
Construction Contingency:	15%	\$	255,450
Construction Cost TOTAL W/ CON	FINGENCY:	\$	1,959,000

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,959,000
Engineering/Survey/Testing:		20%	\$ 391,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 2,350,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

Other:

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-23

Name: UNNAMED A (1) This project consists of the construction

5,785' N OF LAUD HOWELL PKWY of a new four-lane divided greenway
Limits: TO 2,710' S OF LAUD HOWELL arterial.

Impact Fee Class: G4D

Thoroughfare Class: Greenway Arterial

Length (If): 8,495 Service Area(s): D

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
107	Unclassified Street Excavation	83,062	су	\$	10.00	\$ 830,622
207	Lime Treated Subgrade (8") (PI<12)	62,297	sy	\$	7.00	\$ 436,077
307	8" Concrete Pavement	58,521	sy	\$	55.00	\$ 3,218,661
407	4" Topsoil	40,587	sy	\$	2.50	\$ 101,468
507	6" Curb & Gutter	33,980	lf	\$	5.00	\$ 169,900
607	Allotment for Turn Lanes and Median Openings	4,988	sy	\$	72.00	\$ 359,107
707	Moisture Conditioning	62,297	sy	\$	8.00	\$ 498,373

Paving Construction Cost Subtotal: \$ 5,614,208

Majo	or Construction Component Allowance	s**:					
	Item Description	Notes	Allowance		Item Cost		
	Traffic Control	None Anticipated	1%	\$	56,142		
	Pavement Markings/Markers		3%	\$	168,426		
	Roadway Drainage	Standard Internal System	25%	\$	1,403,552		
	Special Drainage Structures	Multiple Stream Crossings		\$	1,200,000		
	Water	None Anticipated	0%	\$	-		
	Sewer	None Anticipated	0%	\$	-		
	Establish Turf / Erosion Control		2%	\$	112,284		
	Illumination	Standard Ilumination System	6%	\$	336,852		
	Other:						
**Allo	wances based on % of Paving Construction Cost S	ubtotal Allowa	nce Subtotal:	\$	3,277,257		
		Paving and Allowa	nce Subtotal:	\$	8,891,465		
		Mobilization:	5%	\$	444,573		
		Site Preparation:	5%	\$	444,573		
	Construction Cost TOTAL:						
		Construction Contingency:	15%	\$	1,467,150		
	Con	struction Cost TOTAL W/ CON	TINGENCY:	\$	11,249,000		
				,	, -,		

Impact Fee Project Cost Summ	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 11,249,000
Engineering/Survey/Testing:		20%	\$ 2,249,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 3,937,150
	Impact Fee Project (	Cost TOTAL:	\$ 17,435,950

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

# 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information:** D-24 Description: Project No.

UNNAMED A (2) Name:

2,710' S OF LAUD HOWELL PKWY

Limits: TO BLOOMDALE RD

**Impact Fee Class:** G4D

Thoroughfare Class: **Greenway Arterial** 

Length (If): 2,590 D, Half Service Area(s):

This project consists of the construction of a new four-lane divided greenway arterial. Based on the existing City Limits, the eastern half of the roadway is not included in the Impact Fee RIP.

Roa	adway Construction Cost Proje	ction					
	Item Description		Quantity	Unit	Un	it Price	Item Cost
107	Unclassified Street Excavation		25,324	СУ	\$	10.00	\$ 253,244
207	Lime Treated Subgrade (8") (PI<12)		18,993	sy	\$	7.00	\$ 132,953
307	8" Concrete Pavement		17,842	sy	\$	55.00	\$ 981,322
407	4" Topsoil		12,374	sy	\$	2.50	\$ 30,936
507	6" Curb & Gutter		10,360	lf	\$	5.00	\$ 51,800
607	Allotment for Turn Lanes and Median (	Openings	1,521	sy	\$	72.00	\$ 109,486
707	Moisture Conditioning		18,993	sy	\$	8.00	\$ 151,947
		F	Paving Const	ruction (	Cost S	Subtotal:	\$ 1,711,689
Majo	or Construction Component Allowand	es**:					
	Item Description	Notes			Allo	owance	Item Cost
	Traffic Control	None Anticipated				1%	\$ 17,117
	Pavement Markings/Markers					3%	\$ 51,351
	Roadway Drainage	Standard Internal Sy	stem			25%	\$ 427,922
	Special Drainage Structures	None Anticipated					\$ -
	Water	None Anticipated				0%	\$ -
	Sewer	None Anticipated				0%	\$ -
	Establish Turf / Erosion Control					2%	\$ 34,234
	Illumination	Standard Ilumination	n System			6%	\$ 102,701
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce S	Subtotal:	\$ 633,325
			Paving an	d Allowa	nce S	Subtotal:	\$ 2,345,014
	Mobilization: 5%					\$ 117,251	
			Site Prep	aration:		5%	\$ 117,251
			Constru	ction C	ost 1	OTAL:	\$ 2,580,000
		Const	ruction Conti	ngency:		15%	\$ 387,000
	Co	nstruction Cos	st TOTAL W	// CON	TING	ENCY:	\$ 2,967,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,967,000
Engineering/Survey/Testing:		20%	\$ 593,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,038,450
	Impact Fee Project	ct Cost TOTAL:	\$ 4,598,850

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information:** D-25 Description: Project No. Name: UNNAMED A (3) This project consists of the Limits: 1,105' N OF WILMETH RD TO WILMETH RD reconstruction of a four-lane divided **Impact Fee Class:** G4D greenway arterial. Based on the existing Thoroughfare Class: **Greenway Arterial** City Limits, the western half of the Length (If): 1,105 roadway is not included in the Impact Service Area(s): D, Half Fee RIP.

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Unit	Price	Item Cost
107	Unclassified Street Excavation	10,804	су	\$	10.00	\$ 108,044
207	Lime Treated Subgrade (8") (PI<12)	8,103	sy	\$	7.00	\$ 56,723
307	8" Concrete Pavement	7,612	sy	\$	55.00	\$ 418,672
407	4" Topsoil	5,279	sy	\$	2.50	\$ 13,199
507	6" Curb & Gutter	4,420	lf	\$	5.00	\$ 22,100
607	Allotment for Turn Lanes and Median Openings	649	sy	\$	72.00	\$ 46,711
707	Moisture Conditioning	8,103	sy	\$	8.00	\$ 64,827

Paving Construction Cost Subtotal: \$ 730,277

Major	Construction Component Allowance	es**:			
lt	tem Description	Notes	Allowance		Item Cost
√ T	raffic Control	Construction Phase Traffic Control	3%	\$	21,908
√ F	Pavement Markings/Markers		3%	\$	21,908
√ F	Roadway Drainage	Standard Internal System	25%	\$	182,569
S	Special Drainage Structures	None Anticipated		\$	-
√ V	Vater	Incidental Adjustments	3%	\$	21,908
√ S	Sewer	Incidental Adjustments	3%	\$	21,908
√ E	Establish Turf / Erosion Control		2%	\$	14,606
√ II	llumination	Standard Ilumination System	6%	\$	43,817
	Other:				
**Allowa	ances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$	328,624
				_	
		Paving and Allowa			1,058,901
		Mobilization: Site Preparation:	5%	*	52,945
	\$	52,945			
		Construction Const	ost TOTAL:	\$	1,165,000
		Construction Contingency:	15%	\$	174,750
	Con	struction Cost TOTAL W/ CON	TINGENCY:	\$	1,340,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,340,000
Engineering/Survey/Testing:		20%	\$ 268,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 268,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-26

Name: UNNAMED A (4) This project consists of the construction of a new

Limits: WILMETH RD TO HARDIN BLVD four-lane divided minor arterial.

Impact Fee Class: M4D
Thoroughfare Class: Minor Arterial

Length (If): 3,940 Service Area(s): D

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
105	Unclassified Street Excavation	31,520	су	\$	10.00	\$ 315,200
205	Lime Treated Subgrade (8") (PI<12)	21,889	sy	\$	7.00	\$ 153,222
305	8" Concrete Pavement	20,138	sy	\$	55.00	\$ 1,107,578
405	4" Topsoil	17,073	sy	\$	2.50	\$ 42,683
505	6" Curb & Gutter	15,760	lf	\$	5.00	\$ 78,800
605	Allotment for Turn Lanes and Median Openings	2,313	sy	\$	72.00	\$ 166,555
705	Moisture Conditioning	21,889	sy	\$	8.00	\$ 175,111

Paving Construction Cost Subtotal: \$ 2,039,149

Majo	Major Construction Component Allowances**:								
	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	None Anticipated			20,391				
	Pavement Markings/Markers		3%	\$	61,174				
	Roadway Drainage	Standard Internal System	25%	\$	509,787				
	Special Drainage Structures	Stream Crossing		\$	250,000				
	Water	None Anticipated	0%	\$	-				
	Sewer	None Anticipated	0%	\$	-				
	Establish Turf / Erosion Control		2%	\$	40,783				
	Illumination	Standard Ilumination System	6%	\$	122,349				
	Other:								
**Allo	wances based on % of Paving Construction Cos	: Subtotal Allowa	nce Subtotal:	\$	1,004,485				
		Paving and Allowa	nce Subtotal:	\$	3,043,634				
		Mobilization:	5%	\$	152,182				
		Site Preparation:	5%	\$	152,182				
		Construction C	ost TOTAL:	\$	3,348,000				
	_	Construction Contingency:	15%	\$	502,200				
	Co	nstruction Cost TOTAL W/ CON	TINGENCY:	\$	3,851,000				

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,851,000
Engineering/Survey/Testing:		20%	\$ 770,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,347,850

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-27

Name: TAYLOR-BURK DR (1) This project consists of the construction of a new

Name: TAYLOR-BURK DR (1) This project consists of the construction of a new four-lane divided minor arterial.

Impact Fee Class: M4D

Thoroughfare Class: Minor Arterial

Length (If): 1,465 Service Area(s): D

Roa	Roadway Construction Cost Projection									
No.	Item Description	Quantity	Unit	Un	it Price		Item Cost			
105	Unclassified Street Excavation	11,720	су	\$	10.00	\$	117,200			
205	Lime Treated Subgrade (8") (PI<12)	8,139	sy	\$	7.00	\$	56,972			
305	8" Concrete Pavement	7,488	sy	\$	55.00	\$	411,828			
405	4" Topsoil	6,348	sy	\$	2.50	\$	15,871			
505	6" Curb & Gutter	5,860	lf	\$	5.00	\$	29,300			
605	Allotment for Turn Lanes and Median Openings	860	sy	\$	72.00	\$	61,930			
705	Moisture Conditioning	8,139	sy	\$	8.00	\$	65,111			

Paving Construction Cost Subtotal: \$ 758,211

Maio	Major Construction Component Allowances**:									
	Item Description	Notes	Allowance	П	Item Cost					
	Traffic Control	None Anticipated	1%	\$	7,582					
	Pavement Markings/Markers		3%	\$	22,746					
	Roadway Drainage	Standard Internal System	25%	\$	189,553					
	Special Drainage Structures	None Anticipated		\$	-					
	Water	None Anticipated	0%	\$	-					
	Sewer	None Anticipated	0%	\$	-					
$\checkmark$	Establish Turf / Erosion Control		2%	\$	15,164					
$\checkmark$	Illumination	Standard Ilumination System	6%	\$	45,493					
	Other:									
**Allo	wances based on % of Paving Construction Cos	t Subtotal Allowa	nce Subtotal:	\$	280,538					
		Paving and Allowa			1,038,750					
		Mobilization:		*	51,937					
		Site Preparation:	5%	\$	51,937					
		Construction C		\$	1,143,000					
		Construction Contingency:	15%	\$	171,450					
	Co	nstruction Cost TOTAL W/ CON	TINGENCY:	\$	1,315,000					

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,315,000
Engineering/Survey/Testing:		20%	\$ 263,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 460,250

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information: D-28** Description: Project No. Name: HARDIN BLVD (4) This project consists of the Limits: UNNAMED 5 TO 1,550' S OF UNNAMED 5 construction of a new six-lane divided **Impact Fee Class:** G₆D greenway arterial. Based on the existing Thoroughfare Class: **Greenway Arterial** City Limits, the eastern half of the Length (If): 1,550 roadway is not included in the Impact Service Area(s): D, Half Fee RIP.

Roa	dway Construction Cost Proje	ection						
	Item Description		Quantity	Unit	Un	it Price		Item Cost
116	Unclassified Street Excavation		18,944	су	\$	10.00	\$	189,444
216	Lime Treated Subgrade (8") (PI<12)		12,400	sy	\$	7.00	\$	86,800
316	9" Concrete Pavement		11,711	sy	\$	60.00	\$	702,667
416	4" Topsoil		9,817	sy	\$	2.50	\$	24,542
516	6" Curb & Gutter		6,200	lf	\$	5.00	\$	31,000
616	Allotment for Turn Lanes and Median	Openings	1,071	sy	\$	77.00	\$	82,480
716	Moisture Conditioning		12,400	sy	\$	8.00	\$	99,200
	Paving Construction Co					Subtotal:	\$	1,216,133
Majo	or Construction Component Allowan	ces**:						
Majo	r Construction Component Allowan Item Description	ces**: Notes			Alle	owance		Item Cost
Majo		•			Alle	owance	\$	Item Cost 12,161
Majo √ √	Item Description	Notes			All			
√ √	Item Description Traffic Control	Notes	System		Alle	1%	\$	12,161
√ √	Item Description Traffic Control Pavement Markings/Markers	Notes  None Anticipated	System		All	1% 3%	\$	12,161 36,484
√ √	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage	Notes  None Anticipated  Standard Internal	System		Alle	1% 3%	\$ \$ \$	12,161 36,484
√ √	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures	Notes  None Anticipated  Standard Internal None Anticipated	System		All	1% 3% 25%	\$ \$ \$ \$	12,161 36,484
√ √	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water	Notes  None Anticipated  Standard Internal None Anticipated None Anticipated	System		Alle	1% 3% 25% 0%	\$ \$ \$ \$ \$	12,161 36,484
\[ \sqrt{1} \]	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer	Notes  None Anticipated  Standard Internal None Anticipated None Anticipated	,		Alle	1% 3% 25% 0% 0%	\$ \$ \$ \$ \$	12,161 36,484 304,033 - -

00.10.	110110 / Ilitioipatou	0,0	Ψ			
√ Establish Turf / Erosion Control		2%	\$	24,323		
$\sqrt{}$ Illumination	Standard Ilumination System 6%			72,968		
Other:						
**Allowances based on % of Paving Construction	**Allowances based on % of Paving Construction Cost Subtotal Allowance Subtotal: \$					
	Paving and Allowance Subtotal: \$					
	Mobilization	5%	\$	83,305		
	Site Preparation	5%	\$	83,305		
	Construction C	ost TOTAL:	\$	1,833,000		
	Construction Contingency	15%	\$	274,950		
	Construction Cost TOTAL W/ CON	TINGENCY:	\$	2,108,000		

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,108,000
Engineering/Survey/Testing:		20%	\$ 421,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 737,800
	Impact Fee Proje	ect Cost TOTAL:	\$ 3,267,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information:** D-29 Description: Project No. Name: HARDIN BLVD (5)

Limits: 1,545' S OF UNNAMED 5 TO TRINITY FALLS PKWY This project consists of the construction of a new six-lane

**Impact Fee Class:** G₆D divided greenway arterial.

Thoroughfare Class: **Greenway Arterial** 

Length (If): 7,310 Service Area(s): D

Roa	Roadway Construction Cost Projection									
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost			
116	Unclassified Street Excavation	89,344	су	\$	10.00	\$	893,444			
216	Lime Treated Subgrade (8") (PI<12)	58,480	sy	\$	7.00	\$	409,360			
316	9" Concrete Pavement	55,231	sy	\$	60.00	\$	3,313,867			
416	4" Topsoil	46,297	sy	\$	2.50	\$	115,742			
516	6" Curb & Gutter	29,240	lf	\$	5.00	\$	146,200			
616	Allotment for Turn Lanes and Median Openings	5,052	sy	\$	77.00	\$	388,987			
716	Moisture Conditioning	58,480	sy	\$	8.00	\$	467,840			

Paving Construction Cost Subtotal: \$ 5,735,440

	Major Construction Component Allowanese**									
Maj	or Construction Component Allowan									
	Item Description	Notes	Allowance		Item Cost					
	Traffic Control	None Anticipated	1%	\$	57,354					
	Pavement Markings/Markers		3%	\$	172,063					
	Roadway Drainage	Standard Internal System	25%	\$	1,433,860					
	Special Drainage Structures	Bridge		\$	3,000,000					
	Water	None Anticipated	0%	\$	-					
	Sewer	None Anticipated	0%	\$	-					
	Establish Turf / Erosion Control		2%	\$	114,709					
	Illumination	Standard Ilumination System	6%	\$	344,126					
	Other:									
**Allo	owances based on % of Paving Construction Cos	st Subtotal Allowa	nce Subtotal:	\$	5,122,113					
		Paving and Allowa	nce Subtotal:	\$	10,857,552					
		Mobilization:	5%	\$	542,878					
		Site Preparation:	5%	\$	542,878					
		Construction C	ost TOTAL:	\$	11,944,000					
		Construction Contingency:	15%	\$	1,791,600					
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	13,736,000					

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 13,736,000
Engineering/Survey/Testing:		20%	\$ 2,747,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 4,807,600

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

Project Information	on:	Description:	Project No.	D-30
Name:	HARDIN BLVD (6)	This n	coinct consists of the	10

Name: HARDIN BLVD (6) This project consists of the

TRINITY FALLS PKWY TO 1,815' S recons

Limits: OF TRINITY FALLS PKWY

Impact Fee Class: G6D

Thoroughfare Class: Greenway Arterial

Length (If): 1,815 Service Area(s): D, Half reconstruction of a two-lane dirt/gravel facility to a six-lane divided greenway arterial. Based on the existing City Limits, the western half of the roadway is not included in the Impact Fee RIP.

Ros	adway Construction Cost Proje	oction						
	Item Description	CHOH	Quantity	Unit	Uni	t Price		Item Cost
116	Unclassified Street Excavation		22,183	СУ	\$	10.00	\$	221,833
216	Lime Treated Subgrade (8") (PI<12)		14,520	sy	\$	7.00	\$	101,640
316	6 9" Concrete Pavement 13,713 sy		\$	60.00	\$	822,800		
416	4" Topsoil		11,495	sy	\$	2.50	\$	28,738
516	6" Curb & Gutter		7,260	lf	\$	5.00	\$	36,300
616	Allotment for Turn Lanes and Median (	Openings	1,254	sy	\$	77.00	\$	96,582
716	Moisture Conditioning		14,520	sy	\$	8.00	\$	116,160
		P	aving Const	ruction (	Cost S	ubtotal:	\$	1,424,052
			•					
Majo	or Construction Component Allowand	es**:						
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	42,722
	Pavement Markings/Markers					3%	\$	42,722
	Roadway Drainage	Standard Internal Sy	rstem			25%	\$	356,013
	Special Drainage Structures	Stream Crossing					\$	250,000
	Water	Incidental Adjustmer	nts			3%	\$	42,722
	Sewer	Incidental Adjustmer	nts			3%	\$	42,722
	Establish Turf / Erosion Control					2%	\$	28,481
	Illumination	Standard Ilumination	System			6%	\$	85,443
	Other:							
**Allo	wances based on % of Paving Construction Cos	Subtotal		Allowa	nce S	ubtotal:	\$	890,824
	Paving and Allowance Subtotal:						\$	2,314,876
	Mobilization: 5%							115,744
			Site Prep	aration:		5%	\$	115,744
			Construc	ction C	ost T	OTAL:	\$	2,547,000
			uction Conti			15%	-	382,050
	Co	nstruction Cos	t TOTAL W	// CON	TING	ENCY:	\$	2,930,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,930,000
Engineering/Survey/Testing:		20%	\$ 586,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 586,000
	Impact Fee Project	Cost TOTAL:	\$ 4,102,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-31

Name: HARDIN BLVD (7) This project consists of the construction

1,815' S OF TRINITY FALLS PKWY of a new six-lane divided greenway
Limits: TO 1,190' S OF BLOOMDALE RD arterial.

Impact Fee Class: G6D

Thoroughfare Class: Greenway Arterial

Length (If): 1,920 Service Area(s): D

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
116	Unclassified Street Excavation	23,467	су	\$	10.00	\$ 234,667
216	Lime Treated Subgrade (8") (PI<12)	15,360	sy	\$	7.00	\$ 107,520
316	9" Concrete Pavement	14,507	sy	\$	60.00	\$ 870,400
416	4" Topsoil	12,160	sy	\$	2.50	\$ 30,400
516	6" Curb & Gutter	7,680	lf	\$	5.00	\$ 38,400
616	Allotment for Turn Lanes and Median Openings	1,327	sy	\$	77.00	\$ 102,169
716	Moisture Conditioning	15,360	sy	\$	8.00	\$ 122,880

Paving Construction Cost Subtotal: \$ 1,506,436

Maj	or Construction Component Allov Item Description	/ances**:  Notes	Allowance		Item Cost	
	Traffic Control	None Anticipated	1%	\$	15,064	
	Pavement Markings/Markers	·	3%	\$	45,193	
	Roadway Drainage	Standard Internal System	25%	\$	376,609	
	Special Drainage Structures	Stream Crossing		\$	250,000	
	Water	None Anticipated	0%	\$	-	
	Sewer	None Anticipated	0%	\$	-	
	Establish Turf / Erosion Control		2%	\$	30,129	
	Illumination	Standard Ilumination System	6%	\$	90,386	
	Other:					
**Allc	wances based on % of Paving Construction	Cost Subtotal Allow	ance Subtotal:	\$	807,381	
		Paving and Allow	ance Subtotal:	\$	2,313,817	
		Mobilization	5%	\$	115,691	
	Site Preparation: 5%					
		Construction C	ost TOTAL:	\$	2,546,000	
		Construction Contingency	15%	\$	381,900	
		<b>Construction Cost TOTAL W/ CON</b>	TINGENCY:	\$	2,928,000	

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,928,000
Engineering/Survey/Testing:		20%	\$ 585,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,024,800
	Impact Fee Projec	ct Cost TOTAL:	\$ 4,538,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information:** D-32 Description: Project No.

Name: HARDIN BLVD (8) This project consists of the

1,190' S OF BLOOMDALE RD TO

Limits: 3,590' S OF BLOOMDALE RD

**Impact Fee Class:** G6D(1/3)

Thoroughfare Class: Greenway Arterial

Length (If): 2,400 Service Area(s): D

construction of two additional through lanes within the existing median of the ultimate six-lane divided greenway

arterial.

dway Construction Cost Projection					
tem Description	Quantity	Unit	Unit Price		Item Cost
Unclassified Street Excavation	6,933	су	\$ 10.00	\$	69,333
Lime Treated Subgrade (8") (PI<12)	6,667	sy	\$ 7.00	\$	46,667
9" Concrete Pavement	6,133	sy	\$ 60.00	\$	368,000
4" Topsoil	6,400	sy	\$ 2.50	\$	16,000
6" Curb & Gutter	4,800	lf	\$ 5.00	\$	24,000
Allotment for Turn Lanes and Median Openings	1,659	sy	\$ 77.00	\$	127,711
	tem Description Unclassified Street Excavation Lime Treated Subgrade (8") (PI<12) " Concrete Pavement Topsoil " Curb & Gutter Allotment for Turn Lanes and Median Openings	Item Description         Quantity           Unclassified Street Excavation         6,933           Lime Treated Subgrade (8") (PI<12)	tem Description  Quantity Unit Unclassified Street Excavation 6,933 cy Lime Treated Subgrade (8") (PI<12) 6,667 sy Concrete Pavement 6,133 sy Topsoil 6,400 sy Curb & Gutter 4,800 lf Allotment for Turn Lanes and Median Openings 1,659 sy	Item Description         Quantity         Unit         Unit Price           Unclassified Street Excavation         6,933         cy         \$ 10.00           Lime Treated Subgrade (8") (PI<12)	Item Description         Quantity         Unit         Unit Price           Unclassified Street Excavation         6,933         cy         \$ 10.00         \$           Lime Treated Subgrade (8") (PI<12)

Paving Construction Cost Subtotal: \$ 651,711

Majo						
	Item Description	Notes	Allowance		Item Cost	
	Traffic Control	Construction Phase Traffic Control	3%	\$	19,551	
	Pavement Markings/Markers		3%	\$	19,551	
	Roadway Drainage	None Anticipated	0%	\$	-	
	Special Drainage Structures	None Anticipated		\$	-	
	Water	None Anticipated	0%	\$	-	
	Sewer	None Anticipated	0%	\$	-	
	Establish Turf / Erosion Control		2%	\$	13,034	
	Illumination	None Anticipated	0%	\$	-	
	Other:					
**Allo	wances based on % of Paving Construction Co	est Subtotal Allowa	nce Subtotal:	\$	52,137	
		Paving and Allowa	nce Subtotal:	\$	703,848	
		Mobilization:	5%	\$	35,192	
	Site Preparation: 5%					
		Construction C			775,000	
		Construction Contingency:	15%	\$	116,250	
	С	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	892,000	

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 892,000
Engineering/Survey/Testing:		20%	\$ 178,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

**Project Information:** 

Kimley-Horn and Associates, Inc.

10/6/2020

2019 Roadway Impact Fee Update

Conceptual Level Project Cost Projection

**D-33** Description: Project No.

Name: HARDIN BLVD (9) This project consists of the

3,590' S OF BLOOMDALE RD TO

Limits: WILMETH RD Impact Fee Class: G6D(2/3)

Thoroughfare Class: Greenway Arterial

Length (If): 1,755 Service Area(s): D, Half construction of four additional through lanes of the ultimate six-lane divided greenway arterial. Based on the existing City Limits, the western half of the

updated:

roadway is not included in the Impact

Fee RIP

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
118	Unclassified Street Excavation	13,455	су	\$	10.00	\$ 134,550
218	Lime Treated Subgrade (8") (PI<12)	9,458	sy	\$	7.00	\$ 66,203
318	9" Concrete Pavement	8,873	sy	\$	60.00	\$ 532,350
418	4" Topsoil	9,068	sy	\$	2.50	\$ 22,669
518	6" Curb & Gutter	5,265	lf	\$	5.00	\$ 26,325
618	Allotment for Turn Lanes and Median Openings	1,213	sy	\$	77.00	\$ 93,389

Paving Construction Cost Subtotal: \$ 875,485

Maio	Major Construction Component Allowances**:							
	Item Description	Notes	Allowance	П	Item Cost			
	Traffic Control	Construction Phase Traffic Control	3%	\$	26,265			
	Pavement Markings/Markers		3%	\$	26,265			
	Roadway Drainage	Standard Internal System	25%	\$	218,871			
	Special Drainage Structures	None Anticipated		\$	-			
	Water	Incidental Adjustments	3%	\$	26,265			
	Sewer	Incidental Adjustments	3%	\$	26,265			
	Establish Turf / Erosion Control		2%	\$	17,510			
	Illumination	Standard Ilumination System	6%	\$	52,529			
	Other:							
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	393,968			
		Paving and Allowa	nce Subtotal:	\$	1,269,453			
		Mobilization:	5%	\$	63,473			
		Site Preparation:	5%	\$	63,473			
		Construction C	ost TOTAL:	\$	1,397,000			
		Construction Contingency:	15%	\$	209,550			
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	1,607,000			

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,607,000
Engineering/Survey/Testing:		20%	\$ 321,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 321,400

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information: D-34** Description: Project No. Name: HARDIN BLVD (10) This project consists of the construction of two Limits: WILMETH RD TO US HIGHWAY 380 additional through lanes within the existing median **Impact Fee Class:** G6D(1/3) of the ultimate six-lane divided greenway arterial. Thoroughfare Class: **Greenway Arterial** 

Length (If): 6,520 Service Area(s): D

Roa	adway Construction Cost Proje	ction					
No.	Item Description		Quantity	Unit	Unit Price		Item Cost
117	Unclassified Street Excavation		18,836	су	\$ 10.0	) \$	188,356
217	Lime Treated Subgrade (8") (PI<12) 18,111 sy			\$ 7.0	) \$	126,778	
317	9" Concrete Pavement		16,662	sy	\$ 60.0	) \$	999,733
417	4" Topsoil		17,387	sy	\$ 2.50	) \$	43,467
517	6" Curb & Gutter		13,040	lf	\$ 5.0	) \$	65,200
617	Allotment for Turn Lanes and Median C	penings	4,506	sy	\$ 77.0	) \$	346,949
		Р	aving Consti	ruction C	Cost Subtota	l: \$	1,770,482
Majo	or Construction Component Allowand						
	Item Description	Notes			Allowance		Item Cost
$\sqrt{}$	Traffic Control	Construction Phase	Traffic Control		_	<mark>%</mark> \$	,
	Pavement Markings/Markers					<mark>%</mark> \$	53,114
	Roadway Drainage	None Anticipated			0'	<mark>%</mark> \$	
	Special Drainage Structures	None Anticipated				\$	
	Water	None Anticipated				<mark>%</mark> \$	
	Sewer	None Anticipated				<mark>%</mark> \$	
	Establish Turf / Erosion Control					<mark>%</mark> \$	,
	Illumination	None Anticipated			0'	<mark>%</mark> \$	-
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce Subtota	l: \$	141,639
						+	4.040.555
			_		nce Subtota		· · ·
				lization:		<b>%</b> \$	,
			Site Prep			<mark>%</mark> \$	,
					ost TOTAL		, ,
			uction Conti			_	,
	Coi	nstruction Cos	t TOTAL W	// CON	TINGENCY	<b>′:</b>  \$	2,420,000

	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,420,000
Engineering/Survey/Testing:		20%	\$ 484,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. D-35

Name: COMMUNITY AVE (1) This project consists of the

TRINITY FALLS PKWY TO 1,275' S reconstruction of a two-lar

Limits: OF TRINITY FALLS PKWY

Impact Fee Class: G4D

Thoroughfare Class: Greenway Arterial

Length (If): 1,275 Service Area(s): D reconstruction of a two-lane asphalt facility to a four-lane divided greenway arterial.

Ros	adway Construction Cost Proje	ction						
	Item Description	Clion	Quantity	Unit	Unit	Price		Item Cost
107	Unclassified Street Excavation		12,467	су	\$	10.00	\$	124,667
207	07 Lime Treated Subgrade (8") (PI<12)		9,350	sy	\$	7.00	\$	65,450
307			8,783	sy	\$	55.00	\$	483,083
407			6,092	sy	\$	2.50	\$	15,229
507			5,100	lf	\$	5.00	\$	25,500
607	Allotment for Turn Lanes and Median C	Openings	749	sy	\$	72.00	\$	53,898
707	Moisture Conditioning		9,350	sy	\$	8.00	\$	74,800
		F	aving Consti	ruction (	Cost Su	ıbtotal:	\$	842,627
	Major Construction Component Allowances**:							
Majo	or Construction Component Allowand	es .						
Majo	Item Description	Notes			Allow	vance		Item Cost
Majo		_	Traffic Control	_	Allow	vance	\$	Item Cost 25,279
	Item Description	Notes	Traffic Control		Allow		\$	
√ √	Item Description Traffic Control	Notes		_	Allow	3%		25,279
√ √	Item Description Traffic Control Pavement Markings/Markers	Notes  Construction Phase			Allow	3% 3%	\$	25,279 25,279
√ √	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage	Notes  Construction Phase  Standard Internal Sy	stem		Allow	3% 3%	\$	25,279 25,279
\ \ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures	Notes  Construction Phase  Standard Internal Sy None Anticipated	stem		Allow	3% 3% 25%	\$ \$	25,279 25,279 210,657
\ \ \ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water	Notes  Construction Phase  Standard Internal Sy None Anticipated Incidental Adjustment	stem		Allow	3% 3% 25% 3%	\$ \$ \$	25,279 25,279 210,657 - 25,279
\ \ \ \ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer	Notes  Construction Phase  Standard Internal Sy None Anticipated Incidental Adjustment	stem nts		Allow	3% 3% 25% 3% 3%	\$ \$ \$ \$ \$	25,279 25,279 210,657 - 25,279 25,279
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer Establish Turf / Erosion Control	Notes  Construction Phase  Standard Internal Sy None Anticipated Incidental Adjustmental Adjustm	stem nts		Allow	3% 3% 25% 3% 3% 2%	\$ \$ \$ \$ \$ \$	25,279 25,279 210,657 - 25,279 25,279 16,853
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer Establish Turf / Erosion Control Illumination	Notes  Construction Phase  Standard Internal Sy None Anticipated Incidental Adjustmental Incidental Adjustmental Adjustmen	stem nts	Allowa	Allow	3% 3% 25% 3% 3% 2% 6%	\$ \$ \$ \$ \$ \$	25,279 25,279 210,657 - 25,279 25,279 16,853
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer Establish Turf / Erosion Control Illumination Other:	Notes  Construction Phase  Standard Internal Sy None Anticipated Incidental Adjustmental Incidental Adjustmental Adjustmen	stem nts nts		ance Su	3% 25% 3% 3% 2% 6% ubtotal:	\$ \$ \$ \$ \$ \$ \$	25,279 25,279 210,657 - 25,279 25,279 16,853 50,558
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer Establish Turf / Erosion Control Illumination Other:	Notes  Construction Phase  Standard Internal Sy None Anticipated Incidental Adjustmental Incidental Adjustmental Adjustmen	estem ents ents ents ents ents ents ents ents		ance Su	3% 25% 3% 3% 2% 6% ubtotal:	\$ \$ \$ \$ \$ \$ \$	25,279 25,279 210,657 - 25,279 25,279 16,853 50,558

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,546,000
Engineering/Survey/Testing:		20%	\$ 309,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 309,200

Site Preparation:

Construction Contingency:

Construction Cost TOTAL W/ CONTINGENCY:

**Construction Cost TOTAL:** 

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

61,090

201,600

1,344,000

1,546,000

\$

\$

Service Area(s):

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

D

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information: D-36** Description: Project No. Name: **COMMUNITY AVE (2)** This project consists of the Limits: 1,275' S OF TRINITY FALLS PKWY TO BLOOMDALE RD construction of two additional **Impact Fee Class:** G4D(1/2) lanes of the ultimate four-lane Thoroughfare Class: **Greenway Arterial** divided greenway arterial. Length (If): 2,655

Roadway Construction Cost Projection						
Item Description	Quantity	Unit	Unit Price		Item Cost	
Unclassified Street Excavation	10,030	су	\$	10.00	\$	100,300
Lime Treated Subgrade (8") (PI<12)	9,735	sy	\$	7.00	\$	68,145
8" Concrete Pavement	9,145	sy	\$	55.00	\$	502,975
4" Topsoil	3,393	sy	\$	2.50	\$	8,481
6" Curb & Gutter	5,310	lf	\$	5.00	\$	26,550
Allotment for Turn Lanes and Median Openings	779	sy	\$	72.00	\$	56,117
	Item Description Unclassified Street Excavation Lime Treated Subgrade (8") (PI<12) 8" Concrete Pavement 4" Topsoil 6" Curb & Gutter	Item DescriptionQuantityUnclassified Street Excavation10,030Lime Treated Subgrade (8") (PI<12)	Item Description         Quantity         Unit           Unclassified Street Excavation         10,030         cy           Lime Treated Subgrade (8") (PI<12)	Item Description         Quantity         Unit         Unit           Unclassified Street Excavation         10,030         cy         \$           Lime Treated Subgrade (8") (PI<12)	Item Description         Quantity         Unit         Unit Price           Unclassified Street Excavation         10,030         cy         \$ 10.00           Lime Treated Subgrade (8") (PI<12)	Item Description         Quantity         Unit         Unit Price           Unclassified Street Excavation         10,030         cy         \$ 10.00         \$           Lime Treated Subgrade (8") (PI<12)

Paving Construction Cost Subtotal: \$ 762,568

Majo	Major Construction Component Allowances**:						
	Item Description	Notes	Allowance		Item Cost		
	Traffic Control	Construction Phase Traffic Control	3%	\$	22,877		
	Pavement Markings/Markers		3%	\$	22,877		
	Roadway Drainage	Standard Internal System	25%	\$	190,642		
	Special Drainage Structures	None Anticipated		\$	-		
	Water	Incidental Adjustments	3%	\$	22,877		
	Sewer	Incidental Adjustments	3%	\$	22,877		
	Establish Turf / Erosion Control		2%	\$	15,251		
	Illumination	Standard Ilumination System	6%	\$	45,754		
	Other:						
**Allo	**Allowances based on % of Paving Construction Cost Subtotal Allowance Subtotal:						
	Paving and Allowance Subtotal:						
	Mobilization: 5%						
	Site Preparation: 5%						
	Construction Cost TOTAL:						
		Construction Contingency:			182,550		
	С	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	1,400,000		

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,400,000
Engineering/Survey/Testing:		20%	\$ 280,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 280,000
·	\$ 1,960,000		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Roadway Construction Cost Projection** 

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information:

Name:

COMMUNITY AVE (3)

Limits:

BLOOMDALE RD TO 2,305' S OF BLOOMDALE RD

M4U(1/2)

Description:

Project No.

This project consists of the construction of two additional lanes of the ultimate four-lane

Thoroughfare Class: Minor Arterial

Length (If): 2,305 Service Area(s): D construction of two additional lanes of the ultimate four-lane undivided minor arterial.

\$

\$

33,111

109,350

729,000

839,000

No.	Item Description		Quantity	Unit	Unit	Price	Item Cost
104	Unclassified Street Excavation		6,147	су	\$	10.00	\$ 61,467
204	Lime Treated Subgrade (8") (PI<12)		6,019	sy	\$	7.00	\$ 42,130
304	8" Concrete Pavement		5,891	sy	\$	55.00	\$ 323,981
404	4" Topsoil		2,433	sy	\$	2.50	\$ 6,083
504	6" Curb & Gutter		4,610	lf	\$	5.00	\$ 23,050
		Р	aving Constr	uction C	Cost S	ubtotal:	\$ 456,710
Majo	or Construction Component Allowanc	es**:					
	Item Description	Notes			Allo	wance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 13,701
	Pavement Markings/Markers					3%	\$ 13,701
	Roadway Drainage	Standard Internal Sy	stem			25%	\$ 114,178
	Special Drainage Structures	None Anticipated					\$ -
	Water	Incidental Adjustmer	nts			3%	\$ 13,701
	Sewer	Incidental Adjustmer	nts			3%	\$ 13,701
	Establish Turf / Erosion Control					2%	\$ 9,134
	Illumination	Standard Ilumination	System			6%	\$ 27,403
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce S	ubtotal:	\$ 205,520
			Paving and				662,230
	Mobilization: 5%						\$ 33,111

Impact Fee Project Cost Sum			
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 839,000
Engineering/Survey/Testing:		20%	\$ 167,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 167,800
	Impact Foo Pr	oject Cost TOTAL:	\$ 1,174,600


Site Preparation:

Construction Contingency:

Construction Cost TOTAL W/ CONTINGENCY:

**Construction Cost TOTAL:** 

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

Roadway Improvements - Service Area E

	Costing					Percent in		Cost in
#	Class	Project	Limits	1	otal Cost	Service Area	Se	rvice Area
E-1	P6D(1/3)	BLOOMDALE RD (12)	US HIGHWAY 75 TO REDBUD BLVD	\$	955,200	100%	\$	955,200
E-2	P6D(2/3)	BLOOMDALE RD (13)	REDBUD BLVD TO AIRPORT DR	\$	3,361,400	100%	\$	3,361,400
E-3	M6D(1/3)	WILMETH RD (10)	US HIGHWAY 75 TO 2,570' E OF REDBUD BLVD	\$	1,935,600	100%	\$	1,935,600
E-4	M6D(2/3)	WILMETH RD (11)	2,570' E OF REDBUD BLVD TO STATE HIGHWAY 5	\$	2,608,200	100%	\$	2,608,200
E-5	M6D	WILMETH RD (12)	STATE HIGHWAY 5 TO 2,100' E OF SH 5	\$	5,068,500	100%	\$	5,068,500
E-6	M6D	WILMETH RD (13)	2,100' E OF SH 5 TO 980' W OF AIRPORT DR	\$	2,804,200	100%	\$	2,804,200
E-7	M6D	WILMETH RD (14)	980' W OF AIRPORT DR TO 235' E OF AIRPORT DR	\$	3,417,400	50%	\$	1,708,700
E-8	M6D	WILMETH RD (15)	1,150' W OF FM 2933 TO 400' E OF FM 2933	\$	3,229,800	50%	\$	1,614,900
E-9	M4D	REDBUD BLVD (1)	BLOOMDALE RD TO 2,930' S OF BLOOMDALE RD	\$	650,000	100%	\$	650,000
E-10	M4D(1/2)	REDBUD BLVD (2)	2,930' S OF BLOOMDALE RD TO WILMETH RD	\$	852,600	100%	\$	852,600
E-11	M6D	LAUD HOWELL PKWY (9)	US HIGHWAY 75 TO 2,620' S OF US HIGHWAY 75	\$	3,909,500	50%	\$	1,954,750
E-12	M6D	LAUD HOWELL PKWY (10)	2,620' S OF US HIGHWAY 75 TO BLOOMDALE RD	\$	1,876,700	100%	\$	1,876,700
E-13	P6D	LAUD HOWELL PKWY (11)	BLOOMDALE RD TO STATE HIGHWAY 5	\$	861,000	100%	\$	861,000
E-14	M6D	STATE HIGHWAY 5 (1)	4,700' N OF AIRPORT DR TO 3,995' N OF AIRPORT DR	\$	695,100	50%	\$	347,550
E-15	M6D	STATE HIGHWAY 5 (2)	1,915' N OF AIRPORT DR TO US HIGHWAY 380	\$	13,994,400	100%	\$	13,994,400
E-16	P6D	AIRPORT DR (1)	STATE HIGHWAY 5 TO 4,070 S OF STATE HIGHWAY 5	\$	9,379,050	100%	\$	9,379,050
E-17	P6D	AIRPORT DR (2)	WILMETH RD TO WOODLAWN RD (N)	\$	6,582,850	100%	\$	6,582,850
E-18	P6D	AIRPORT DR (3)	WOODLAWN RD (N) TO WOODLAWN RD (S)	\$	3,648,400	100%	\$	3,648,400
E-19	P6D	AIRPORT DR (4)	WOODLAWN RD (S) TO US HIGHWAY 380	\$	8,952,800	100%	\$	8,952,800
E-20	P6D(1/3)	UNNAMED C (1)	410' E OF STATE HIGHWAY 5 TO 3,010' E OF STATE HIGHWAY 5	\$	986,400	100%	\$	986,400
E-21	P6D	UNNAMED C (2)	WILMETH RD TO 2,615' S OF WILMETH RD	\$	2,806,300	50%	\$	1,403,150
11		Interchange Signals	US HIGHWAY 75 & LAUD HOWELL PKWY	\$	600,000	50%	\$	300,000
19		Interchange Signals	US HIGHWAY 75 & BLOOMDALE RD	\$	600,000	50%	\$	300,000
20		Signal	BLOOMDALE RD & REDBUD BLVD	\$	300,000	100%	\$	300,000
21	uc	Signal	LAUD HOWELL PKWY & BLOOMDALE RD	\$	300,000	100%	\$	300,000
22	actie	Signal Mod	STATE HIGHWAY 5 & LAUD HOWELL PKWY	\$	150,000	100%	\$	150,000
28	Intersection	Signal	WILMETH RD & REDBUD BLVD	\$	300,000	100%	\$	300,000
29	Ĕ	Signal Mod	STATE HIGHWAY 5 & WILMETH RD	\$	150,000	100%	\$	150,000
30	1	Signal	AIRPORT DR & WILMETH RD	\$	300,000	50%	\$	150,000
31	1	Signal	UNNAMED C & WILMETH RD	\$	300,000	50%	\$	150,000
41	1	Signal Mod	US HIGHWAY 380 & AIRPORT DR	\$	150,000	50%	\$	75,000
		g		\$	81,725,400		\$	73,721,350

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

lanes within the existing median of the

ultimate six-lane divided principal

arterial.

updated: 10/6/2020

Project Information: Description: Project No. E-

Name: BLOOMDALE RD (12) This project consists of the

Limits: US HIGHWAY 75 TO REDBUD BLVD construction of two additional through

Impact Fee Class: P6D(1/3)
Thoroughfare Class: Principal Arterial

Length (If): 2,520

Service Area(s): E

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
114	Unclassified Street Excavation	7,840	су	\$	10.00	\$ 78,400
214	Lime Treated Subgrade (8") (PI<12)	7,560	sy	\$	7.00	\$ 52,920
314	9" Concrete Pavement	7,000	sy	\$	60.00	\$ 420,000
414	4" Topsoil	2,240	sy	\$	2.50	\$ 5,600
514	6" Curb & Gutter	5,040	lf	\$	5.00	\$ 25,200

Paving Construction Cost Subtotal: \$ 582,120

Major Construction Component Allowances**:							
	Item Description	Notes	Allowance		Item Cost		
	Traffic Control	Construction Phase Traffic Control	3%	\$	17,464		
	Pavement Markings/Markers		3%	\$	17,464		
	Roadway Drainage	None Anticipated	0%	\$	-		
	Special Drainage Structures	None Anticipated		\$	-		
	Water	None Anticipated	0%	\$	-		
	Sewer	None Anticipated	0%	\$	-		
	Establish Turf / Erosion Control		2%	\$	11,642		
	Illumination	None Anticipated	0%	\$	-		
	Other:						
**Allo	**Allowances based on % of Paving Construction Cost Subtotal Allowance Subtotal:						
		Paving and Allow	ance Subtotal:	\$	628,690		
		Mobilization			31,434		
		Site Preparation	5%	\$	31,434		
		Construction C	ost TOTAL:	\$	692,000		
		Construction Contingency	15%	\$	103,800		
	Со	nstruction Cost TOTAL W/ CON	TINGENCY:	\$	796,000		

Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	796,000
Engineering/Survey/Testing:		20%	\$	159,200
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-
34.	Impact Fee Project	Cost TOTAL:	•	955,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. E-2

Name: BLOOMDALE RD (13) This project consists of the construction of four additional through lanes of the ultimate six-lane

Impact Fee Class: P6D(2/3) divided principal arterial.

Thoroughfare Class: Principal Arterial

Length (If): 2,695 Service Area(s): E

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	nit Price	Item Cost
115	Unclassified Street Excavation	24,554	су	\$	10.00	\$ 245,544
215	Lime Treated Subgrade (8") (PI<12)	15,721	sy	\$	7.00	\$ 110,046
315	9" Concrete Pavement	14,823	sy	\$	60.00	\$ 889,350
415	4" Topsoil	9,133	sy	\$	2.50	\$ 22,833
515	6" Curb & Gutter	8,085	lf	\$	5.00	\$ 40,425

Paving Construction Cost Subtotal: \$ 1,308,198

Mai					
iviaj	or Construction Component Allowa Item Description	Notes	Allowance		Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$	39,246
	Pavement Markings/Markers		3%	\$	39,246
	Roadway Drainage	Standard Internal System	25%	\$	327,049
	Special Drainage Structures None Anticipated				-
	Water	Incidental Adjustments	3%	\$	39,246
	Sewer	Incidental Adjustments	3%	\$	39,246
	Establish Turf / Erosion Control		2%	\$	26,164
	Illumination	Standard Ilumination System	6%	\$	78,492
	Other:				
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	588,689
		Paving and Allowa	nce Subtotal:	\$	1,896,887
		Mobilization:	5%	\$	94,844
		Site Preparation:	5%	\$	94,844
		Construction C	ost TOTAL:	\$	2,087,000
		Construction Contingency:	15%	\$	313,050
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	2,401,000

Impact Fee Project Cost Sum Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,401,000
Engineering/Survey/Testing:		20%	\$ 480,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 480,200
	Impact Fee Proje	ct Cost TOTAL:	\$ 3,361,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information:	Description:	Project No.	E-3

Name: WILMETH RD (10) This project consists of the

Limits: US HIGHWAY 75 TO 2,570' E OF REDBUD BLVD construction of two additional through

Impact Fee Class: M6D(1/3) Ianes within the existing median of the Thoroughfare Class: Major Arterial ultimate six-lane divided major arterial.

Length (If): 4,105
Service Area(s): E

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
111	Unclassified Street Excavation	12,771	су	\$	10.00	\$ 127,711
211	Lime Treated Subgrade (8") (PI<12)	12,315	sy	\$	7.00	\$ 86,205
311	9" Concrete Pavement	11,403	sy	\$	60.00	\$ 684,167
411	4" Topsoil	3,649	sy	\$	2.50	\$ 9,122
511	6" Curb & Gutter	8,210	lf	\$	5.00	\$ 41,050

Paving Construction Cost Subtotal: \$ 948,255

Maio	or Construction Component Allowand	:es**:			
Maj	Item Description	Notes	Allowance		Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$	28,448
	Pavement Markings/Markers		3%	\$	28,448
	Roadway Drainage	None Anticipated	0%	\$	-
	Special Drainage Structures	Stream Crossing		\$	250,000
	Water	None Anticipated	0%	\$	-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	18,965
	Illumination	None Anticipated	0%	\$	-
	Other:				
**Allc	\$	325,860			
		Daving and Allawa	naa Cubtatali	¢	4 074 445
		Paving and Allowa			1,274,115
		Mobilization:		L	63,706
		Site Preparation:		_	63,706
		Construction C	ost TOTAL:	\$	1,402,000
		Construction Contingency:	15%	\$	210,300
	Со	nstruction Cost TOTAL W/ CON	TINGENCY:	\$	1,613,000

Cost
,613,000
322,600
-
-
-
4

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: E-4 Description: Project No. Name: WILMETH RD (11) This project consists of the

Limits: 2,570' E OF REDBUD BLVD TO STATE HIGHWAY 5

construction of four additional **Impact Fee Class:** M6D(2/3) through lanes of the ultimate Thoroughfare Class: Major Arterial six-lane divided major arterial.

Length (If): 2,145 Service Area(s): Ε

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
112	Unclassified Street Excavation	17,160	су	\$	10.00	\$ 171,600
212	Lime Treated Subgrade (8") (PI<12)	12,513	sy	\$	7.00	\$ 87,588
312	9" Concrete Pavement	11,798	sy	\$	60.00	\$ 707,850
412	4" Topsoil	6,554	sy	\$	2.50	\$ 16,385
512	6" Curb & Gutter	6,435	lf	\$	5.00	\$ 32,175

Paving Construction Cost Subtotal: \$ 1,015,598

Majo					
	Item Description	Notes	Allowance		Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$	30,468
	Pavement Markings/Markers		3%	\$	30,468
	Roadway Drainage	Standard Internal System	25%	\$	253,899
	Special Drainage Structures	None Anticipated		\$	-
	Water	Incidental Adjustments	3%	\$	30,468
	Sewer	Incidental Adjustments	3%	\$	30,468
	Establish Turf / Erosion Control		2%	\$	20,312
	Illumination	Standard Ilumination System	6%	\$	60,936
	Other:				
**Allo	wances based on % of Paving Construction C	ost Subtotal Allowa	nce Subtotal:	\$	457,019
				_	
		Paving and Allowa			1,472,617
		Mobilization:		*	73,631
		Site Preparation:		-	73,631
		Construction C		\$	1,620,000
		Construction Contingency:	15%	\$	243,000
		Construction Cost TOTAL W/ CON	FINGENCY:	\$	1,863,000

Impact Fee Project Cost Sumi	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,863,000
Engineering/Survey/Testing:		20%	\$ 372,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 372,600
	Impact Fee Pi	roject Cost TOTAL:	\$ 2,608,200

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. E-5

Name: WILMETH RD (12) This project consists of the Limits: STATE HIGHWAY 5 TO 2,100' E OF SH 5 construction of a new six-lane

Impact Fee Class: M6D divided major arterial.

Thoroughfare Class: Major Arterial Length (If): 2,100

Length (If): 2,1 Service Area(s): E

Roa	dway Construction Cost Projection									
No.	Item Description	Quantity	Unit	Unit Price		Unit Price		Unit Price		Item Cost
109	Unclassified Street Excavation	23,333	су	\$	10.00	\$ 233,333				
209	Lime Treated Subgrade (8") (PI<12)	18,200	sy	\$	7.00	\$ 127,400				
309	9" Concrete Pavement	17,267	sy	\$	60.00	\$ 1,036,000				
409	4" Topsoil	8,167	sy	\$	2.50	\$ 20,417				
509	6" Curb & Gutter	8,400	lf	\$	5.00	\$ 42,000				
609	Allotment for Turn Lanes and Median Openings	1,282	sy	\$	77.00	\$ 98,681				
709	Moisture Conditioning	18,200	sy	\$	8.00	\$ 145,600				

Paving Construction Cost Subtotal: \$ 1,703,431

Major Construction Component Allowances**:								
	Item Description	Notes	Allowance		Item Cost			
	Traffic Control	None Anticipated	1%	\$	17,034			
	Pavement Markings/Markers		3%	\$	51,103			
	Roadway Drainage	Standard Internal System	25%	\$	425,858			
	Special Drainage Structures	Stream Crossing		\$	250,000			
	Water	None Anticipated	0%	\$	-			
	Sewer	None Anticipated	0%	\$	-			
	Establish Turf / Erosion Control		2%	\$	34,069			
	Illumination	Standard Ilumination System	6%	\$	102,206			
	Other:							
**Allo	**Allowances based on % of Paving Construction Cost Subtotal Allowance Subtotal:							
		Paving and Allowa	nce Subtotal:	\$	2,583,700			
		Mobilization:	5%	\$	129,185			
		Site Preparation:	5%	\$	129,185			
		Construction C	ost TOTAL:	\$	2,843,000			
		Construction Contingency:	15%	\$	426,450			
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	3,270,000			

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,270,000
Engineering/Survey/Testing:		20%	\$ 654,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,144,500

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. E-6

Name: WILMETH RD (13) This project consists of the

Limits: 2,100' E OF SH 5 TO 980' W OF AIRPORT DR reconstruction of a two

Impact Fee Class: M6D

Thoroughfare Class: Major Arterial

Length (If): 1,345 Service Area(s): E reconstruction of a two-lane asphalt facility to a six-lane divided major

arterial.

Roa	adway Construction Cost Projection																				
No.	Item Description	Quantity	Unit	Unit Price		Unit Price		Unit Price		Unit Price		Unit Price		Unit Price		Unit Price		Unit Price			Item Cost
109	Unclassified Street Excavation	14,944	су	\$	10.00	\$	149,444														
209	Lime Treated Subgrade (8") (PI<12)	11,657	sy	\$	7.00	\$	81,597														
309	9" Concrete Pavement	11,059	sy	\$	60.00	\$	663,533														
409	4" Topsoil	5,231	sy	\$	2.50	\$	13,076														
509	6" Curb & Gutter	5,380	lf	\$	5.00	\$	26,900														
609	Allotment for Turn Lanes and Median Openings	821	sy	\$	77.00	\$	63,203														
709	Moisture Conditioning	11,657	sy	\$	8.00	\$	93,253														
Boying Construction Cost Subtataly \$																					

Paving Construction Cost Subtotal: \$ 1,091,007

Major Construction Component Allowances**:								
Item Description	Notes	Allowance		Item Cost				
√ Traffic Control	Construction Phase Traffic Control	3%	\$	32,730				
√ Pavement Markings/Markers		3%	\$	32,730				
$\sqrt{}$ Roadway Drainage	Standard Internal System	25%	\$	272,752				
Special Drainage Structures	None Anticipated		\$	-				
$\sqrt{}$ Water	Incidental Adjustments	3%	\$	32,730				
√ Sewer	Incidental Adjustments	3%	\$	32,730				
√ Establish Turf / Erosion Control		2%	\$	21,820				
$\sqrt{}$ Illumination	Standard Ilumination System	6%	\$	65,460				
Other:								
**Allowances based on % of Paving Construction	**Allowances based on % of Paving Construction Cost Subtotal Allowance Subtotal:							
	Paving and Allowa	nce Subtotal:	\$	1,581,960				
	Mobilization:	5%	\$	79,098				
	Site Preparation:	5%	\$	79,098				
	Construction C	ost TOTAL:	\$	1,741,000				
	Construction Contingency:	15%	\$	261,150				
	Construction Cost TOTAL W/ CON	TINGENCY:	\$	2,003,000				

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,003,000
Engineering/Survey/Testing:		20%	\$ 400,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 400,600

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No. E-7					
Name:	WILMETH RD (14) 980' W OF AIRPORT DR TO 235' E		his project consists of the econstruction of a two-lane asphalt					
Limits: Impact Fee Class: Thoroughfare Class:	OF AIRPORT DR M6D Major Arterial	fa a	facility to a six-lane divided major arterial. Based on the existing City Limits, the northern half of the roadway					
Length (If): Service Area(s):	1,215 E, Half	is	s not included in the Impact Fee RIP.					

Pos	adway Construction Cost Brain	ction						
	adway Construction Cost Proje Item Description	Clion	Quantity	Unit	Un	it Price		Item Cost
109	Unclassified Street Excavation		13,500	су	\$	10.00	\$	135,000
209	09 Lime Treated Subgrade (8") (PI<12) 10,5			sy	\$	7.00	\$	73,710
309	9" Concrete Pavement		9,990	sy	\$	60.00	\$	599,400
409	4" Topsoil		4,725	sy	\$	2.50	\$	11,813
509	6" Curb & Gutter		4,860	lf	\$	5.00	\$	24,300
	Allotment for Turn Lanes and Median (	Openings	741	sy	\$	77.00	\$	57,094
709	Moisture Conditioning		10,530	sy	\$	8.00	\$	84,240
		P	Paving Const	ruction (	Cost S	Subtotal:	\$	985,556
Majo	or Construction Component Allowand	es**:						
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	29,567
	Pavement Markings/Markers					3%	\$	29,567
	Roadway Drainage	Standard Internal Sy	rstem			25%	\$	246,389
	Special Drainage Structures	None Anticipated					\$	-
	Water	Incidental Adjustmer	nts			3%	\$	29,567
	Sewer	Incidental Adjustmer	nts			3%	\$	29,567
	Establish Turf / Erosion Control					2%	\$	19,711
	Illumination	Standard Ilumination	System			6%	\$	59,133
	Other:	Railroad Crossing					\$	500,000
**Allo	wances based on % of Paving Construction Cost	Subtotal	•	Allowa	nce S	Subtotal:	\$	943,500
			Paving an	d Allowa	nce S	Subtotal:	\$	1,929,057
			Mobi	lization:		5%	\$	96,453
			Site Prep	aration:		5%	\$	96,453
			Construc	ction C	ost	TOTAL:	\$	2,122,000
			uction Conti			15%	_	318,300
	Construction Cost TOTAL W/ CONTINGENCY:							2,441,000

Impact Fee Project Cost Summ	nary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	2,441,000
Engineering/Survey/Testing:		20%	\$	488,200
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	Existing Alignment	20%	\$	488,200
Impact Fee Project Cost TOTAL:				3,417,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No. E-8
Name:	WILMETH RD (15) 1,150' W OF FM 2933 TO 400' E OF		This project consists of the reconstruction of a two-lane asphalt
Limits: Impact Fee Class: Thoroughfare Class:	FM 2933 M6D Major Arterial		facility to a six-lane divided major arterial. Based on the existing City Limits, the northern half of the roadway
Length (If): Service Area(s):	1,550 E, Half		is not included in the Impact Fee RIP.

Roa	adway Construction Cost Proje	ction						
	Item Description		Quantity	Unit	Un	it Price		Item Cost
109	Unclassified Street Excavation		17,222	су	\$	10.00	\$	172,222
209	Lime Treated Subgrade (8") (PI<12)		13,433	sy	\$	7.00	\$	94,033
309	9" Concrete Pavement		12,744	sy	\$	60.00	\$	764,667
409	4" Topsoil		6,028	sy	\$	2.50	\$	15,069
509	6" Curb & Gutter		6,200	lf	\$	5.00	\$	31,000
609	Allotment for Turn Lanes and Median C	Openings	946	sy	\$	77.00	\$	72,836
709	Moisture Conditioning	-	13,433	sy	\$	8.00	\$	107,467
		F	Paving Const	ruction (	Cost	Subtotal:	\$	1,257,294
Majo	or Construction Component Allowand	es**:						
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	37,719
	Pavement Markings/Markers					3%	\$	37,719
	Roadway Drainage	Standard Internal Sy	rstem			25%	\$	314,323
	Special Drainage Structures	None Anticipated					\$	-
	Water	Incidental Adjustmer	nts			3%	\$	37,719
	Sewer	Incidental Adjustmer	nts			3%	\$	37,719
	Establish Turf / Erosion Control					2%	\$	25,146
	Illumination	Standard Ilumination	System			6%	\$	75,438
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal	<del></del>	Allowa	nce :	Subtotal:	\$	565,782
Paving and Allowance Subtotal:						\$	1,823,076	
	Mobilization: 5%					\$	91,154	
	Site Preparation: 5%					\$	91,154	
Construction Cost TOTAL:						\$	2,006,000	
			ruction Conti			15%	_	300,900
	Construction Cost TOTAL W/ CONTINGENCY:						\$	2,307,000

Impact Fee Project Cost Sumr	nary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	2,307,000
Engineering/Survey/Testing:		20%	\$	461,400
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	Existing Alignment	20%	\$	461,400
Impact Fee Project Cost TOTAL:				3,229,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	E-9
Name:	REDBUD BLVD (1)		This completed pro	oject
Limits:	BLOOMDALE RD TO 2,930' S OF BLO	OMDALE RD	consists of the cor	nstruction of
Impact Fee Class:	M4D		a four-lane divided	l minor
Thoroughfare Class:	Minor Arterial		arterial. The City c	ontributed
Length (If):	2,930		approximatley \$65	
Service Area(s):	E		eligible funds from	•

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 650,000
	\$ 650,000		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information: Description: Project No. E-10

Name: REDBUD BLVD (2) This project consists of the

Limits: 2,930' S OF BLOOMDALE RD TO WILMETH RD construction of two additional lanes of

Impact Fee Class: M4D(1/2) the ultimate four-lane divided minor

Thoroughfare Class: Minor Arterial arterial.

Length (If): 1,645 Service Area(s): E

Roa	dway Construction Cost Projection							
No.	Item Description	Quantity	Unit	Unit Price		Unit Price It		Item Cost
106	Unclassified Street Excavation	4,752	су	\$	10.00	\$	47,522	
206	Lime Treated Subgrade (8") (PI<12)	4,569	sy	\$	7.00	\$	31,986	
306	8" Concrete Pavement	4,204	sy	\$	55.00	\$	231,214	
406	4" Topsoil	1,736	sy	\$	2.50	\$	4,341	
506	6" Curb & Gutter	3,290	lf	\$	5.00	\$	16,450	

Paving Construction Cost Subtotal: \$ 331,513

Majo	Major Construction Component Allowances**:							
	Item Description	Notes	Allowance		Item Cost			
	Traffic Control	Construction Phase Traffic Control	3%	\$	9,945			
	Pavement Markings/Markers		3%	\$	9,945			
	Roadway Drainage	Standard Internal System	25%	\$	82,878			
	Special Drainage Structures	None Anticipated		\$	-			
	Water	Incidental Adjustments	3%	\$	9,945			
	Sewer	Incidental Adjustments	3%	\$	9,945			
	Establish Turf / Erosion Control		2%	\$	6,630			
	Illumination	Standard Ilumination System	6%	\$	19,891			
	Other:							
**Allo	wances based on % of Paving Construction C	ost Subtotal Allowa	nce Subtotal:	\$	149,181			
-		Daving and Allana		•	400.004			
		Paving and Allowa		i	480,694			
		Mobilization: Site Preparation:		\$	24,035			
	\$	24,035						
	\$	529,000						
		Construction Contingency:		\$	79,350			
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	609,000			

Impact Fee Project Cost Sum	mary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	609,000
Engineering/Survey/Testing:		20%	\$	121,800
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	Existing Alignment	20%	\$	121,800
Impact Fee Project Cost TOTAL:				852,600

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc. updated: 10/6/2020

Project Information	n:	Description:	Project No. E-11
Name:	LAUD HOWELL PKWY (9) US HIGHWAY 75 TO 2,620' S OF US		This project consists of the reconstruction of a two-lane asphalt
Limits: Impact Fee Class:	HIGHWAY 75 M6D		facility to a six-lane divided major
Thoroughfare Class:	Major Arterial		arterial. Based on the existing City Limits, the eastern half of the roadway
Length (If):	2,620		is not included in the Impact Fee RIP.
Service Area(s):	E, Half		

Roa	adway Construction Cost Projec	ction						
No.	Item Description		Quantity	Unit	Uni	t Price		Item Cost
109	Unclassified Street Excavation		14,556	су	\$	15.00	\$	218,333
209	Lime Treated Subgrade (8") (PI<12)		22,707	sy	\$	7.00	\$	158,947
309	4" TY D HMAC Underlayment		21,542	sy	\$	5.00	\$	107,711
409	9" Concrete Pavement		21,542	sy	\$	60.00	\$	1,292,533
509	4" Topsoil		10,189	sy	\$	4.00	\$	40,756
609	6" Curb & Gutter		10,480	lf	\$	5.00	\$	52,400
709	Allotment for Turn Lanes and Median O	penings	1,599	sy	\$	87.00	\$	139,105
			Paving Consti	ruction (	Cost S	ubtotal:	\$	2,009,785
Majo	or Construction Component Allowance							
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	60,294
	Pavement Markings/Markers					3%	\$	60,294
	Roadway Drainage					25%	\$	502,446
	Special Drainage Structures	Bridge					\$	1,500,000
	Water	Incidental Adjustmer	nts			3%	\$	60,294
	Sewer	Incidental Adjustmer	nts			3%	\$	60,294
	Establish Turf / Erosion Control					2%	\$	40,196
	Illumination	Standard Ilumination	System			6%	\$	120,587
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce S	ubtotal:	\$	2,404,403
Paving and Allowance Subtotal:							\$	4,414,188
	Mobilization: 5%					\$	220,709	
	Site Preparation: 5%					\$	220,709	
Construction Cost TOTAL:						\$	4,856,000	
	-		truction Conti			15%	,	728,400
	Construction Cost TOTAL W/ CONTINGENCY:					\$	5,585,000	

Impact Fee Project Cost Summa	nry		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 5,585,000
Engineering/Survey/Testing:		20%	\$ 1,117,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 1,117,000
Impact F	\$ 3,909,500		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

M6D

709 Allotment for Turn Lanes and Median Openings

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

 Project Information:
 Description:
 Project No.
 E-12

 Name:
 LAUD HOWELL PKWY (10)
 This project consists of the

Limits: 2,620' S OF US HIGHWAY 75 TO BLOOMDALE RD

reconstruction of a two-lane asphalt facility to a six-lane

Thoroughfare Class: Major Arterial div

divided major arterial.

5.00

87.00

\$

\$

32,700

86,808

Length (If): 1,635 Service Area(s): E

Impact Fee Class:

609 6" Curb & Gutter

**Roadway Construction Cost Projection** No. Item Description Quantity Unit **Unit Price Item Cost** 109 Unclassified Street Excavation 9,083 \$ 15.00 \$ 136,250 су 209 Lime Treated Subgrade (8") (PI<12) 14,170 \$ 7.00 \$ 99,190 sy 309 4" TY D HMAC Underlayment 13,443 \$ 5.00 \$ 67,217 sy 409 9" Concrete Pavement 13,443 \$ 60.00 \$ 806,600 sy 509 4" Topsoil 6,358 \$ 4.00 \$ 25,433 sy

6,540

998

Paving Construction Cost Subtotal: \$ 1,254,198

\$

\$

lf

sy

	i aving conduction	ocor oubrotun	•	1,204,100					
Major Construction Con	Major Construction Component Allowances**:								
Item Description	Notes	Allowance	П	Item Cost					
√ Traffic Control	Construction Phase Traffic Control	3%	\$	37,626					
√ Pavement Markings.	/Markers	3%	\$	37,626					
√ Roadway Drainage		25%	\$	313,549					
√ Special Drainage St	ructures Stream Crossing		\$	300,000					
√ Water	Incidental Adjustments	3%	\$	37,626					
√ Sewer	Incidental Adjustments	3%	\$	37,626					
√ Establish Turf / Eros	sion Control	2%	\$	25,084					
√ Illumination	Standard Ilumination System	6%	\$	75,252					
Other:									
**Allowances based on % of Pa	aving Construction Cost Subtotal Allo	wance Subtotal:	\$	864,389					
	<del>-</del>	wa <u>nce Subtotal:</u>		2,118,587					
	Mobilization			105,929					
	Site Preparation		,	105,929					
	Construction Cost TOTAL:								
	Construction Contingen	cy: 15%	\$	349,650					
	Construction Cost TOTAL W/ CO	ONTINGENCY:	\$	2,681,000					

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,681,000
Engineering/Survey/Testing:		20%	\$ 536,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 536,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. E-13

Name: LAUD HOWELL PKWY (11) This project consists of the

Limits: BLOOMDALE RD TO STATE HIGHWAY 5 reconstruction of a two-lane asphalt

Impact Fee Class: P6D facility to a six-lane divided principal

Thoroughfare Class: Principal Arterial arterial.

Length (If): 870 Service Area(s): E

Roa	dway Construction Cost Projection													
No.	Item Description	Quantity	Unit	Unit Price		Unit Price		Unit Price		Unit Price			Item Cost	
113	Unclassified Street Excavation	4,833	су	\$	15.00	\$	72,500							
213	Lime Treated Subgrade (8") (PI<12)	7,540	sy	\$	7.00	\$	52,780							
313	4" TY D HMAC Underlayment	7,153	sy	\$	5.00	\$	35,767							
413	9" Concrete Pavement	7,153	sy	\$	60.00	\$	429,200							
513	4" Topsoil	3,963	sy	\$	4.00	\$	15,853							
613	6" Curb & Gutter	3,480	lf	\$	5.00	\$	17,400							
713	Allotment for Turn Lanes and Median Openings	531	sy	\$	87.00	\$	46,191							
	Desires Construction Cost Cultistate A													

Paving Construction Cost Subtotal: \$ 669,691

Maj				
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$ 20,091
	Pavement Markings/Markers		3%	\$ 20,091
	Roadway Drainage		25%	\$ 167,423
	Special Drainage Structures	None Anticipated		\$ -
	Water	Incidental Adjustments	3%	\$ 20,091
	Sewer	Incidental Adjustments	3%	\$ 20,091
	Establish Turf / Erosion Control		2%	\$ 13,394
	Illumination	Standard Ilumination System	6%	\$ 40,181
	Other:			
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$ 301,361
		Paving and Allowa	nce Subtotal:	\$ 971,052
		Mobilization:	5%	\$ 48,553
		Site Preparation:	5%	\$ 48,553
		Construction C	ost TOTAL:	\$ 1,069,000
		Construction Contingency:	15%	\$ 160,350
	Co	nstruction Cost TOTAL W/ CON	TINGENCY:	\$ 1,230,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,230,000
Engineering/Survey/Testing:		20%	\$ 246,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 246,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No. E-14
Name:	STATE HIGHWAY 5 (1) 4,700' N OF AIRPORT DR TO 3,995'		This project consists of the reconstruction of a two-lane asphalt
Limits:	N OF AIRPORT DR		facility to a six-lane divided major
Impact Fee Class:	M6D		arterial. Based on the existing City
Thoroughfare Class:	Major Arterial		Limits, the western half of the roadway
Length (If):	705		is not included in the Impact Fee RIP.
Service Area(s):	E, Half		

	adway Construction Cost Proje	ction										
No.	Item Description		Quantity	Unit		it Price		Item Cost				
109	Unclassified Street Excavation		3,917	су	\$	15.00	\$	58,750				
209	Lime Treated Subgrade (8") (PI<12)		6,110	sy	\$	7.00	\$	42,770				
309	4" TY D HMAC Underlayment		5,797	sy	\$	5.00	\$	28,983				
409	9" Concrete Pavement		5,797	sy	\$	60.00	\$	347,800				
509	4" Topsoil		2,742	sy	\$	4.00	\$	10,967				
609	6" Curb & Gutter		2,820	lf	\$	5.00	\$	14,100				
709	Allotment for Turn Lanes and Median C	penings	430	sy	\$	87.00	\$	37,431				
		P	Paving Consti	ruction (	Cost	Subtotal:	\$	540,801				
Majo	or Construction Component Allowand	es**:										
	Item Description	Notes			All	owance		Item Cost				
	Traffic Control	Construction Phase	Traffic Control			3%	\$	16,224				
	Pavement Markings/Markers					3%	\$	16,224				
	Roadway Drainage					25%	\$	135,200				
	Special Drainage Structures	None Anticipated					\$	-				
	Water	Incidental Adjustmer	nts			3%	\$	16,224				
	Sewer	Incidental Adjustmer	nts			3%	\$	16,224				
	Establish Turf / Erosion Control					2%	\$	10,816				
	Illumination	Standard Ilumination	System			6%	\$	32,448				
	Other:											
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce :	Subtotal:	\$	243,360				
			Paving an	d Allowa	nce	Subtotal:	\$	784,161				
			Mobi	lization:		5%	\$	39,208				
			Site Prep	aration:		5%	\$	39,208				
			Construc			TOTAL:	\$	863,000				
			uction Conti			15%	\$	129,450 <b>993,000</b>				
	Со	nstruction Cos	t TOTAL W	// CON	TING	Construction Cost TOTAL W/ CONTINGENCY:						

Impact Fee Project Cost Summa	ry		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 993,000
Engineering/Survey/Testing:		20%	\$ 198,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 198,600
Impact Fed	\$ 695,100		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

M6D

**Roadway Construction Cost Projection** 

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information:** E-15 Project No. Description:

Name: STATE HIGHWAY 5 (2) Limits: 1,915' N OF AIRPORT DR TO US HIGHWAY 380

This project consists of the reconstruction of the existing asphalt facility to a six-lane

**Impact Fee Class:** Thoroughfare Class: Major Arterial

divided major arterial.

Length (If):

11,960 Service Area(s): Ε

No.	Item Description	o.   Item Description   Quantity   Unit   Un			Uni	t Price		Item Cost
109	Unclassified Street Excavation		66,444	су	\$	15.00	\$	996,667
209	Lime Treated Subgrade (8") (PI<12)		103,653	sy	\$	7.00	\$	725,573
309	4" TY D HMAC Underlayment		98,338	sy	\$	5.00	\$	491,689
409	9" Concrete Pavement		98,338	sy	\$	60.00	\$	5,900,267
509	4" Topsoil		46,511	sy	\$	4.00	\$	186,044
609	6" Curb & Gutter		47,840	lf	\$	5.00	\$	239,200
709	Allotment for Turn Lanes and Median O	penings	7,299	sy	\$	87.00	\$	634,997
		P	aving Constr	uction C	ost S	ubtotal:	\$	9,174,437
Majo	or Construction Component Allowance							
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%		275,233
$\sqrt{}$	Pavement Markings/Markers					3%		275,233
$\sqrt{}$	Roadway Drainage					25%	\$	2,293,609
$\sqrt{}$	Special Drainage Structures	Bridge					\$	2,500,000
$\sqrt{}$	Water	Incidental Adjustmer	nts			3%	\$	275,233
$\sqrt{}$	Sewer	Incidental Adjustmer	nts			3%	\$	275,233
	Establish Turf / Erosion Control					2%	\$	183,489
	Illumination	Standard Ilumination	System			6%	\$	550,466
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce S	ubtotal:	\$	6,628,497
							_	15.000.001
			Paving and		nce S			15,802,934
	Mobilization: 5%					\$	790,147	
			Site Prep			5%	\$	790,147
			Construc				\$	17,384,000
			uction Conti			15%	_	2,607,600
	Cor	struction Cos	t TOTAL W	// CON	ΓING	ENCY:	\$	19,992,000

Impact Fee Project Cost Summ	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 19,992,000
Engineering/Survey/Testing:		20%	\$ 3,998,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 3,998,400
Impact Fe	\$ 13,994,400		

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. E-16

Name: AIRPORT DR (1) This project consists of the Limits: STATE HIGHWAY 5 TO 4,070 S OF STATE HIGHWAY 5 construction of a new six-lane

Impact Fee Class: P6D divided principal arterial.

Thoroughfare Class: Principal Arterial

Length (If): 4,070 Service Area(s): E

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
113	Unclassified Street Excavation	45,222	су	\$	10.00	\$ 452,222
213	Lime Treated Subgrade (8") (PI<12)	35,273	sy	\$	7.00	\$ 246,913
313	9" Concrete Pavement	33,464	sy	\$	60.00	\$ 2,007,867
413	4" Topsoil	18,541	sy	\$	2.50	\$ 46,353
513	6" Curb & Gutter	16,280	lf	\$	5.00	\$ 81,400
613	Allotment for Turn Lanes and Median Openings	2,484	sy	\$	77.00	\$ 191,252
713	Moisture Conditioning	35,273	sy	\$	8.00	\$ 282,187

Paving Construction Cost Subtotal: \$ 3,308,194

Majo				
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	None Anticipated	1%	\$ 33,082
	Pavement Markings/Markers		3%	\$ 99,246
	Roadway Drainage	Standard Internal System	25%	\$ 827,048
	Special Drainage Structures	Stream Crossing		\$ 250,000
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 66,164
	Illumination	Standard Ilumination System	6%	\$ 198,492
	Other:			
**Allo	wances based on % of Paving Construction Cos	t Subtotal Allowa	nce Subtotal:	\$ 1,474,032
		Paving and Allowa	nce Subtotal:	\$ 4,782,226
		Mobilization:	5%	\$ 239,111
		Site Preparation:	5%	\$ 239,111
		Construction C	ost TOTAL:	\$ 5,261,000
		Construction Contingency:	15%	\$ 789,150
	Co	nstruction Cost TOTAL W/ CON	TINGENCY:	\$ 6,051,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 6,051,000
Engineering/Survey/Testing:		20%	\$ 1,210,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 2,117,850

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. E-17

Name: AIRPORT DR (2) This project consists of the

Limits: WILMETH RD TO WOODLAWN RD (N) construction of a new six-lane divided

Impact Fee Class: P6D principal arterial.

Thoroughfare Class: Principal Arterial

Length (If): 2,790 Service Area(s): E

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
113	Unclassified Street Excavation	31,000	су	\$	10.00	\$ 310,000
213	Lime Treated Subgrade (8") (PI<12)	24,180	sy	\$	7.00	\$ 169,260
313	9" Concrete Pavement	22,940	sy	\$	60.00	\$ 1,376,400
413	4" Topsoil	12,710	sy	\$	2.50	\$ 31,775
513	6" Curb & Gutter	11,160	lf	\$	5.00	\$ 55,800
613	Allotment for Turn Lanes and Median Openings	1,703	sy	\$	77.00	\$ 131,104
713	Moisture Conditioning	24,180	sy	\$	8.00	\$ 193,440

Paving Construction Cost Subtotal: \$ 2,267,779

Majo	Major Construction Component Allowances**:						
	Item Description	Notes	Allowance		Item Cost		
	Traffic Control	None Anticipated	1%	\$	22,678		
	Pavement Markings/Markers		3%	\$	68,033		
	Roadway Drainage	Standard Internal System	25%	\$	566,945		
	Special Drainage Structures	Stream Crossing		\$	250,000		
	Water	None Anticipated	0%	\$	-		
	Sewer	None Anticipated	0%	\$	-		
	Establish Turf / Erosion Control		2%	\$	45,356		
	Illumination	Standard Ilumination System	6%	\$	136,067		
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$	1,089,078		
		Paving and Allowa	nce Subtotal:	\$	3,356,857		
		Mobilization:	5%	\$	167,843		
		Site Preparation:	5%	\$	167,843		
		Construction C	ost TOTAL:	\$	3,693,000		
		Construction Contingency:	15%	\$	553,950		
	Со	nstruction Cost TOTAL W/ CON	FINGENCY:	\$	4,247,000		

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,247,000
Engineering/Survey/Testing:		20%	\$ 849,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,486,450
	Impact Fee Project	t Cost TOTAL:	\$ 6,582,850

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. E-18

Name: AIRPORT DR (3) This project consists of the

Limits: WOODLAWN RD (N) TO WOODLAWN RD (S) reconstruction of a two-

Impact Fee Class: P6D facilit

Thoroughfare Class: Principal Arterial

Length (If): 1,535 Service Area(s): E reconstruction of a two-lane asphalt facility to a six-lane divided principal

arterial.

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
113	Unclassified Street Excavation	17,056	су	\$	10.00	\$ 170,556
213	Lime Treated Subgrade (8") (PI<12)	13,303	sy	\$	7.00	\$ 93,123
313	9" Concrete Pavement	12,621	sy	\$	60.00	\$ 757,267
413	4" Topsoil	6,993	sy	\$	2.50	\$ 17,482
513	6" Curb & Gutter	6,140	lf	\$	5.00	\$ 30,700
613	Allotment for Turn Lanes and Median Openings	937	sy	\$	77.00	\$ 72,131
713	Moisture Conditioning	13,303	sy	\$	8.00	\$ 106,427
		Paving Constr	ruction C	ost S	Subtotal:	\$ 1,247,685

Major Construction Componen	+ Allowanaac**		
Item Description	Notes	Allowance	Item Cost
√ Traffic Control	Construction Phase Traffic Control	3%	\$ 37,431
√ Pavement Markings/Markers	s	3%	\$ 37,431
√ Roadway Drainage	Standard Internal System	25%	\$ 311,921
√ Special Drainage Structures	Stream Crossing		\$ 250,000
√ Water	Incidental Adjustments	3%	\$ 37,431
√ Sewer	Incidental Adjustments	3%	\$ 37,431
$\sqrt{}$ Establish Turf / Erosion Con	itrol	2%	\$ 24,954
$\sqrt{}$ Illumination	Standard Ilumination System	6%	\$ 74,861
Other:			
**Allowances based on % of Paving Cons	struction Cost Subtotal Allowa	ance Subtotal:	\$ 811,458
	Paving and Allowa	ance Subtotal:	\$ 2,059,143
	Mobilization:	5%	\$ 102,957
	Site Preparation:	5%	\$ 102,957
	Construction C	ost TOTAL:	\$ 2,266,000
	Construction Contingency:	15%	\$ 339,900
	Construction Cost TOTAL W/ CON	TINGENCY:	\$ 2,606,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,606,000
Engineering/Survey/Testing:		20%	\$ 521,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 521,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

613 Allotment for Turn Lanes and Median Openings

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. E-19

Name: AIRPORT DR (4) This project consists of the

Limits: WOODLAWN RD (S) TO US HIGHWAY 380 construction of a new six-lane divided

Impact Fee Class: P6D principal arterial.

Thoroughfare Class: Principal Arterial

Length (If): 3,875 Service Area(s): E

713 Moisture Conditioning

00	100 / 11 ou (0).					
Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	it Price	Item Cost
113	Unclassified Street Excavation	43,056	су	\$	10.00	\$ 430,556
213	Lime Treated Subgrade (8") (PI<12)	33,583	sy	\$	7.00	\$ 235,083
313	9" Concrete Pavement	31,861	sy	\$	60.00	\$ 1,911,667
413	4" Topsoil	17,653	sy	\$	2.50	\$ 44,132
513	6" Curb & Gutter	15,500	lf	\$	5.00	\$ 77,500

2,365

33,583

Paving Construction Cost Subtotal: \$ 3,149,693

77.00

8.00

\$

\$

182,089

268,667

\$

\$

sy

sy

		<u> </u>		
Maj	or Construction Component Allow	vances**:		
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	None Anticipated	1%	\$ 31,497
	Pavement Markings/Markers		3%	\$ 94,491
	Roadway Drainage	Standard Internal System	25%	\$ 787,423
	Special Drainage Structures	Stream Crossing		\$ 250,000
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 62,994
	Illumination	Standard Ilumination System	6%	\$ 188,982
	Other:			
**Allc	wances based on % of Paving Construction	Cost Subtotal Allowa	nce Subtotal:	\$ 1,415,387
		Paving and Allowa	nce Subtotal:	\$ 4,565,080
		Mobilization:	5%	\$ 228,254
		Site Preparation:	5%	\$ 228,254
		Construction C	ost TOTAL:	\$ 5,022,000
		Construction Contingency:	15%	\$ 753,300
		<b>Construction Cost TOTAL W/ CON</b>	TINGENCY:	\$ 5,776,000

2 4 4:		Allowance	Item Cost
Construction:		-	\$ 5,776,000
Engineering/Survey/Testing:		20%	\$ 1,155,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 2,021,600

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	E-20
Name:	UNNAMED C (1) 410' E OF STATE HIGHWAY 5 TO 3,	010' E OF	This project cons	
Limits: Impact Fee Class:	STATE HIGHWAY 5 P6D(1/3)		through lanes wi	thin the
Thoroughfare Class: Length (If):	Principal Arterial 2.600		six-lane divided p	orincipal
Lengui (II).	2,000		arterial. This sect currently under c	onstruction for
Service Area(s):	Е		the four-lane divi Willowwood.	ded section by

Roa	adway Construction Cost Proje	ection					
No.	Item Description		Quantity	Unit	Uni	it Price	Item Cost
114	Unclassified Street Excavation		8,089	су	\$	10.00	\$ 80,889
214	Lime Treated Subgrade (8") (PI<12)		7,800	sy	\$	7.00	\$ 54,600
314	9" Concrete Pavement		7,222	sy	\$	60.00	\$ 433,333
414	4" Topsoil		2,311	sy	\$	2.50	\$ 5,778
514	6" Curb & Gutter		5,200	lf	\$	5.00	\$ 26,000
	Paving Construction Cost Subtotal:						\$ 600,600
Majo	or Construction Component Allowan	ces**:		-		-	
	Item Description	Notes			Allo	wance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 18,018
	Pavement Markings/Markers					3%	\$ 18,018
	Roadway Drainage	None Anticipated				0%	\$ -
	Special Drainage Structures	None Anticipated					\$ -
	Water	None Anticipated				0%	\$ -
	Sewer	None Anticipated				0%	\$ -
	Establish Turf / Erosion Control					2%	\$ 12,012
	Illumination	None Anticipated				0%	\$ -
	Other:						
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	ince S	Subtotal:	\$ 48,048
			Paving an	d Allowa	nce S	Subtotal:	\$ 648,648
			Mobi	lization:		5%	\$ 32,432
			Site Prep	aration:		5%	\$ 32,432
			Construc				714,000
			ruction Conti			15%	107,100
	Co	onstruction Cos	st TOTAL W	II CON	TING	ENCY:	\$ 822,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 822,000
Engineering/Survey/Testing:		20%	\$ 164,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No.	E-21
Name:	UNNAMED C (2) WILMETH RD TO 2,615' S OF		roject consists of th struction of a two-la	
Limits: Impact Fee Class:	WILMETH RD P6D	facility	y to a six-lane divide al. Based on the exis	d principal
Thoroughfare Class: Length (If):	Principal Arterial 2.615	Limits	s, the eastern half of	the roadway
Service Area(s):	E, Half	is not	included in the Impa	act Fee RIP.

	dway Construction Cost Proje	ection					
	Item Description		Quantity	Unit		it Price	Item Cost
113	Unclassified Street Excavation		14,528	су	\$	15.00	\$ 217,917
	Lime Treated Subgrade (8") (PI<12)		22,663	sy	\$	7.00	\$ 158,643
	4" TY D HMAC Underlayment		21,501	sy	\$	5.00	\$ 107,506
	9" Concrete Pavement		21,501	sy	\$	60.00	\$ 1,290,067
	4" Topsoil		11,913	sy	\$	4.00	\$ 47,651
	6" Curb & Gutter		10,460	lf	\$	5.00	\$ 52,300
713	Allotment for Turn Lanes and Median		1,596	sy	\$	87.00	\$ 138,839
		P	Paving Consti	ruction (	Cost	Subtotal:	\$ 2,012,923
Majo	or Construction Component Allowand	ces**:					
	Item Description	Notes			All	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 60,388
	Pavement Markings/Markers					3%	\$ 60,388
	Roadway Drainage					25%	\$ 503,231
	Special Drainage Structures	Stream Crossing					\$ 250,000
	Water	Incidental Adjustmer	nts			3%	\$ 60,388
	Sewer	Incidental Adjustmer	nts			3%	\$ 60,388
	Establish Turf / Erosion Control					2%	\$ 40,258
	Illumination	Standard Ilumination	System			6%	\$ 120,775
	Other:						
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce	Subtotal:	\$ 1,155,815
			Paving and	d Allowa	nce	Subtotal:	\$ 3,168,738
			Mobi	lization:		5%	\$ 158,437
			Site Prep	aration:		5%	\$ 158,437
			Construc			TOTAL:	\$ 3,486,000
			ruction Conti			15%	\$ 522,900
	Co	Instruction Cos	st TOTAL W	// CON	TING	SENCY:	\$ 4,009,000

Impact Fee Project Cost Summ	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,009,000
Engineering/Survey/Testing:		20%	\$ 801,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 801,800
Impact Fe	ee Project Cost TOTAL (50% City C	ontribution)	\$ 2,806,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.


#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

Roadway Improvements - Service Area F

	Costing				Percent in	Cost in
#	Class	Project	Limits	Total Cost	Service Area	Service Area
		No	Thoroughfare Roadways within City Limits Currently Present within Service	e Area F		

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

#### Roadway Improvements - Service Area G

	Costing					Percent in		Cost in
#	Class	Project	Limits	Te	otal Cost	Service Area	Se	rvice Area
G-1	M6D(1/3)	VIRGINIA PKWY (1)	COIT RD TO 500' W OF INDEPENDENCE PKWY	\$	2,158,800	100%	\$	2,158,800
G-2	M6D(1/3)	VIRGINIA PKWY (2)	500' W OF INDEPENDENCE PKWY TO 325' E OF FORKHORN DR	\$	794,400	50%	\$	397,200
G-3	M6D(1/3)	VIRGINIA PKWY (3)	325' E OF FORKHORN DR TO 935' W OF VIRGINIA HILLS DR	\$	913,196	50%	\$	456,598
G-4	M6D(1/3)	VIRGINIA PKWY (4)	935' W OF VIRGINIA HILLS DR TO CUSTER RD	\$	1,661,863	100%	\$	1,661,863
G-5	M6D(1/3)	VIRGINIA PKWY (5)	CUSTER RD TO 410' E OF DANBURY RD	\$	1,182,000	100%	\$	1,182,000
G-6	M6D(1/6)	VIRGINIA PKWY (6)	410' E OF DANBURY RD TO VIRGINIA PARKLANDS BLVD	\$	392,400	100%	\$	392,400
G-7	M6D(1/3)	WESTRIDGE BLVD (1)	COIT RD TO 1,635' E OF COIT RD	\$	745,200	50%	\$	372,600
G-8	M6D(1/3)	WESTRIDGE BLVD (2)	1,635' E OF COIT RD TO 2,720' E OF INDEPENDENCE PKWY	\$	2,931,600	100%	\$	2,931,600
G-9	M6D(1/3)	WESTRIDGE BLVD (3)	2,720' E OF INDEPENDENCE PKWY TO CUSTER RD	\$	1,192,800	50%	\$	596,400
H-1, G-10	G6D(1/3)	ELDORADO PKWY (1)	CUSTER RD TO RIDGE RD	\$	5,202,000	50%	\$	2,601,000
G-11	M6D(1/3)	COIT RD (1)	US HIGHWAY 380 TO 2,610' S OF VIRGINIA PKWY	\$	3,681,600	50%	\$	1,840,800
G-12	M6D(1/3)	COIT RD (2)	WESTRIDGE BLVD TO 2,595' S OF WESTRIDGE BLVD	\$	1,184,400	50%	\$	592,200
G-13	M6D(1/3)	INDEPENDENCE PKWY (1)	2,380' S OF US HIGHWAY 380 TO 4,465' S OF US HIGHWAY 380	\$	951,600	100%	\$	951,600
G-14	M6D(1/3)	INDEPENDENCE PKWY (2)	VIRGINIA PKWY TO 2,690' S OF WESTRIDGE BLVD	\$	3,666,000	100%	\$	3,666,000
G-15	P6D	CUSTER RD (4)	US HIGHWAY 380 TO WESTRIDGE BLVD	\$	3,260,945	100%	\$	3,260,945
G-16	P6D	CUSTER RD (5)	WESTRIDGE BLVD TO ELDORADO PKWY	\$	1,476,398	100%	\$	1,476,398
G-17, I-8	G4D	RIDGE RD (8)	US HIGHWAY 380 TO CREEKSIDE DR	\$	550,813	50%	\$	275,407
33		Signal Mod	US HIGHWAY 380 & STONEBRIDGE DR	\$	150,000	50%	\$	75,000
34		Signal	US HIGHWAY 380 & FOREST RIDGE LN	\$	300,000	50%	\$	150,000
37		Signal	STONEBRIDGE DR & LACIMA DR	\$	300,000	100%	\$	300,000
38		Signal	RIDGE RD & HABERSHAM WAY	\$	343,000	50%	\$	171,500
43	_	Signal	INDEPENDENCE PKWY & VIRGINIA PKWY	\$	80,000	50%	\$	40,000
44	tior	Under Construction	VIRGINIA PKWY & RIDGE RD	\$	390,341	50%	\$	195,171
47	Intersection	Signal	INDEPENDENCE PKWY & WESTRIDGE BLVD	\$	300,000	100%	\$	300,000
48	nter	Under Construction	CUSTER RD & WESTRIDGE BLVD	\$	390,341	75%	\$	292,756
49	_	Roundabout	STONEBRIDGE DR & GLEN OAKS DR	\$	1,950,000	100%	\$	1,950,000
50		Roundabout	RIDGE RD & GLEN OAKS DR	\$	2,640,000	50%	\$	1,320,000
55		Signal	STONEBRIDGE DR & ALMA DR	\$	300,000	100%	\$	300,000
56		Signal	RIDGE RD & RUSH CREEK RD	\$	300,000	50%	\$	150,000
57		Signal	RIDGE RD & BERKSHIRE RD	\$	300,000	50%	\$	150,000
		g		\$	39,689,697		\$	30,208,237

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

10/6/2020

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated:

**Project Information: G-1** Description: Project No.

Name: VIRGINIA PKWY (1) This project consists of the

Limits: COIT RD TO 500' W OF INDEPENDENCE PKWY construction of two additional through **Impact Fee Class:** M6D(1/3)

lanes within the existing median of the Thoroughfare Class: Major Arterial ultimate six-lane divided major arterial.

Length (If): 4,735 Service Area(s): G

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
111	Unclassified Street Excavation	14,731	су	\$	10.00	\$ 147,311
211	Lime Treated Subgrade (8") (PI<12)	14,205	sy	\$	7.00	\$ 99,435
311	9" Concrete Pavement	13,153	sy	\$	60.00	\$ 789,167
411	4" Topsoil	4,209	sy	\$	2.50	\$ 10,522
511	6" Curb & Gutter	9,470	lf	\$	5.00	\$ 47,350
611	Allotment for Turn Lanes and Median Openings	2,890	sy	\$	77.00	\$ 222,501
		Paving Constr	ruction C	Cost S	Subtotal:	\$ 1,316,286
	or Construction Component Allowances**					

Maj	or Construction Component Allowa	nces**:		
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$ 39,489
	Pavement Markings/Markers		3%	\$ 39,489
	Roadway Drainage	None Anticipated	0%	\$ -
	Special Drainage Structures	None Anticipated		\$ -
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 26,326
	Illumination	None Anticipated	0%	\$ -
	Other:			
**Allc	owances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$ 105,303
		Paving and Allowa	nce Subtotal:	\$ 1,421,589
		Mobilization:	5%	\$ 71,079
		Site Preparation:	5%	\$ 71,079
		Construction C	ost TOTAL:	\$ 1,564,000
		Construction Contingency:	15%	\$ 234,600
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$ 1,799,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,799,000
Engineering/Survey/Testing:		20%	\$ 359,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Information</b>	n:	Description:	Project No. G-2
Name: Limits: Impact Fee Class: Thoroughfare Class: Length (If):	VIRGINIA PKWY (2) 500' W OF INDEPENDENCE PKWY TO 325' E OF FORKHORN DR M6D(1/3) Major Arterial 1,740		This project consists of the construction of two additional through lanes within the existing median of the ultimate sixlane divided major arterial. Based on the existing City Limits, the northern half of the roadway is not included in the Impact Fee RIP for the 510' western section while the southern half of the roadway is not included for the remaining 1,230' eastern section.
Service Area(s):	G, Half		1,200 castom coolem

Day	dway Canathyatian Coat Brai	action					
	Idway Construction Cost Proje	ection	Quantity	Unit	Un	it Price	Item Cost
111	Unclassified Street Excavation		5,413	су	\$	10.00	\$ 54,133
211	Lime Treated Subgrade (8") (PI<12)		5,220	sy	\$	7.00	\$ 36,540
311	9" Concrete Pavement		4,833	sy	\$	60.00	\$ 290,000
411	4" Topsoil		1,547	sy	\$	2.50	\$ 3,867
511	6" Curb & Gutter		3,480	lf	\$	5.00	\$ 17,400
611	Allotment for Turn Lanes and Median	Openings	1,062	sy	\$	77.00	\$ 81,764
		ı	Paving Const	ruction (	Cost	Subtotal:	\$ 483,704
Majo	or Construction Component Allowan	ces**:	_	-		_	_
	Item Description	Notes			Alle	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 14,511
	Pavement Markings/Markers					3%	\$ 14,511
	Roadway Drainage	None Anticipated				0%	\$ -
	Special Drainage Structures	None Anticipated					\$ -
	Water	None Anticipated				0%	\$ -
	Sewer	None Anticipated				0%	\$ -
	Establish Turf / Erosion Control					2%	\$ 9,674
	Illumination	None Anticipated				0%	\$ -
	Other:						
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce S	Subtotal:	\$ 38,696
			Paving an	d Allowa	nce (	Subtotal:	\$ 522,400
				lization:		5%	26,120
			Site Prep	aration:		5%	\$ 26,120
			Constru	ction C	ost		\$ 575,000
		Const	ruction Conti	ngency:		15%	\$ 86,250
	C	onstruction Co	st TOTAL V	V/ CON	TING	ENCY:	\$ 662,000

Construction: Engineering/Survey/Testing:		20%	\$ \$	662,000
		20%	Ф	122 100
anno and a City and without an		_0,0	Ψ	132,400
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition: No ROW Acquis	sition Costs included	0%	\$	-

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No. G-3
Name:	VIRGINIA PKWY (3) 325' E OF FORKHORN DR TO 935'		This project consists of the construction of two additional through lanes within
Limits: Impact Fee Class: Thoroughfare Class: Length (If):	W OF VIRGINIA HILLS DR M6D(1/3) Major Arterial 1,465		the existing median of the ultimate six- lane divided major arterial. Based on the existing City Limits, the northern half of the roadway is not included in the
Service Area(s):	G, Half		Impact Fee RIP.

Ro	adway Construction Cost Pro	iection						
	Item Description	COLIOII	Quantity	Unit	Un	it Price		Item Cost
111	Unclassified Street Excavation		4,558	су	\$	10.00	\$	45,578
211	Lime Treated Subgrade (8") (PI<12)		4,395	sy	\$	7.00	\$	30,765
311	9" Concrete Pavement		4,069	sy	\$	60.00	\$	244,167
411	411 4" Topsoil		1,302	sy	\$	2.50	\$	3,256
511	·		2,930	lf	\$	5.00	\$	14,650
611			\$	77.00	\$	68,841		
Paving Construction Cost Subtotal							\$	407,256
Majo	or Construction Component Allowa	nces**:	_			_		
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	12,218
	Pavement Markings/Markers					3%	\$	12,218
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	8,145
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	ance S	Subtotal:	\$	32,581
			Paving an	d Allowa	nce (	Subtotal:	\$	439,837
			Mobi	lization:		5%	\$	21,992
			Site Prep	aration:		5%	\$	21,992
			Constru				\$	484,000
			ruction Conti			15%	т.	72,600
	C	onstruction Cos	st TOTAL W	II CON	TING	BENCY:	\$	557,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 557,000
Engineering/Survey/Testing:		20%	\$ 111,400
2008 - 2012 City contribution			\$ 244,796
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Informatio	n:	Description:	Project No.	G-4
Name:	VIRGINIA PKWY (4) 935' W OF VIRGINIA HILLS DR TO		This project consists of the construction of two additi	
Limits: Impact Fee Class:	CUSTER RD M6D(1/3)	la	anes within the existing n	nedian of the
Thoroughfare Class: Length (If):	Major Arterial 2,685	T	The City contributed appro	oximately
Service Area(s):	G	4	5430,003 or engible funds	110111 00- 12.

Roa	dway Construction Cost Proje	ction								
No.	Item Description		Quantity	Unit	Unit Price	:	Item Cost			
111	Unclassified Street Excavation		8,353	су	\$ 10.0	0 \$	83,533			
211	Lime Treated Subgrade (8") (PI<12)		8,055	sy	\$ 7.0	0 \$	56,385			
311	9" Concrete Pavement		7,458	sy	\$ 60.0	0 \$	447,500			
411	411 4" Topsoil		2,387	sy	\$ 2.5					
511	511 6" Curb & Gutter		5,370	lf	\$ 5.0					
611	Allotment for Turn Lanes and Median C		1,639	sy	\$ 77.0	- +	,			
Paving Construction Cost Subtotal:							746,405			
Majo	or Construction Component Allowand									
	Item Description	Notes			Allowance		Item Cost			
$\sqrt{}$	Traffic Control	Construction Phase	Traffic Control		_	<mark>%</mark> \$	,			
	Pavement Markings/Markers					<mark>%</mark> \$	22,392			
	Roadway Drainage	None Anticipated			0	<mark>%</mark> \$				
	Special Drainage Structures	None Anticipated				\$				
	Water	None Anticipated				<mark>%</mark> \$				
	Sewer	None Anticipated				<mark>%</mark> \$				
	Establish Turf / Erosion Control					<mark>%</mark> \$	,			
	Illumination	None Anticipated			0	<mark>%</mark> \$	-			
	Other:									
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce Subtota	ıl: \$	59,712			
						+				
			_		nce Subtota		,			
				lization:		<b>%</b> \$	- ,			
			Site Prep			<mark>%</mark> \$	,			
					ost TOTAI		<b>,</b>			
			uction Conti				,			
	Coi	nstruction Cos	t TOTAL W	// CON	TINGENC	<b>/: </b> \$	1,021,000			

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,021,000
Engineering/Survey/Testing:		20%	\$ 204,200
2008 - 2012 City contribution			\$ 436,663
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. G-5

Name: VIRGINIA PKWY (5) This project consists of the

Limits: CUSTER RD TO 410' E OF DANBURY RD construction of two additional through

Impact Fee Class: M6D(1/3) Ianes within the existing median of the Thoroughfare Class: Major Arterial ultimate six-lane divided major arterial.

Length (If): 2,590 Service Area(s): G

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
111	Unclassified Street Excavation	8,058	су	\$	10.00	\$ 80,578
211	Lime Treated Subgrade (8") (PI<12)	7,770	sy	\$	7.00	\$ 54,390
311	9" Concrete Pavement	7,194	sy	\$	60.00	\$ 431,667
411	4" Topsoil	2,302	sy	\$	2.50	\$ 5,756
511	6" Curb & Gutter	5,180	lf	\$	5.00	\$ 25,900
611	Allotment for Turn Lanes and Median Openings	1,581	sy	\$	77.00	\$ 121,706

Paving Construction Cost Subtotal: \$ 719,996

Maio	or Construction Component Allowa	ices**:		
11(23)	Item Description	Notes	Allowance	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$ 21,600
	Pavement Markings/Markers		3%	\$ 21,600
	Roadway Drainage	None Anticipated	0%	\$ -
	Special Drainage Structures	None Anticipated		\$ -
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 14,400
	Illumination	None Anticipated	0%	\$ -
	Other:			
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$ 57,600
		Paving and Allowa	nce Subtotal:	\$ 777,596
		Mobilization:		38,880
		Site Preparation:		38,880
		Construction C	ost TOTAL:	\$ 856,000
		Construction Contingency:	15%	\$ 128,400
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$ 985,000

Impact Fee Project Cost Sumi	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 985,000
Engineering/Survey/Testing:		20%	\$ 197,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 1,182,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No.	G-6
Name:	VIRGINIA PKWY (6)		This project consi	sts of the
Limits:	410' E OF DANBURY RD TO VIRO	GINIA PARKLANDS BL'	VD construction of or	ne additional
Impact Fee Class:	M6D(1/6)		through lane with	in the existing
Thoroughfare Class:	Major Arterial		median of the ulti	mate six-lane
Length (If):	2,050		divided major arte	erial.
Service Area(s):	G		•	

	adway Construction Cost Pro	ection						
No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
110	Unclassified Street Excavation		3,189	су	\$	10.00	<b>9</b> 3	31,889
210	Lime Treated Subgrade (8") (PI<12)		3,075	sy	\$	7.00	\$	21,525
310	9" Concrete Pavement		2,847	sy	\$	60.00	\$	170,833
			1,822	sy	\$	2.50	\$	4,556
510	510 6" Curb & Gutter		2,050	lf	\$	5.00	\$	10,250
610	Allotment for Turn Lanes and Median	Openings	0	sy	\$	77.00	\$	-
	Paving Construction Cost Subtotal:						\$	239,053
Majo	or Construction Component Allowa	nces**:						
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	7,172
	Pavement Markings/Markers					3%	\$	7,172
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	4,781
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Co	st Subtotal	·	Allowa	nce :	Subtotal:	\$	19,124
			Paving and	d Allowa	nce s	Subtotal:	\$	258,177
			Mobi	lization:		5%	\$	12,909
	Site Preparation: 5%							

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 327,000
Engineering/Survey/Testing:		20%	\$ 65,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 392,400

**Construction Cost TOTAL:** 

Construction Contingency:

**Construction Cost TOTAL W/ CONTINGENCY:** 

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

284,000

327,000

42,600

\$

10/6/2020

#### updated:

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Information</b>	n:	Description:	Project No.	G-7
Name:	WESTRIDGE BLVD (1)	This project consists of	the constructi	on of two
Limits:	COIT RD TO 1,635' E OF COIT RD	additional through lane	s within the ex	isting median
Impact Fee Class:	M6D(1/3)	of the ultimate six-lane	divided major a	arterial. Based
Thoroughfare Class:	Major Arterial	on the existing City Lim	•	
Length (If):	1,635	roadway is not included	•	
Service Area(s):	G, Half			

	adway Construction Cost Proj	ection					
No.	Item Description		Quantity	Unit	Un	it Price	Item Cost
111	Unclassified Street Excavation		5,087	су	\$	10.00	\$ 50,867
211	Lime Treated Subgrade (8") (PI<12)		4,905	sy	\$	7.00	\$ 34,335
311	9" Concrete Pavement		4,542	sy	\$	60.00	\$ 272,500
411	4" Topsoil		1,453	sy	\$	2.50	\$ 3,633
511			3,270	lf	\$	5.00	\$ 16,350
611 Allotment for Turn Lanes and Median Openings 998		sy	\$	77.00	\$ 76,830		
		Р	aving Constr	uction C	Cost S	Subtotal:	\$ 454,515
Majo	or Construction Component Allowar	nces**:					
	Item Description	Notes			Allo	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 13,635
	Pavement Markings/Markers					3%	\$ 13,635
	Roadway Drainage	None Anticipated				0%	\$ -
	Special Drainage Structures	None Anticipated					\$ -
	Water	None Anticipated				0%	-
	Sewer	None Anticipated				0%	-
	Establish Turf / Erosion Control					2%	\$ 9,090
	Illumination	None Anticipated				0%	\$ -
	Other:						
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	nce S	Subtotal:	\$ 36,361
			Paving and	d Allowa	nce S	Subtotal:	\$ 490,876
			Mobi	lization:		5%	\$ 24,544
			Site Prep	aration:		5%	\$ 24,544
			Construc				\$ 540,000
			uction Conti			15%	81,000
	C	onstruction Cos	t TOTAL W	// CON	TING	ENCY:	\$ 621,000

Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	621,000
Engineering/Survey/Testing:		20%	\$	124,200
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-
•	Impact Fee Project	Cost TOTAL:	4	745,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. G-8

Name: WESTRIDGE BLVD (2) This project consists of the

1,635' E OF COIT RD TO 2,720' E construction of two additions and additional construction of two additions are constructed as a construction of the construction of two additions are constructed as a construction of two addition

Limits: OF INDEPENDENCE PKWY

Impact Fee Class: M6D(1/3)
Thoroughfare Class: Major Arterial

Length (If): 6,430 Service Area(s): G construction of two additional through lanes within the existing median of the ultimate six-lane divided major arterial.

Roa	adway Construction Cost Pro	jection						
No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
111	Unclassified Street Excavation		20,004	су	\$	10.00	\$	200,044
211	11 Lime Treated Subgrade (8") (PI<12)		19,290	sy	\$	7.00	\$	135,030
311	9" Concrete Pavement		17,861	sy	\$	60.00	\$	1,071,667
411	11 4" Topsoil		5,716	sy	\$	2.50	\$	14,289
511	6" Curb & Gutter		12,860	lf	\$	5.00	\$	64,300
644	11 Allotment for Turn Lanes and Median Openings		3,924	sy	\$	77.00	\$	302,150
ווט								
611			aving Constr	ruction (	Cost S	Subtotal:	\$	1,787,480
		P	aving Constr	ruction (	Cost S	Subtotal:	\$	1,787,480
	or Construction Component Allowa	P	aving Constr	ruction (	Cost S	Subtotal:	\$	1,787,480
	or Construction Component Allowa Item Description	P	aving Constr	ruction (		Subtotal: owance	\$	1,787,480 Item Cost
		nces**:		ruction (				
	Item Description	nces**:   Notes		ruction (		owance	\$	Item Cost
Majo	Item Description Traffic Control	nces**:   Notes		ruction (		owance 3%	\$	Item Cost 53,624
Majo	Item Description Traffic Control Pavement Markings/Markers	nces**:  Notes  Construction Phase		ruction (		owance 3% 3%	\$	Item Cost 53,624
Majo	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage	P nces**: Notes Construction Phase None Anticipated		ruction (		owance 3% 3%	\$ \$ \$	Item Cost 53,624
Majo	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures	P nces**: Notes Construction Phase None Anticipated None Anticipated		ruction (		3% 3% 0%	\$ \$ \$ \$	Item Cost 53,624

Illumination	None Anticipated	0%	\$ -
Other:			
**Allowances based on % of Paving Construction Cost S	Subtotal Allov	vance Subtotal:	\$ 142,998
	Paving and Allov	vance Subtotal:	\$ 1,930,479
	Mobilizatio	n: 5%	\$ 96,524
	Site Preparatio	n: 5%	\$ 96,524
	Construction	Cost TOTAL:	\$ 2,124,000
	Construction Contingence	y: 15%	\$ 318,600
Con	struction Cost TOTAL W/ CO	NTINGENCY:	\$ 2,443,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,443,000
Engineering/Survey/Testing:		20%	\$ 488,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	G-9
Name:	WESTRIDGE BLVD (3) 2,720' E OF INDEPENDENCE		nis project consists of the one additional through la	
Limits: Impact Fee Class:	PKWY TO CUSTER RD M6D(1/3)		isting median of the ultin vided major arterial. Base	
Thoroughfare Class: Length (If):	Major Arterial 2,615	ex	cisting City Limits, the so e roadway is not included	uthern half of
Service Area(s):	G, Half		pact Fee RIP.	

No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
111	Unclassified Street Excavation		8,136	СУ	\$	10.00	\$	81,356
211	Lime Treated Subgrade (8") (PI<12)		7,845	sy	\$	7.00	\$	54,915
311	9" Concrete Pavement		7,264	sy	\$	60.00	\$	435,833
411	4" Topsoil		2,324	sy	\$	2.50	\$	5,811
511	6" Curb & Gutter		5,230	lf	\$	5.00	\$	26,150
611	Allotment for Turn Lanes and Median Openings 1,596 sy \$ 77		77.00	\$	122,881			
	•	F	Paving Consti	ruction (	Cost	Subtotal:	\$	726,946
Maio	or Construction Component Allowa	nces**:	_	-		_		
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	21,808
	Pavement Markings/Markers					3%	\$	21,808
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	14,539
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	nce	Subtotal:	\$	58,156
			Paving an	d Allowa	nce :	Subtotal:	\$	785,101
			_	lization:		5%	\$	39,255
			Site Prep	aration:		5%	\$	39,255
			Construc		•		_	864,000
		Const	ruction Conti	ngency:		15%	\$	129,600
	C	onstruction Cos				FNCY.	\$	994,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 994,000
Engineering/Survey/Testing:		20%	\$ 198,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. H-1, G-10

Name: ELDORADO PKWY (1) This project consists of the construction of two

Limits: CUSTER RD TO RIDGE RD

Impact Fee Class: G6D(1/3)

Thoroughfare Class: Greenway Arterial

Length (If): 10,830 Service Area(s): G and H

Sewer

This project consists of the construction of two additional through lanes within the existing median of the ultimate six-lane divided greenway arterial.

Roa	adway Construction Cost Pro	ojection						
No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
117	Unclassified Street Excavation		31,287	су	\$	10.00	\$	312,867
217	Lime Treated Subgrade (8") (PI<12)		30,083	sy	\$	7.00	\$	210,583
317	9" Concrete Pavement		27,677	sy	\$	60.00	\$	1,660,600
417	4" Topsoil		28,880	sy	\$	2.50	\$	72,200
517	6" Curb & Gutter		21,660	lf	\$	5.00	\$	108,300
617	Allotment for Turn Lanes and Media	n Openings	7,484	sy	\$	77.00	\$	576,296
		P	aving Consti	ruction (	Cost S	Subtotal:	\$	2,940,846
Majo	or Construction Component Allow	ances**:						
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	88,225
	Pavement Markings/Markers					3%	\$	88,225
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	Bridge Widening					\$	250,000
	operation and outside of	29					-	,

√ Establish Turf / Erosion Control		2%	\$ 58,817
Illumination	None Anticipated	0%	\$ -
Other:			
**Allowances based on % of Paving Construction Cost S	Subtotal	wance Subtotal:	\$ 485,268
	Paving and Alle	wa <u>nce Subtotal:</u>	\$ 3,426,114
	Mobilizati	on: 5%	\$ 171,306
	Site Preparati	on: 5%	\$ 171,306
	Construction	Cost TOTAL:	\$ 3,769,000
	Construction Continger	cy: 15%	\$ 565,350

Construction Cost TOTAL W/ CONTINGENCY:

None Anticipated

<b>Impact Fee Project Cost Summ</b>	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,335,000
Engineering/Survey/Testing:		20%	\$ 867,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 5,202,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

4,335,000

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	G-11
Name:	COIT RD (1) US HIGHWAY 380 TO 2,610' S OF		This project consists of the of two additional through	
Limits: Impact Fee Class: Thoroughfare Class: Length (If):	VIRGINIA PKWY M6D(1/3) Major Arterial 8,075		the existing median of the lane divided major arteria existing City Limits, the w the roadway is not includ	e ultimate six- II. Based on the vestern half of
Service Area(s):	G. Half		Impact Fee RIP.	

Roa	adway Construction Cost Pro	jection						
No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
111	Unclassified Street Excavation		25,122	су	\$	10.00	\$	251,222
211	Lime Treated Subgrade (8") (PI<12)		24,225	sy	\$	7.00	\$	169,575
311	9" Concrete Pavement		22,431	sy	\$	60.00	\$	1,345,833
411	4" Topsoil		7,178	sy	\$	2.50	\$	17,944
511	6" Curb & Gutter		16,150	lf	\$	5.00	\$	80,750
611	Allotment for Turn Lanes and Media	n Openings	4,928	sy	\$	77.00	\$	379,450
			Paving Const	ruction (	Cost	Subtotal:	\$	2,244,775
Majo	or Construction Component Allowa	nces**:						
	Item Description	Notes			Alle	owance		Item Cost
V	Traffic Control	Construction P	hase Traffic Control			3%	\$	67,343
	Pavement Markings/Markers					3%	\$	67,343
	Roadway Drainage	None Anticipate	ed			0%	\$	-
	Special Drainage Structures	None Anticipat	od				Ф	

	Item Description	Notes	Allowance	П	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$	67,343
	Pavement Markings/Markers		3%	\$	67,343
	Roadway Drainage	None Anticipated	0%	\$	-
	Special Drainage Structures	None Anticipated		\$	-
	Water	None Anticipated	0%	\$	-
	Sewer	None Anticipated	0%	\$	-
	Establish Turf / Erosion Control		2%	\$	44,896
	Illumination	None Anticipated	0%	\$	-
	Other:				
**Allo	wances based on % of Paving Construction (	Cost Subtotal Allow	ance Subtotal:	\$	179,582
		Paving and Allow	ance Subtotal:	\$	2,424,357
		Mobilization	5%	\$	121,218
		Site Preparation	5%	\$	121,218
		Construction C	ost TOTAL:	\$	2,667,000
		Construction Contingency	15%	\$	400,050
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	3,068,000

Impact Fee Project Cost Summa	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,068,000
Engineering/Survey/Testing:		20%	\$ 613,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 3,681,600

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No. G-12
Name:	COIT RD (2) WESTRIDGE BLVD TO 2,595' S OF		This project consists of the construction of two additional through lanes within
Limits:	WESTRIDGE BLVD		the existing median of the ultimate six-
Impact Fee Class:	M6D(1/3)		lane divided major arterial. Based on the
Thoroughfare Class:	Major Arterial		existing City Limits, the western half of
Length (If):	2,595		the roadway is not included in the
Service Area(s):	G, Half		Impact Fee RIP.

No.	adway Construction Cost Proj Item Description		Quantity	Unit	Un	it Price		Item Cost
111	Unclassified Street Excavation		8,073	су	\$	10.00	\$	80,733
211	Lime Treated Subgrade (8") (PI<12)		7,785	sy	\$	7.00	\$	54,495
311	9" Concrete Pavement		7,208	sy	\$	60.00	\$	432,500
411	4" Topsoil		2,307	sy	\$	2.50	\$	5,767
511	6" Curb & Gutter		5,190	lf	\$	5.00	\$	25,950
611	Allotment for Turn Lanes and Median	Openings	1,584	sy	\$	77.00	\$	121,941
		F	aving Consti	uction (	Cost S	Subtotal:	\$	721,386
Majo	or Construction Component Allowar	nces**:						
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	21,642
	Pavement Markings/Markers					3%	\$	21,642
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	14,428
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	ance S	Subtotal:	\$	57,711
			Paving and			Subtotal:	\$	779,097
			Mobi	lization:		5%	-	38,955
			Site Prep	aration:		5%	\$	38,955
			Construc			ΓΟΤΑL:	\$	858,000
		Const	uction Conti	ngency:		15%	\$	128,700
		onstruction Cos	4 TOTAL VA	// OON!	TINIO	ENION	\$	987,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 987,000
Engineering/Survey/Testing:		20%	\$ 197,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. G-13

Name: INDEPENDENCE PKWY (1) This project consists of the

2,380' S OF US HIGHWAY 380 TO construction of two additional through

Limits: 4,465' S OF US HIGHWAY 380 lanes within the existing median of the

Impact Fee Class: M6D(1/3) ultimate six-lane divided major arterial.

Thoroughfare Class: Major Arterial

Length (If): 2,085 Service Area(s): G

**Roadway Construction Cost Projection** No. Item Description Quantity Unit **Unit Price** Item Cost 111 Unclassified Street Excavation 6,487 \$ 10.00 \$ 64,867 СУ 211 Lime Treated Subgrade (8") (PI<12) 6,255 sy \$ 7.00 \$ 43,785 311 9" Concrete Pavement 5,792 \$ 60.00 \$ 347,500 sy 411 4" Topsoil 1,853 \$ 2.50 \$ 4,633 sy 511 6" Curb & Gutter 4,170 lf \$ 5.00 \$ 20,850 611 Allotment for Turn Lanes and Median Openings \$ \$ 97,976 1,272 77.00 sy

Paving Construction Cost Subtotal: \$ 579,611

Maio	or Construction Component Allow	ances**:			
maj	Item Description	Notes	Allowance		Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$	17,388
	Pavement Markings/Markers		3%	\$	17,388
	Roadway Drainage	None Anticipated	0%	\$	-
	Special Drainage Structures	None Anticipated		\$	-
	Water	None Anticipated	0%	\$	- 1
	Sewer	None Anticipated	0%	\$	- 1
	Establish Turf / Erosion Control		2%	\$	11,592
	Illumination	None Anticipated	0%	\$	-
	Other:				
**Allo	wances based on % of Paving Construction	Cost Subtotal Allow	ance Subtotal:	\$	46,369
				_	
		Paving and Allow			625,980
		Mobilization	: 5%	\$	31,299
		Site Preparation	: 5%	\$	31,299
		Construction C	Cost TOTAL:	\$	689,000
		Construction Contingency	: 15%	\$	103,350
	•	Construction Cost TOTAL W/ CON	ITINGENCY:	\$	793,000

Item Description	Notes:	Allowance	I	tem Cost
Construction:		-	\$	793,000
Engineering/Survey/Testing:		20%	\$	158,600
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

<b>Project Information</b>	ា: ព	escription:	Project No.	G-14
Name:	INDEPENDENCE PKWY (2)		This project cons	ists of the
Limits:	VIRGINIA PKWY TO 2,690' S OF WES	TRIDGE BLVD	construction of to	wo additional
Impact Fee Class:	M6D(1/3)		through lanes wit	thin the
Thoroughfare Class:	Major Arterial		existing median of	of the ultimate
Length (If):	8,040		six-lane divided n	
Service Area(s):	G			•

	idway Construction Cost Proje	Cuon						
No.	Item Description		Quantity	Unit	Uni	it Price		Item Cost
111	Unclassified Street Excavation		25,013	су	\$	10.00	\$	250,133
211	Lime Treated Subgrade (8") (PI<12)		24,120	sy	\$	7.00	\$	168,840
311	9" Concrete Pavement		22,333	sy	\$	60.00	\$	1,340,000
411	4" Topsoil		7,147	sy	\$	2.50	65	17,867
511	6" Curb & Gutter		16,080	lf	\$	5.00	65	80,400
611	Allotment for Turn Lanes and Median	Openings	4,907	sy	\$	77.00	\$	377,806
		Р	aving Constr	uction C	Cost S	Subtotal:	\$	2,235,046
Majo	r Construction Component Allowan	ces**:						
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	67,051
	Pavement Markings/Markers					3%	\$	67,051
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	44,701
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce S	Subtotal:	\$	178,804
			Daving and	A Allowa	nco S	Subtotal	\$	2,413,849
	Paving and Allowance Subtotal:  Mobilization: 5%						\$	120,692
						\$	120,692	
			Construc				\$	2,656,000
		Constr	uction Conti			15%	<b>3</b>	398,400
	0-						_	3,055,000
	Co	Instruction Cos	Construction Cost TOTAL W/ CONTINGENCY: \$					

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,055,000
Engineering/Survey/Testing:		20%	\$ 611,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No. G-15
Name:	CUSTER RD (4)		This completed project consists of the
Limits:	<b>US HIGHWAY 380 TO WESTRIDGE</b>	BLVD	construction of a six-lane divided
Impact Fee Class:	P6D		principal arterial. The City contributed
Thoroughfare Class:	Principal Arterial		approximately \$2,653,673 of eligible
Length (If):	10,720		funds from '08-'12. This project was
			also part of Custer Road project from
			Stonebridge to US 380 which had a total
			City contribution of approximately
			\$1,029,274 from '12-'19. This projected
Service Area(s):	G		accounted for \$607,272 of eligible

Impact Fee Project Cost Summary				
Item Description	Notes:	Allowance		Item Cost
2008 - 2012 City contribution			\$	2,653,673
2012 - 2019 City contribution			\$	607,272
Impact Fee Project Cost TOTAL:				3,260,945

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No. G-16
Name:	CUSTER RD (5)		This completed project consists of the
Limits:	WESTRIDGE BLVD TO ELDORADO	PKWY	construction of a six-lane divided
Impact Fee Class:	P6D		principal arterial. The City contributed
Thoroughfare Class:	Principal Arterial		approximately \$1,167,616 of eligible
Length (If):	5,380		funds from '08-'12. This project was
			also part of Custer Road project from
			Stonebridge to US 380 which had a total
			City contribution of approximately
			\$1,029,274 from '12-'19. This projected
Service Area(s):	G		accounted for \$308,782 of eligible

Impact Fee Project Cost Summary				
Item Description	Notes:	Allowance		Item Cost
2008 - 2012 City contribution			\$	1,167,616
2012 - 2019 City contribution			\$	308,782
Impact Fee Project Cost TOTAL:				1,476,398


**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

**Project Information:** G-17, I-8 Description: Project No. Name: RIDGE RD (8) This completed project consists of the Limits: US HIGHWAY 380 TO CREEKSIDE DR construction of a four-lane divided **Impact Fee Class:** G4D greenway arterial. The City contributed Thoroughfare Class: Greenway Arterial approximately \$550,813 of eligible funds 6,875 Length (If): from '08-'12. Service Area(s): G and I

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ 550,813
2012 - 2019 City contribution			\$ -
	Impact Fee Project C	ost TOTAL:	\$ 550,813

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

#### Roadway Improvements - Service Area H

	Costing					Percent in		Cost in
#	Class	Project	Limits	Т	otal Cost	Service Area	Se	rvice Area
H-1, G-10	G6D(1/3)	ELDORADO PKWY (1)	CUSTER RD TO RIDGE RD	\$	5,202,000	50%	\$	2,601,000
H-2	M4D(1/2)	SILVERADO TRL (1)	CUSTER RD TO BURNETT DR	\$	2,746,293	100%	\$	2,746,293
H-3	M4D	SILVERADO TRL (2)	ALMA DR TO ALFALFA DR	\$	141,088	100%	\$	141,088
H-4	P6D(1/3)	STACY RD (1)	CUSTER RD TO RIDGE RD	\$	4,479,991	100%	\$	4,479,991
H-5	P6D	CUSTER RD (6)	ELDORADO PKWY TO STONEBRIDGE DR	\$	622,725	100%	\$	622,725
H-6	G4D	ALMA DR (1)	805' S OF BEAVER CREEK DR TO SILVERADO TRL	\$	239,850	100%	\$	239,850
H-7	M6D(1/3)	ALMA DR (2)	SILVERADO TRL TO STACY RD	\$	1,522,102	100%	\$	1,522,102
H-8, I-9	M6D(1/3)	RIDGE RD (9)	MCKINNEY RANCH PKWY TO STACY RD	\$	1,662,000	50%	\$	831,000
H-9	M6D(1/3)	MCKINNEY RANCH PKWY (1)	RIDGE RD TO STACY RD	\$	1,857,600	100%	\$	1,857,600
65		Signal	CUSTER RD & SILVERADO TRL	\$	300,000	50%	\$	150,000
66	on	Signal	MCKINNEY RANCH PKWY & SILVERADO TRL	\$	300,000	100%	\$	300,000
71	ecti	Signal	STACY RD & MCKINNEY RANCH PKWY	\$	300,000	100%	\$	300,000
75	Intersection	Signal	CUSTER RD & PARADISE DR	\$	300,000	50%	\$	150,000
76	<u>=</u>	Signal	STACY RD & COLLIN MCKINNEY PKWY	\$	300,000	50%	\$	150,000
77		Signal	ALMA DR & HENNEMAN WAY	\$	300,000	100%	\$	300,000
		_		\$	20,273,649		\$	16,391,649

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information:

Name:

ELDORADO PKWY (1)

Limits:

CUSTER RD TO RIDGE RD

Impact Fee Class:

Description:

Project No. H-1, G-10

This project consists of the construction of two additional through lanes within the existing median of the ultimate six-lane divided greenway arterial.

Thoroughfare Class: Greenway Arterial

Roadway Construction Cost Projection

Length (If): 10,830 Service Area(s): G and H

	Item Description		Quantity	Unit	Unit Price		Item Cost
117	Unclassified Street Excavation		31,287	СУ	\$ 10.00	\$	312,867
217	Lime Treated Subgrade (8") (PI<12)		30,083	sy	\$ 7.00	\$	210,583
317	9" Concrete Pavement		27,677	sy	\$ 60.00	\$	1,660,600
417	4" Topsoil		28,880	sy	\$ 2.50	\$	72,200
517	6" Curb & Gutter		21,660	If	\$ 5.00	\$	108,300
617	Allotment for Turn Lanes and Median	Openinas	7,484	SV	\$ 77.00	\$	576,296
				,	Cost Subtotal:		2,940,846
Maio	or Construction Component Allowan	*****					
Iviajo	Item Description	Notes			Allowance		Item Cost
	Traffic Control	Construction Phase	Traffic Control		3%	\$	88,225
	Pavement Markings/Markers				3%	\$	88,225
	Roadway Drainage	None Anticipated			0%	\$	-
	Special Drainage Structures	Bridge Widening				\$	250,000
	Water	None Anticipated			0%	\$	-
	Sewer	None Anticipated			0%	\$	-
	Establish Turf / Erosion Control				2%	\$	58,817
	Illumination	None Anticipated			0%	\$	-
	Other:						
**Allo	wances based on % of Paving Construction Cos	st Subtotal		Allowa	nce Subtotal:	\$	485,268
			Paving and	d Allowa	nce Subtotal:	\$	3,426,114
	Mobilization: 5%						171,306
	Site Preparation: 5%					\$	171,306
					ost TOTAL:		3,769,000
			uction Conti			_	565,350
	Co	onstruction Cos	t TOTAL W	// CON	TINGENCY:	\$	4,335,000

<b>Impact Fee Project Cost Sumr</b>	nary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	4,335,000
Engineering/Survey/Testing:		20%	\$	867,000
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-
Impact Fee Project Cost TOTAL:				5,202,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Informatio</b>	n:	Description:	Project No.	H-2		
Name:	SILVERADO TRL (1)	This project consists of	of the construction	n of two		
Limits:	CUSTER RD TO BURNETT DR	additional lanes of the ultimate four-lane divided				
Impact Fee Class:	M4D(1/2)	minor arterial. The City contributed approximately				
Thoroughfare Class:	Minor Arterial	\$224,893 of eligible funds from '12-'19.				
Length (If):	1,930					
Service Area(s):	Н					

	adway Construction Cost Proje	ection					
No.	Item Description		Quantity	Unit	Un	it Price	Item Cost
106	Unclassified Street Excavation		5,576	су	\$	10.00	\$ 55,756
206	Lime Treated Subgrade (8") (PI<12)		5,361	sy	\$	7.00	\$ 37,528
306	8" Concrete Pavement		4,932	sy	\$	55.00	\$ 271,272
406	4" Topsoil		2,037	sy	\$	2.50	\$ 5,093
506	6" Curb & Gutter		3,860	lf	\$	5.00	\$ 19,300
606	Allotment for Turn Lanes and Median	Openings	567	sy	\$	72.00	\$ 40,793
		Р	aving Constr	ruction (	Cost S	Subtotal:	\$ 429,742
Majo	or Construction Component Allowar	ices**:					
	Item Description	Notes			Allo	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 12,892
	Pavement Markings/Markers					3%	\$ 12,892
	Roadway Drainage	Standard Internal Sy	/stem			25%	\$ 107,435
	Special Drainage Structures	Bridge					\$ 800,000
$\sqrt{}$	Water	Incidental Adjustme	nts			3%	 12,892
$\sqrt{}$	Sewer	Incidental Adjustmen	nts			3%	\$ 12,892
$\sqrt{}$	Establish Turf / Erosion Control					2%	 8,595
	Illumination	Standard Ilumination	n System			6%	\$ 25,785
	Other:						
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	nce S	Subtotal:	\$ 993,384
Paving and Allowa <u>nce Subtotal:</u>						\$ 1,423,126	
Mobilization: 5%						\$ 71,156	
Site Preparation: 5%						\$ 71,156	
Construction Cost TOTAL:						\$ 1,566,000	
		Constr	uction Conti	ngency:		15%	\$ 234,900
Construction Cost TOTAL W/ CONTINGENCY:						\$ 1,801,000	

<b>Impact Fee Project Cost Summ</b>	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,801,000
Engineering/Survey/Testing:		20%	\$ 360,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 224,893
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 360,200
Impact Fee Project Cost TOTAL:			\$ 2,746,293

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No.	H-3			
Name:	SILVERADO TRL (2)	This completed project consists of the construction					
Limits:	ALMA DR TO ALFALFA DR	of a four-lane divided minor arterial. This project					
Impact Fee Class:	M4D	was part of the Alma Rd and Silverado Trail project					
Thoroughfare Class:	Minor Arterial	which had a total City contribution of approximately					
Length (If):	1,170	\$705,400 from '08-'12. This project accounted for					
Service Area(s):	Н	\$141,088 of eligible funds.					

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ 141,088
2012 - 2019 City contribution			\$ -
	Impact Fee Project C	ost TOTAL:	\$ 141,088

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	H-4			
Name:	STACY RD (1)	This project consists of the construction of two					
Limits:	CUSTER RD TO RIDGE RD	additional through lanes within the existing median					
Impact Fee Class: P6D(1/3)		of the ultimate six-lane divided principal arterial.					
Thoroughfare Class:	Principal Arterial	This project is currently	y under design	and the City			
Length (If):	10,715	provided a cost estima	•	•			
Service Area(s):	H	•					

Impact Fee Project Cost Summary				
Item Description	Notes:	Allowance		Item Cost
2008 - 2012 City contribution		·	\$	-
2012 - 2019 City contribution			\$	4,479,991
Impact Fee Project Cost TOTAL:				4,479,991

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Informatio</b>	n: c	escription:	Project No. H-5	
Name:	CUSTER RD (6)		This completed project consists of the	
Limits:	<b>ELDORADO PKWY TO STONEBRIDG</b>	E DR	construction of a six-lane divided	
Impact Fee Class:	P6D		principal arterial. The City contributed	
Thoroughfare Class:	Principal Arterial		approximately \$509,505 of eligible fund	Is
Length (If):	2,040		from '08-'12. This project was also part	
Service Area(s):	Н		of Custer Road project from	
			Stonebridge to US 380 which had a tot	al
			City contribution of approximately	
			\$1,029,274 from '12-'19. This projected	
			accounted for \$113,220 of eligible	

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ 509,505
2012 - 2019 City contribution			\$ 113,220
Impact Fee Project Cost TOTAL:			\$ 622,725

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Information</b>	1:	Description:	Project No. H-6
Name: Limits: Impact Fee Class: Thoroughfare Class: Length (If): Service Area(s):	ALMA DR (1) 805' S OF BEAVER CREEK DR TO S G4D Greenway Arterial 1,960 H	ILVERADO TRL	This completed project consists of the construction of a four-lane divided greenway arterial. This project was part of the Alma Rd and Silverado Trail project which had a total City contribution of approximately \$705,400 from '08-'12. This project accounted for \$239,850 of eligible funds.

Impact Fee Project Cost Summary				
Item Description	Notes:	Allowance		Item Cost
2008 - 2012 City contribution			\$	239,850
2012 - 2019 City contribution			\$	-
Impact Fee Project Cost TOTAL:				239,850

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

10/6/2020 updated:

<b>Project Informatio</b>	n:	Description:	Project No.	H-7
Name:	ALMA DR (2)	This project consists	s of the construction of t	wo additional
Limits:	SILVERADO TRL TO STACY RD	through lanes within	the existing median of	the ultimate
Impact Fee Class:	M6D(1/3)	six-lane divided maje	or arterial. This project v	vas part of the
Thoroughfare Class:	Major Arterial		do Trail project which ha	•
Length (If):	2,625		oximately \$705,400 from	•
Service Area(s):	Н		or \$324,502 of eligible fu	

Roa	dway Construction Cost Proje	ction					
No.	Item Description		Quantity	Unit	Unit Price		Item Cost
111	Unclassified Street Excavation		8,167	су	\$ 10.00	\$	81,667
211	Lime Treated Subgrade (8") (PI<12)		7,875	sy	\$ 7.00	\$	55,125
311	9" Concrete Pavement		7,292	sy	\$ 60.00	\$	437,500
411	4" Topsoil		2,333	sy	\$ 2.50	\$	5,833
511	6" Curb & Gutter		5,250	lf	\$ 5.00	\$	26,250
611	Allotment for Turn Lanes and Median (	Openings	1,602	sy	\$ 77.00	\$	123,351
			Paving Constr	uction (	Cost Subtotal	: \$	729,726
Maio	or Construction Component Allowand	ces**:					
	Item Description	Notes			Allowance	Т	Item Cost
	Traffic Control	Construction Phase	Traffic Control		3%	\$	21,892
	Pavement Markings/Markers				3%	\$	21,892
	Roadway Drainage	None Anticipated			0%	\$	-
	Special Drainage Structures	None Anticipated				\$	-
	Water	None Anticipated			0%	\$	-
	Sewer	None Anticipated			0%	\$	-
	Establish Turf / Erosion Control				2%	\$	14,595
	Illumination	None Anticipated			0%	\$	-
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	ance Subtotal	: \$	58,378
			Daving an	d Allance	on a a Culptatal		700 404
							788,104
							39,405
							39,405
							,
Construction Contingency: 15%							130,050
	Construction Cost TOTAL W/ CONTINGENCY:						998,000

Impact Fee Project Cost Summ	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 998,000
Engineering/Survey/Testing:		20%	\$ 199,600
2008 - 2012 City contribution			\$ 324,502
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ 
	Impact Fee Project	Cost TOTAL:	\$ 1,522,102

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

**Project Information:** H-8, I-9 Description: Project No.

Name: RIDGE RD (9) This project consists of the

Limits: MCKINNEY RANCH PKWY TO STACY RD construction of two additional through

**Impact Fee Class:** M6D(1/3) lanes within the existing median of the Thoroughfare Class: Major Arterial ultimate six-lane divided major arterial.

Length (If): 3,645

Service Area(s): H and I

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
111	Unclassified Street Excavation	11,340	су	\$	10.00	\$ 113,400
211	Lime Treated Subgrade (8") (PI<12)	10,935	sy	\$	7.00	\$ 76,545
311	9" Concrete Pavement	10,125	sy	\$	60.00	\$ 607,500
411	4" Topsoil	3,240	sy	\$	2.50	\$ 8,100
511	6" Curb & Gutter	7,290	lf	\$	5.00	\$ 36,450
611	Allotment for Turn Lanes and Median Openings	2,224	sy	\$	77.00	\$ 171,281

Paving Construction Cost Subtotal: \$ 1,013,276

Majo	Major Construction Component Allowances**:										
	Item Description	Notes	Allowance		Item Cost						
	Traffic Control	Construction Phase Traffic Control	3%	\$	30,398						
	Pavement Markings/Markers		3%	\$	30,398						
	Roadway Drainage	None Anticipated	0%	\$	-						
	Special Drainage Structures	None Anticipated		\$	-						
	Water	None Anticipated	0%	\$	-						
	Sewer	None Anticipated	0%	\$	-						
	Establish Turf / Erosion Control		2%	\$	20,266						
	Illumination	None Anticipated	0%	\$	-						
	Other:										
**Allo	wances based on % of Paving Construction Co	ost Subtotal Allowa	ance Subtotal:	\$	81,062						
		Paving and Allowa	ance Subtotal:	\$	1,094,338						
		Mobilization:	5%	\$	54,717						
		Site Preparation:	5%	\$	54,717						
		Construction C	ost TOTAL:	\$	1,204,000						
		Construction Contingency:			180,600						
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	1,385,000						

Impact Fee Project Cost Sumr	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,385,000
Engineering/Survey/Testing:		20%	\$ 277,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	Impact Fee Project	Cost TOTAL:	\$ 1,662,000

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information:** H-9 Description: Project No. Name: MCKINNEY RANCH PKWY (1) This project consists of the construction of two Limits: RIDGE RD TO STACY RD additional through lanes within the existing median **Impact Fee Class:** M6D(1/3) of the ultimate six-lane divided major arterial.


Thoroughfare Class: Major Arterial

Length (If): 4,075 Service Area(s): Н

Roa	dway Construction Cost Project	ction					
No.	Item Description		Quantity	Unit	Unit Pri	се	Item Cost
111	Unclassified Street Excavation		12,678	су	\$ 10	.00	\$ 126,778
211	Lime Treated Subgrade (8") (PI<12)		12,225	sy	\$ 7	.00	\$ 85,575
311	9" Concrete Pavement		11,319	sy	\$ 60	.00	\$ 679,167
411	4" Topsoil		3,622	sy		.50	\$ 9,056
511	6" Curb & Gutter		8,150	lf	\$ 5	.00	\$ 40,750
611	Allotment for Turn Lanes and Median O		2,487	sy		.00	\$ 191,487
		P	aving Consti	ruction (	Cost Subto	tal:	\$ 1,132,812
Majo	or Construction Component Allowanc						
	Item Description	Notes			Allowan	се	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 33,984
	Pavement Markings/Markers					3%	\$ 33,984
	Roadway Drainage	None Anticipated				0%	\$ -
	Special Drainage Structures	None Anticipated					\$ -
	Water	None Anticipated				0%	\$ -
	Sewer	None Anticipated				0%	\$ -
	Establish Turf / Erosion Control					2%	\$ 22,656
	Illumination	None Anticipated				0%	\$ -
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce Subto	otal:	\$ 90,625
			Paving and		nce Subto		\$ 1,223,437
				lization:		5%	\$ 61,172
			Site Prep			5%	\$ 61,172
			Construc			AL:	\$ 1,346,000
		Constr	uction Conti	ngency:	,	15%	\$ 201,900
	Cor	struction Cos	t TOTAL W	// CON	TINGEN	CY:	\$ 1,548,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,548,000
Engineering/Survey/Testing:		20%	\$ 309,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

#### Roadway Improvements - Service Area I

	Costing				Percent in		Cost in
#	Class	Project	Limits	Total Cost	Service Area	Se	rvice Area
I-1	M6D	VIRGINIA PKWY (7)	1035' E OF RIDGE RD TO 1355' W OF HARDIN BLVD	\$ 2,567,378	100%	\$	2,567,378
I-2	M6D	VIRGINIA PKWY (8)	1355' W OF HARDIN BLVD TO HARDIN BLVD	\$ 531,979	100%	\$	531,979
I-3	G6D(1/3)	ELDORADO PKWY (2)	RIDGE RD TO HARDIN BLVD	\$ 4,857,600	100%	\$	4,857,600
I-4	M6D(1/3)	MCKINNEY RANCH PKWY (2)	RIDGE RD TO HARDIN BLVD	\$ 4,338,000	100%	\$	4,338,000
I-5	G4D	COLLIN MCKINNEY PKWY (2)	LAKE FOREST DR TO COTTONWOOD CREEK	\$ 1,777,105	100%	\$	1,777,105
I-6	G4D(1/2)	COLLIN MCKINNEY PKWY (3)	COTTONWOOD CREEK TO 1110' E OF TINA DR	\$ 3,221,002	100%	\$	3,221,002
I-7	G4D	COLLIN MCKINNEY PKWY (4)	1110' E OF TINA TO HARDIN BLVD	\$ 1,101,893	100%	\$	1,101,893
G-17, I-8	G4D	RIDGE RD (8)	US HIGHWAY 380 TO CREEKSIDE DR	\$ 550,813	50%	\$	275,407
H-8, I-9	M6D(1/3)	RIDGE RD (9)	MCKINNEY RANCH PKWY TO STACY RD	\$ 1,662,000	50%	\$	831,000
I-10, J-6	G6D(1/3)	HARDIN BLVD (11)	US HIGHWAY 380 TO VIRGINIA PKWY	\$ 13,584,097	50%	\$	6,792,049
I-11, J-7	G6D(1/3)	HARDIN BLVD (12)	VIRGINIA PKWY TO MCKINNEY RANCH PKWY	\$ 6,208,800	50%	\$	3,104,400
35		Signal	US HIGHWAY 380 & AUBURN HILLS PKWY	\$ 300,000	50%	\$	150,000
36		Under Construction	US HIGHWAY 380 & HARDIN BLVD	\$ 780,682	25%	\$	195,171
38		Signal	RIDGE RD & HABERSHAM WAY	\$ 343,000	50%	\$	171,500
44		Under Construction	VIRGINIA PKWY & RIDGE RD	\$ 390,341	50%	\$	195,171
45		Signal	VIRGINIA PKWY & JOPLIN DR	\$ 300,000	100%	\$	300,000
46		Signal	VIRGINIA PKWY & VILLAGE DR	\$ 300,000	100%	\$	300,000
50	ь	Roundabout	RIDGE RD & GLEN OAKS DR	\$ 2,640,000	50%	\$	1,320,000
51	Intersection	Roundabout	LAKE FOREST DR & GLEN OAKS DR	\$ 1,900,000	100%	\$	1,900,000
56	ers	Signal	RIDGE RD & RUSH CREEK RD	\$ 300,000	50%	\$	150,000
57	<u>=</u>	Signal	RIDGE RD & BERKSHIRE RD	\$ 300,000	50%	\$	150,000
58		Signal	HARDIN BLVD & MAVERICK TRL	\$ 300,000	50%	\$	150,000
59		Signal	ELDORADO PKWY & WOODSON DR	\$ 300,000	100%	\$	300,000
60		Signal	ELDORADO PKWY & HIGHLANDS DR	\$ 300,000	100%	\$	300,000
72		Signal	LAKE FOREST DR & COLLIN MCKINNEY PKWY	\$ 300,000	100%	\$	300,000
73		Signal	HARDIN BLVD & COLLIN MCKINNEY PKWY	\$ 300,000	50%	\$	150,000
76		Signal	STACY RD & COLLIN MCKINNEY PKWY	\$ 300,000	50%	\$	150,000
		· ·		\$ 49,754,690		\$	35,579,653

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc. updated: 10/6/2020

Project Informatio	<b>n:</b>	escription:	Project No.	I-1			
Name:	VIRGINIA PKWY (7)		This completed p	roject			
Limits:	1035' E OF RIDGE RD TO 1355' W OF	HARDIN BLVD	consists of the co	nstruction of			
Impact Fee Class:	M6D		a six-lane divided	major arterial.			
Thoroughfare Class:	Major Arterial		The City contribu	ted			
Length (If):	7,565		approximately \$2,567,37				
Service Area(s):	I		elaible funds from '12-'19				

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 2,567,378
	Impact Fee Project C	ost TOTAL:	\$ 2,567,378

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No. <b>I-2</b>
Name:	VIRGINIA PKWY (8)		This completed project consists of the
Limits:	1355' W OF HARDIN BLVD TO HARD	DIN BLVD	construction of a six-lane divided major
Impact Fee Class:	M6D		arterial. This project was part of the
Thoroughfare Class:	Major Arterial		Virginia Pkwy project from Bellegrove
Length (If):	1,380		to US 75 which had a total City
			contribution of approximately
			\$3,799,852 from '12-'19. This projected
			accounted for \$531,979 of eligible funds
Service Area(s):	1		and is currently under construction.

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 531,979
	Impact Fee Project C	ost TOTAL:	\$ 531,979

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information: I-3** Description: Project No. Name: **ELDORADO PKWY (2)** This project consists of the construction of two Limits: RIDGE RD TO HARDIN BLVD additional through lanes within the existing median **Impact Fee Class:** G6D(1/3) of the ultimate six-lane divided greenway arterial.

Thoroughfare Class: **Greenway Arterial** 

Length (If): 10,910

Service Area(s):

Roa	adway Construction Cost Project	tion					
No.	Item Description		Quantity	Unit	Un	it Price	Item Cost
117	Unclassified Street Excavation		31,518	су	\$	10.00	\$ 315,178
217	Lime Treated Subgrade (8") (PI<12)		30,306	sy	\$	7.00	\$ 212,139
317	9" Concrete Pavement		27,881	sy	\$	60.00	\$ 1,672,867
417	4" Topsoil		29,093	sy	\$	2.50	\$ 72,733
517	6" Curb & Gutter		21,820	lf	\$	5.00	\$ 109,100
617	Allotment for Turn Lanes and Median Op	enings	7,540	sy	\$	77.00	\$ 580,553
		Р	aving Consti	ruction C	ost S	Subtotal:	\$ 2,962,570
Majo	or Construction Component Allowance	s**:					
	Item Description	Notes			Allo	owance	Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$ 88,877

Iviaj	Major Construction Component Allowances":							
	Item Description	Notes	Allowance		Item Cost			
	Traffic Control	Construction Phase Traffic Control	3%	\$	88,877			
	Pavement Markings/Markers		3%	\$	88,877			
	Roadway Drainage	None Anticipated	0%	\$	-			
	Special Drainage Structures	None Anticipated		\$	-			
	Water	None Anticipated	0%	\$	-			
	Sewer	None Anticipated	0%	\$	_ !			
	Establish Turf / Erosion Control		2%	\$	59,251			
	Illumination	None Anticipated	0%	\$	_ !			
	Other:							
**Allo	wances based on % of Paving Construction (	Cost Subtotal Allow	ance Subtotal:	\$	237,006			
		Paving and Allow	ance Subtotal:	\$	3,199,576			
		Mobilization	: 5%	\$	159,979			
	\$	159,979						
	\$	3,520,000						
Construction Contingency: 15%					528,000			
	\$	4,048,000						

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,048,000
Engineering/Survey/Testing:		20%	\$ 809,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated:

10/6/2020

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information:

Name:

MCKINNEY RANCH PKWY (2)

Limits:

RIDGE RD TO HARDIN BLVD

Impact Fee Class:

Thoroughfare Class:

Major Arterial

Description:

Project No. I-4

This project consists of the construction of two additional through lanes within the existing median of the ultimate six-lane divided major arterial.

Length (If): 9,515 Service Area(s):

Roa	adway Construction Cost Proje	ection						
No.	Item Description		Quantity	Unit	Unit	Price		Item Cost
111	Unclassified Street Excavation		29,602	су	\$	10.00	\$	296,022
211	Lime Treated Subgrade (8") (PI<12)		28,545	sy	\$	7.00	\$	199,815
311	9" Concrete Pavement		26,431	sy	\$	60.00	\$	1,585,833
411	4" Topsoil		8,458	sy	\$	2.50	\$	21,144
	6" Curb & Gutter		19,030	lf	\$	5.00	\$	95,150
611	Allotment for Turn Lanes and Median	Openings	5,807	sy	\$	77.00	\$	447,117
		Р	aving Constr	uction C	Cost S	ubtotal:	\$	2,645,082
Majo	or Construction Component Allowan							
	Item Description	Notes			Allo	wance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%		79,352
	Pavement Markings/Markers					3%		79,352
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%		-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	-	52,902
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce S	ubtotal:	\$	211,607
								2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
Paving and Allowance Subtotal:							2,856,688	
Mobilization: 5%						\$	142,834	
Site Preparation: 5%							142,834	
Construction Cost TOTAL:							3,143,000	
			uction Conti			15%		471,450
	Construction Cost TOTAL W/ CONTINGENCY:							3,615,000

<b>Impact Fee Project Cost Sumr</b>	nary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	3,615,000
Engineering/Survey/Testing:		20%	\$	723,000
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-
Impact Fee Project Cost TOTAL:				4,338,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Informatio</b>	n: Descript	ion:	Project No. <b>I-5</b>			
Name:	COLLIN MCKINNEY PKWY (2)	Т	his project consists of the			
Limits:	LAKE FOREST DR TO COTTONWOOD CRE	EK c	construction of a four-lane divided			
Impact Fee Class:	G4D	g	reenway arterial. This project is part of			
Thoroughfare Class:	Greenway Arterial	t	the Collin McKinney Pkwy project from			
Length (If):	1,615	L	Lake Forest to Hardin which the City			
		р	provided an anticipated construction			
		C	ost of approximately \$6,100,000 from			
		14	12-'19. This projected accounted for			
Service Area(s):	I	\$	1,777,105 of eligible funds.			

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 1,777,105
	Impact Fee Project C	ost TOTAL:	\$ 1,777,105

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Information</b>	n:	Description:	Project No. <b>I-6</b>	
Name:	COLLIN MCKINNEY PKWY (3)		This project consists of the	
Limits:	COTTONWOOD CREEK TO 1110' E C	OF TINA DR	construction of two additional lane	es of
Impact Fee Class:	G4D(1/2)		the ultimate four-lane divided gree	nway
Thoroughfare Class:	Greenway Arterial		arterial. This project is part of the 0	Collin
Length (If):	2,930		<b>McKinney Pkwy project from Lake</b>	
			Forest to Hardin which the City	
			provided an anticipated constructi	on
			cost of approximately \$6,100,000 fr	om
			'12-'19. This projected accounted for	or
			\$3,221,002 of eligible funds.	
Service Area(s):	1		3	

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 3,221,002
	Impact Fee Project C	ost TOTAL:	\$ 3,221,002

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No. <b>I-7</b>			
Name:	COLLIN MCKINNEY PKWY (4)		This project consists of the			
Limits:	1110' E OF TINA TO HARDIN BLVD		construction of a four-lane divided			
Impact Fee Class:	G4D		greenway arterial. This project is part of			
Thoroughfare Class: Greenway Arterial			the Collin McKinney Pkwy project from			
Length (If):	1,000		Lake Forest to Hardin which the City			
			provided an anticipated construction			
			cost of approximately \$6,100,000 from			
			'12-'19. This projected accounted for			
Service Area(s):	1		\$1,101,893 of eligible funds.			

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 1,101,893
	Impact Fee Project C	ost TOTAL:	\$ 1,101,893

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

**Project Information:** G-17, I-8 Description: Project No. Name: RIDGE RD (8) This completed project consists of the Limits: US HIGHWAY 380 TO CREEKSIDE DR construction of a four-lane divided **Impact Fee Class:** G4D greenway arterial. The City contributed Thoroughfare Class: Greenway Arterial approximately \$550,813 of eligible funds Length (If): 6,875 from '08-'12. Service Area(s): G and I

<b>Impact Fee Project Cost Summary</b>			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ 550,813
2012 - 2019 City contribution			\$ -
Impact Fee Project Cost TOTAL:			\$ 550,813

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

**Project Information:** H-8, I-9 Description: Project No.

Name: RIDGE RD (9) This project consists of the

Limits: MCKINNEY RANCH PKWY TO STACY RD construction of two additional through

**Impact Fee Class:** M6D(1/3) lanes within the existing median of the Thoroughfare Class: Major Arterial ultimate six-lane divided major arterial.

Length (If): 3,645

Service Area(s): H and I

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
111	Unclassified Street Excavation	11,340	су	\$	10.00	\$ 113,400
211	Lime Treated Subgrade (8") (PI<12)	10,935	sy	\$	7.00	\$ 76,545
311	9" Concrete Pavement	10,125	sy	\$	60.00	\$ 607,500
411	4" Topsoil	3,240	sy	\$	2.50	\$ 8,100
511	6" Curb & Gutter	7,290	lf	\$	5.00	\$ 36,450
611	Allotment for Turn Lanes and Median Openings	2,224	sy	\$	77.00	\$ 171,281

Paving Construction Cost Subtotal: \$ 1,013,276

Majo	Major Construction Component Allowances**:							
	Item Description	Notes	Allowance		Item Cost			
	Traffic Control	Construction Phase Traffic Control	3%	\$	30,398			
	Pavement Markings/Markers		3%	\$	30,398			
	Roadway Drainage	None Anticipated	0%	\$	-			
	Special Drainage Structures	None Anticipated		\$	-			
	Water	None Anticipated	0%	\$	-			
	Sewer	None Anticipated	0%	\$	-			
	Establish Turf / Erosion Control		2%	\$	20,266			
	Illumination	None Anticipated	0%	\$	-			
	Other:							
**Allo	wances based on % of Paving Construction Co	ost Subtotal Allowa	ance Subtotal:	\$	81,062			
		Paving and Allowa	ance Subtotal:	\$	1,094,338			
		Mobilization:	5%	\$	54,717			
	Site Preparation: 5%							
	Construction Cost TOTAL:							
	Construction Contingency: 15%							
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	1,385,000			

Impact Fee Project Cost Sumr	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,385,000
Engineering/Survey/Testing:		20%	\$ 277,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
Impact Fee Project Cost TOTAL:			\$ 1,662,000

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

<b>Project Information</b>	Description: Project No.	I-10, J-6

Name: HARDIN BLVD (11) This project consists of the

Limits: US HIGHWAY 380 TO VIRGINIA PKWY construction of two additional through

**Impact Fee Class:** G6D(1/3)

lanes within the existing median of the Thoroughfare Class: **Greenway Arterial** 

ultimate six-lane divided greenway Length (If): 8,340 arterial. The City contributed

approximately \$8,352,097 of elgible

funds from '08-'12. Service Area(s): I and J

Do	dway Construction Cost Proje	oction					
	Item Description	CUOII	Quantity	Unit	Unit Price		Item Cost
117	Unclassified Street Excavation		24,093	СУ	\$ 10.00	\$	240,933
217	Lime Treated Subgrade (8") (PI<12)		23,167	sy	\$ 7.00	\$	162,167
317	9" Concrete Pavement		21,313	sy	\$ 60.00	\$	1,278,800
417	4" Topsoil		22,240	sy	\$ 2.50	\$	55,600
517	6" Curb & Gutter		16,680	If	\$ 5.00	\$	83,400
617	Allotment for Turn Lanes and Median	Openings	5,764	sy	\$ 77.00	\$	443,796
		<u>.                                      </u>	aving Constr	uction C	Cost Subtotal:	\$	2,264,696
			•				
Majo	or Construction Component Allowan	ces**:					
	Item Description	Notes			Allowance		Item Cost
	Traffic Control	Construction Phase	Traffic Control		3%	\$	67,941
	Pavement Markings/Markers				3%	\$	67,941
	Roadway Drainage	None Anticipated			0%	\$	-
	Special Drainage Structures	Bridge				\$	1,000,000
	Water	None Anticipated			0%	\$	-
	Sewer	None Anticipated			0%	\$	-
	Establish Turf / Erosion Control				2%	\$	45,294
	Illumination	None Anticipated			0%	\$	-
	Other:						
**Allo	wances based on % of Paving Construction Cos	st Subtotal		Allowa	nce Subtotal:	\$	1,181,176
Paving and Allowance Subtotal:							3,445,872
Mobilization: 5%							172,294
			Site Prep	aration:	5%	\$	172,294
Construction Cost TOTAL:						\$	3,791,000
	-		uction Conti			_	568,650
	Co	nstruction Cos	t TOTAL W	// CON	TINGENCY:	\$	4,360,000

Impact Fee Project Cost Sumi	mary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	4,360,000
Engineering/Survey/Testing:		20%	\$	872,000
2008 - 2012 City contribution			\$	8,352,097
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-
Impact Fee Project Cost TOTAL:				13,584,097

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. I-11, J-7

Name: HARDIN BLVD (12)

Limits: VIRGINIA PKWY TO MCKINNEY RANCH PKWY

Impact Fee Class: G6D(1/3)

Thoroughfare Class: Greenway Arterial

Length (If): 13,945

This project consists of the

construction of two additional through lanes within the existing median of the ultimate six-lane divided greenway


arterial.

Service Area(s): I and J

Pos	Roadway Construction Cost Projection							
	Item Description	CHOII	Quantity	Unit	Unit Price		Item Cost	
117	Unclassified Street Excavation		40,286	СУ	\$ 10.00	\$		
217	Lime Treated Subgrade (8") (PI<12)		38,736	sy	\$ 7.00	_		
317	9" Concrete Pavement		35,637	sy	\$ 60.00			
417	4" Topsoil		37,187	sy	\$ 2.50	_		
517	6" Curb & Gutter		27,890	lf	\$ 5.00	\$	139,450	
617	Allotment for Turn Lanes and Median	Openings	9,637	sy	\$ 77.00	\$	742,055	
		P	aving Constr	uction (	Cost Subtota	: \$	3,786,713	
Majo	or Construction Component Allowan	ces**:						
	Item Description	Notes			Allowance		Item Cost	
	Traffic Control	Construction Phase	Traffic Control		3%	<mark>6</mark> \$	113,601	
	Pavement Markings/Markers				3%	<mark>6</mark> \$	113,601	
	Roadway Drainage	None Anticipated			0%		-	
	Special Drainage Structures	None Anticipated				\$	-	
	Water	None Anticipated			0%		-	
	Sewer	None Anticipated			0%	<mark>6</mark> \$	-	
	Establish Turf / Erosion Control				29		75,734	
	Illumination	None Anticipated			0%	<mark>6</mark> \$	-	
	Other:							
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	ince Subtotal	: \$	302,937	
Paving and Allowance Subtotal:							4,089,650	
	Mobilization: 5%						204,483	
			Site Prep	aration:	5%	<mark>6</mark> \$	204,483	
Construction Cost TOTAL:						: \$	4,499,000	
		Constr	uction Conti	ngency:	15%	<mark>6</mark> \$	674,850	
	Co	nstruction Cos	t TOTAL W	// CON	TINGENCY	: \$	5,174,000	

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 5,174,000
Engineering/Survey/Testing:		20%	\$ 1,034,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

Roadway Improvements - Service Area J

	Costing					Percent in		Cost in
#	Class	Project	Limits	Т	otal Cost	Service Area	Se	rvice Area
J-1	M4D	WHITE AVE (1)	HARDIN BLVD TO BOIS D'ARC RD	\$	981,328	100%	\$	981,328
J-2	M4D	WHITE AVE (2)	BOIS D'ARC RD TO COMMUNITY AVE	\$	213,991	100%	\$	213,991
J-3	M6D	VIRGINIA PKWY (9)	HARDIN BLVD TO US HIGHWAY 75	\$	3,267,873	100%	\$	3,267,873
J-4	G6D(1/3)	ELDORADO PKWY (3)	710' E OF US HIGHWAY 75 TO 1,180' E OF BARRANCA WAY	\$	4,047,600	100%	\$	4,047,600
J-5	M3U	COLLIN MCKINNEY PKWY (5)	2,100' E OF HARDIN BLVD TO MCKINNEY RANCH PKWY	\$	1,953,000	100%	\$	1,953,000
I-10, J-6	G6D(1/3)	HARDIN BLVD (11)	US HIGHWAY 380 TO VIRGINIA PKWY	\$	13,584,097	50%	\$	6,792,049
I-11, J-7	G6D(1/3)	HARDIN BLVD (12)	VIRGINIA PKWY TO MCKINNEY RANCH PKWY	\$	6,208,800	50%	\$	3,104,400
J-8	M4D	MEDICAL CENTER DR	STATE HIGHWAY 121 TO 1,685' S OF STATE HIGHWAY 121	\$	2,240,000	100%	\$	2,240,000
J-9, K-7	M6D	STATE HIGHWAY 5 (4)	640' S OF HARRY MCKILLOP BLVD / FM 546 TO STATE HIGHWAY 121	\$	4,647,300	50%	\$	2,323,650
J-10, K-8	M4D	STATE HIGHWAY 5 (5)	STATE HIGHWAY 121 TO 3,525' S OF STATE HIGHWAY 121	\$	2,223,200	50%	\$	1,111,600
J-11	M4D	STATE HIGHWAY 5 (6)	3,525' S OF STATE HIGHWAY 121 TO 4,520' S OF STATE HIGHWAY 121	\$	627,900	50%	\$	313,950
36		Under Construction	US HIGHWAY 380 & HARDIN BLVD	\$	780,682	25%	\$	195,171
39		Signal	WHITE AVE & JORDAN RD	\$	300,000	100%	\$	300,000
58	_	Signal	HARDIN BLVD & MAVERICK TRL	\$	300,000	50%	\$	150,000
61	tior	Intersection Improvements	ELDORADO PKWY & CRAIG DR	\$	150,000	100%	\$	150,000
62	rsec	Signal	STATE HIGHWAY 5 & STEWART RD	\$	300,000	50%	\$	150,000
67	Intersection	Signal	MCKINNEY RANCH PKWY & COLLIN MCKINNEY PKWY	\$	300,000	100%	\$	300,000
68	_	Signal	COLLIN MCKINNEY PKWY & CRAIG DR	\$	300,000	100%	\$	300,000
69		Signal	STATE HIGHWAY 5 & ENTERPRISE DR	\$	300,000	50%	\$	150,000
73		Signal	HARDIN BLVD & COLLIN MCKINNEY PKWY	\$	300,000	50%	\$	150,000
_			·	\$	43,025,771		\$	28,194,611

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

Project Information:		Description:	Project No.	J-1	
Name:	WHITE AVE (1)	This completed project	consists of the	construction	
Limits:	HARDIN BLVD TO BOIS D'ARC RD	RD of a four-lane divided minor arterial. The City			
Impact Fee Class:	M4D	contributed approximate	tely \$981,327 of	elgible funds	
Thoroughfare Class:	Minor Arterial	from '08-'12.			
Length (If):	905				
Service Area(s):	J				

Impact Fee Project Cost Summary				
Item Description	Notes:	Allowance		Item Cost
2008 - 2012 City contribution			\$	981,328
2012 - 2019 City contribution			\$	-
Impact Fee Project Cost TOTAL:				981,328

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc. updated: 10/6/2020

**Project Information: J-2** Description: Project No. Name: WHITE AVE (2) This completed project consists of the Limits: BOIS D'ARC RD TO COMMUNITY AVE construction of a four-lane divided **Impact Fee Class:** M4D minor arterial. The City contributed Thoroughfare Class: Minor Arterial approximately \$231,991 of elgible funds Length (If): 4,930 from '08-'12 Service Area(s): J

<b>Impact Fee Project Cost Summary</b>			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ 213,991
2012 - 2019 City contribution			\$ -
Impact Fee Project Cost TOTAL:			\$ 213,991

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc. updated: 10/6/2020

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

<b>Project Informatio</b>	n:	Description:	Project No.	J-3			
Name:	VIRGINIA PKWY (9)	This completed project	t consists of the	construction			
Limits:	HARDIN BLVD TO US HIGHWAY 75	of a six-lane divided m	najor arterial. Thi	is project was			
Impact Fee Class:	M6D	part of the Virginia Pkwy project from Bellegrove to					
Thoroughfare Class:	Major Arterial	US 75 which had a total		•			
Length (If):	8,470	approximately \$3,799,8	•				
		projected accounted for	or \$3,267,873 of	eligible funds			
Service Area(s):	J	and is currently under	construction.				

Impact Fee Project Cost Summary			
Item Description	Notes:	Allowance	Item Cost
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ 3,267,873
	Impact Fee Project Co	ost TOTAL:	\$ 3,267,873

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. J-4

Name: ELDORADO PKWY (3) This project consists of the

710' E OF US HIGHWAY 75 TO construction of two additional construction of two additional constructions of two additional const

Limits: 1,180' E OF BARRANCA WAY lanes within the existing median

Impact Fee Class: G6D(1/3)

Thoroughfare Class: Greenway Arterial

Length (If): 5,680 Service Area(s): J construction of two additional through lanes within the existing median of the ultimate six-lane divided greenway

arterial.

No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
117	Unclassified Street Excavation	16,409	су	\$	10.00	\$ 164,089
217	Lime Treated Subgrade (8") (PI<12)	15,778	sy	\$	7.00	\$ 110,444
317	9" Concrete Pavement	14,516	sy	\$	60.00	\$ 870,933
417	4" Topsoil	15,147	sy	\$	2.50	\$ 37,867
517	6" Curb & Gutter	11,360	lf	\$	5.00	\$ 56,800
617	Allotment for Turn Lanes and Median Openings	3,925	sy	\$	77.00	\$ 302,250
		Paving Constr	uction C	Cost	Subtotal:	\$ 1,542,383
Maio	or Construction Component Allowances**:		_		_	
Maje	Item Description Notes			ΔII	owance	Item Cost

Major Construction Component Allowances**:							
	Item Description	Notes	Allowance		Item Cost		
	Traffic Control	Construction Phase Traffic Control	3%	\$	46,271		
	Pavement Markings/Markers		3%	\$	46,271		
	Roadway Drainage	None Anticipated	0%	\$	-		
	Special Drainage Structures	Bridge		\$	1,000,000		
	Water	None Anticipated	0%	\$	-		
	Sewer	None Anticipated	0%	\$	-		
	Establish Turf / Erosion Control		2%	\$	30,848		
	Illumination	None Anticipated	0%	\$	-		
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$	1,123,391		
		Paving and Allowa	nce Subtotal:	\$	2,665,774		
		Mobilization:	5%	\$	133,289		
		Site Preparation:	5%	\$	133,289		
		Construction C		\$	2,933,000		
		Construction Contingency:	15%	\$	439,950		
	Con	struction Cost TOTAL W/ CON	FINGENCY:	\$	3,373,000		

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,373,000
Engineering/Survey/Testing:		20%	\$ 674,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. J-5

Name: COLLIN MCKINNEY PKWY (5) This project consists of the

Limits: 2,100' E OF HARDIN BLVD TO MCKINNEY RANCH PKWY construction of a new three-lmpact Fee Class: M3U lane undivided minor arterial.

Thoroughfare Class: Minor Arterial

Length (If): 1,720 Service Area(s): J

Roa	dway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Un	it Price		Item Cost
102	Unclassified Street Excavation	3,822	су	\$	8.00	\$	30,578
202	Lime Treated Subgrade (6") (PI<12)	7,453	sy	\$	5.00	\$	37,267
302	8" Concrete Pavement	7,071	sy	\$	55.00	\$	388,911
402	4" Topsoil	4,013	sy	\$	2.50	\$	10,033
502	6" Curb & Gutter	3,440	lf	\$	5.00	\$	17,200
602	0	0	0	\$	-	\$	-
702	Moisture Conditioning	7,453	sy	\$	8.00	\$	59,627
	Paving Construction Cost Subtotal: \$						543,616

Maj	or Construction Component Allowar	ices**:								
	Item Description	Notes	Allowance		Item Cost					
	Traffic Control	None Anticipated	1%	\$	5,436					
	Pavement Markings/Markers		3%	\$	16,308					
	Roadway Drainage	Standard Internal System	25%	\$	135,904					
	Special Drainage Structures	Stream Crossing		\$	250,000					
	Water	None Anticipated	0%	\$	-					
	Sewer	None Anticipated	0%	\$	-					
	Establish Turf / Erosion Control		2%	\$	10,872					
	Illumination	Standard Ilumination System	6%	\$	32,617					
	Other:									
**Allo	owances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	451,138					
		Paving and Allowa	nce Subtotal:	\$	994,753					
		Mobilization:	5%	\$	49,738					
		Site Preparation:	5%	\$	49,738					
		Construction C	ost TOTAL:	\$	1,095,000					
		Construction Contingency:	15%	\$	164,250					
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	1,260,000					

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,260,000
Engineering/Survey/Testing:		20%	\$ 252,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 441,000

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

<b>Project Information</b>	Description: Project No.	I-10, J-6

Name: HARDIN BLVD (11) This project consists of the

Limits: US HIGHWAY 380 TO VIRGINIA PKWY construction of two additional through

**Impact Fee Class:** G6D(1/3)

lanes within the existing median of the Thoroughfare Class: **Greenway Arterial** 

ultimate six-lane divided greenway Length (If): 8,340 arterial. The City contributed

approximately \$8,352,097 of elgible

funds from '08-'12. Service Area(s): I and J

Do	adway Construction Cost Proje	oction					
	Item Description	ection .	Quantity	Unit	Unit Price		Item Cost
117	Unclassified Street Excavation		24,093	СУ	\$ 10.00	\$	240,933
217	Lime Treated Subgrade (8") (PI<12)		23,167	sy	\$ 7.00	\$	162,167
317	9" Concrete Pavement		21,313	sy	\$ 60.00	\$	1,278,800
417	4" Topsoil		22,240	sy	\$ 2.50	\$	55,600
517	6" Curb & Gutter		16,680	lf	\$ 5.00	\$	83,400
617	Allotment for Turn Lanes and Median	Openings	5,764	sy	\$ 77.00	\$	443,796
			aving Consti	uction (	Cost Subtotal:	\$	2,264,696
			Ü			·	, ,
Majo	or Construction Component Allowan	ces**:					
	Item Description	Notes			Allowance		Item Cost
	Traffic Control	Construction Phase	Traffic Control		3%	\$	67,941
	Pavement Markings/Markers				3%	\$	67,941
	Roadway Drainage	None Anticipated			0%	\$	-
	Special Drainage Structures	Bridge				\$	1,000,000
	Water	None Anticipated			0%	\$	-
	Sewer	None Anticipated			0%	\$	-
	Establish Turf / Erosion Control				2%	\$	45,294
	Illumination	None Anticipated			0%	\$	-
	Other:						
**Allo	wances based on % of Paving Construction Cos	st Subtotal		Allowa	nce Subtotal:	\$	1,181,176
			Paving and	d Allowa	nce Subtotal:	\$	3,445,872
			Mobi	lization:	5%	\$	172,294
			Site Prep	aration:	5%	\$	172,294
					ost TOTAL:	\$	3,791,000
			uction Conti				568,650
	Co	Construction Cost TOTAL W/ CONTINGENCY:					

Impact Fee Project Cost Sumi	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,360,000
Engineering/Survey/Testing:		20%	\$ 872,000
2008 - 2012 City contribution			\$ 8,352,097
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
	\$ 13,584,097		

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. I-11, J-7

Name: HARDIN BLVD (12)

Limits: VIRGINIA PKWY TO MCKINNEY RANCH PKWY

Impact Fee Class: G6D(1/3)

Thoroughfare Class: Greenway Arterial

**Length (If):** 13,945

Service Area(s): I and J

This project consists of the

construction of two additional through lanes within the existing median of the ultimate six-lane divided greenway

arterial.

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Unit Price		Item Cost
117	Unclassified Street Excavation	40,286	су	\$	10.00	\$ 402,856
217	Lime Treated Subgrade (8") (PI<12)	38,736	sy	\$	7.00	\$ 271,153
317	9" Concrete Pavement	35,637	sy	\$	60.00	\$ 2,138,233
417	4" Topsoil	37,187	sy	\$	2.50	\$ 92,967
517	6" Curb & Gutter	27,890	lf	\$	5.00	\$ 139,450
617	Allotment for Turn Lanes and Median Openings	9,637	sy	\$	77.00	\$ 742,055

Paving Construction Cost Subtotal: \$ 3,786,713

Maj						
	Item Description	Notes	Allowance		Item Cost	
	Traffic Control	Construction Phase Traffic Control	3%	\$	113,601	
	Pavement Markings/Markers		3%	\$	113,601	
	Roadway Drainage	None Anticipated	0%	\$	-	
	Special Drainage Structures	None Anticipated		\$	-	
	Water	None Anticipated	0%	\$	-	
	Sewer	None Anticipated	0%	\$	-	
	Establish Turf / Erosion Control		2%	\$	75,734	
	Illumination	None Anticipated	0%	\$	-	
	Other:					
**Allo	owances based on % of Paving Construction Co	ost Subtotal Allowa	ance Subtotal:	\$	302,937	
		Paving and Allowa	ance Subtotal:	\$	4,089,650	
		Mobilization:	5%	\$	204,483	
	Site Preparation: 5%					
	Construction Cost TOTAL:					
	Construction Contingency: 15%					
Construction Cost TOTAL W/ CONTINGENCY:					5,174,000	

Impact Fee Project Cost Sumi	mary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	5,174,000
Engineering/Survey/Testing:		20%	\$	1,034,800
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-
Impact Fee Project Cost TOTAL:				6,208,800

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated:

**Project Information: J-8** Description: Project No.

Name: MEDICAL CENTER DR This project consists of the

STATE HIGHWAY 121 TO 1,685' S

Limits: **OF STATE HIGHWAY 121** 

**Impact Fee Class:** M4D

Thoroughfare Class: Minor Arterial

Length (If): 1,685 Service Area(s): J

reconstruction of a three-lane concrete facility to a four-lane divided minor arterial.

		4.					
	adway Construction Cost Project   Item Description	tion	Quantity	Unit	Unit Price		Item Cost
105	Unclassified Street Excavation		13,480	CV	\$ 10.00	) \$	
	Lime Treated Subgrade (8") (PI<12)		9,361		\$ 7.00		
305	8" Concrete Pavement		8.612	sy sy	\$ 55.00		
405	4" Topsoil		7,302	sy	\$ 2.50	_	
505	6" Curb & Gutter		6,740	If	\$ 5.00	_	
	Allotment for Turn Lanes and Median O	noninge	989		\$ 72.00	_	
	Moisture Conditioning	periirigs	9,361	sy sy	\$ 72.00		
703	Moisture Conditioning			,		_	
		r	Paving Const	ruction (	Jost Subtota	I: Þ	872,073
N I	0 ( )	. <b>.</b>					
Majo	or Construction Component Allowance				A.II		Ham Cast
	Item Description	Notes			Allowance	_	Item Cost
<b>V</b>	Traffic Control	Construction Phase	Traffic Control		30	-	
٧,	Pavement Markings/Markers				39		
V	Roadway Drainage	Standard Internal Sy	stem		259		-,
١,	Special Drainage Structures	None Anticipated				\$	
√,	Water	Incidental Adjustmer	nts		39		
√,	Sewer	Incidental Adjustmer	nts		39	-	•
	Establish Turf / Erosion Control				20	<mark>6</mark> \$	•
	Illumination	Standard Ilumination	System		60	<mark>%</mark> \$	52,324
	Other:						
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	ance Subtota	l: \$	392,433
	Paving and Allowance Subtotal:						1,264,505
	Mobilization: 5%						63,225
			Site Prep	aration:	59	<mark>6</mark> \$	63,225
	Construction Cost TOTAL:						1,391,000
						<mark>6</mark> \$	
Construction Cost TOTAL W/ CONTINGENCY:						: \$	1,600,000

Impact Fee Project Cost Summa	ary			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	1,600,000
Engineering/Survey/Testing:		20%	\$	320,000
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	Existing Alignment	20%	\$	320,000
Impact Fee Project Cost TOTAL:				2,240,000

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

Project Information: Description: Project No. J-9, K-7

Name: STATE HIGHWAY 5 (4) This project consists of the

reconstruction of a four-lane asphalt section to a six-lane divided major

Limits: / FM 546 TO STATE HIGHWAY 121 arterial.

Impact Fee Class: M6D

Thoroughfare Class: Major Arterial

Length (If): 2,470 Service Area(s): J and K

Roa	adway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	it Price		Item Cost
109	Unclassified Street Excavation	13,722	су	\$	15.00	\$	205,833
209	Lime Treated Subgrade (8") (PI<12)	21,407	sy	\$	7.00	\$	149,847
309	4" TY D HMAC Underlayment	20,309	sy	\$	5.00	\$	101,544
409	9" Concrete Pavement	20,309	sy	\$	60.00	\$	1,218,533
509	4" Topsoil	9,606	sy	\$	4.00	\$	38,422
609	6" Curb & Gutter	9,880	lf	\$	5.00	\$	49,400
709	Allotment for Turn Lanes and Median Openings	1,507	sy	\$	87.00	\$	131,141
	Paying Construction Cost Subtotal: 9						1.894.721

	, <b>g</b>	-,
Major Construction Component Allowances**:		

Major Construction Component Allowances**:						
	Item Description	Notes	Allowance		Item Cost	
	Traffic Control	Construction Phase Traffic Control	3%	\$	56,842	
	Pavement Markings/Markers		3%	\$	56,842	
	Roadway Drainage		25%	\$	473,680	
	Special Drainage Structures	Bridge		\$	2,500,000	
	Water	Incidental Adjustments	3%	\$	56,842	
	Sewer	Incidental Adjustments	3%	\$	56,842	
	Establish Turf / Erosion Control		2%	\$	37,894	
	Illumination	Standard Ilumination System	6%	\$	113,683	
	Other:					
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$	3,352,624	
		Paving and Allowa	nce Subtotal:	\$	5,247,345	
		Mobilization:	5%	\$	262,367	
	Site Preparation: 5%					
	Construction Cost TOTAL:					
	Construction Contingency: 15%					
	Construction Cost TOTAL W/ CONTINGENCY:					

Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	6,639,000
Engineering/Survey/Testing:		20%	\$	1,327,800
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	Existing Alignment	20%	\$	1,327,800
Impact Fee Project Cost TOTAL (50% City Contribution)				4,647,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

10/6/2020

updated:

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information: Description: Project No. J-10, K-8

Name: STATE HIGHWAY 5 (5) This project consists of the

STATE HIGHWAY 121 TO 3,525' S reconstruction of a two-lane asphalt

Limits: OF STATE HIGHWAY 121 facility to a four-lane divided minor

Impact Fee Class: M4D arterial.

Thoroughfare Class: Minor Arterial

Length (If): 3,525 Service Area(s): J and K

No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
105	Unclassified Street Excavation	14,100	су	\$	15.00	\$ 211,500
205	Lime Treated Subgrade (8") (PI<12)	19,583	sy	\$	7.00	\$ 137,083
305	4" TY D HMAC Underlayment	18,017	sy	\$	5.00	\$ 90,083
405	8" Concrete Pavement	18,017	sy	\$	55.00	\$ 990,917
505	4" Topsoil	15,275	sy	\$	4.00	\$ 61,100
605	6" Curb & Gutter	14,100	lf	\$	5.00	\$ 70,500
705	Allotment for Turn Lanes and Median Openings	2,070	sy	\$	82.00	\$ 169,707
		Paving Const	ruction (	Cost S	Subtotal:	\$ 1,730,891
Majo	r Construction Component Allowances**:					

Major Construction Component Allowances**:						
	Item Description	Notes	Allowance		Item Cost	
	Traffic Control	Construction Phase Traffic Control	3%	\$	51,927	
	Pavement Markings/Markers		3%	\$	51,927	
	Roadway Drainage		25%	\$	432,723	
	Special Drainage Structures	None Anticipated		\$	-	
	Water	Incidental Adjustments	3%	\$	51,927	
	Sewer	Incidental Adjustments	3%	\$	51,927	
√.	Establish Turf / Erosion Control		2%	\$	34,618	
	Illumination	Standard Ilumination System	6%	\$	103,853	
	Other:					
**Allo	**Allowances based on % of Paving Construction Cost Subtotal Allowance Subtotal:					
		Paving and Allowa	nce Subtotal:	\$	2,509,792	
		Mobilization:	5%	\$	125,490	
	\$	125,490				
Construction Cost TOTAL:					2,761,000	
	Construction Contingency: 15%					
Construction Cost TOTAL W/ CONTINGENCY:					3,176,000	

Impact Fee Project Cost Summa	iry			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	3,176,000
Engineering/Survey/Testing:		20%	\$	635,200
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	Existing Alignment	20%	\$	635,200
Impact Fee Project Cost TOTAL (50% City Contribution)				2,223,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.


updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No. J-11
Name:	STATE HIGHWAY 5 (6)		This project consists of the
3,525' S OF STATE HIGHWAY 121			reconstruction of a two-lane asphalt
TO 4,520' S OF STATE HIGHWAY			facility to a four-lane divided minor
Limits:	121		arterial. Based on the existing City
Impact Fee Class:	M4D		Limits, the eastern half of the roadway
Thoroughfare Class:	Minor Arterial		is not included in the Impact Fee RIP.
Length (If):	995		•
Service Area(s):	J, Half		

Roa	adway Construction Cost Project	ction					
No.	Item Description		Quantity	Unit	Unit Price		Item Cost
105	Unclassified Street Excavation		3,980	су	\$ 15.00	\$	59,700
205	Lime Treated Subgrade (8") (PI<12)		5,528	sy	\$ 7.00	\$	38,694
305	4" TY D HMAC Underlayment		5,086	sy	\$ 5.00	\$	25,428
405	8" Concrete Pavement		5,086	sy	\$ 55.00	\$	279,706
505	4" Topsoil		4,312	sy	\$ 4.00	\$	17,247
605	6" Curb & Gutter		3,980	lf	\$ 5.00	\$	19,900
705	Allotment for Turn Lanes and Median O		584	sy	\$ 82.00	\$	47,903
		P	aving Const	ruction (	Cost Subtotal:	\$	488,578
Major Construction Component Allowances**:							
Iviajo	Item Description	Notes			Allowance	П	Item Cost
	Traffic Control	Construction Phase	Troffic Control		3%	\$	14,657
V	Pavement Markings/Markers	Construction Friase	Trailic Control		3%		14,657
Ì	Roadway Drainage				25%		122,144
•	Special Drainage Structures	None Anticipated			2070	\$	-
	Water	Incidental Adjustmer	nts		3%	-	14,657
Ż	Sewer	Incidental Adjustmer			3%		14,657
V	Establish Turf / Erosion Control				2%		9,772
	Illumination	Standard Ilumination	Svstem		6%		29,315
	Other:		,			ľ	,
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	nce Subtotal:	\$	219,860
					nce Subtotal:	4	708,438
Mobilization: 5%							35,422
			Site Prep			-	35,422
					ost TOTAL:		780,000
			uction Conti				117,000
	Cor	struction Cos	t TOTAL W	// CON	TINGENCY:	\$	897,000

Impact Fee Project Cost Sumi		Allamanaa	Itam Oast
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 897,000
Engineering/Survey/Testing:		20%	\$ 179,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 179,400
Impact I	\$ 627,900		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

Roadway Improvements - Service Area K

	Costing				Percent in		Cost in
#	Class	Project	Limits	Total Cost	Service Area	Se	rvice Area
K-1	2UO	VIRGINIA STREET	225' W OF AIRPORT DR TO AIRPORT DR	\$ 779,650	100%	\$	779,650
K-2	G6D(1/3)	ELDORADO PKWY (4)	1,180' E OF BARRANCA WAY TO STATE HIGHWAY 5	\$ 1,699,200	100%	\$	1,699,200
K-3	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (1)	STATE HIGHWAY 121 TO AIRPORT DR	\$ 1,839,600	100%	\$	1,839,600
K-4, L-1	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (2)	AIRPORT DR TO 980' E OF AIRPORT DR	\$ 234,600	50%	\$	117,300
K-5, L-2	P6D	HARRY MCKILLOP BLVD / FM 546 (3)	975' E OF AIRPORT DR TO 510' W OF HARRY MCKILLOP BLVD / FM 546 (N)	\$ 3,267,400	50%	\$	1,633,700
K-6	M6D	STATE HIGHWAY 5 (3)	INDUSTRIAL BLVD TO 640' S OF HARRY MCKILLOP BLVD / FM 546	\$ 2,064,300	100%	\$	2,064,300
J-9, K-7	M6D	STATE HIGHWAY 5 (4)	640' S OF HARRY MCKILLOP BLVD / FM 546 TO STATE HIGHWAY 121	\$ 4,647,300	50%	\$	2,323,650
J-10, K-8	M4D	STATE HIGHWAY 5 (5)	STATE HIGHWAY 121 TO 3,525' S OF STATE HIGHWAY 121	\$ 2,223,200	50%	\$	1,111,600
K-9, L-6	P6D(1/3)	AIRPORT DR (5)	US HIGHWAY 380 TO 470' N OF HARRY MCKILLOP BLVD / FM 546	\$ 6,322,800	50%	\$	3,161,400
K-10, L-7	P6D	AIRPORT DR (6)	470' N OF HARRY MCKILLOP BLVD / FM 546 TO HARRY MCKILLOP BLVD / FM 546	\$ 2,925,200	50%	\$	1,462,600
40		Signal	STATE HIGHWAY 5 & SMITH ST	\$ 300,000	100%	\$	300,000
41		Signal Mod	US HIGHWAY 380 & AIRPORT DR	\$ 150,000	50%	\$	75,000
52	ction	Roundabout	WILSON CREEK PKWY & PARK VIEW AVE	\$ 1,820,000	100%	\$	1,820,000
53	ectiv	Signal	WILSON CREEK PKWY & COLLEGE ST	\$ 300,000	100%	\$	300,000
54	nters	Signal	AIRPORT DR & ELM ST	\$ 300,000	50%	\$	150,000
62	ᆵ	Signal	STATE HIGHWAY 5 & STEWART RD	\$ 300,000	50%	\$	150,000
63		Signal	HARRY MCKILLOP BLVD / FM 546 & AIRPORT DR	\$ 300,000	75%	\$	225,000
69		Signal	STATE HIGHWAY 5 & ENTERPRISE DR	\$ 300,000	50%	\$	150,000
		-		\$ 29,773,250		\$	19,363,000

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

#### updated:

10/6/2020

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

**Project Information:** K-1 Description: Project No.

Name: VIRGINIA STREET This project consists of the Limits: 225' W OF AIRPORT DR TO AIRPORT DR

225 Length (If): Service Area(s): Κ

construction of a new two-lane **Impact Fee Class: 2UO** undivided town thoroughfare. Thoroughfare Class: Town Thoroughfare

Roa	adway Construction Cost Pro	jection					
No.	Item Description		Quantity	Unit	Ur	nit Price	Item Cost
101	Unclassified Street Excavation		500	су	\$	8.00	\$ 4,000
201	Lime Treated Subgrade (6") (PI<12)		975	sy	\$	5.00	\$ 4,875
301	8" Concrete Pavement		925	sy	\$	55.00	\$ 50,875
401	4" Topsoil		275	sy	\$	2.50	\$ 688
501	6" Curb & Gutter		450	lf	\$	5.00	\$ 2,250
701	Moisture Conditioning		975	sy	\$	8.00	\$ 7,800
		F	Paving Consti	ruction (	Cost	Subtotal:	\$ 70,488
			_				
Majo	or Construction Component Allowa	nces**:					
	Item Description	Notes			All	owance	Item Cost
	Traffic Control	None Anticipated				1%	\$ 705
	Pavement Markings/Markers					3%	\$ 2.115

	Item Description	Notes	Allowance	Item Cost
	Traffic Control	None Anticipated	1%	\$ 705
	Pavement Markings/Markers		3%	\$ 2,115
	Roadway Drainage	Standard Internal System	25%	\$ 17,622
	Special Drainage Structures	Stream Crossing		\$ 300,000
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 1,410
	Illumination	Standard Ilumination System	6%	\$ 4,229
	Other:			
**Allo	owances based on % of Paving Construction Cos	st Subtotal Allowa	nce Subtotal:	\$ 326,080
		Paving and Allowa	nce Subtotal:	\$ 396,568
		Mobilization:	5%	\$ 19,828
	\$ 19,828			
	\$ 437,000			
		Construction Contingency:	15%	\$ 65,550
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$ 503,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 503,000
Engineering/Survey/Testing:		20%	\$ 100,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 176,050
	\$ 779.65		

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

<b>Project Informatio</b>	n:	Description:	Project No.	K-2
Name:	ELDORADO PKWY (4)		This project cons	ists of the
Limits:	1,180' E OF BARRANCA WAY TO STA	TE HIGHWAY 5	construction of tw	vo additional
Impact Fee Class:	G6D(1/3)		through lanes wit	hin the
Thoroughfare Class:	Greenway Arterial		existing median o	
Length (If):	2,110		six-lane divided g	
Service Area(s):	K		arterial	

Roa	adway Construction Cost Projec	ction					
No.	Item Description		Quantity	Unit	Unit Price		Item Cost
117	Unclassified Street Excavation		6,096	су	\$ 10.00	\$	60,956
217	Lime Treated Subgrade (8") (PI<12)		5,861	sy	\$ 7.00	\$	41,028
317	9" Concrete Pavement		5,392	sy	\$ 60.00	\$	323,533
417	4" Topsoil		5,627	sy	\$ 2.50	\$	14,067
517	6" Curb & Gutter		4,220	lf	\$ 5.00	\$	21,100
617	Allotment for Turn Lanes and Median O	penings	1,458	sy	\$ 77.00	\$	112,279
Paving Construction Cost Subtotal:							572,963
Majo	Major Construction Component Allowances**:						
	Item Description	Notes			Allowance		Item Cost
$\sqrt{}$	Traffic Control	Construction Phase	Traffic Control		3%		17,189
	Pavement Markings/Markers				3%	,	17,189
,	Roadway Drainage	None Anticipated			0%		-
	Special Drainage Structures	Stream Crossing				\$	500,000
	Water	None Anticipated			0%		-
١,	Sewer	None Anticipated			0%	,	-
	Establish Turf / Erosion Control				2%		11,459
	Illumination	None Anticipated			0%	\$	-
	Other:						
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce Subtotal:	\$	545,837
						\$	
Paving and Allowance Subtotal:							1,118,800
Mobilization: 5%						4 :	55,940
			Site Prep				55,940
					ost TOTAL:		1,231,000
		Constr	uction Conti	ngency:	15%	\$	184,650
	Cor	struction Cos	t TOTAL W	// CON	TINGENCY:	\$	1,416,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,416,000
Engineering/Survey/Testing:		20%	\$ 283,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. K-3

Name: HARRY MCKILLOP BLVD / FM 546 (1) This project consists of the

Limits: STATE HIGHWAY 121 TO AIRPORT DR construction of two additional through

Impact Fee Class: P6D(1/3) Ianes within the existing median of the Ultimate six-lane divided principal

Length (If): 7,695 arterial.

Service Area(s):

Roa	adway Construction Cost Projec	tion						
	Item Description		Quantity	Unit	Ur	it Price		Item Cost
114	Unclassified Street Excavation		11,970	су	\$	15.00	\$	179,550
214	Lime Treated Subgrade (8") (PI<12)		23,085	sy	\$	7.00	\$	161,595
	4" TY D HMAC Underlayment		21,375	sy	\$	5.00	\$	106,875
414	9" Concrete Pavement		21,375	sy	\$	60.00	\$	1,282,500
514	4" Topsoil		6,840	sy	\$	4.00	\$	27,360
614	6" Curb & Gutter		15,390	lf	\$	5.00	\$	76,950
714	Allotment for Turn Lanes and Median Op	enings	4,696	sy	\$	87.00	\$	408,554
		Р	aving Constr	uction C	Cost	Subtotal:	\$	2,243,384
Majo	or Construction Component Allowance	s**:						
	Item Description	Notes			All	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	\$	67,302
	Pavement Markings/Markers					3%	\$	67,302
	Roadway Drainage					0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	44,868
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	nce :	Subtotal:	\$	179,471
								2,422,855
							\$	121,143
			Site Prep			5%	\$	121,143
			Construc				\$	2,666,000
			uction Conti			15%	\$	399,900
	Con	struction Cos	t TOTAL W	/ CON	TINC	BENCY:	\$	3,066,000

Impact Fee Project Cost Summa	ry			
Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	3,066,000
Engineering/Survey/Testing:		20%	\$	613,200
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$	-
Impact Fee	<b>\$</b>	1,839,600		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

10/6/2020

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated:

**Project Information:** K-4, L-1 Description: Project No.

Name: HARRY MCKILLOP BLVD / FM 546 (2)

Limits: AIRPORT DR TO 980' E OF AIRPORT DR

**Impact Fee Class:** P6D(1/3)

Thoroughfare Class: Principal Arterial

Length (If): Service Area(s): L and K

980

This project consists of the

construction of two additional through lanes within the existing median of the ultimate six-lane divided principal

arterial.

Roa	adway Construction Cost Projection							
No.	Item Description	Quantity	Unit	Unit Price			Item Cost	
114	Unclassified Street Excavation	1,524	су	\$	15.00	\$	22,867	
214	Lime Treated Subgrade (8") (PI<12)	2,940	sy	\$	7.00	\$	20,580	
314	4" TY D HMAC Underlayment	2,722	sy	\$	5.00	\$	13,611	
414	9" Concrete Pavement	2,722	sy	\$	60.00	\$	163,333	
514	4" Topsoil	871	sy	\$	4.00	\$	3,484	
614	6" Curb & Gutter	1,960	lf	\$	5.00	\$	9,800	
714	Allotment for Turn Lanes and Median Openings	598	sy	\$	87.00	\$	52,032	

Paving Construction Cost Subtotal: \$ 285,707

Majo	or Construction Component Allowar	ices**:		
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$ 8,571
	Pavement Markings/Markers		3%	\$ 8,571
	Roadway Drainage		0%	\$ -
	Special Drainage Structures	None Anticipated		\$ -
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 5,714
	Illumination	None Anticipated	0%	\$ -
	Other:			
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$ 22,857
		Paving and Allowa	nce Subtotal:	\$ 308,564
		Mobilization:	5%	\$ 15,428
		Site Preparation:	5%	\$ 15,428
	\$ 340,000			
		Construction Contingency:	15%	\$ 51,000
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$ 391,000

Impact Fee Project Cost Summa	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 391,000
Engineering/Survey/Testing:		20%	\$ 78,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
Impact Fe	e Project Cost TOTAL (50% City (	Contribution)	\$ 234,600

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc. updated: 10/6/2020

Project No.

Project Information: Description:

Name: HARRY MCKILLOP BLVD / FM 546 (3)

975' E OF AIRPORT DR TO 510' W OF HARRY

MCKILLOP BLVD / FM 546 (N)

Limits: MCKILLOP BL Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 3,160
Service Area(s): K and L

This project consists of the construction of a new six-lane divided principal arterial.

Roa	adway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Ur	nit Price		Item Cost
113	Unclassified Street Excavation	17,556	су	\$	15.00	\$	263,333
213	Lime Treated Subgrade (8") (PI<12)	27,387	sy	\$	7.00	\$	191,707
313	4" TY D HMAC Underlayment	25,982	sy	\$	5.00	\$	129,911
413	9" Concrete Pavement	25,982	sy	\$	60.00	\$	1,558,933
513	4" Topsoil	14,396	sy	\$	4.00	\$	57,582
613	6" Curb & Gutter	12,640	lf	\$	5.00	\$	63,200
713	Allotment for Turn Lanes and Median Openings	1,928	sy	\$	87.00	\$	167,775
	Paving Construction Cost Subtotal: \$						2,432,442

Maj	or Construction Component Allowand	-				
	Item Description	Notes	Allowance		Item Cost	
	Traffic Control	None Anticipated	1%	\$	24,324	
	Pavement Markings/Markers		3%	\$	72,973	
	Roadway Drainage		25%	\$	608,110	
	Special Drainage Structures	None Anticipated		\$	-	
	Water	None Anticipated	0%	\$	-	
	Sewer	None Anticipated	0%	\$	-	
	Establish Turf / Erosion Control		2%	\$	48,649	
	Illumination	Standard Ilumination System	6%	\$	145,947	
	Other:					
**Allo	wances based on % of Paving Construction Cos	t Subtotal Allowa	nce Subtotal:	\$	900,004	
		Paving and Allowa	nce Subtotal:	\$	3,332,445	
		Mobilization:	5%	\$	166,622	
		Site Preparation:	5%	\$	166,622	
	Construction Cost TOTAL:					
		Construction Contingency:	15%	\$	549,900	
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	4,216,000	

Impact Fee Project Cost Summa	ry		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,216,000
Engineering/Survey/Testing:		20%	\$ 843,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,475,600
Impact Fed	e Project Cost TOTAL (50% City C	ontribution)	\$ 3,267,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Project Information: Description: Project No. K-6

Name: STATE HIGHWAY 5 (3) This project consists of the

INDUSTRIAL BLVD TO 640' S OF reconstruction of a four-lane asphalt
Limits: HARRY MCKILLOP BLVD / FM 546 section to a six-lane divided major

Impact Fee Class: M6D arterial.

Thoroughfare Class: Major Arterial

Length (If): 2,095 Service Area(s): K

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Uı	nit Price	Item Cost
109	Unclassified Street Excavation	11,639	су	\$	15.00	\$ 174,583
209	Lime Treated Subgrade (8") (PI<12)	18,157	sy	\$	7.00	\$ 127,097
309	4" TY D HMAC Underlayment	17,226	sy	\$	5.00	\$ 86,128
409	9" Concrete Pavement	17,226	sy	\$	60.00	\$ 1,033,533
509	4" Topsoil	8,147	sy	\$	4.00	\$ 32,589
609	6" Curb & Gutter	8,380	lf	\$	5.00	\$ 41,900
709	Allotment for Turn Lanes and Median Openings	1,279	sy	\$	87.00	\$ 111,231

Paving Construction Cost Subtotal: \$ 1,607,061

Mai	or Construction Component Allowa	ncac**•			
Iviaj	Item Description	Notes	Allowance		Item Cost
	Traffic Control	Construction Phase Traffic Control	3%	\$	48,212
	Pavement Markings/Markers		3%	\$	48,212
	Roadway Drainage		25%	\$	401,765
	Special Drainage Structures	None Anticipated		\$	-
	Water	Incidental Adjustments	3%	\$	48,212
	Sewer	Incidental Adjustments	3%	\$	48,212
	Establish Turf / Erosion Control		2%	\$	32,141
	Illumination	Standard Ilumination System	6%	\$	96,424
	Other:				
**Allo	wances based on % of Paving Construction C	ost Subtotal Allowa	nce Subtotal:	\$	723,177
		5	0.14.4.1		2 222 222
		Paving and Allowa		_	2,330,238
		Mobilization:	5%	\$	116,512
		Site Preparation:		\$ <b>\$</b>	116,512 <b>2,564,000</b>
	Construction Cost TOTAL:				
		Construction Contingency:	15%	\$	384,600
		Construction Cost TOTAL W/ CON	TINGENCY:	\$	2,949,000

Impact Fee Project Cost Sumn	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,949,000
Engineering/Survey/Testing:		20%	\$ 589,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 589,800
Impact F	ee Project Cost TOTAL (50%	<b>City Contribution)</b>	\$ 2,064,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

updated: 10/6/2020

Project Information: Description: Project No. J-9, K-7

Name: STATE HIGHWAY 5 (4) This project consists of the

reconstruction of a four-lane asphalt section to a six-lane divided major

Limits: / FM 546 TO STATE HIGHWAY 121 arterial.

Impact Fee Class: M6D

Thoroughfare Class: Major Arterial

Length (If): 2,470 Service Area(s): J and K

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	it Price	Item Cost
109	Unclassified Street Excavation	13,722	су	\$	15.00	\$ 205,833
209	Lime Treated Subgrade (8") (PI<12)	21,407	sy	\$	7.00	\$ 149,847
309	4" TY D HMAC Underlayment	20,309	sy	\$	5.00	\$ 101,544
409	9" Concrete Pavement	20,309	sy	\$	60.00	\$ 1,218,533
509	4" Topsoil	9,606	sy	\$	4.00	\$ 38,422
609	6" Curb & Gutter	9,880	lf	\$	5.00	\$ 49,400
709	Allotment for Turn Lanes and Median Openings	1,507	sy	\$	87.00	\$ 131,141
		Paving Const	ruction (	ost	Subtotal:	\$ 1.894.721

	, <b>g</b>	-,
Major Construction Component Allowances**:		

Maj	Major Construction Component Allowances**:							
	Item Description	Notes	Allowance		Item Cost			
	Traffic Control	Construction Phase Traffic Control	3%	\$	56,842			
	Pavement Markings/Markers		3%	\$	56,842			
	Roadway Drainage		25%	\$	473,680			
	Special Drainage Structures	Bridge		\$	2,500,000			
	Water	Incidental Adjustments	3%	\$	56,842			
	Sewer	Incidental Adjustments	3%	\$	56,842			
	Establish Turf / Erosion Control		2%	\$	37,894			
	Illumination	Standard Ilumination System	6%	\$	113,683			
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal Allowa	nce Subtotal:	\$	3,352,624			
		Paving and Allowa	nce Subtotal:	\$	5,247,345			
		Mobilization:	5%	\$	262,367			
		Site Preparation:	5%	\$	262,367			
	Construction Cost TOTAL:							
		Construction Contingency:	15%	\$	865,950			
	Со	nstruction Cost TOTAL W/ CON	TINGENCY:	\$	6,639,000			

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 6,639,000
Engineering/Survey/Testing:		20%	\$ 1,327,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 1,327,800
Impact I	Fee Project Cost TOTAL (50% City C	ontribution)	\$ 4,647,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc. updated: 10/6/2020

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information: Description: Project No. J-10, K-8

Name: STATE HIGHWAY 5 (5) This project consists of the

STATE HIGHWAY 121 TO 3,525' S reconstruction of a two-lane asphalt

Limits: OF STATE HIGHWAY 121 facility to a four-lane divided minor

Impact Fee Class: M4D arterial.

Thoroughfare Class: Minor Arterial

Length (If): 3,525 Service Area(s): J and K

KO	adway Construction Cost Proj	ection						
No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
105	Unclassified Street Excavation		14,100	су	\$	15.00	\$	211,500
205	Lime Treated Subgrade (8") (PI<12)		19,583	sy	\$	7.00	\$	137,083
305	4" TY D HMAC Underlayment		18,017	sy	\$	5.00	\$	90,083
405	8" Concrete Pavement		18,017	sy	\$	55.00	\$	990,917
505	4" Topsoil		15,275	sy	\$	4.00	\$	61,100
605	6" Curb & Gutter		14,100	lf	\$	5.00	\$	70,500
705	Allotment for Turn Lanes and Median	Openings	2,070	sy	\$	82.00	\$	169,707
			Paving Consti	ruction (	Cost	Subtotal:	\$	1,730,891
Majo	or Construction Component Allowar	Major Construction Component Allowances**:						
	Item Description	Notes			All	owance		Item Cost
<b>√</b>	Item Description Traffic Control		Traffic Control		All	owance 3%	\$	Item Cost 51,927
√ √	·	Notes	Traffic Control	_	All			
,	Traffic Control	Notes	Traffic Control		All	3%	\$	51,927
$\sqrt{}$	Traffic Control Pavement Markings/Markers	Notes	Traffic Control		All	3% 3%	\$	51,927 51,927
V	Traffic Control Pavement Markings/Markers Roadway Drainage	Notes  Construction Phase			All	3% 3%	\$ \$ \$	51,927 51,927
1	Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures	Notes  Construction Phase  None Anticipated	ents		All	3% 3% 25%	\$ \$ \$ \$	51,927 51,927 432,723
\[ \sqrt{1} \]	Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water	Notes  Construction Phase  None Anticipated Incidental Adjustmental	ents		All	3% 3% 25% 3%	\$ \$ \$ \$ \$	51,927 51,927 432,723 - 51,927
\[ \sqrt{1} \]	Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer	Notes  Construction Phase  None Anticipated Incidental Adjustmental	ents ents		All	3% 3% 25% 3% 3%	\$ \$ \$ \$ \$ \$ \$	51,927 51,927 432,723 - 51,927 51,927
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer Establish Turf / Erosion Control	Notes  Construction Phase  None Anticipated Incidental Adjustme	ents ents		All	3% 3% 25% 3% 3% 2%	\$ \$ \$ \$ \$ \$ \$	51,927 51,927 432,723 - 51,927 51,927 34,618

**Allowances based on % of Paving Construction Cost Subtotal	Allowa	nce Subtotal:	\$ 778,901
	Paving and Allowa	nce Subtotal:	\$ 2,509,792
	Mobilization:	5%	\$ 125,490
	Site Preparation:	5%	\$ 125,490
	Construction Co	ost TOTAL:	\$ 2,761,000
Cor	nstruction Contingency:	15%	\$ 414,150
Construction C	ost TOTAL W/ CONT	INGENCY:	\$ 3,176,000

Impact Fee Project Cost Summa	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,176,000
Engineering/Survey/Testing:		20%	\$ 635,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	Existing Alignment	20%	\$ 635,200
Impact Fe	e Project Cost TOTAL (50%	City Contribution)	\$ 2,223,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information:	Description:	Project No.	K-9, L-6
----------------------	--------------	-------------	----------

Name: AIRPORT DR (5) This project consists of the

US HIGHWAY 380 TO 470' N OF construction of two additional through

Limits: HARRY MCKILLOP BLVD / FM 546 lanes within the existing median of the

Impact Fee Class: P6D(1/3) ultimate six-lane divided principal

Thoroughfare Class: Principal Arterial arterial.

Length (If): arterial

Length (If): 13,870 Service Area(s): K and L

Roa	dway Construction Cost Proj	ection						
	Item Description		Quantity	Unit	Un	it Price		Item Cost
114	Unclassified Street Excavation 43,151 cy \$ 10.00						\$	431,511
214	Lime Treated Subgrade (8") (PI<12)		41,610	sy	\$	7.00	\$	291,270
314	9" Concrete Pavement		38,528	sy	\$	60.00	\$	2,311,667
414	4" Topsoil		12,329	sy	\$	2.50	\$	30,822
514	6" Curb & Gutter		27,740	lf	\$	5.00	\$	138,700
614	Allotment for Turn Lanes and Median	Openings	8,464	sy	\$	77.00	\$	651,762
		P	aving Constr	uction (	Cost	Subtotal:	\$	3,855,732
Majo	or Construction Component Allowar							
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%		115,672
	Pavement Markings/Markers					3%	\$	115,672
	Roadway Drainage	None Anticipated				0%	\$	-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%		-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	77,115
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Co	st Subtotal		Allowa	nce S	Subtotal:	\$	308,459
			Paving and		nce S		\$	4,164,190
				lization:		5%	\$	208,210
			Site Prep		_	5%	_	208,210
			Construc					4,581,000
			ruction Conti			15%	\$	687,150
	Co	onstruction Cos	st TOTAL W	// CON	TING	SENCY:	\$	5,269,000

Notes:	Allowance		Item Cost
	-	\$	5,269,000
	20%	\$	1,053,800
		\$	-
		\$	-
No ROW Acquisition Costs included	0%	\$	-
			6,322,80
	No ROW Acquisition Costs included	No ROW Acquisition Costs included 0%	20% \$ \$ \$

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.


updated: 10/6/2020

<b>Project Informatio</b>	n: De	escription:	Project No. K-10, L-7
Name:	AIRPORT DR (6)		This project consists of the
	470' N OF HARRY MCKILLOP BLVD / F	M 546 TO	reconstruction of a two-lane asphalt
Limits:	HARRY MCKILLOP BLVD / FM 546		facility to a six-lane divided principal
Impact Fee Class:	P6D		arterial. The City contributed
Thoroughfare Class:	Principal Arterial		approximately \$1,500,000 of eligible
Length (If):	470		funds from '12-'19.
Service Area(s):	K and L		

00										
В	advery Construction Cost Dusing	4ion								
No.	dway Construction Cost Project Item Description	ction	Quantity	Unit	Unit Price		Item Cost			
113	Unclassified Street Excavation 5,222 cy \$					\$	52,222			
213	Lime Treated Subgrade (8") (PI<12)		4,073	sy	\$ 7.00	\$	28,513			
313	9" Concrete Pavement		3,864	sy	\$ 60.00	\$	231,867			
413	4" Topsoil		2,141	sy	\$ 2.50	\$	5,353			
513	6" Curb & Gutter		1,880	lf	\$ 5.00	\$	9,400			
613	Allotment for Turn Lanes and Median O	penings	287	sy	\$ 77.00	\$	22,086			
713	Moisture Conditioning	-	4,073	sy	\$ 8.00	\$	32,587			
	•	P	aving Const	ruction (	Cost Subtotal:	\$	382,027			
Majo	or Construction Component Allowance									
	Item Description	Notes			Allowance		Item Cost			
	Traffic Control	Construction Phase	Traffic Control		3%		11,461			
√,	Pavement Markings/Markers				3%		11,461			
	Roadway Drainage	Standard Internal Sy	rstem		25%		95,507			
$\sqrt{}$	Special Drainage Structures	Stream Crossing				\$	250,000			
	Water	Incidental Adjustmer	nts		3%	\$	11,461			
	Sewer	Incidental Adjustmer	nts		3%	\$	11,461			
	Establish Turf / Erosion Control				2%	\$	7,641			
	Illumination	Standard Ilumination	System		6%	\$	22,922			
	Other:									
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	ınce Subtotal:	\$	421,912			
					nce Subtotal:		803,940			
				lization:	5%	\$	40,197			
			Site Prep		5%	_	40,197			
			Construc	ction C	ost TOTAL:	\$	885,000			
		Constr	uction Conti	ngency:	15%	\$	132,750			
	Cor	struction Cos	t TOTAL W	// CON	TINGENCY:	\$	1,018,000			

Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	1,018,000
Engineering/Survey/Testing:		20%	\$	203,600
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	1,500,000
ROW/Easement Acquisition:	Existing Alignment	20%	\$	203,600
		roject Cost TOTAL:	_	2,925,20

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

Roadway Improvements - Service Area L

	Costing					Percent in		Cost in
#	Class	Project	Limits	T	otal Cost	Service Area	Ser	rvice Area
K-4, L-1	P6D(1/3)	HARRY MCKILLOP BLVD / FM 546 (2)	AIRPORT DR TO 980' E OF AIRPORT DR	\$	234,600	50%	\$	117,300
K-5, L-2	P6D	HARRY MCKILLOP BLVD / FM 546 (3)	975' E OF AIRPORT DR TO 510' W OF HARRY MCKILLOP BLVD / FM 546 (N)	\$	3,267,400	50%	\$	1,633,700
L-3	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (1)	510' W OF HARRY MCKILLOP BLVD / FM 546 (N) TO 1,335' E OF HARRY MCKILLOP BLVD / FM 546 (N)	\$	2,153,725	100%	\$	2,153,725
L-4	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (2)	3,480' W OF UNNAMED D TO UNNAMED D	\$	3,843,225	100%	\$	3,843,225
L-5	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (1)	HARRY MCKILLOP BLVD / FM 546 (S) TO 1,865' E OF HARRY MCKILLOP BLVD / FM 546 (S)	\$	2,166,900	100%	\$	2,166,900
K-9, L-6	P6D(1/3)	AIRPORT DR (5)	US HIGHWAY 380 TO 470' N OF HARRY MCKILLOP BLVD / FM 546	\$	6,322,800	50%	\$	3,161,400
K-10, L-7	P6D	AIRPORT DR (6)	470' N OF HARRY MCKILLOP BLVD / FM 546 TO HARRY MCKILLOP BLVD / FM 546	\$	2,925,200	50%	\$	1,462,600
L-8	P6D	UNNAMED C (3)	US HIGHWAY 380 TO 2,435' S OF US HIGHWAY 380	\$	5,807,850	100%	\$	5,807,850
L-9, M-5	P6D	UNNAMED C (4)	2,525' N OF HARRY MCKILLOP BLVD / FM 546 TO 1,230' N OF HARRY MCKILLOP BLVD / FM 546	\$	2,830,300	50%	\$	1,415,150
L-10, M-6	P6D	UNNAMED C (5)	HARRY MCKILLOP BLVD / FM 546 (N) TO 705' S OF HARRY MCKILLOP BLVD / FM 546 (S)	\$	10,002,150	50%	\$	5,001,075
41		Signal Mod	US HIGHWAY 380 & AIRPORT DR	\$	150,000	50%	\$	75,000
42		Signal	US HIGHWAY 380 & UNNAMED C	\$	300,000	50%	\$	150,000
54	Inter-	Signal	AIRPORT DR & ELM ST	\$	300,000	50%	\$	150,000
63	section	Signal	HARRY MCKILLOP BLVD / FM 546 & AIRPORT DR	\$	300,000	75%	\$	225,000
70		Signal	HARRY MCKILLOP BLVD / FM 546 (S) & HARRY MCKILLOP BLVD / FM 546 (N)	\$	300,000	100%	\$	300,000
74		Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (S)	\$	300,000	50%	\$	150,000
		-	<u> </u>	\$	41,204,150		\$	27,812,925

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

**Project Information:** 

Kimley-Horn and Associates, Inc.

10/6/2020

2019 Roadway Impact Fee Update

Conceptual Level Project Cost Projection

K-4, L-1 Description: Project No.

Name: HARRY MCKILLOP BLVD / FM 546 (2)

Limits: AIRPORT DR TO 980' E OF AIRPORT DR

Impact Fee Class: P6D(1/3) Thoroughfare Class: Principal Arterial

Length (If): 980

Service Area(s): L and K This project consists of the

construction of two additional through lanes within the existing median of the ultimate six-lane divided principal

updated:

arterial.

Roa	dway Construction Cost Projection																					
No.	Item Description	Quantity	Unit	Ur	Unit Price		Unit Price		Unit Price		Unit Price		Unit Price		Unit Price		Unit Price		Unit Price		Item Cost	
114	Unclassified Street Excavation	1,524	су	\$	15.00	\$	22,867															
214	Lime Treated Subgrade (8") (PI<12)	2,940	sy	\$	7.00	\$	20,580															
314	4" TY D HMAC Underlayment	2,722	sy	\$	5.00	\$	13,611															
414	9" Concrete Pavement	2,722	sy	\$	60.00	\$	163,333															
514	4" Topsoil	871	sy	\$	4.00	\$	3,484															
614	6" Curb & Gutter	1,960	lf	\$	5.00	\$	9,800															
714	Allotment for Turn Lanes and Median Openings	598	sy	\$	87.00	\$	52,032															

Paving Construction Cost Subtotal: \$ 285,707

Majo	or Construction Component Allowa							
	Item Description	Notes	Allowance		Item Cost			
	Traffic Control	Construction Phase Traffic Control	3%	\$	8,571			
	Pavement Markings/Markers		3%	\$	8,571			
	Roadway Drainage		0%	\$	-			
	Special Drainage Structures	None Anticipated		\$	-			
	Water	None Anticipated	0%	\$	-			
	Sewer	None Anticipated	0%	\$	-			
	Establish Turf / Erosion Control		2%	\$	5,714			
	Illumination	None Anticipated	0%	\$	-			
	Other:							
**Allo	wances based on % of Paving Construction C	ost Subtotal Allowa	nce Subtotal:	\$	22,857			
		Paving and Allowa	nce Subtotal:	\$	308,564			
		Mobilization:	5%	\$	15,428			
		Site Preparation:	5%	\$	15,428			
	Construction Cost TOTAL:							
		Construction Contingency:	15%	\$	51,000			
	C	Construction Cost TOTAL W/ CON	TINGENCY:	\$	391,000			

Impact Fee Project Cost Summar	у		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 391,000
Engineering/Survey/Testing:		20%	\$ 78,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -
Impact Fee	Project Cost TOTAL (50% City (	Contribution)	\$ 234,600

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. K-5, L-

Name: HARRY MCKILLOP BLVD / FM 546 (3) This project consists of the construction

975' E OF AIRPORT DR TO 510' W OF HARRY of a new six-lane divided principal

Limits: MCKILLOP BLVD / FM 546 (N) arterial.

Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 3,160
Service Area(s): K and L

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ur	nit Price	Item Cost
113	Unclassified Street Excavation	17,556	су	\$	15.00	\$ 263,333
213	Lime Treated Subgrade (8") (PI<12)	27,387	sy	\$	7.00	\$ 191,707
313	4" TY D HMAC Underlayment	25,982	sy	\$	5.00	\$ 129,911
413	9" Concrete Pavement	25,982	sy	\$	60.00	\$ 1,558,933
513	4" Topsoil	14,396	sy	\$	4.00	\$ 57,582
613	6" Curb & Gutter	12,640	lf	\$	5.00	\$ 63,200
713	Allotment for Turn Lanes and Median Openings	1,928	sy	\$	87.00	\$ 167,775
		Paving Const	ruction (	Cost	Subtotal:	\$ 2,432,442

Mai	Major Construction Component Allowances**:								
Iviaj			Allowonoo		Ham Coot				
	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	None Anticipated	1%	\$	24,324				
	Pavement Markings/Markers		3%	\$	72,973				
	Roadway Drainage		25%	\$	608,110				
	Special Drainage Structures	None Anticipated		\$	-				
	Water	None Anticipated	0%	\$	-				
	Sewer	None Anticipated	0%	\$	-				
	Establish Turf / Erosion Control		2%	\$	48,649				
	Illumination	Standard Ilumination System	6%	\$	145,947				
	Other:				·				
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	900,004				
		Paving and Allowa	nce Subtotal:	\$	3,332,445				
		Mobilization:	5%	\$	166,622				
	\$	166,622							
	\$	3,666,000							
	\$	549,900							
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	4,216,000				

Impact Fee Project Cost Summa	ry		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,216,000
Engineering/Survey/Testing:		20%	\$ 843,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,475,600
Impact Fee	Project Cost TOTAL (50% City C	ontribution)	\$ 3,267,400

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. L-3

Name: HARRY MCKILLOP BLVD / FM 546 (S) (1) This project consists of the construction

510' W OF HARRY MCKILLOP BLVD / FM 546 (N) of a new six-lane divided principal

TO 1,335' E OF HARRY MCKILLOP BLVD / FM arterial

Limits: 546 (N)
Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 1,845 Service Area(s): L

	dway Construction Cost Proje	ction						
No.	Item Description		Quantity	Unit	Ur	nit Price		Item Cost
113	Unclassified Street Excavation		10,250	су	\$	15.00	\$	153,750
213	Lime Treated Subgrade (8") (PI<12)		15,990	sy	\$	7.00	\$	111,930
313	4" TY D HMAC Underlayment		15,170	sy	\$	5.00	69	75,850
413	9" Concrete Pavement		15,170	sy	\$	60.00	\$	910,200
	4" Topsoil		8,405	sy	\$	4.00	<b>65</b>	33,620
613	6" Curb & Gutter		7,380	lf	\$	5.00	\$	36,900
713	Allotment for Turn Lanes and Median (	Openings	1,126	sy	\$	87.00	\$	97,957
		F	Paving Consti	ruction (	Cost	Subtotal:	\$	1,420,207
			_					
Majo	r Construction Component Allowand	es**:						
	Item Description	Notes			All	lowance		Item Cost
	Traffic Control	None Anticipated				1%	\$	14,202
	Pavement Markings/Markers					3%	\$	42,606
	Roadway Drainage					25%	\$	355,052
	Special Drainage Structures	Stream Crossing					\$	250,000
	Water	None Anticipated				0%	\$	-
	Sewer	None Anticipated				0%	\$	-
	Establish Turf / Erosion Control					2%	\$	28,404
	Illumination	Standard Ilumination	n System			6%	\$	85,212
	Other:							
**Allo	wances based on % of Paving Construction Cost	Subtotal		Allowa	nce	Subtotal:	\$	775,477
	Paving and Allowance Subtotal:							2,195,684
	Mobilization: 5%						\$	109,784
	Site Preparation: 5%					\$	109,784	
			Construc		_	TOTAL:	\$	2,416,000
			ruction Conti			15%	-	362,400 <b>2,779,000</b>
	Co	nstruction Cos	Construction Cost TOTAL W/ CONTINGENCY:					

Impact Fee Project Cost Summar	у		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,779,000
Engineering/Survey/Testing:		20%	\$ 555,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 972,650
Impact Fee	Project Cost TOTAL (50% City Co	ontribution)	\$ 2,153,725

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. L-4

Name: HARRY MCKILLOP BLVD / FM 546 (S) (2) This project consists of the

Limits: 3,480' W OF UNNAMED D TO UNNAMED D construction of a new six-lane divided

Impact Fee Class: P6D principal arterial.

Thoroughfare Class: Principal Arterial

Length (If): 3,480 Service Area(s):

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	U	nit Price	Item Cost
113	Unclassified Street Excavation	19,333	су	\$	15.00	\$ 290,000
213	Lime Treated Subgrade (8") (PI<12)	30,160	sy	\$	7.00	\$ 211,120
313	4" TY D HMAC Underlayment	28,613	sy	\$	5.00	\$ 143,067
413	9" Concrete Pavement	28,613	sy	\$	60.00	\$ 1,716,800
513	4" Topsoil	15,853	sy	\$	4.00	\$ 63,413
613	6" Curb & Gutter	13,920	lf	\$	5.00	\$ 69,600
713	Allotment for Turn Lanes and Median Openings	2,124	sy	\$	87.00	\$ 184,765

Paving Construction Cost Subtotal: \$ 2,678,765

Maj	Major Construction Component Allowances**:								
	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	None Anticipated	1%	\$	26,788				
	Pavement Markings/Markers		3%	\$	80,363				
	Roadway Drainage		25%	\$	669,691				
	Special Drainage Structures	Stream Crossing		\$	250,000				
	Water	None Anticipated	0%	\$	-				
	Sewer	None Anticipated	0%	\$	-				
	Establish Turf / Erosion Control		2%	\$	53,575				
	Illumination	Standard Ilumination System	6%	\$	160,726				
	Other:								
**Allo	wances based on % of Paving Construction Co	ost Subtotal Allowa	nce Subtotal:	\$	1,241,143				
		Paving and Allowa	nce Subtotal:	\$	3,919,908				
		Mobilization:	5%	\$	195,995				
		Site Preparation:	5%	\$	195,995				
		Construction C	ost TOTAL:	\$	4,312,000				
		Construction Contingency:	15%	\$	646,800				
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	4,959,000				

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 4,959,000
Engineering/Survey/Testing:		20%	\$ 991,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,735,650

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

# 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information: Description: Project No. L-5

Name: HARRY MCKILLOP BLVD / FM 546 (N) (1) This project consists of the construction HARRY MCKILLOP BLVD / FM 546 (S) TO 1,865' of a new six-lane divided major arterial.

Limits: E OF HARRY MCKILLOP BLVD / FM 546 (S)

Impact Fee Class: M6D

Thoroughfare Class: Major Arterial

Length (If): 1,865 Service Area(s): L

Roa	dway Construction Cost Proje	ection					
No.	Item Description		Quantity	Unit	Unit Price		Item Cost
109	Unclassified Street Excavation		10,361	су	\$ 15.00	\$	155,417
209	Lime Treated Subgrade (8") (PI<12)		16,163	sy	\$ 7.00	\$	113,143
309	4" TY D HMAC Underlayment		15,334	sy	\$ 5.00	\$	76,672
	9" Concrete Pavement		15,334	sy	\$ 60.00	\$	920,067
	4" Topsoil		7,253	sy	\$ 4.00	\$	29,011
	6" Curb & Gutter		7,460	lf	\$ 5.00	\$	37,300
709	Allotment for Turn Lanes and Median		1,138	sy	\$ 87.00	\$	99,019
		F	Paving Const	ruction (	Cost Subtotal:	\$	1,430,629
Majo	or Construction Component Allowan						
	Item Description	Notes			Allowance		Item Cost
	Traffic Control	None Anticipated			1%	\$	14,306
	Pavement Markings/Markers				3%		42,919
	Roadway Drainage				25%	\$	357,657
	Special Drainage Structures	Stream Crossing				\$	250,000
	Water	None Anticipated			0%	\$	-
	Sewer	None Anticipated			0%	\$	-
	Establish Turf / Erosion Control				2%	\$	28,613
	Illumination	Standard Ilumination	n System		6%	\$	85,838
	Other:						
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce Subtotal:	\$	779,333
			•		nce Subtotal:	\$	2,209,962
	Mobilization: 5%						110,498
			Site Prep				110,498
					ost TOTAL:		<b>2,431,000</b> 364,650
	Construction Contingency: 15%						

Impact Fee Project Cost Summa	ry		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 2,796,000
Engineering/Survey/Testing:		20%	\$ 559,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 978,600
Impact Fee	Project Cost TOTAL (50% City Co	ontribution)	\$ 2,166,900

Construction Cost TOTAL W/ CONTINGENCY:

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

2,796,000

2019 Roadway Impact Fee Update
Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. K-9, L-6

Name: AIRPORT DR (5) This project consists of the

US HIGHWAY 380 TO 470' N OF construction of two additional through

Limits: HARRY MCKILLOP BLVD / FM 546 lanes within the existing median of the

Impact Fee Class: P6D(1/3) ultimate six-lane divided principal Thoroughfare Class: Principal Arterial arterial

ngth (If): arterial arterial arterial.

Length (If): 13,870 Service Area(s): K and L

Roa	dway Construction Cost Proje	ection						
	Item Description		Quantity	Unit	Un	it Price		Item Cost
114	Unclassified Street Excavation 43,151 cy			\$	10.00	\$	431,511	
214	Lime Treated Subgrade (8") (PI<12)		41,610	sy	\$	7.00	\$	291,270
314	9" Concrete Pavement		38,528	sy	\$	60.00	\$	2,311,667
414	4" Topsoil		12,329	sy	\$	2.50	\$	30,822
	6" Curb & Gutter		27,740	lf	\$	5.00	\$	138,700
614	Allotment for Turn Lanes and Median (	Openings	8,464	sy	\$	77.00	\$	651,762
		P	aving Constr	uction (	Cost S	Subtotal:	\$	3,855,732
Majo	or Construction Component Allowan							
	Item Description	Notes			Alle	owance		Item Cost
	Traffic Control	Construction Phase	Traffic Control			3%	_	115,672
	Pavement Markings/Markers					3%		115,672
	Roadway Drainage	None Anticipated				0%		-
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%		-
	Sewer	None Anticipated				0%		-
	Establish Turf / Erosion Control					2%	\$	77,115
	Illumination	None Anticipated				0%	\$	-
	Other:							
**Allo	wances based on % of Paving Construction Cos	t Subtota <b>l</b>		Allowa	nce S	Subtotal:	\$	308,459
							_	
			Paving and					4,164,190
	Mobilization: 5%							208,210
			Site Prep			5%		208,210
			Construc				\$	4,581,000
	-		uction Conti			15%	_	687,150
	Со	nstruction Cos	t TOTAL W	// CON	TING	ENCY:	\$	5,269,000

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 5,269,000
Engineering/Survey/Testing:		20%	\$ 1,053,800
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	No ROW Acquisition Costs included	0%	\$ -

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated:

10/6/2020

<b>Project Informatio</b>	n: D	escription:	Project No. K-10, L-7
Name:	AIRPORT DR (6)		This project consists of the
	470' N OF HARRY MCKILLOP BLVD / F	M 546 TO	reconstruction of a two-lane asphalt
Limits:	HARRY MCKILLOP BLVD / FM 546		facility to a six-lane divided principal
Impact Fee Class:	P6D		arterial. The City contributed
Thoroughfare Class:	Principal Arterial	approximately \$1,500,000 of eligible	
Length (If):	470		funds from '12-'19.
Service Area(s):	K and L		

	dway Construction Cost Projec	tion					
	Item Description		Quantity	Unit		it Price	Item Cost
113	Unclassified Street Excavation		5,222	су	\$	10.00	\$ 52,222
213	Lime Treated Subgrade (8") (PI<12)		4,073	sy	\$	7.00	\$ 28,513
313	9" Concrete Pavement		3,864	sy	\$	60.00	\$ 231,867
	4" Topsoil		2,141	sy	\$	2.50	\$ 5,353
	6" Curb & Gutter		1,880	lf	\$	5.00	\$ 9,400
	Allotment for Turn Lanes and Median O	penings	287	sy	\$	77.00	\$ 22,086
713	Moisture Conditioning		4,073	sy	\$	8.00	\$ 32,587
		Р	aving Const	ruction (	Cost S	Subtotal:	\$ 382,027
Majo	or Construction Component Allowance	es**:					
	Item Description	Notes			Alle	owance	Item Cost
V	Traffic Control	Construction Phase	Traffic Control			3%	\$ 11,461
	Pavement Markings/Markers					3%	\$ 11,461
	Roadway Drainage	Standard Internal Sy	stem			25%	\$ 95,507
	Special Drainage Structures	Stream Crossing					\$ 250,000
	Water	Incidental Adjustmen	nts			3%	\$ 11,461
	Sewer	Incidental Adjustmen	nts			3%	\$ 11,461
	Establish Turf / Erosion Control					2%	\$ 7,641
	Illumination	Standard Ilumination	System			6%	\$ 22,922
	Other:						
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	nce S	Subtotal:	\$ 421,912
			Paving an	d Allowa	nce S	Subtotal:	\$ 803,940
			Mobi	lization:		5%	\$ 40,197
			Site Prep	aration:		5%	\$ 40,197
			Construc			TOTAL:	\$ 885,000
			uction Conti			15%	\$ 132,750
	Cor	struction Cos	t TOTAL W	// CON	TING	ENCY:	\$ 1,018,000

Item Description	Notes:	Allowance		Item Cost
Construction:		-	\$	1,018,000
Engineering/Survey/Testing:		20%	\$	203,600
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	1,500,000
ROW/Easement Acquisition:	Existing Alignment	20%	\$	203,600
•	Impact Fee P	roject Cost TOTAL:	9	2,925,200

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

**Project Information: L-8** Description: Project No.

UNNAMED C (3) Name: Limits: US HIGHWAY 380 TO 2,435' S OF US HIGHWAY 380

This project consists of the construction of a new six-lane

Impact Fee Class: P6D

divided principal arterial.

Thoroughfare Class: Principal Arterial

Length (If): 2,435 Service Area(s):

Roa	dway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Uni	t Price	Item Cost
113	Unclassified Street Excavation	27,056	су	\$	10.00	\$ 270,556
213	Lime Treated Subgrade (8") (PI<12)	21,103	sy	\$	7.00	\$ 147,723
313	9" Concrete Pavement	20,021	sy	\$	60.00	\$ 1,201,267
413	4" Topsoil	11,093	sy	\$	2.50	\$ 27,732
513	6" Curb & Gutter	9,740	lf	\$	5.00	\$ 48,700
613	Allotment for Turn Lanes and Median Openings	1,486	sy	\$	77.00	\$ 114,422
713	Moisture Conditioning	21,103	sy	\$	8.00	\$ 168,827

Paving Construction Cost Subtotal: \$ 1,979,227

Majo	Major Construction Component Allowances**:							
	Item Description	Notes	Allowance		Item Cost			
	Traffic Control	None Anticipated	1%	\$	19,792			
	Pavement Markings/Markers		3%	\$	59,377			
	Roadway Drainage	Standard Internal System	25%	\$	494,807			
	Special Drainage Structures	Stream Crossing		\$	250,000			
	Water	None Anticipated	0%	\$	-			
	Sewer	None Anticipated	0%	\$	-			
	Establish Turf / Erosion Control		2%	\$	39,585			
	Illumination	Standard Ilumination System	6%	\$	118,754			
	Other:							
**Allo	wances based on % of Paving Construction Cos	st Subtotal Allowa	nce Subtotal:	\$	982,314			
		Paving and Allowa			2,961,540			
		Mobilization:	5%	\$	148,077			
		Site Preparation:	5%	\$	148,077			
		Construction C	ost TOTAL:	\$	3,258,000			
		Construction Contingency:	15%	\$	488,700			
	Co	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	3,747,000			

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 3,747,000
Engineering/Survey/Testing:		20%	\$ 749,400
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 1,311,450

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

# 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information: Description: Project No. L-9, I

Name: UNNAMED C (4) This project consists of the construction

2,525' N OF HARRY MCKILLOP of a new six-lane divided principal BLVD / FM 546 TO 1,230' N OF arterial.

Limits: HARRY MCKILLOP BLVD / FM 546

Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 1,295 Service Area(s): L and M

Roa	adway Construction Cost Proj	ection						
	Item Description		Quantity	Unit	Un	it Price		Item Cost
113	Unclassified Street Excavation		14,389	су	\$	10.00	\$	143,889
213	Lime Treated Subgrade (8") (PI<12)		11,223	sy	\$	7.00	\$	78,563
313	9" Concrete Pavement		10,648	sy	\$	60.00	\$	638,867
413	4" Topsoil		5,899	sy	\$	2.50	\$	14,749
513	6" Curb & Gutter		5,180	lf	\$	5.00	\$	25,900
613	Allotment for Turn Lanes and Median	Openings	790	sy	\$	77.00	\$	60,853
713	Moisture Conditioning		11,223	sy	\$	8.00	\$	89,787
	Paving Construction Co							
			Paving Const	ruction (	Cost S	Subtotal:	\$	1,052,607
			Paving Const	ruction (	Cost	Subtotal:	\$	1,052,607
Majo	or Construction Component Allowar	nces**:	Paving Const	ruction (	Cost	Subtotal:	\$	1,052,607
Мајо	or Construction Component Allowar Item Description	nces**:	Paving Const	ruction (		Subtotal: owance	\$ 	1,052,607 Item Cost
Majo	-			ruction (			<b>\$</b> \$	
	Item Description	Notes		ruction (		owance	\$	Item Cost
√ ,	Item Description Traffic Control	Notes	3	ruction (		owance 1%	\$	Item Cost
√ √	Item Description Traffic Control Pavement Markings/Markers	Notes  None Anticipated	d I System	ruction (		owance 1% 3%	\$	Item Cost 10,526 31,578
\ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage	Notes  None Anticipated  Standard Interna	d I System	ruction (		owance 1% 3%	\$	Item Cost 10,526 31,578
\ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures	Notes  None Anticipated  Standard Interna None Anticipated	d System	ruction (		0wance 1% 3% 25%	\$	Item Cost 10,526 31,578
\ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water	Notes  None Anticipated  Standard Interna  None Anticipated  None Anticipated	d System	ruction (		1% 3% 25%	\$	Item Cost 10,526 31,578

Paving and Allowance Su	ıbtotal:	\$ 1,442,072
Mobilization:	5%	\$ 72,104
Site Preparation:	5%	\$ 72,104
Construction Cost To	OTAL:	\$ 1,587,000
Construction Contingency:	15%	\$ 238,050
Construction Cost TOTAL W/ CONTINGE	INCY:	\$ 1,826,000
Impact Fee Project Cost Summary		

Impact Fee Project Cost Summa	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,826,000
Engineering/Survey/Testing:		20%	\$ 365,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 639,100
	Impact Fee Project (	Cost TOTAL:	\$ 2,830,300

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

Other:

*Allowances based on % of Paving Construction Cost Subtotal

Allowance Subtotal:

389,465

updated:

10/6/2020

317,547

# 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Project Information: Name:

Description:

Project No. This project consists of the construction

of a new six-lane divided principal

UNNAMED C (5)

HARRY MCKILLOP BLVD / FM 546

(N) TO 705' S OF HARRY

arterial.

Limits: MCKILLOP BLVD / FM 546 (S)

**Impact Fee Class:** P6D

713 Moisture Conditioning

**Thoroughfare Class: Principal Arterial** 

Length (If): 4,580 Service Area(s): L and M

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Un	it Price	Item Cost
113	Unclassified Street Excavation	50,889	су	\$	10.00	\$ 508,889
	Lime Treated Subgrade (8") (PI<12)	39,693	sy	\$	7.00	\$ 277,853
313	9" Concrete Pavement	37,658	sy	\$	60.00	\$ 2,259,467
413	4" Topsoil	20,864	sy	\$	2.50	\$ 52,161
513	6" Curb & Gutter	18,320	lf	\$	5.00	\$ 91,600
613	Allotment for Turn Lanes and Median Openings	2,795	sv	\$	77.00	\$ 215.218

39,693

Paving Construction Cost Subtotal: \$ 3,722,734


8.00 \$

\$

		3		•	-,,-				
Major Construction Component Allowances**:									
	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	None Anticipated	1%	\$	37,227				
	Pavement Markings/Markers		3%	\$	111,682				
	Roadway Drainage	Standard Internal System	25%	\$	930,684				
	Special Drainage Structures	None Anticipated		\$	-				
	Water	None Anticipated	0%	\$	-				
	Sewer	None Anticipated	0%	\$	-				
	Establish Turf / Erosion Control		2%	\$	74,455				
	Illumination	Standard Ilumination System	6%	\$	223,364				
	Other:								
**Allo	wances based on % of Paving Construction Co	ost Subtotal Allowa	nce Subtotal:	\$	1,377,412				
		Paving and Allowa			5,100,146				
		Mobilization:	0,1		255,007				
		Site Preparation:		_	255,007				
		Construction C	ost TOTAL:	\$	5,611,000				
		Construction Contingency:	15%	\$	841,650				
		onstruction Cost TOTAL W/ CON	TINGENCY:	\$	6,453,000				

Impact Fee Project Cost Sumr	nary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 6,453,000
Engineering/Survey/Testing:		20%	\$ 1,290,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 2,258,550
	\$ 10,002,150		

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.



#### City of McKinney - 2019 Roadway Impact Fee Update

Roadway Improvement Plan for Roadway Impact Fees Appendix A - Summary of Conceptual Level Project Cost Projections

Roadway Improvements - Service Area M

	Costing					Percent in		Cost in														
#	Class	Project	Limits	Total Cost		Total Cost		Total Cost		Total Cost		Total Cost		Total Cost		Total Cost		Total Cost		Service Area	Ser	vice Area
M-1	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (2)	110' E OF UNNAMED C TO 300' E OF UNNAMED C	\$	196,075	50%	\$	98,038														
M-2	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (3)	1,700' N OF HARRY MCKILLOP BLVD / FM 546 TO 2,050' N OF HARRY MCKILLOP BLVD / FM 546	\$	361,150	50%	\$	180,575														
M-3	M6D	HARRY MCKILLOP BLVD / FM 546 (N) (4)	405' N OF HARRY MCKILLOP BLVD / FM 546 TO 675' N OF HARRY MCKILLOP BLVD / FM 546	\$	279,000	50%	\$	139,500														
M-4	P6D	HARRY MCKILLOP BLVD / FM 546 (S) (3)	UNNAMED C TO 695' E OF UNNAMED C	\$	719,975	100%	\$	719,975														
L-9, M-5	P6D	UNNAMED C (4)	2,525' N OF HARRY MCKILLOP BLVD / FM 546 TO 1,230' N OF HARRY MCKILLOP BLVD / FM 546	\$	2,830,300	50%	\$	1,415,150														
L-10, M-6	P6D	UNNAMED C (5)	HARRY MCKILLOP BLVD / FM 546 (N) TO 705' S OF HARRY MCKILLOP BLVD / FM 546 (S)	\$	10,002,150	50%	\$	5,001,075														
64	Inter-	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (N)	\$	300,000	50%	\$	150,000														
74	section	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (S)	\$	300,000	50%	\$	150,000														
				•	14 000 CEO		•	7 054 242														

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney. The planning level cost projections shall not supersede the City's design standards contained within the Subdivision Ordinance or the determination of the City Engineer for a specific project.

#### 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

199,674

220,000

253,000

9,984

9,984

33,000

\$

\$

\$

**15%** \$

5%

**5%** \$

Project Information: Description: Project No. M-1

Name: HARRY MCKILLOP BLVD / FM 546 (N) (2) This project continuits: 110' E OF UNNAMED C TO 300' E OF UNNAMED C construction of the continuity of the construction of t

Impact Fee Class: M6D

Thoroughfare Class: Major Arterial

Length (If): 190 Service Area(s): M This project consists of the construction of a new six-lane

divided major arterial.

No.	Item Description		Quantity	Unit	Un	it Price		Item Cost
109	Unclassified Street Excavation		1,056	су	\$	15.00	\$	15,833
209	Lime Treated Subgrade (8") (PI<12)		1,647	sy	\$	7.00	\$	11,527
309	4" TY D HMAC Underlayment		1,562	sy	\$	5.00	\$	7,811
409	9" Concrete Pavement		1,562	sy	\$	60.00	\$	93,733
509	4" Topsoil		739	sy	\$	4.00	\$	2,956
609	6" Curb & Gutter		760	lf	\$	5.00	\$	3,800
709	Allotment for Turn Lanes and Mediar	n Openings	116	sy	\$	87.00	\$	10,088
		Б	aving Constr	uction (	nst 9	Subtotal:	\$	145,748
		Г	aving consti	uction (	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Jubioiai.	Ψ	173,770
			aving consti	uction		Jubioiui.		173,770
Majo	or Construction Component Allowa		aving consti	uction			_	143,740
Majo	or Construction Component Allowa Item Description		aving consti	detion		owance	Ľ	Item Cost
Majo		nces**:	aving consti	detion				
	Item Description	nces**: Notes	aving const.			owance	\$	Item Cost
1	Item Description Traffic Control	nces**: Notes	uviiig 001131.			owance 1%	\$	Item Cost
\ \ \	Item Description Traffic Control Pavement Markings/Markers	nces**: Notes	uviiig 001131.			owance 1% 3%	\$	Item Cost 1,457 4,372
\ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage	Notes  None Anticipated	uviiig 001131.			owance 1% 3%	\$ \$ \$ \$	Item Cost 1,457 4,372
\ \ \	Item Description  Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures	Notes  None Anticipated  None Anticipated	aving const.			1% 3% 25%	\$ \$ \$ \$	Item Cost 1,457 4,372
\ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water	Notes  None Anticipated  None Anticipated  None Anticipated	uviiig 001131.			1% 3% 25%	\$ \$ \$ \$ \$	Item Cost 1,457 4,372
\ \ \	Item Description Traffic Control Pavement Markings/Markers Roadway Drainage Special Drainage Structures Water Sewer	Notes  None Anticipated  None Anticipated  None Anticipated				0% 0% 0%	\$ \$ \$ \$ \$ \$ \$	1,457 4,372 36,437

Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 253,000
Engineering/Survey/Testing:		20%	\$ 50,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 88,550

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

The planning level cost projections shall not supersede the City's design standards contained or the determination of the City Engineer for a specific project.

Paving and Allowance Subtotal:

**Construction Cost TOTAL:** 

Mobilization:

Site Preparation:

Construction Contingency:

**Construction Cost TOTAL W/ CONTINGENCY:** 

# **City of McKinney**

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. M-2

Name: HARRY MCKILLOP BLVD / FM 546 (N) (3) This p

1,700' N OF HARRY MCKILLOP BLVD / FM 546 TO 2,050' N OF This project consists of the construction of a new six-lane divided major arterial.

Limits: HARRY MCKILLOP BLVD / FM 546

Impact Fee Class: M6D

Thoroughfare Class: Major Arterial

Length (If): 350 Service Area(s): M

	.,							
Roa	dway Construction Cost Projec	tion						
	Item Description		Quantity	Unit	Ur	nit Price		Item Cost
109	Unclassified Street Excavation		1,944	су	\$	15.00	\$	29,167
209	Lime Treated Subgrade (8") (PI<12)		3,033	sy	\$	7.00	\$	21,233
309	4" TY D HMAC Underlayment		2,878	sy	\$	5.00	\$	14,389
409	9" Concrete Pavement		2,878	sy	\$	60.00	\$	172,667
509	4" Topsoil		1,361	sy	\$	4.00	\$	5,444
609	6" Curb & Gutter		1,400	lf	\$	5.00	\$	7,000
709	Allotment for Turn Lanes and Median O		214	sy	\$	87.00	\$	18,583
		P	Paving Const	ruction (	Cost	Subtotal:	\$	268,483
Majo	r Construction Component Allowance							
	Item Description	Notes			All	lowance		Item Cost
	Traffic Control	None Anticipated				1%	\$	2,685
$\sqrt{}$	Pavement Markings/Markers					3%	\$	8,054
	Roadway Drainage					25%	\$	67,121
	Special Drainage Structures	None Anticipated					\$	-
	Water	None Anticipated				0%		-
	Sewer	None Anticipated				0%	-	-
$\sqrt{}$	Establish Turf / Erosion Control					2%	\$	5,370
	Illumination	Standard Ilumination	n System			6%	\$	16,109
	Other:							
**Allo	wances based on % of Paving Construction Cost S	Subtotal		Allowa	ınce	Subtotal:	\$	99,339
			Paving an			Subtotal:	\$	367,821
Mobilization: 5%						\$	18,391	
			Site Prep			5%	-	18,391
			Construc				\$	405,000
			ruction Conti			15%	_	60,750
	Cor	struction Cos	t TOTAL W	// CON	TINC	GENCY:	\$	466,000

Impact Fee Project Cost Summ	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 466,000
Engineering/Survey/Testing:		20%	\$ 93,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 163,100
Impact Fe	\$ 361,150		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

# **City of McKinney**

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. M-3

Name: HARRY MCKILLOP BLVD / FM 546 (N) (4) This project consists of the

405' N OF HARRY MCKILLOP BLVD construction of a new six-lane / FM 546 TO 675' N OF HARRY divided major arterial.

Limits: MCKILLOP BLVD / FM 546

Impact Fee Class: M6D

Thoroughfare Class: Major Arterial

Length (If): 270 Service Area(s): M

	adway Construction Cost Proje	ection					
	Item Description		Quantity	Unit	Unit Price		Item Cost
109	Unclassified Street Excavation		1,500	су	\$ 15.00	\$	22,500
209	Lime Treated Subgrade (8") (PI<12)		2,340	sy	\$ 7.00	\$	16,380
309	4" TY D HMAC Underlayment		2,220	sy	\$ 5.00	\$	11,100
409	9" Concrete Pavement		2,220	sy	\$ 60.00	\$	133,200
	4" Topsoil		1,050	sy	\$ 4.00	\$	4,200
	6" Curb & Gutter		1,080	lf	\$ 5.00	\$	5,400
709	Allotment for Turn Lanes and Median		165	sy	\$ 87.00	\$	14,335
		P	Paving Consti	uction (	Cost Subtotal:	\$	207,115
Majo	or Construction Component Allowan						
	Item Description	Notes			Allowance		Item Cost
	Traffic Control	None Anticipated			1%		2,071
	Pavement Markings/Markers				3%	\$	6,213
	Roadway Drainage				25%	\$	51,779
	Special Drainage Structures	None Anticipated				\$	-
	Water	None Anticipated			0%	\$	-
	Sewer	None Anticipated			0%	-	-
	Establish Turf / Erosion Control				2%	\$	4,142
	Illumination	Standard Ilumination	System		6%	\$	12,427
	Other:						
**Allo	wances based on % of Paving Construction Cos	t Subtotal		Allowa	nce Subtotal:	\$	76,633
	Paving and Allowance Subtotal:						
	Mobilization: 5%						14,187
			Site Prep	<u>aration:</u>	5%	\$	14,187
					ost TOTAL:	\$	313,000
		Constr	ruction Conti	ngency:	15%	\$	46,950
	Co	onstruction Cos	t TOTAL W	// CON	TINGENCY:	\$	360,000

Impact Fee Project Cost Summa	ry		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 360,000
Engineering/Survey/Testing:		20%	\$ 72,000
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 126,000
Impact Fed	\$ 279,000		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

# **City of McKinney**

# 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.

updated: 10/6/2020

Project Information: Description: Project No. M-4

Name: HARRY MCKILLOP BLVD / FM 546 (S) (3) This project consists of the

Limits: UNNAMED C TO 695' E OF UNNAMED C construction of a new six-lane divided

Impact Fee Class: P6D principal arterial.

Thoroughfare Class: Principal Arterial

Length (If): 695 Service Area(s): M

Roa	adway Construction Cost Projection								
No.	Item Description	Quantity	Quantity Unit Unit Price		Unit Price		Unit Price		Item Cost
113	Unclassified Street Excavation	3,861	су	\$	15.00	\$	57,917		
213	Lime Treated Subgrade (8") (PI<12)	6,023	sy	\$	7.00	\$	42,163		
313	4" TY D HMAC Underlayment	5,714	sy	\$	5.00	\$	28,572		
413	9" Concrete Pavement	5,714	sy	\$	60.00	\$	342,867		
513	4" Topsoil	3,166	sy	\$	4.00	\$	12,664		
613	6" Curb & Gutter	2,780	lf	\$	5.00	\$	13,900		
713	Allotment for Turn Lanes and Median Openings	424	sy	\$	87.00	\$	36,900		

Paving Construction Cost Subtotal: \$ 534,983

Majo				
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	None Anticipated	1%	\$ 5,350
	Pavement Markings/Markers		3%	\$ 16,049
	Roadway Drainage		25%	\$ 133,746
	Special Drainage Structures	None Anticipated		\$ -
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 10,700
	Illumination	Standard Ilumination System	6%	\$ 32,099
	Other:			
**Allo	wances based on % of Paving Construction Cos	: Subtotal Allowa	nce Subtotal:	\$ 197,944
		Paving and Allowa	nce Subtotal:	\$ 732,927
		Mobilization:	5%	\$ 36,646
		Site Preparation:	5%	\$ 36,646
	\$ 807,000			
		Construction Contingency:		121,050
	Co	nstruction Cost TOTAL W/ CON	TINGENCY:	\$ 929,000

Item Description	Notes:	Allowance	ľ	tem Cost
Construction:		-	\$	929,000
Engineering/Survey/Testing:		20%	\$	185,800
2008 - 2012 City contribution			\$	-
2012 - 2019 City contribution			\$	-
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$	325,150

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc.

## 2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. L-9, M-5

Name: UNNAMED C (4) This project consists of the construction

2,525' N OF HARRY MCKILLOP of a new six-lane divided principal BLVD / FM 546 TO 1.230' N OF arterial.

Limits: HARRY MCKILLOP BLVD / FM 546

Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 1,295 Service Area(s): M and L

Roa	adway Construction Cost Projection					
No.	Item Description	Quantity	Unit	Ū	nit Price	Item Cost
113	Unclassified Street Excavation	14,389	су	\$	10.00	\$ 143,889
213	Lime Treated Subgrade (8") (PI<12)	11,223	sy	\$	7.00	\$ 78,563
313	9" Concrete Pavement	10,648	sy	\$	60.00	\$ 638,867
413	4" Topsoil	5,899	sy	\$	2.50	\$ 14,749
513	6" Curb & Gutter	5,180	lf	\$	5.00	\$ 25,900
613	Allotment for Turn Lanes and Median Openings	790	sy	\$	77.00	\$ 60,853
713	Moisture Conditioning	11,223	sy	\$	8.00	\$ 89,787

Paving Construction Cost Subtotal: \$ 1,052,607

		3		•	-,,				
Majo	Major Construction Component Allowances**:								
	Item Description	Notes	Allowance		Item Cost				
	Traffic Control	None Anticipated	1%	\$	10,526				
	Pavement Markings/Markers		3%	\$	31,578				
	Roadway Drainage	Standard Internal System	25%	\$	263,152				
	Special Drainage Structures	None Anticipated		\$	-				
	Water	None Anticipated	0%	\$	-				
	Sewer	None Anticipated	0%	\$	-				
	Establish Turf / Erosion Control		2%	\$	21,052				
	Illumination	Standard Ilumination System	6%	\$	63,156				
	Other:								
**Allo	wances based on % of Paving Construction Co	st Subtotal Allowa	nce Subtotal:	\$	389,465				
		Paving and Allowa			1,442,072				
		Mobilization:	0,1		72,104				
		Site Preparation:			72,104				
		Construction C	ost TOTAL:	\$	1,587,000				
		Construction Contingency:	15%	\$	238,050				
	C	onstruction Cost TOTAL W/ CON	TINGENCY:	\$	1,826,000				

Impact Fee Project Cost Summ	ary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 1,826,000
Engineering/Survey/Testing:		20%	\$ 365,200
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 639,100
	\$ 2,830,300		

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.

Kimley-Horn and Associates, Inc.

2019 Roadway Impact Fee Update Conceptual Level Project Cost Projection

updated: 10/6/2020

Project Information: Description: Project No. L-10, M-6

Name: UNNAMED C (5) This project consists of the construction

HARRY MCKILLOP BLVD / FM 546 of a new six-lane divided principal

(N) TO 705' S OF HARRY arterial.

Limits: MCKILLOP BLVD / FM 546 (S)

Impact Fee Class: P6D

Thoroughfare Class: Principal Arterial

Length (If): 4,580 Service Area(s): M and L

Roa	dway Construction Cost Projection						
No.	Item Description	Quantity	Unit	Unit Price		t Price Item	
113	Unclassified Street Excavation	50,889	су	\$	10.00	\$	508,889
213	Lime Treated Subgrade (8") (PI<12)	39,693	sy	\$	7.00	\$	277,853
313	9" Concrete Pavement	37,658	sy	\$	60.00	\$	2,259,467
413	4" Topsoil	20,864	sy	\$	2.50	\$	52,161
513	6" Curb & Gutter	18,320	lf	\$	5.00	\$	91,600
613	Allotment for Turn Lanes and Median Openings	2,795	sy	\$	77.00	\$	215,218
713	Moisture Conditioning	39,693	sy	\$	8.00	\$	317,547

Paving Construction Cost Subtotal: \$ 3,722,734

	or Construction Component Allow			
Maj				
	Item Description	Notes	Allowance	Item Cost
	Traffic Control	None Anticipated	1%	\$ 37,227
	Pavement Markings/Markers		3%	\$ 111,682
	Roadway Drainage	Standard Internal System	25%	\$ 930,684
	Special Drainage Structures	None Anticipated		\$ -
	Water	None Anticipated	0%	\$ -
	Sewer	None Anticipated	0%	\$ -
	Establish Turf / Erosion Control		2%	\$ 74,455
	Illumination	Standard Ilumination System	6%	\$ 223,364
	Other:			
**Allo	owances based on % of Paving Construction	Cost Subtotal Allowa	ance Subtotal:	\$ 1,377,412
		Paving and Allowa	ance Subtotal:	\$ 5,100,146
		Mobilization:	5%	\$ 255,007
		Site Preparation:	5%	\$ 255,007
		Construction C	ost TOTAL:	\$ 5,611,000
		Construction Contingency:	15%	\$ 841,650
		<b>Construction Cost TOTAL W/ CON</b>	TINGENCY:	\$ 6,453,000

Impact Fee Project Cost Sumr	mary		
Item Description	Notes:	Allowance	Item Cost
Construction:		-	\$ 6,453,000
Engineering/Survey/Testing:		20%	\$ 1,290,600
2008 - 2012 City contribution			\$ -
2012 - 2019 City contribution			\$ -
ROW/Easement Acquisition:	New Roadway Alignment	35%	\$ 2,258,550
	Impact Fee Projec	t Cost TOTAL:	\$ 10,002,150

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of McKinney.





Appendix B – Roadway Impact Fee RIP Service Units of Supply

## **RIP Service Units of Supply**

## Service Area A

Project ID	ROADWAY	LIMITS	LENGTH (ft)	LANES	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	TOTAL PROJ COST	-(,11	TOTAL PROJECT COST IN SERVICE AREA
A-1, C-1	UNNAMED 5 (1)	635' W OF STONEBRIDGE DR TO CR 168	3,326	6	M6D	New	50%	700	1,323	6,985,000	0	1,323	\$ 7,715,	900	\$ 3,857,950
A-2, D-1	UNNAMED 5 (3)	CR 168 TO 1,560' E OF CR 168	1,584	6	M6D	New	50%	700	630	3,326,000	0	630	\$ 7,517,	500	\$ 3,758,750
A-3	STONEBRIDGE DR (1)	2,635' N OF UNNAMED 5 TO UNNAMED 5	2,640	4	G4D	New	50%	700	700	3,696,000	0	700	\$ 4,679,	450	\$ 2,339,725
SUBTOTA	L								2,653		0	2,653	\$ 19,912,	850	\$ 9,956,425

11,692

TOTAL COST IN SERVICE AREA A \$ 9,968,117

## **RIP Service Units of Supply**

Service Area B

Project ID #	ROADWAY	LIMITS	LENGTH (ft)	LANES	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	тот	AL PROJECT COST	COST	. PROJECT N SERVICE AREA
B-1, D-2	UNNAMED 5 (4)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD	2,270	6	M6D	New	50%	700	903	4,768,000	0	903	\$	4,904,200	\$	2,452,100
B-2	HARDIN BLVD (1)	CR 204 TO CR 206	422	6	G6D	100	50%	700	168	887,000	4	164	\$	877,800	\$	438,900
B-3	HARDIN BLVD (2)	1,670' N OF OLYMPIC TO 730' S OF OLYMPIC	2,376	6	G6D	100	50%	700	945	4,990,000	23	923	\$	4,837,000	\$	2,418,500
B-4	HARDIN BLVD (3)	1,940' N OF UNNAMED 5 TO UNNAMED 5	1,954	6	G6D	New	100%	700	1,554	8,205,000	0	1,554	\$	4,090,450	\$	4,090,450
1	Signal	HARDIN BLVD & OLYMPIC					50%						\$	300,000	\$	150,000
3	Signal	HARDIN BLVD & UNNAMED 5					50%						\$	300,000	\$	150,000
SUBTOTA	L								3,570		27	3,544	\$	15,309,450	\$	9,699,950

\$ 11,692

TOTAL COST IN SERVICE AREA B \$ 9,711,642

#### RIP Service Units of Supply

Service Area C

roject ID	ROADWAY	LIMITS	LENGTH	LANES	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR	VEH-MI SUPPLY PK-HR	VEH-FT SUPPLY PK-HR	VEH-MI TOTAL DEMAND	EXCESS CAPACITY PK-HR		PROJECT OST	COST	IL PROJECT IN SERVICE AREA
			. ,			VOLUME	AREA	PER LN	TOTAL	TOTAL	PK-HR	VEH-MI			,	AKEA
A-1, C-1	UNNAMED 5 (1)	635' W OF STONEBRIDGE DR TO CR 168	3,326	6	M6D	New	50%	700	1,323	6,985,440	0	1,323	\$ 7	7,715,900	\$	3,857,95
C-2	UNNAMED 5 (2)	RIDGE RD TO 1,505' E OF RIDGE RD	1,531	6	M6D	100	50%	700	609	3,215,520	15	595	\$ 3	3,137,400	\$	1,568,70
C-3	LAUD HOWELL PKWY (1)	695' W OF CUSTER RD TO CUSTER RD	686	6	G6D	542	50%	700	273	1,441,440	35	238	\$		\$	332,50
C-4	LAUD HOWELL PKWY (2)	CUSTER RD TO 1,225' E OF CUSTER RD	1,214	6	G6D	542	100%	700	966	5,100,480	125	841	\$ 1	1,171,800	\$	1,171,80
C-5	LAUD HOWELL PKWY (3)	1,225' E OF CUSTER RD TO 2,070' E OF CUSTER RD	845	6	G6D	542	50%	700	336	1,774,080	43	293	\$	808,500	\$	404,25
C-6	LAUD HOWELL PKWY (4)	840' E OF STONEBRIDGE DR TO 2,905' E OF STONEBRIDGE DR	2,059	6	G6D	542	50%	700	819	4,324,320	106	713			\$	1,429,75
C-7	LAUD HOWELL PKWY (5)	1,985' W OF RIDGE RD TO 1,230' E OF RIDGE RD	3,221	6	G6D	542	50%	700	1,281	6,763,680	165	1,116		3,073,000	\$	1,536,50
C-8	BLOOMDALE RD (1)	CUSTER RD TO 1,310' E OF CUSTER RD	1,320	6	P6D	316	100%	780	1,170	6,177,600	79	1,091		., ,	\$	3,179,40
C-9	BLOOMDALE RD (2)	1,310' E OF CUSTER RD TO 2,030' W OF STONEBRIDGE DR	2,112	6	P6D	316	50%	780	936	4,942,080	63	873		4,838,400	\$	2,419,20
C-10	BLOOMDALE RD (3)	2,030' W OF STONEBRIDGE DR TO 3,245' E OF STONEBRIDGE DR	5,280	6	P6D	316	100%	780	4,680	24,710,400	316	4,364		3,314,000	\$	13,314,00
C-11	BLOOMDALE RD (4)	3,245' E OF STONEBRIDGE DR TO 695' W OF RIDGE RD	1,373	6	P6D	316	50%	780	608	3,212,352	41	567			\$	1,646,40
C-12	BLOOMDALE RD (5)	695' W OF RIDGE RD TO RIDGE RD	686	6	P6D	316	100%	780	608	3,212,352	41	567		1,453,200	\$	1,453,20
C-13	BLOOMDALE RD (6)	3,400' W OF LAKE FOREST DR TO LAKE FOREST DR	3,379	4	P6D(2/3)	New	50%	780	998	5,271,552	0	998		4,650,800	\$	2,325,40
C-14	WILMETH RD (1)	3,725' W OF STONEBRIDGE DR TO 815' E OF STONEBRIDGE DR	4,541	4	G4D	New	100%	700	2,408	12,714,240	0	2,408		0,010,000	\$	8,845,85
C-15	WILMETH RD (2)	815' E OF STONEBRIDGE DR TO 995' W OF RIDGE RD	3,326	4	G4D	34	50%	700	882	4,656,960	11	871		6,200,600	\$	3,100,30
C-16	WILMETH RD (3)	RIDGE RD TO 585' E OF RIDGE RD	581	4	G4D(1/2)	131	100%	700	308	1,626,240	14	294	\$ 1	7 7	\$	1,593,00
C-17	WILMETH RD (4)	1,095' E OF RIDGE RD TO 1,365' E OF RIDGE RD	264	4	G4D(1/2)	131	100%	700	140	739,200	7	133	\$	100,000	\$	708,00
C-18	CUSTER RD (1)	1,855' N OF LAUD HOWELL PKWY TO LAUD HOWELL PKWY	1,848	6	P6D	615	50%	780	819	4,324,320	108	711		1,834,000	\$	917,00
C-19	CUSTER RD (2)	LAUD HOWELL PKWY TO 2,775 N OF BLOOMDALE RD	2,798	6	P6D	New	100%	780	2,480	13,096,512	0	2,480			\$	2,869,82
C-20	CUSTER RD (3)	2,655 N OF BLOOMDALE RD TO 375' N OF WILMETH RD	6,283	6	P6D	1,111	50%	780	2,785	14,702,688	661	2,124		8,071,300	\$	4,035,65
C-21	STONEBRIDGE DR (2)	UNNAMED 5 TO 1,280' S OF UNNAMED 5	1,267	4	G4D	New	100%	700	672	3,548,160	0	672		2,763,650	\$	2,763,65
C-22	STONEBRIDGE DR (3)	1,570' S OF LAUD HOWELL PKWY TO 280' S OF WILMETH RD	7,973	4	G4D	New	100%	700	4,228	22,323,840	0	4,228		4,194,900	\$	14,194,90
C-23	STONEBRIDGE DR (4)	280' S OF WILMETH RD TO 1,195' S OF WILMETH RD	898	4	G4D	New	50%	700	238	1,256,640	0	238		2,117,300	\$	1,058,65
C-24	STONEBRIDGE DR (5)	1,195' S OF WILMETH RD TO 5,555' S OF WILMETH RD	4,382	4	G4D	New	100%	700	2,324	12,270,720	0	2,324			\$	8,232,05
C-25	STONEBRIDGE DR (6)	580' N OF US HIGHWAY 380 TO US HIGHWAY 380	581	4	G4D	New	100%	700	308	1,626,240	0	308		1,030,750	\$	1,030,75
C-26	RIDGE RD (1)	UNNAMED 5 TO 1,485' S OF UNNAMED 5	1,478	6	M6D	100	50%	700	588	3,104,640	14	574		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	\$	1,547,70
C-27	RIDGE RD (2)	LAUD HOWELL PKWY TO BAXTER WELL RD	3,115	6	M6D	New	100%	700	2,478	13,083,840	0	2,478		,20,,000	\$	7,267,95
C-28	RIDGE RD (3)	BAXTER WELL RD TO 2,160' S OF BLOOMDALE RD	4,382	6	M6D	87	50%	700	1,743	9,203,040	36	1,707		9,144,800	\$	4,572,40
C-29	RIDGE RD (4)	1,590' N OF WILMETH RD TO WILMETH RD	1,584	6	M6D	87	50%	700	630	3,326,400	13	617			\$	1,878,10
C-30	RIDGE RD (5)	WILMETH RD TO 2,280' S OF WILMETH RD	2,270	6	M6D	New	100%	700	1,806	9,535,680	0	1,806			\$	7,411,20
C-31	RIDGE RD (6)	1,860' N OF US HIGHWAY 380 TO 1,390' N OF US HIGHWAY 380	475	6	M6D	New	50%	700	189	997,920	0	189		.,,	\$	727,50
C-32	RIDGE RD (7)	775' N OF US HIGHWAY 380 TO US HIGHWAY 380	792	6	M6D	New	100%	700	630	3,326,400	0	630			\$	2,857,20
C-33	LAKE FOREST DR (2)	BLOOMDALE RD TO WILMETH RD	5,386	6	M6D(1/3)	841	50%	700	2,142	11,309,760	429	1,713		.,,	\$	2,504,49
-34, D-22	LAKE FOREST DR (3)	WILMETH RD TO US HIGHWAY 380	5,174	2	M6D(1/3)	New	50%	700	686	3,622,080	0	686		2,350,800	\$	1,175,40
2	Signal	RIDGE RD & UNNAMED 5					25%						\$		\$	75,00
4	Signal	LAUD HOWELL PKWY & CUSTER RD					75%						\$	,	\$	225,00
5	Signal	LAUD HOWELL PKWY & RIDGE RD					50%						\$	000,000	\$	150,00
12	Intersection Improvement	CUSTER RD & BLOOMDALE RD					50%						\$		\$	75,00
13	Signal	BLOOMDALE RD & STONEBRIDGE DR					100%						\$	000,000	\$	300,00
14	Signal	BLOOMDALE RD & RIDGE RD	1	1			50%						\$		\$	150,00
15	Signal	BLOOMDALE RD & LAKE FOREST DR	1	<b> </b>			25%						\$	000,000	\$	75,00
23	Signal	STONEBRIDGE DR & WILMETH RD	1	<b>!</b>			100%						\$	300,000	\$	300,00
24	Signal	WILMETH RD & RIDGEKNOLL AVE	1	<b>!</b>			100%						\$		\$	300,00
25	Roundabout	LAKE FOREST DR & WILMETH RD	1	<b>!</b>			50%						\$ 1	1,000,000	\$	915,00
33	Signal Mod	US HIGHWAY 380 & STONEBRIDGE DR	1	1			50%						\$	,	\$	75,00
34	Signal	US HIGHWAY 380 & FOREST RIDGE LN	1	<u> </u>			50%						\$	300,000	\$	150,00
35	Signal	US HIGHWAY 380 & AUBURN HILLS PKWY		<u> </u>			50%				ļ	ļ	\$	300,000	\$	150,00 <b>116.870.61</b>
UBTOTAL		·	•	•					43,092		2,321	40,771	\$ 156	6,098,456	\$	-

TOTAL COST IN SERVICE AREA C \$ 116,882,308

#### RIP Service Units of Supply

Service Area D

D-4   D-5   D-6   D-7   D-8   D-9   D-9   D-7   D-8   D-9   D-9   D-7   D-8   D-9	ROADWAY  UNNAMED 5 (3)  UNNAMED 5 (4)  LAUD HOWELL PKWY (6)  LAUD HOWELL PKWY (7)  LAUD HOWELL PKWY (17)  TRINITY FALLS PKWY (17)  TRINITY FALLS PKWY (27)  BLOOMDALE RD (77)  BLOOMDALE RD (87)  BLOOMDALE RD (87)	LIMITS  CR 168 TO 1,560' E OF CR 168  1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD  LAKE FOREST DR TO 1860' E OF HARDIN BLVD  4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY FALLS PKWY  240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75  HARDIN BLVD TO 1,910' E OF HARDIN BLVD  COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY  LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY  4,275' N OF WESTON RD TO LAUD HOWELL PKWY  1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	LENGTH (ft)  1,584 2,270 13,992 3,907 2,006 1,901 739 1,795 2,218 5,544	6 6 6 6 6 4 4	M6D M6D G6D G6D G6D(1/3) G4D	PEAK HOUR VOLUME New New New New 802	% IN SERVICE AREA 50% 50% 100%	VEH-MI CAPACITY PK-HR PER LN 700 700 700	VEH-MI SUPPLY PK-HR TOTAL 630 903 11,130	VEH-FT SUPPLY PK-HR TOTAL 3,326,000 4,768,000 58,766,000	VEH-MI TOTAL DEMAND PK-HR 0 0	EXCESS CAPACITY PK-HR VEH-MI 630 903 11,130	TOTAL PROJECT COST \$ 7,517,500 \$ 4,904,200 \$ 39,497,100	TOTAL PROJECT COST IN SERVICE AREA \$ 3,758,750 \$ 2,452,100 \$ 39,497,100
# h2, D-1 h3, D-2 h3 h5, D-4 h5 h5 h5, D-8 h5	UNNAMED 5 (3)  UNNAMED 5 (4)  LAUD HOWELL PKWY (6)  LAUD HOWELL PKWY (7)  LAUD HOWELL PKWY (7)  TRINITY FALLS PKWY (1)  TRINITY FALLS PKWY (2)  TRINITY FALLS PKWY (3)  TRINITY FALLS PKWY (4)  TRINITY FALLS PKWY (6)  BLOOMDALE RD (7)  BLOOMDALE RD (8)  BLOOMDALE RD (9)	CR 168 TO 1,560' E OF CR 168  1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD  LAKE FOREST DR TO 1860' E OF HARDIN BLVD  4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY FALLS PKWY  240' N OF TRINITY FALLS PKWY TO 18 HIGHWAY 75  HARDIN BLVD TO 1,910' E OF HARDIN BLVD  1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD  COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY  LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY  4,275' N OF WESTON RD TO LAUD HOWELL PKWY  1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	(ft)  1,584 2,270 13,992 3,907 2,006 1,901 739 1,795 2,218	6 6 6 6 4 4	CLASSIFICATION  M6D  M6D  G6D  G6D  G6D  G6D  G4D	HOUR VOLUME New New New New	SERVICE AREA 50% 50% 100%	PK-HR PER LN 700 700 700	PK-HR TOTAL 630 903 11,130	PK-HR TOTAL 3,326,000 4,768,000 58,766,000	DEMAND PK-HR 0 0	PK-HR VEH-MI 630 903 11,130	\$ 7,517,500 \$ 4,904,200 \$ 39,497,100	COST IN SERVICE AREA \$ 3,758,750 \$ 2,452,100
73, 10-12 10-13 10-12 10-13 10-14 10-13 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14 10-14	UNNAMED 5 (3)  UNNAMED 5 (4)  LAUD HOWELL PKWY (6)  LAUD HOWELL PKWY (7)  LAUD HOWELL PKWY (7)  TRINITY FALLS PKWY (1)  TRINITY FALLS PKWY (2)  TRINITY FALLS PKWY (3)  TRINITY FALLS PKWY (4)  TRINITY FALLS PKWY (6)  BLOOMDALE RD (7)  BLOOMDALE RD (8)  BLOOMDALE RD (9)	CR 168 TO 1,560' E OF CR 168  1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD  LAKE FOREST DR TO 1860' E OF HARDIN BLVD  4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY FALLS PKWY  240' N OF TRINITY FALLS PKWY TO 18 HIGHWAY 75  HARDIN BLVD TO 1,910' E OF HARDIN BLVD  1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD  COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY  LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY  4,275' N OF WESTON RD TO LAUD HOWELL PKWY  1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	1,584 2,270 13,992 3,907 2,006 1,901 739 1,795 2,218	6 6 6 6 4 4	M6D M6D G6D G6D G6D(1/3) G4D	New New New New New	50% 50% 100%	700 700 700 700	TOTAL 630 903 11,130	TOTAL 3,326,000 4,768,000 58,766,000	PK-HR 0 0 0	VEH-MI 630 903 11,130	\$ 7,517,500 \$ 4,904,200 \$ 39,497,100	\$ 3,758,750 \$ 2,452,100
3-1, D-2 D-3 D-4 D-5 D-6 D-7 D-7 D-8 D-9 D-10 D-11 D-12 D-13 D-14	UNNAMED 5 (4) LAUD HOWELL PKWY (6) LAUD HOWELL PKWY (7) LAUD HOWELL PKWY (7) LAUD HOWELL PKWY (1) TRINITY FALLS PKWY (1) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD  LAKE FOREST DR TO 1860' E OF HARDIN BLVD  4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY FALLS PKWY  240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75  HARDIN BLVD TO 1,910' E OF HARDIN BLVD  1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD  COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY  LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY  4,275' N OF WESTON RD TO LAUD HOWELL PKWY  1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	2,270 13,992 3,907 2,006 1,901 739 1,795 2,218	6 6 6 6 4 4	M6D G6D G6D G6D(1/3) G4D	New New New	50% 50% 100%	700 700 700	630 903 11,130	3,326,000 4,768,000 58,766,000	0 0 0	630 903 11,130	\$ 4,904,200 \$ 39,497,100	\$ 3,758,750 \$ 2,452,100
3-1, D-2 D-3 D-4 D-5 D-6 D-7 D-7 D-8 D-9 D-10 D-11 D-12 D-13 D-14	UNNAMED 5 (4) LAUD HOWELL PKWY (6) LAUD HOWELL PKWY (7) LAUD HOWELL PKWY (7) LAUD HOWELL PKWY (1) TRINITY FALLS PKWY (1) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	1,050' W OF HARDIN BLVD TO 1,200' E OF HARDIN BLVD  LAKE FOREST DR TO 1860' E OF HARDIN BLVD  4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY FALLS PKWY  240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75  HARDIN BLVD TO 1,910' E OF HARDIN BLVD  1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD  COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY  LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY  4,275' N OF WESTON RD TO LAUD HOWELL PKWY  1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	2,270 13,992 3,907 2,006 1,901 739 1,795 2,218	6 6 6 6 4 4	M6D G6D G6D G6D(1/3) G4D	New New New	50% 100%	700 700	903 11,130	4,768,000 58,766,000	0	903 11,130	\$ 4,904,200 \$ 39,497,100	\$ 2,452,100
D-3 D-4 D-5 D-6 D-7 D-8 D-9 D-10 D-11 D-12 D-13 D-14	LAUD HOWELL PKWY (6) LAUD HOWELL PKWY (7) LAUD HOWELL PKWY (7) LAUD HOWELL PKWY (8) TRINITY FALLS PKWY (1) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (3) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (7) BLOOMDALE RD (9)	LAKE FOREST OR TO 1860' E OF HARDIN BLVD 4,170' N OF TRINITY FALLS PKWY TO 240' N OF TRINITY FALLS PKWY 240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75 HARDIN BLVD TO 1,910' E OF HARDIN BLVD 1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY 4,275' N OF WESTON RD TO LAUD HOWELL PKWY 1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	13,992 3,907 2,006 1,901 739 1,795 2,218	6 6 6 4 4	G6D G6D G6D(1/3) G4D	New New	100%	700	11,130	58,766,000	0	11,130	\$ 39,497,100	
D-4 D-5 D-6 D-7 D-8 D-9 D-10 D-11 D-12 D-13 D-14	LAUD HOWELL PKWY (7) LAUD HOWELL PKWY (8) TRINITY FALLS PKWY (1) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	4.170 N OF TRINITY FALLS PKWY TO 240 N OF TRINITY FALLS PKWY 240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75 HARDIN BLVD TO 1,910 E OF HARDIN BLVD 1,910 E OF HARDIN BLVD TO 2,675 E OF HARDIN BLVD COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY 4,275 N OF WESTON RD TO LAUD HOWELL PKWY 1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	3,907 2,006 1,901 739 1,795 2,218	6 6 4 4	G6D G6D(1/3) G4D	New								\$ 39,497,100
D-5   D-6   D-7   D-8   D-9   D-10   D-11   D-12   D-13   D-14	LAUD HOWELL PKWY (8) TRINITY FALLS PKWY (1) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (6) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	240' N OF TRINITY FALLS PKWY TO US HIGHWAY 75 HARDIN BLVD TO 1,910' E OF HARDIN BLVD 1,910' E OF HARDIN BLVD COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY 4,275' N OF WESTON RD TO LAUD HOWELL PKWY 1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	2,006 1,901 739 1,795 2,218	6 4 4	G6D(1/3) G4D		100%	700						
D-6 D-7 D-8 D-9 D-10 D-11 D-12 D-13 D-14	TRINITY FALLS PKWY (1) TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (3) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	HARDIN BLVD TO 1,910° E OF HARDIN BLVD 1,910° E OF HARDIN BLVD TO 2,675° E OF HARDIN BLVD COMMUNITY AVE TO 2,200° W OF LAUD HOWELL PKWY LAUD HOWELL PKWY TO 2,200° W OF LAUD HOWELL PKWY 4,275° N OF WESTON RD TO LAUD HOWELL PKWY 1,820° W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	1,901 739 1,795 2,218	4	G4D	802			3,108	16,410,000	0	3,108	\$ 8,774,550	\$ 8,774,550
D-7 D-8 D-9 D-10 D-11 D-12 D-13 D-14	TRINITY FALLS PKWY (2) TRINITY FALLS PKWY (3) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	1,910' E OF HARDIN BLVD TO 2,675' E OF HARDIN BLVD COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY 4,275' N OF WESTON RD TO LAUD HOWELL PKWY 1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	739 1,795 2,218	4			100%	700	1,596	8,427,000	305	1,291	\$ 2,220,027	\$ 2,220,027
D-8 D-9 D-10 D-11 D-12 D-13 D-14	TRINITY FALLS PKWY (3) TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	COMMUNITY AVE TO 2,200' W OF LAUD HOWELL PKWY LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY 4,275'N OF WESTON RD TO LAUD HOWELL PKWY 1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	1,795 2,218			100	100%	700	1,008	5,322,000	36	972	\$ 3,243,800	\$ 3,243,800
D-9 D-10 D-11 D-12 D-13 D-14	TRINITY FALLS PKWY (4) TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	LAUD HOWELL PKWY TO 2,200' W OF LAUD HOWELL PKWY 4,275' N OF WESTON RD TO LAUD HOWELL PKWY 1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	2,218	4	G4D	100	50%	700	196	1,035,000	7	189	\$ 1,300,600	\$ 650,300
D-10	TRINITY FALLS PKWY (5) BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	4,275' N OF WESTON RD TO LAUD HOWELL PKWY 1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR		4	G4D	New	50%	700	476	2,513,000	0	476	\$ 5,976,800	\$ 2,988,400
D-11 D-12 D-13 D-14	BLOOMDALE RD (7) BLOOMDALE RD (8) BLOOMDALE RD (9)	1,820' W OF TAYLOR-BURK DR TO TAYLOR-BURK DR	F F 4 4	4	G4D	New	100%	700	1,176	6,209,000	0	1,176	\$ 8,418,050	\$ 8,418,050
D-12 D-13 D-14	BLOOMDALE RD (8) BLOOMDALE RD (9)			6	M6D(1/3)	1,229	100%	700	4,410	23,285,000	1,291	3,119	\$ 7,622,400	\$ 7,622,400
D-13 D-14	BLOOMDALE RD (9)		1,795	6	P6D	12	50%	780	796	4,201,000	2	794	\$ 3,799,600	\$ 1,899,800
D-14		1,485' E OF CR 1006 TO 1,215' W OF CR 1007	1,531	6	P6D	12	100%	780	1,357	7,166,000	3	1,354	\$ 3,206,000	\$ 3,206,000
		1,225' W OF CR 1007 TO CR 1007	1,214	6	P6D	12	50%	780	538	2,842,000	1	537	\$ 3,001,600	\$ 1,500,800
D-15	BLOOMDALE RD (10)	CR 1007 TO HARDIN BLVD	1,954	6	P6D(2/3)	New	100%	780	1,732	9,143,000	0	1,732	\$ 5,885,810	\$ 5,885,810
2.3	BLOOMDALE RD (11)	HARDIN BLVD TO COMMUNITY AVE	2,587	6	P6D(1/3)	New	100%	780	2,293	12,108,000	0	2,293	\$ 5,165,390	\$ 5,165,390
D-16	WILMETH RD (5)	LAKE FOREST DR TO UNNAMED A	4,752	4	G4D	New	50%	700	1,260	6,653,000	0	1,260	\$ 10,991,050	\$ 5,495,525
D-17	WILMETH RD (6)	UNNAMED A TO 825' E OF UNNAMED A	845	4	G4D	86	100%	700	448	2,365,000	14	434	\$ 1,401,400	\$ 1,401,400
D-18	WILMETH RD (7)	825' E OF TAYLOR-BURK DR TO 1,380' E OF TAYLOR-BURK DR	581	2	G4D(1/2)	New	100%	700	154	813,000	0	154	\$ 411,600	\$ 411,600
D-19	WILMETH RD (8)	1,380' E OF TAYLOR-BURK DR TO HARDIN BLVD	2,218	4	G4D	86	50%	700	588	3,105,000	18	570	\$ 3,803,800	\$ 1,901,900
D-20	WILMETH RD (9)	HARDIN BLVD TO US HIGHWAY 75	6,125	2	M6D(1/3)	New	100%	700	1,624	8,575,000	0	1,624	\$ 2,799,600	\$ 2,799,600
D-21	LAKE FOREST DR (1)	LAUD HOWELL PKWY TO 3,200' S OF LAUD HOWELL PKWY	3,221	6	G6D	466	50%	700	1,281	6,764,000	142	1,139	\$ 6,448,400	\$ 3,224,200
34, D-22	LAKE FOREST DR (3)	WILMETH RD TO US HIGHWAY 380	5,174	2	M6D(1/3)	New	50%	700	686	3,622,000	0	686	\$ 2,350,800	\$ 1,175,400
D-23	UNNAMED A (1)	5,785' N OF LAUD HOWELL PKWY TO 2,710' S OF LAUD HOWELL PKWY	8,501	4	G4D	New	100%	700	4,508	23,802,000	0	4,508	\$ 17,435,950	\$ 17,435,950
D-24	UNNAMED A (2)	2,710' S OF LAUD HOWELL PKWY TO BLOOMDALE RD	2,587	4	G4D	New	50%	700	686	3,622,000	0	686	\$ 4,598,850	\$ 2,299,425
D-25	UNNAMED A (3)	1,105' N OF WILMETH RD TO WILMETH RD	1,109	4	G4D	86	50%	700	294	1,552,000	9	285	\$ 1,876,000	\$ 938,000
D-26	UNNAMED A (4)	WILMETH RD TO HARDIN BLVD	3,960	4	M4D	New	100%	700	2,100	11,088,000	0	2,100	\$ 5,969,050	\$ 5,969,050
D-27	TAYLOR-BURK DR (1)	HARDIN BLVD TO SKYLINE DR	1,478	4	M4D	New	100%	700	784	4,140,000	0	784	\$ 2,038,250	\$ 2,038,250
D-28	HARDIN BLVD (4)	UNNAMED 5 TO 1,550' S OF UNNAMED 5	1,531	6	G6D	New	50%	700	609	3,216,000	0	609	\$ 3,267,400	\$ 1,633,700
D-29	HARDIN BLVD (5)	1,545' S OF UNNAMED 5 TO TRINITY FALLS PKWY	7,286	6	G6D	New	100%	700	5,796	30,603,000	0	5,796	\$ 21,290,800	\$ 21,290,800
D-30	HARDIN BLVD (6)	TRINITY FALLS PKWY TO 1,815' S OF TRINITY FALLS PKWY	1,795	6	G6D	12	50%	700	714	3,770,000	2	712	\$ 4,102,000	\$ 2,051,000
D-31	HARDIN BLVD (7)	1,815' S OF TRINITY FALLS PKWY TO 1,190' S OF BLOOMDALE RD	1,901	6	G6D	New	100%	700	1,512	7,983,000	0	1,512	\$ 4,538,400	\$ 4,538,400
D-32	HARDIN BLVD (8)	1,190' S OF BLOOMDALE RD TO 3,590' S OF BLOOMDALE RD	2,376	2	G6D(1/3)	New	100%	700	630	3,326,000	0	630	\$ 1,070,400	\$ 1,070,400
D-33	HARDIN BLVD (9)	3,590' S OF BLOOMDALE RD TO WILMETH RD	1,742	4	G6D(2/3)	New	50%	700	462	2,439,000	0	462	\$ 2,249,800	\$ 1,124,900
D-34	HARDIN BLVD (10)	WILMETH RD TO US HIGHWAY 380	6,494	2	G6D(1/3)	New	100%	700	1,722	9,092,000	0	1,722	\$ 2,904,000	\$ 2,904,000
D-35	COMMUNITY AVE (1)	TRINITY FALLS PKWY TO 1,275' S OF TRINITY FALLS PKWY	1,267	4	G4D	387	100%	700	672	3,548,000	93	579	\$ 2,164,400	\$ 2,164,400
D-36	COMMUNITY AVE (2)	1,275' S OF TRINITY FALLS PKWY TO BLOOMDALE RD	2,640	2	G4D(1/2)	New	100%	700	700	3,696,000	0	700	\$ 1,960,000	\$ 1,960,000
D-37	COMMUNITY AVE (3)	BLOOMDALE RD TO 2,305' S OF BLOOMDALE RD	2,323	2	M4U(1/2)	New	100%	525	462	2,439,000	0	462	\$ 1,174,600	\$ 1,174,600
3	Signal	HARDIN BLVD & UNNAMED 5					50%			í '			\$ 300,000	\$ 150,000
6	Signal	LAUD HOWELL PKWY & LAKE FOREST DR					50%			í T	i '		\$ 300,000	\$ 150,000
7	Signal	LAUD HOWELL PKWY & UNNAMED A					100%			í '			\$ 300,000	\$ 300,000
8	Signal	LAUD HOWELL PKWY & HARDIN BLVD					100%			í T	i '		\$ 300,000	\$ 300,000
9	Signal	HARDIN BLVD & TRINITY FALLS PKWY					75%			í T	i '		\$ 300,000	\$ 225,000
10	Roundabout	TRINITY FALLS PKWY & COMMUNITY AVE					50%			í T	i '		\$ 200,000	\$ 100,000
11	Interchange Signals	US HIGHWAY 75 & LAUD HOWELL PKWY					50%			i			\$ 600,000	\$ 300,000
16	Signal	BLOOMDALE RD & UNNAMED A					25%			í T	i '		\$ 300,000	\$ 75,000
17	Signal	BLOOMDALE RD & HARDIN BLVD					100%			·			\$ 300,000	\$ 300,000
18	Signal	BLOOMDALE RD & COMMUNITY AVE					100%			í '			\$ 300,000	\$ 300,000
19	Interchange Signals	US HIGHWAY 75 & BLOOMDALE RD					50%			í T		,	\$ 600,000	\$ 300,000
25	Roundabout	LAKE FOREST DR & WILMETH RD					50%			í T	i '		\$ 1,830,000	\$ 915,000
26	Roundabout	WILMETH RD & UNNAMED A					75%			i			\$ 200,000	\$ 150,000
27	Roundabout	HARDIN BLVD & WILMETH RD	İ	1			75%			i '			\$ 2,100,000	\$ 1,575,000
32	Roundabout	HARDIN BLVD & TAYLOR-BURK DR	İ	1			100%			i '			\$ 1,200,000	\$ 1,200,000
36	Under Construction	US HIGHWAY 380 & HARDIN BLVD	1	1			50%			i			\$ 780,682	\$ 390,34
JBTOTAL		•	•	•				•	59.041		1.923	57,118	\$ 225,290,659	

\$ 11,692 TOTAL COST IN SERVICE AREA D \$ 189,027,810

#### RIP Service Units of Supply

Service Area E

Project ID #	ROADWAY	LIMITS	LENGTH (ft)	LANES	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI		. PROJECT COST	COST	L PROJECT IN SERVICE AREA
E-1	BLOOMDALE RD (12)	US HIGHWAY 75 TO REDBUD BLVD	2.534	2	P6D(1/3)	New	100%	780	749	3.954.000	0	749	S	955.200	\$	955,200
E-2	BLOOMDALE RD (13)	REDBUD BLVD TO AIRPORT DR	2.693	4	P6D(2/3)	New	100%	780	1,591	8,402,000	0	1,591		3,361,400	\$	3,361,400
E-3	WILMETH RD (10)	US HIGHWAY 75 TO 2.570' E OF REDBUD BLVD	4.118	2	M6D(1/3)	New	100%	700	1.092	5,766,000	0	1,092			\$	1,935,600
E-4	WILMETH RD (11)	2.570' E OF REDBUD BLVD TO STATE HIGHWAY 5	2.165	4	M6D(2/3)	New	100%	700	1,148	6.061.000	0	1,148			\$	2,608,200
E-5	WILMETH RD (12)	STATE HIGHWAY 5 TO 2.100' E OF SH 5	2,112	6	M6D	New	100%	700	1.680	8.870.000	0	1,680	\$	5,068,500	\$	5,068,500
E-6	WILMETH RD (13)	2,100' E OF SH 5 TO 980' W OF AIRPORT DR	1,320	6	M6D	102	100%	675	1,013	5,346,000	26	987			\$	2,804,200
E-7	WILMETH RD (14)	980' W OF AIRPORT DR TO 235' E OF AIRPORT DR	1,214	6	M6D	102	50%	700	483	2.550.000	12	471	\$	3.417.400	\$	1,708,700
E-8	WILMETH RD (15)	1,150' W OF FM 2933 TO 400' E OF FM 2933	1,531	6	M6D	233	50%	700	609	3,216,000	34	575	\$	3,229,800	\$	1,614,900
E-9	REDBUD BLVD (1)	BLOOMDALE RD TO 2,930' S OF BLOOMDALE RD	2,904	4	M4D	162	100%	700	1,540	8,131,000	89	1,451	\$	650,000	\$	650,000
E-10	REDBUD BLVD (2)	2,930' S OF BLOOMDALE RD TO WILMETH RD	1,637	2	M4D(1/2)	New	100%	700	434	2,292,000	0	434	\$	852,600	\$	852,600
E-11	LAUD HOWELL PKWY (9)	US HIGHWAY 75 TO 2,620' S OF US HIGHWAY 75	2,640	6	M6D	200	50%	700	1,050	5,544,000	50	1,000	\$	3,909,500	\$	1,954,750
E-12	LAUD HOWELL PKWY (10)	2,620' S OF US HIGHWAY 75 TO BLOOMDALE RD	1,637	6	M6D	200	100%	700	1,302	6,875,000	62	1,240	\$	1,876,700	\$	1,876,700
E-13	LAUD HOWELL PKWY (11)	BLOOMDALE RD TO STATE HIGHWAY 5	845	6	P6D	332	100%	780	749	3,954,000	53	696	\$	861,000	\$	861,000
E-14	STATE HIGHWAY 5 (1)	4,700' N OF AIRPORT DR TO 3,995' N OF AIRPORT DR	686	6	M6D	675	50%	700	273	1,441,000	44	229	\$	695,100	\$	347,550
E-15	STATE HIGHWAY 5 (2)	1,915' N OF AIRPORT DR TO US HIGHWAY 380	11,986	6	M6D	1,302	100%	700	9,534	50,340,000	2,956	6,578	\$ 1	13,994,400	\$	13,994,400
E-16	AIRPORT DR (1)	STATE HIGHWAY 5 TO 4,070 S OF STATE HIGHWAY 5	4,066	6	P6D	New	100%	780	3,604	19,027,000	0	3,604	\$	9,379,050	\$	9,379,050
E-17	AIRPORT DR (2)	WILMETH RD TO WOODLAWN RD (N)	2,798	6	P6D	New	100%	780	2,480	13,097,000	0	2,480	\$	6,582,850	\$	6,582,850
E-18	AIRPORT DR (3)	WOODLAWN RD (N) TO WOODLAWN RD (S)	1,531	6	P6D	863	100%	780	1,357	7,166,000	250	1,107	\$	3,648,400	\$	3,648,400
E-19	AIRPORT DR (4)	WOODLAWN RD (S) TO US HIGHWAY 380	3,854	6	P6D	New	100%	780	3,416	18,039,000	0	3,416	\$	8,952,800	\$	8,952,800
E-20	UNNAMED C (1)	410' E OF STATE HIGHWAY 5 TO 3,010' E OF STATE H	2,587	2	P6D(1/3)	New	100%	780	764	4,036,000	0	764	\$	986,400	\$	986,400
E-21	UNNAMED C (2)	WILMETH RD TO 2,615' S OF WILMETH RD	2,640	6	P6D	106	50%	780	1,170	6,178,000	27	1,143	\$	2,806,300	\$	1,403,150
11	Interchange Signals	US HIGHWAY 75 & LAUD HOWELL PKWY					50%						\$	600,000	\$	300,000
19	Interchange Signals	US HIGHWAY 75 & BLOOMDALE RD					50%						\$	600,000	\$	300,000
20	Signal	BLOOMDALE RD & REDBUD BLVD					100%						\$		\$	300,000
21	Signal	LAUD HOWELL PKWY & BLOOMDALE RD					100%						\$	300,000	\$	300,000
22	Signal Mod	STATE HIGHWAY 5 & LAUD HOWELL PKWY					100%						\$	150,000	\$	150,000
28	Signal	WILMETH RD & REDBUD BLVD					100%						\$	300,000	\$	300,000
29	Signal Mod	STATE HIGHWAY 5 & WILMETH RD					100%						\$	150,000	\$	150,000
30	Signal	AIRPORT DR & WILMETH RD					50%						\$	300,000	\$	150,000
31	Signal	UNNAMED C & WILMETH RD					50%						\$		\$	150,000
41	Signal Mod	US HIGHWAY 380 & AIRPORT DR					50%						\$	150,000		75,000
SUBTOTAL	-	<u> </u>							36,038		3,602	32,437	\$ 8	81,725,400	\$	73,721,350
															\$	11,692

TOTAL COST IN SERVICE AREA E \$ 73,733,042

#### RIP Service Units of Supply

Service	e Area F													10/7/2020
Project ID #	ROADWAY	LIMITS	LENGTH (ft)	ES CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	TOTAL PROJECT COST	. TOTAL PRO COST IN SE AREA	RVICE
		No Thoroughfare Road	lways within the	City Limits Currently P	resent withir	n Service Ar	ea F							
SUBTOTAL								0		0	0	\$ -	\$	-
													\$	11,692

TOTAL COST IN SERVICE AREA F \$

11,692

## RIP Service Units of Supply

Service Area G 10/6/2020

	Alca O															
Project ID #	ROADWAY	LIMITS	LENGTH (ft)	LANES	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	тот	AL PROJECT COST	COST I	. PROJECT N SERVICE AREA
G-1	VIRGINIA PKWY (1)	COIT RD TO 500' W OF INDEPENDENCE PKWY	4,752	2	M6D(1/3)	New	100%	700	1,260	6,653,000	0	1,260	\$	2.158.800	S	2,158,800
G-2	VIRGINIA PKWY (2)	500' W OF INDEPENDENCE PKWY TO 325' E OF FORKHORN DR	1,742	2	M6D(1/3)	New	50%	700	231	1,220,000	0	231	φ	794,400	\$	397,200
G-3	VIRGINIA PKWY (3)	325' E OF FORKHORN DR TO 935' W OF VIRGINIA HILLS DR	1,478	6	M6D(1/3)	1,755	50%	700	588	3,105,000	246	342	\$	913,196	\$	456,598
G-4	VIRGINIA PKWY (4)	935' W OF VIRGINIA HILLS DR TO CUSTER RD	2,693	6	M6D(1/3)	1,620	100%	700	2,142	11,310,000	826	1,316	\$	1,661,863	s	1,661,863
G-5	VIRGINIA PKWY (5)	CUSTER RD TO 410' E OF DANBURY RD	2.587	2	M6D(1/3)	New	100%	700	686	3.622.000	0	686	\$	1,182,000	S	1.182.000
G-6	VIRGINIA PKWY (6)	410' E OF DANBURY RD TO VIRGINIA PARKLANDS BLVD	2,059	1	M6D(1/6)	New	100%	700	273	1.441.000	0	273	\$	392,400	\$	392,400
G-7	WESTRIDGE BLVD (1)	COIT RD TO 1.635' E OF COIT RD	1.637	2	M6D(1/3)	New	50%	700	217	1,146,000	0	217	\$	745,200	\$	372,600
G-8	WESTRIDGE BLVD (2)	1,635' E OF COIT RD TO 2,720' E OF INDEPENDENCE PKWY	6,442	2	M6D(1/3)	New	100%	700	1,708	9,018,000	0	1.708	\$	2,931,600	S	2,931,600
G-9	WESTRIDGE BLVD (3)	2.720' E OF INDEPENDENCE PKWY TO CUSTER RD	2,640	2	M6D(1/3)	New	50%	700	350	1,848,000	0	350	\$	1,192,800	\$	596,400
H-1, G-10	ELDORADO PKWY (1)	CUSTER RD TO RIDGE RD	10.824	2	G6D(1/3)	New	50%	700	1,435	7,577,000	0	1.435	\$	5,202,000	\$	2,601,000
G-11	COIT RD (1)	US HIGHWAY 380 TO 2,610' S OF VIRGINIA PKWY	8,078	2	M6D(1/3)	New	50%	700	1,071	5,655,000	0	1,071	\$	3.681.600	\$	1,840,800
G-12	COIT RD (2)	WESTRIDGE BLVD TO 2,595' S OF WESTRIDGE BLVD	2,587	2	M6D(1/3)	New	50%	700	343	1,811,000	0	343	\$	1,184,400	\$	592,200
G-13	INDEPENDENCE PKWY (1)	2.380' S OF US HIGHWAY 380 TO 4.465' S OF US HIGHWAY 380	2,059	2	M6D(1/3)	New	100%	700	546	2,883,000	0	546	\$	951,600	\$	951,600
G-14	INDEPENDENCE PKWY (2)	VIRGINIA PKWY TO 2,690' S OF WESTRIDGE BLVD	8,026	2	M6D(1/3)	New	100%	700	2,128	11,236,000	0	2,128	\$	3.666,000	\$	3,666,000
G-15	CUSTER RD (4)	US HIGHWAY 380 TO WESTRIDGE BLVD	10,718	6	P6D	2,821	100%	780	9,500	50,162,000	5,726	3,775	\$	3,260,945	\$	3,260,945
G-16	CUSTER RD (5)	WESTRIDGE BLVD TO ELDORADO PKWY	5,386	6	P6D	3,292	100%	780	4,774	25,205,000	3,358	1,416	\$	1,476,398	\$	1,476,398
G-17, I-8	RIDGE RD (8)	US HIGHWAY 380 TO CREEKSIDE DR	6,864	4	G4D	561	50%	700	1,820	9,610,000	365	1,455	\$	550,813	\$	275,407
33	Signal Mod	US HIGHWAY 380 & STONEBRIDGE DR					50%						\$	150,000	\$	75,000
34	Signal	US HIGHWAY 380 & FOREST RIDGE LN					50%						\$	300,000	\$	150,000
37	Signal	STONEBRIDGE DR & LACIMA DR					100%						\$	300,000	\$	300,000
38	Signal	RIDGE RD & HABERSHAM WAY					50%						\$	343,000	\$	171,500
43	Signal	INDEPENDENCE PKWY & VIRGINIA PKWY					50%						\$	80,000	\$	40,000
44	Under Construction	VIRGINIA PKWY & RIDGE RD					50%						\$	390,341	\$	195,171
47	Signal	INDEPENDENCE PKWY & WESTRIDGE BLVD					100%						\$	300,000	\$	300,000
48	Under Construction	CUSTER RD & WESTRIDGE BLVD					75%						\$	390,341	\$	292,756
49	Roundabout	STONEBRIDGE DR & GLEN OAKS DR					100%						\$	1,950,000	\$	1,950,000
50	Roundabout	RIDGE RD & GLEN OAKS DR					50%						\$	2,640,000	\$	1,320,000
55	Signal	STONEBRIDGE DR & ALMA DR					100%						\$	300,000	\$	300,000
56	Signal	RIDGE RD & RUSH CREEK RD					50%						\$	300,000	\$	150,000
57	Signal	RIDGE RD & BERKSHIRE RD					50%						\$	300,000	\$	150,000
SUBTOTAL	<u> </u>					·			29,072		10,520	18,552	\$	39,689,697	\$	30,208,237

TOTAL COST IN SERVICE AREA G \$

11,692 30,219,929

#### RIP Service Units of Supply

Service Area H

Project ID #	ROADWAY	LIMITS	LENGTH (ft)	LANES	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	тот	AL PROJECT COST	AL PROJECT IN SERVICE AREA
H-1, G-10	ELDORADO PKWY (1)	CUSTER RD TO RIDGE RD	10,830	2	G6D(1/3)	New	50%	700	1,436	7,581,000	0	1,436	\$	5,202,000	\$ 2,601,000
H-2	SILVERADO TRL (1)	CUSTER RD TO BURNETT DR	1,930	4	M4D(1/2)	397	100%	700	1,023	5,404,000	145	879	\$	2,746,293	\$ 2,746,293
H-3	SILVERADO TRL (2)	ALMA DR TO ALFALFA DR	1,170	4	M4D	424	100%	700	620	3,276,000	94	526	\$	141,088	\$ 141,088
H-4	STACY RD (1)	CUSTER RD TO RIDGE RD	10,715	6	P6D(1/3)	2,065	100%	780	9,497	50,146,000	4,191	5,306	\$	4,479,991	\$ 4,479,991
H-5	CUSTER RD (6)	ELDORADO PKWY TO STONEBRIDGE DR	2,040	6	P6D	3,416	100%	780	1,808	9,547,000	1,320	488	\$	622,725	\$ 622,725
H-6	ALMA DR (1)	805' S OF BEAVER CREEK DR TO SILVERADO TRL	1,960	4	G4D	1,396	100%	700	1,039	5,488,000	518	521	\$	239,850	\$ 239,850
H-7	ALMA DR (2)	SILVERADO TRL TO STACY RD	2,625	6	M6D(1/3)	1,642	100%	700	2,088	11,025,000	817	1,272	\$	1,522,102	\$ 1,522,102
H-8, I-9	RIDGE RD (9)	MCKINNEY RANCH PKWY TO STACY RD	3,645	2	M6D(1/3)	New	50%	700	483	2,552,000	0	483	\$	1,662,000	\$ 831,000
H-9	MCKINNEY RANCH PKWY (1)	RIDGE RD TO STACY RD	4,075	2	M6D(1/3)	New	100%	700	1,080	5,705,000	0	1,080	\$	1,857,600	\$ 1,857,600
65	Signal	CUSTER RD & SILVERADO TRL					50%						\$	300,000	\$ 150,000
66	Signal	MCKINNEY RANCH PKWY & SILVERADO TRL					100%						\$	300,000	\$ 300,000
71	Signal	STACY RD & MCKINNEY RANCH PKWY					100%						\$	300,000	\$ 300,000
75	Signal	CUSTER RD & PARADISE DR					50%						\$	300,000	\$ 150,000
76	Signal	STACY RD & COLLIN MCKINNEY PKWY					50%						\$	300,000	150,000
77	Signal	ALMA DR & HENNEMAN WAY					100%						\$	300,000	\$ 300,000
SUBTOTAL		_							19,076		7,085	11,991	\$	20,273,649	\$ 16,391,649
															\$ 11.692

TOTAL COST IN SERVICE AREA H \$

16,403,341

#### **RIP Service Units of Supply**

Service Area I 10/6/2020

	AICUI														
Project ID #	ROADWAY	LIMITS	LENGTH (ft)	LANES	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	L PROJECT COST	COST IN	PROJECT I SERVICE REA
I-1	VIRGINIA PKWY (7)	1035' E OF RIDGE RD TO 1355' W OF HARDIN BLVD	7.550	6	M6D	2.802	100%	700	6.006	31.712.000	4.006	2.000	\$ 2.567.378	\$	2.567.378
I-2	VIRGINIA PKWY (8)	1355' W OF HARDIN BLVD TO HARDIN BLVD	1,373	6	M6D	2,740	100%	700	1.092	5.766.000	712	380	\$ 531,979		531,979
I-3	ELDORADO PKWY (2)	RIDGE RD TO HARDIN BLVD	10,930	2	G6D(1/3)	New	100%	700	2.898	15.301.000	0	2.898	\$ 4.857.600		4,857,600
1-4	MCKINNEY RANCH PKWY (2)	RIDGE RD TO HARDIN BLVD	9.504	2	M6D(1/3)	New	100%	700	2,520	13,306,000	0	2,520	\$ 4,338,000		4,338,000
I-5	COLLIN MCKINNEY PKWY (2)	LAKE FOREST DR TO COTTONWOOD CREEK	1.637	4	G4D	New	100%	700	868	4.583.000	0	868	\$ 1,777,105		1,777,105
I-6	COLLIN MCKINNEY PKWY (3)	COTTONWOOD CREEK TO 1110' E OF TINA DR	2.904	4	G4D(1/2)	200	100%	700	1,540	8,131,000	110	1,430	\$ 3,221,002		3,221,002
1-7	COLLIN MCKINNEY PKWY (4)	1110' E OF TINA TO HARDIN BLVD	1.003	4	G4D	New	100%	700	532	2,809,000	0	532	\$ 1,101,893	•	1.101.893
G-17, I-8	RIDGE RD (8)	US HIGHWAY 380 TO CREEKSIDE DR	6,864	4	G4D	561	50%	700	1.820	9,610,000	365	1,455	\$ 550,813	\$	275,407
H-8, I-9	RIDGE RD (9)	MCKINNEY RANCH PKWY TO STACY RD	3,643	2	M6D(1/3)	New	50%	700	483	2,550,000	0	483	\$ 1.662.000	\$	831,000
I-10, J-6	HARDIN BLVD (11)	US HIGHWAY 380 TO VIRGINIA PKWY	8,342	6	G6D(1/3)	1,402	50%	700	3,318	17,519,000	1,108	2,210	\$ 13,584,097	\$	6,792,049
I-11, J-7	HARDIN BLVD (12)	VIRGINIA PKWY TO MCKINNEY RANCH PKWY	13,939	2	G6D(1/3)	New	50%	700	1,848	9,757,000	0	1,848	\$ 6,208,800	\$	3,104,400
35	Signal	US HIGHWAY 380 & AUBURN HILLS PKWY			` ′		50%						\$ 300,000	\$	150,000
36	Under Construction	US HIGHWAY 380 & HARDIN BLVD					25%						\$ 780,682	\$	195,171
38	Signal	RIDGE RD & HABERSHAM WAY					50%						\$ 343,000	\$	171,500
44	Under Construction	VIRGINIA PKWY & RIDGE RD					50%						\$ 390,341	\$	195,171
45	Signal	VIRGINIA PKWY & JOPLIN DR					100%						\$ 300,000	\$	300,000
46	Signal	VIRGINIA PKWY & VILLAGE DR					100%						\$ 300,000	\$	300,000
50	Roundabout	RIDGE RD & GLEN OAKS DR					50%						\$ 2,640,000	\$	1,320,000
51	Roundabout	LAKE FOREST DR & GLEN OAKS DR					100%						\$ 1,900,000	\$	1,900,000
56	Signal	RIDGE RD & RUSH CREEK RD					50%						\$ 300,000	\$	150,000
57	Signal	RIDGE RD & BERKSHIRE RD					50%						\$ 300,000	\$	150,000
58	Signal	HARDIN BLVD & MAVERICK TRL					50%						\$ 300,000	\$	150,000
59	Signal	ELDORADO PKWY & WOODSON DR					100%						\$ 300,000	\$	300,000
60	Signal	ELDORADO PKWY & HIGHLANDS DR					100%						\$ 300,000	\$	300,000
72	Signal	LAKE FOREST DR & COLLIN MCKINNEY PKWY					100%						\$ 300,000	\$	300,000
73	Signal	HARDIN BLVD & COLLIN MCKINNEY PKWY					50%						\$ 300,000	\$	150,000
76	Signal	STACY RD & COLLIN MCKINNEY PKWY					50%						\$ 300,000	\$	150,000
SUBTOTAL	·	·							22,925		6,301	16,624	\$ 49,754,690	\$ 3	35,579,653

11,692

TOTAL COST IN SERVICE AREA I \$

35,591,345

ANES

2

4

LENGTH

(ft)

898

4.910 4

8,448 6

5,702 2

1,742

8,342

13,939

1,690

2,482 6

3.538 4

1,003 4

LIMITS

710' E OF US HIGHWAY 75 TO 1,180' E OF BARRANCA WAY

STATE HIGHWAY 121 TO 1,685' S OF STATE HIGHWAY 121

STATE HIGHWAY 121 TO 3,525' S OF STATE HIGHWAY 121

MCKINNEY RANCH PKWY & COLLIN MCKINNEY PKWY

640' S OF HARRY MCKILLOP BLVD / FM 546 TO STATE HIGHWAY 121

3,525' S OF STATE HIGHWAY 121 TO 4,520' S OF STATE HIGHWAY 121

2,100' E OF HARDIN BLVD TO MCKINNEY RANCH PKWY

HARDIN BLVD TO BOIS D'ARC RD

HARDIN BLVD TO US HIGHWAY 75

BOIS D'ARC RD TO COMMUNITY AVE

US HIGHWAY 380 TO VIRGINIA PKWY

US HIGHWAY 380 & HARDIN BLVD

STATE HIGHWAY 5 & STEWART RD

COLLIN MCKINNEY PKWY & CRAIG DR

STATE HIGHWAY 5 & ENTERPRISE DR

HARDIN BLVD & COLLIN MCKINNEY PKWY

HARDIN BLVD & MAVERICK TRL

ELDORADO PKWY & CRAIG DR

WHITE AVE & JORDAN RD

VIRGINIA PKWY TO MCKINNEY RANCH PKWY

#### **RIP Service Units of Supply**

IMPACT FEE

CLASSIFICATION

M4D

M4D

M6D

G6D(1/3)

M3U

G6D(1/3)

G6D(1/3)

M4D

M6D

M4D

M4D

PEAK

HOUR

VOLUME

625

714

2,163

New

New

1,402

New

760

4.141

1.281

1,281

% IN

SERVICE

AREA

100%

100%

100%

100%

100%

50%

50%

100%

50%

50%

50%

25%

100%

50%

100%

50%

100%

100%

50%

50%

12,550

#### Service Area J

ROADWAY

WHITE AVE (1)

WHITE AVE (2)

VIRGINIA PKWY (9)

ELDORADO PKWY (3)

COLLIN MCKINNEY PKWY (5)

HARDIN BLVD (11)

HARDIN BLVD (12)

MEDICAL CENTER DR

STATE HIGHWAY 5 (4)

STATE HIGHWAY 5 (5)

STATE HIGHWAY 5 (6)

Under Construction

Signal

Signal

Intersection Improvements

Signal

Signal

Signal

Signal

Signal

Project ID

J-1

J-2

J-3

J-4

J-5

I-10, J-6

I-11, J-7

J-8

J-9, K-7

J-10, K-8

J-11

36

39

58

61

62

67

68

69

73

SUBTOTAL

VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	тот	AL PROJECT COST		AL PROJECT T IN SERVICE AREA
700	476	2,513,000	106	370	\$	981,328	\$	981,328
700	2,604	13,749,000	664	1,940	\$	213,991	\$	213,991
700	427	2,255,000	3,461	-3,034	\$	3,267,873	\$	3,267,873
700	427	2,255,000	0	427	\$	4,047,600	\$	4,047,600
550	363	1,917,000	0	363	\$	1,953,000	\$	1,953,000
700	3,318	17,519,000	1,108	2,210	\$	13,584,097	\$	6,792,049
700	1,848	9,757,000	0	1,848	\$	6,208,800	\$	3,104,400
700	896	4,731,000	243	653	\$	2,240,000	\$	2,240,000
700	987	5,211,000	973	14	\$	4,647,300	\$	2,323,650
700	938	4,953,000	429	509	\$	2,223,200	\$	1,111,600
700	266	1,404,000	122	144	\$	627,900	\$	313,950
					\$	780,682	\$	195,171
					\$	300,000	\$	300,000
	CAPACITY PK-HR PER LN 700 700 700 700 700 700 700 700 700 70	CAPACITY SUPPLY PK-HR PK-HR PFR LN TOTAL 700 476 700 2,604 700 427 700 427 550 363 700 1,848 700 896 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 700 938 93 700 938 938 700 938 938 938 938 938 938 938 938 938 938	CAPACITY SUPPLY PK-HR PK-HR PK-HR PK-HR TOTAL TOTAL TOTAL TOTAL 700 476 2,513,000 700 427 2,255,000 700 427 2,255,000 7550 363 1,917,000 700 1,848 9,757,000 700 986 4,731,000 700 987 5,211,000 700 938 4,933,000 700 938 4,933,000	CAPACITY PK-HR         SUPPLY PK-HR         SUPPLY PK-HR PK-HR         DEMAND PK-HR DEMAND PK-HR           PGR LN         TOTAL         DEMAND PK-HR         DEMAND PK-HR           700         476         2,513,000         106           700         2,664         13,749,000         664           700         427         2,255,000         0           700         427         2,255,000         0           550         363         1,917,000         0           700         3,318         17,519,000         1,108           700         1,848         9,757,000         0           700         896         4,731,000         243           700         987         5,211,000         973           700         988         4,953,000         429	CAPACITY PK-HR         SUPPLY PK-HR         SUPPLY PK-HR PK-HR         TOTAL DEMAND PK-HR PK-HR PK-HR PK-HR PK-HR         DEMAND PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-H	CAPACITY PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-H	CAPACITY PK-HR         SUPPLY PK-HR         SUPPLY PK-HR         TOTAL DEMAND PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR         TOTAL PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR PK-HR	CAPACITY PK-HR         SUPPLY PK-HR         SUPPLY PK-HR         TOTAL DEMAND DEMAND PK-HR         TOTAL PROJECT COST         TOTAL COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST         COST <t< td=""></t<>

7,106

TOTAL COST IN SERVICE AREA J \$ 28,206,303

5,444 \$

11,692

300,000

150,000

300,000

300,000

300 000

300,000

300.000

43,025,771 \$

10/6/2020

150,000

150,000

150,000

300,000

300 000

150,000

150 000

28,194,611

#### **RIP Service Units of Supply**

#### Service Area K

6/2020	

Service	e Area K														10/6/2020
Project ID #	ROADWAY	LIMITS	LENGTH (ft)	LANES	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	SERVICE	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	AL PROJECT COST	COST II	. PROJECT N SERVICE AREA
K-1	VIRGINIA STREET	225' W OF AIRPORT DR TO AIRPORT DR	211	2	2UO	New	100%	500	40	211,000	0	40	\$ 779,650	\$	779,650
K-2	ELDORADO PKWY (4)	1,180' E OF BARRANCA WAY TO STATE HIGHWAY 5	2,112	2	G6D(1/3)	New	100%	700	560	2,957,000	0	560	\$ 1,699,200	\$	1,699,200
K-3	HARRY MCKILLOP BLVD / FM 546 (1)	STATE HIGHWAY 121 TO AIRPORT DR	7,709	2	P6D(1/3)	New	100%	780	2,278	12,026,000	0	2,278	\$ 1,839,600	\$	1,839,600
K-4, L-1	HARRY MCKILLOP BLVD / FM 546 (2)	AIRPORT DR TO 980' E OF AIRPORT DR	1,003	2	P6D(1/3)	New	50%	780	148	782,000	0	148	\$ 234,600	\$	117,300
K-5, L-2	HARRY MCKILLOP BLVD / FM 546 (3)	975' E OF AIRPORT DR TO 510' W OF HARRY MCKILLOP BLVD / FM 546 (N)	3,168	6	P6D	New	50%	780	1,404	7,413,000	0	1,404	\$ 3,267,400	\$	1,633,700
K-6	STATE HIGHWAY 5 (3)	INDUSTRIAL BLVD TO 640' S OF HARRY MCKILLOP BLVD / FM 546	2,112	6	M6D	4,141	100%	700	1,680	8,870,000	1,656	24	\$ 2,064,300	\$	2,064,300
J-9, K-7	STATE HIGHWAY 5 (4)	640' S OF HARRY MCKILLOP BLVD / FM 546 TO STATE HIGHWAY 121	2,482	6	M6D	4,141	50%	700	987	5,211,000	973	14	\$ 4,647,300	\$	2,323,650
J-10, K-8	STATE HIGHWAY 5 (5)	STATE HIGHWAY 121 TO 3,525' S OF STATE HIGHWAY 121	3,538	4	M4D	1,281	50%	700	938	4,953,000	429	509	\$ 2,223,200	\$	1,111,600
K-9, L-6	AIRPORT DR (5)	US HIGHWAY 380 TO 470' N OF HARRY MCKILLOP BLVD / FM 546	13,886	2	P6D(1/3)	New	50%	780	2,051	10,831,000	0	2,051	\$ 6,322,800	\$	3,161,400
K-10, L-7	AIRPORT DR (6)	470' N OF HARRY MCKILLOP BLVD / FM 546 TO HARRY MCKILLOP BLVD / FM 546	475	6	P6D	43	50%	780	211	1,112,000	2	209	\$ 2,925,200	\$	1,462,600
40	Signal	STATE HIGHWAY 5 & SMITH ST					100%						\$ 300,000	\$	300,000
41	Signal Mod	US HIGHWAY 380 & AIRPORT DR					50%						\$ 150,000	\$	75,000
52	Roundabout	WILSON CREEK PKWY & PARK VIEW AVE					100%						\$ 1,820,000	\$	1,820,000
53	Signal	WILSON CREEK PKWY & COLLEGE ST					100%						\$ 300,000	\$	300,000
54	Signal	AIRPORT DR & ELM ST					50%						\$ 300,000	\$	150,000
62	Signal	STATE HIGHWAY 5 & STEWART RD					50%						\$ 300,000	\$	150,000
63	Signal	HARRY MCKILLOP BLVD / FM 546 & AIRPORT DR					75%						\$ 300,000	\$	225,000
69	Signal	STATE HIGHWAY 5 & ENTERPRISE DR					50%						\$ 300,000	\$	150,000
SUBTOTAL									10,297		3,061	7,236	\$ 29,773,250	\$	19,363,000

\$ 11,692 TOTAL COST IN SERVICE AREA K \$ 19,374,692

#### RIP Service Units of Supply

Service Area L

Service	Area L													10/6/2020
Project ID #	ROADWAY	LIMITS	LENGTH (ft)	LANE	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI	L PROJECT COST	TOTAL PROJECT COST IN SERVICE AREA
K-4, L-1	HARRY MCKILLOP BLVD / FM 546 (2)	AIRPORT DR TO 980' E OF AIRPORT DR	1,003	2	P6D(1/3)	New	50%	780	148	782,000	0	148	\$ 234,600	\$ 117,300
K-5, L-2	HARRY MCKILLOP BLVD / FM 546 (3)	975' E OF AIRPORT DR TO 510' W OF HARRY MCKILLOP BLVD / FM 546 (N)	3,168	6	P6D	New	50%	780	1,404	7,413,000	0	1,404	\$ 3,267,400	
L-3	HARRY MCKILLOP BLVD / FM 546 (S) (1)	510' W OF HARRY MCKILLOP BLVD / FM 546 (N) TO 1,335' E OF HARRY MCKILLOP BLVD / FM 546 (N)	1,848	6	P6D	New	100%	780	1,638	8,649,000	0	1,638	\$ 2,153,725	\$ 2,153,725
L-4		3,480' W OF UNNAMED D TO UNNAMED D	3,485	6	P6D	New	100%	780	3,089	16,309,000	0	3,089	\$ 3,843,225	\$ 3,843,225
L-5	HARRY MCKILLOP BLVD / FM 546 (N) (1)	HARRY MCKILLOP BLVD / FM 546 (S) TO 1,865' E OF HARRY MCKILLOP BLVD / FM 546 (S)	1,848	6	M6D	New	100%	700	1,470	7,762,000	0	1,470	\$ 2,166,900	\$ 2,166,900
K-9, L-6	AIRPORT DR (5)	US HIGHWAY 380 TO 470' N OF HARRY MCKILLOP BLVD / FM 546	13,886	2	P6D(1/3)	New	50%	780	2,051	10,831,000	0	2,051	\$ 6,322,800	\$ 3,161,400
K-10, L-7	AIRPORT DR (6)	470' N OF HARRY MCKILLOP BLVD / FM 546 TO HARRY MCKILLOP BLVD / FM 546	475	6	P6D	43	50%	780	211	1,112,000	2	209	\$ 2,925,200	
L-8	UNNAMED C (3)	US HIGHWAY 380 TO 2,435' S OF US HIGHWAY 380	2,429	6	P6D	New	100%	780	2,153	11,367,000	0	2,153	\$ 5,807,850	\$ 5,807,850
L-9, M-5	UNNAMED C (4)	2,525' N OF HARRY MCKILLOP BLVD / FM 546 TO 1,230' N OF HARRY MCKILLOP BLVD / FM 546	1,320	6	P6D	New	50%	780	585	3,089,000	0	585	\$ 2,830,300	\$ 1,415,150
L-10, M-6	UNNAMED C (5)	HARRY MCKILLOP BLVD / FM 546 (N) TO 705' S OF HARRY MCKILLOP BLVD / FM 546 (S)	4,594	6	P6D	New	50%	780	2,036	10,749,000	0	2,036	\$ 10,002,150	\$ 5,001,075
41	Signal Mod	US HIGHWAY 380 & AIRPORT DR					50%						\$ 150,000	\$ 75,000
42	Signal	US HIGHWAY 380 & UNNAMED C					50%						\$ 300,000	\$ 150,000
54	Signal	AIRPORT DR & ELM ST					50%						\$ 300,000	\$ 150,000
63	Signal	HARRY MCKILLOP BLVD / FM 546 & AIRPORT DR					75%						\$ 300,000	\$ 225,000
70	Signal	HARRY MCKILLOP BLVD / FM 546 (S) & HARRY MCKILLOP BLVD / FM 546 (N)					100%						\$ 300,000	\$ 300,000
74	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (S)					50%						\$ 300,000	\$ 150,000
SUBTOTAL									14,785	•	2	14,783	\$ 41,204,150	\$ 27,812,925

\$ 11,692 TOTAL COST IN SERVICE AREA L \$ 27,824,617

#### **RIP Service Units of Supply**

Service Area M

Project ID #	ROADWAY	LIMITS	LENGTH (ft)	LANES (	IMPACT FEE CLASSIFICATION	PEAK HOUR VOLUME	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR PER LN	VEH-MI SUPPLY PK-HR TOTAL	VEH-FT SUPPLY PK-HR TOTAL	VEH-MI TOTAL DEMAND PK-HR	EXCESS CAPACITY PK-HR VEH-MI		TOTAL PROJECT COST IN SERVICE AREA
M-1	HARRY MCKILLOP BLVD / FM 546 (N) (2)	110' E OF UNNAMED C TO 300' E OF UNNAMED C	211	6	M6D	New	50%	700	84	444,000	0	84	\$ 196,075	\$ 98,038
M-2	HARRY MCKILLOP BLVD / FM 546 (N) (3)	1,700' N OF HARRY MCKILLOP BLVD / FM 546 TO 2,050' N OF HARRY MCKILLOP BLVD / FM 546	370	6	M6D	New	50%	700	147	776,000	0	147	\$ 361,150	\$ 180,575
M-3	HARRY MCKILLOP BLVD / FM 546 (N) (4)	405' N OF HARRY MCKILLOP BLVD / FM 546 TO 675' N OF HARRY MCKILLOP BLVD / FM 546	264	6	M6D	New	50%	700	105	554,000	0	105	\$ 279,000	\$ 139,500
M-4	HARRY MCKILLOP BLVD / FM 546 (S) (3)	UNNAMED C TO 695' E OF UNNAMED C	686	6	P6D	New	100%	780	608	3,212,000	0	608	\$ 719,975	\$ 719,975
L-9, M-5	UNNAMED C (4)	2,525' N OF HARRY MCKILLOP BLVD / FM 546 TO 1,230' N OF HARRY MCKILLOP BLVD / FM 546	1,320	6	P6D	New	50%	780	585	3,089,000	0	585	\$ 2,830,300	\$ 1,415,150
L-10, M-6	UNNAMED C (5)	HARRY MCKILLOP BLVD / FM 546 (N) TO 705' S OF HARRY MCKILLOP BLVD / FM 546 (S)	4,594	6	P6D	New	50%	780	2,036	10,749,000	0	2,036	\$ 10,002,150	\$ 5,001,075
64	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (N)					50%						\$ 300,000	\$ 150,000
74	Signal	UNNAMED C & HARRY MCKILLOP BLVD / FM 546 (S)					50%						\$ 300,000	\$ 150,000
SUBTOTA									3,565		0	3,565	\$ 14,988,650	\$ 7,854,313
														\$ 11,692

TOTAL COST IN SERVICE AREA B \$ 7,866,005

2019 Roadway Impact Fee Update City of McKinney, Texas





Appendix C – Existing Roadway Facilities Inventory

Service Area A

ROADWAY	FROM	то	LENGTH (ft)	LENGTH (mi)	EXI LAN	_	TYPE	P PE HO VO	AK UR	% IN SERVICE AREA	VEH CAPA PK- PER	CITY	VEH SUP PK- TO	PLY -HR	VEH DEM PK- TOT	AND HR	EXC CAPA PK- VEI	-HR	PK-	TING ENCIES -HR H-MI
					NB/EB	SB/WB		NB/EB	SB/WB		NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB
UNNAMED 5	RIDGE RD	1,505' E OF RIDGE RD	1,504	0.28	1	1	2U	50	50	50%	475	475	68	68	7	7	61	61		
SUBTOTAL			1,504	0.28									68	68	7	7	61	61	0	0
													1:	35	1	4	12	21	(	<del></del>

Service Area B

								P	M	% IN	VEI	H-MI	VEI	H-MI	VEI	I-MI	EXC	ESS	EXIS	TING
ROADWAY	FROM	то	LENGTH	LENGTH	EX	IST	TYPE	PE	AK	SERVICE	CAPA	ACITY	SUF	PLY	DEM	AND	CAP	ACITY	DEFICI	<b>ENCIES</b>
			(ft)	(mi)	LAI	NES		HO	UR	AREA	PK	-HR	PK	-HR	PK-	-HR	PK	-HR	PK-	-HR
								V	OL		PEF	R LN	TO	TAL	TO	TAL	VEI	н-мі	VE	Н-МІ
					NB/EB	SB/WB		NB/EB	SB/WB		NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB
HARDIN BLVD	CR 204	CR 206	433	0.08	1	1	2U	50	50	50%	475	475	19	19	2	2	17	17		
HARDIN BLVD	1,670' N OF MELISSA RD	MELISSA RD	1,668	0.32	1	1	2U	50	50	50%	475	475	75	75	8	8	67	67		
HARDIN BLVD	MELISSA RD	730' S OF MELISSA RD	730	0.14	1	1	2U	50	50	50%	475	475	33	33	3	3	29	29		
SUBTOTAL			2,831	0.54									127	127	13	13	114	114	0	0
													2	55	2	7	2	28	(	ó –

Service Area C

ROADWAY	FROM	то	LENGTH	LENGTH	EX	IST	TYPE		M AK	% IN SERVICE		H-MI ACITY		H-MI PPLY		H-MI IAND		CESS	EXIS DEFICI	STING IENCIE
			(ft)	(mi)	LA	NES		HC	UR	AREA		-HR	PK	-HR	PK	-HR	PK	K-HR	PK	-HR
									OL			LN		TAL		TAL		Н-МІ		H-MI
						SB/WB			SB/WB										NB/EB	SB/WI
US HIGHWAY 380	RIDGE RD	LAKE FOREST DR	5,517	1.04	3	3	6D	2,025	2,025	100%	780	780	2,445	2,445	2,116		329	329		
US HIGHWAY 380	CUSTER RD	STONEBRIDGE DR	3,371	0.64	3	3	6D	1,679	1,731	100%	780	780	1,494	1,494			422	389		
US HIGHWAY 380	STONEBRIDGE DR	RIDGE RD	7,516	1.42	3	3	6D	1,913	1,913	100%	780	780	3,331	3,331	2,724	2,724	608	608		
LAKE FOREST DR	WILMETH RD	US HIGHWAY 380	5,153	0.98	2	2	4D	922	922	50%	700	700	683	683	450	450	233	233		
WILMETH RD	265' W OF SUNNYSIDE DR	LAKE FOREST DR	1,692	0.32	2	2	4D	249	249	100%	700	700	449	449	80	80	369	369		
WILMETH RD	3,230' E OF STONEBRIDGE DR	995' W OF RIDGE RD	1,701	0.32	1	1	2U	17	17	50%	475	475	77	77	3	3	74	74		
CUSTER RD	BLOOMDALE RD	375' N OF WILMETH RD	3,623	0.69	1	1	2U	549	562	50%	475	475	163	163	188	193	-25	-30	25	30
BLOOMDALE RD	1,310' E OF CUSTER RD	2,030' W OF STONEBRIDGE DR	2,104	0.40	1	1	2U	187	129	50%	475	475	95	95	37	26	57	69		
BLOOMDALE RD	STONEBRIDGE DR	3,245' E OF STONEBRIDGE DR	3,243	0.61	1	1	2U	187	129	100%	475	475	292	292	115	79	177	213		
RIDGE RD	1,590' N OF WILMETH RD	WILMETH RD	1,591	0.30	1	1	2U	39	48	50%	475	475	72	72	6	7	66	64		Î
BLOOMDALE RD	3,400' W OF LAKE FOREST DR	LAKE FOREST DR	3,402	0.64	1	1	2U	58	58	50%	475	475	153	153	19	19	134	134		
LAKE FOREST DR	BLOOMDALE RD	WILMETH RD	5,410	1.02	2	2	4D	421	421	50%	700	700	717	717	216	216	502	502	1	
LAUD HOWELL PKWY	700' W OF CUSTER RD	CUSTER RD	695	0.13	1	1	2U	271	271	50%	475	475	31	31	18	18	13	13		
LAUD HOWELL PKWY	1,985' W OF RIDGE RD	RIDGE RD	1,984	0.38	1	1	2U	271	271	50%	475	475	89	89	51	51	38	38	1	
CUSTER RD	2,655 N OF BLOOMDALE RD	BLOOMDALE RD	2,654	0.50	1	1	2U	309	306	50%	475	475	119	119	78	77	42	42		
CUSTER RD	1,855' N OF LAUD HOWELL PKWY	LAUD HOWELL PKWY	1,853	0.35	1	1	2U	309	306	50%	475	475	83	83	54	54	29	30		
RIDGE RD	UNNAMED 5	1,485' S OF UNNAMED 5	1,486	0.28	1	1	2U	50	50	50%	475	475	67	67	7	7	60	60	1	1
RIDGE RD	BAXTER WELL RD	BLOOMDALE RD	2,225	0.42	1	1	2U	5	4	50%	475	475	100	100	1	1	99	99	1	
RIDGE RD	BLOOMDALE RD	1,315' S OF BLOOMDALE RD	1,316	0.25	1	1	2U	39	48	50%	475	475	59	59	5	6	54	53		
RIDGE RD	1,315' S OF BLOOMDALE RD	2,160' S OF BLOOMDALE RD	846	0.16	1	1	2U	39	48	50%	475	475	38	38	3	4	35	34	1	1
UNNAMED 5	RIDGE RD	1,505' E OF RIDGE RD	1,504	0.28	1	1	2U	50	50	50%	475	475	68	68	7	7	61	61	1	1
LAUD HOWELL PKWY	CUSTER RD	1,225' E OF CUSTER RD	1,227	0.23	1	1	2U	271	271	100%	475	475	110	110	63	63	47	47	1	<b>†</b>
LAUD HOWELL PKWY	1,225' E OF CUSTER RD	2,070' E OF CUSTER RD	844	0.16	1	1	2U	271	271	50%	475	475	38	38	22	22	16	16	1	1
LAUD HOWELL PKWY	840' E OF STONEBRIDGE DR	2.905' E OF STONEBRIDGE DR	2.067	0.39	1	1	2U	271	271	50%	475	475	93	93	53	53	40	40	1	<b>†</b>
LAUD HOWELL PKWY	RIDGE RD	1,230' E OF RIDGE RD	1,230	0.23	1	1	2U	271	271	50%	475	475	55	55	32	32	24	24	1	<b>†</b>
BLOOMDALE RD	CUSTER RD	1,310' E OF CUSTER RD	1,308	0.25	1	1	2U	187	129	100%	475	475	118	118	46	32	71	86	†	
BLOOMDALE RD	2.030' W OF STONEBRIDGE DR	STONEBRIDGE DR	2,030	0.38	1	1	2U	187	129	100%	475	475	183	183	72	50	111	133	+	
BLOOMDALE RD	3.245' E OF STONEBRIDGE DR	695' W OF RIDGE RD	1,366	0.26	1	1	2U	187	129	50%	475	475	61	61	24	17	37	45	1	<b>†</b>
BLOOMDALE RD	695' W OF RIDGE RD	RIDGE RD	696	0.13	1	1	2U	187	129	100%	475	475	63	63	25	17	38	46	†	
WILMETH RD	815' E OF STONEBRIDGE DR	1.450' E OF STONEBRIDGE DR	634	0.12	1	1	2U	17	17	50%	475	475	29	29	1	1	27	27	+	
WILMETH RD	1.575' E OF STONEBRIDGE DR	2,295' E OF STONEBRIDGE DR	719	0.14	1	1	2U	17	17	50%	475	475	32	32	1	1	31	31	+	1
WILMETH RD	2.445' E OF STONEBRIDGE DR	2,730' E OF STONEBRIDGE DR	286	0.05	1	1	2U	17	17	50%	475	475	13	13	0	0	12	12	<del>                                     </del>	+
WILMETH RD	RIDGE RD	585' E OF RIDGE RD	585	0.11	1	1	2U	66	66	100%	475	475	53	53	7	7	45	45	+	
WILMETH RD	RIDGEWAY DR	RIDGEKNOLL AVE	1,222	0.23	2	2	4D	66	66	100%	700	700	324	324	15	15	309	309	1	<del>                                     </del>
WILMETH RD	585' E OF RIDGE RD	1.095' E OF RIDGE RD	508	0.10	2	2	4D	66	66	100%	700	700	135	135	6	6	128	128	1	<del>                                     </del>
WILMETH RD	1.095' E OF RIDGE RD	1.365' E OF RIDGE RD	268	0.10	1	1	2U	66	66	50%	475	475	12	12	2	2	10	10	+	<del>                                     </del>
WILMETH RD	RIDGEKNOLL AVE	265' W OF SUNNYSIDE DR	1,304	0.25	2	2	4D	249	249	100%	700	700	346	346	62	62	284	284	+	<del>                                     </del>
SUBTOTAL			75.180	14.24	<del>-</del> -	<del>  -</del>	<u> </u>		5	.0070			12.288		4		4.609	_	25	30
JUDIUIAL	L	I.	13,100	14.24	Ĺ	I	ı	Ĺ	1	l	1			577		.299		.278	4	55

Service Area D

ROADWAY	FROM	то	LENGTH	LENGTH	EX	IST	TYPE		M AK	% IN SERVICE	VEI CAPA	H-MI ACITY		H-MI PPLY		I-MI	_	ESS ACITY	DEFICIE	STING ENCIE
			(ft)	(mi)	LA	NES		нс	UR	AREA	PK-	-HR	PK	-HR	PK	-HR	PK	-HR	PK-	-HR
			. ,	` ′				V	OL		PEF	RLN	то	TAL	то	TAL	VEI	н-мі	VEH	н-МІ
					NB/EB	SB/WB		NB/EB	SB/WB		NB/EB	SB/WE	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/W
US HIGHWAY 380	COMMUNITY AVE	US HIGHWAY 75	2357	0.45	3	3	6D	2441	2441	100%	780	780	1,044	1,044	1,090	1,090	-45	-45	45	45
US HIGHWAY 380	HARDIN BLVD	COMMUNITY AVE	5281	1.00	3	3	6D	2169	2169	100%	780	780	2,340	2,340	2,170	2,170	171	171		
US HIGHWAY 380	LAKE FOREST DR	HARDIN BLVD	5,496	1.04	3	3	6D	2583	2583	100%	780	780	2,436	2,436	2,689	2,689	-253	-253	253	253
COMMUNITY AVE	TAYLOR-BURK DR	US HIGHWAY 380	2,389	0.45	2	2	4U	790	790	100%	525	525	475	475	358	358	117	117		
TAYLOR-BURK DR	COMMUNITY AVE	US HIGHWAY 75	2,526	0.48	1	1	2U	329	234	100%	475	475	227	227	158	112	70	115		
TAYLOR-BURK DR	SKYLINE DR	COMMUNITY AVE	2,840	0.54	1	1	2U	150	140	100%	475	475	256	256	81	76	175	180		
HARDIN BLVD	TAYLOR-BURK DR	US HIGHWAY 380	2,879	0.55	2	2	4D	340	340	100%	700	700	763	763	185	185	578	578		
COMMUNITY AVE	WILMETH RD	TAYLOR-BURK DR	2,436	0.46	2	2	4U	293	293	100%	525	525	484	484	135	135	349	349		
WILMETH RD	COMMUNITY AVE	US HIGHWAY 75	2,275	0.43	2	2	4D	615	615	100%	700	700	603	603	265	265	338	338		
LAKE FOREST DR	WILMETH RD	US HIGHWAY 380	5,153	0.98	2	2	4D	922	922	50%	700	700	683	683	450	450	233	233		
WILMETH RD	1,380' E OF UNNAMED A	HARDIN BLVD	2,240	0.42	1	1	2U	43	43	50%	475	475	101	101	9	9	92	92		
HARDIN BLVD	WILMETH RD	TAYLOR-BURK DR	3,641	0.69	2	2	4D	340	340	100%	700	700	965	965	234	234	731	731		
WILMETH RD	HARDIN BLVD	COMMUNITY AVE	3,866	0.73	2	2	4D	470	470	100%	700	700	1,025	1,025	344	344	681	681		
COMMUNITY AVE	BLOOMDALE RD	2,305' S OF BLOOMDALE RD	2,306	0.44	1	1	2U	356	356	100%	475	475	207	207	155	155	52	52		1
BLOOMDALE RD	COMMUNITY AVE	US HIGHWAY 75	2,548	0.48	3	3	6D	260	260	100%	780	780	1,129	1,129	125	125	1,004	1,004		
HARDIN BLVD	1,190' S OF BLOOMDALE RD	3,590' S OF BLOOMDALE RD	2,398	0.45	2	2	4D	35	35	100%	700	700	636	636	16	16	620	620		
COMMUNITY AVE	1,275' S OF TRINITY FALLS PKWY	BLOOMDALE RD	2,654	0.50	1	1	2U	193	193	100%	475	475	239	239	97	97	142	142		
HARDIN BLVD	TRINITY FALLS PKWY	1,815' S OF TRINITY FALLS PKWY	1,817	0.34	1	1	2UG	6	6	50%	150	150	26	26	1	1	25	25		
TRINITY FALLS PKWY	HARDIN BLVD	1,910' E OF HARDIN BLVD	1,908	0.36	1	1	2U	50	50	100%	475	475	172	172	18	18	154	154		
LAUD HOWELL PKWY	240' N OF TRINITY FALLS PKWY	US HIGHWAY 75	2,018	0.38	2	2	4D	401	401	100%	700	700	535	535	153	153	382	382		
LAKE FOREST DR	LAUD HOWELL PKWY	3,200' S OF LAUD HOWELL PKWY	3,198	0.61	1	1	2U	233	233	50%	475	475	144	144	71	71	73	73		
TRINITY FALLS PKWY	4,275' N OF WESTON RD	WESTON RD	4,273	0.81	2	2	4D	618	611	100%	700	700	1,133	1,133	500	495	633	638		
HARDIN BLVD	3,590' S OF BLOOMDALE RD	295' N OF WILMETH RD	1,460	0.28	1	1	2U	35	35	50%	475	475	66	66	5	5	61	61		
UNNAMED A	1,100' N OF WILMETH RD	WILMETH RD	1,103	0.21	1	1	2U	43	43	50%	475	475	50	50	5	5	45	45		
TRINITY FALLS PKWY	1,910' E OF HARDIN BLVD	2,670' E OF HARDIN BLVD	763	0.14	1	1	2U	50	50	100%	475	475	69	69	7	7	61	61		
COMMUNITY AVE	TRINITY FALLS PKWY	1,275' S OF TRINITY FALLS PKWY	1,274	0.24	1	1	2U	193	193	100%	475	475	115	115	47	47	68	68		
COMMUNITY AVE	2,305' S OF BLOOMDALE RD	WILMETH RD	2,151	0.41	2	2	4U	356	356	100%	525	525	428	428	145	145	283	283		
BLOOMDALE RD	1,820' W OF UNNAMED A	UNNAMED A	1,822	0.34	1	1	2U	6	6	50%	475	475	82	82	1	1	81	81		
BLOOMDALE RD	1,485' E OF CR 1006	1,215' W OF CR 1007	1,537	0.29	1	1	2UG	6	6	100%	150	150	44	44	2	2	42	42		
BLOOMDALE RD	1,215' W OF CR 1007	CR 1007	1,224	0.23	1	1	2UG	6	6	50%	150	150	17	17	1	1	17	17		t
WILMETH RD	UNNAMED A	825' E OF UNNAMED A	825	0.16	1	1	2U	43	43	100%	475	475	74	74	7	7	67	67		t
WILMETH RD	825' E OF UNNAMED A	1,380' E OF UNNAMED A	557	0.11	1	1	2U	43	43	100%	475	475	50	50	5	5	46	46		t
UNNAMED A	1,800' N OF WILMETH RD	1,100' N OF WILMETH RD	698	0.13	1	1	2U	43	43	50%	475	475	31	31	3	3	29	29		t
HARDIN BLVD	295' N OF WILMETH RD	WILMETH RD	294	0.06	2	2	4D	35	35	50%	700	700	39	39	1	1	38	38		t
TRINITY FALLS PKWY	WESTON RD	LAUD HOWELL PKWY	1,257	0.24	1	1	2U	618	611	100%	475	475	113	113	147	146	-34	-32	34	32
SUBTOTAL			81.465	15.43									16.802	16,802	9,678	9.621	7.124	7.181	332	33
	L	1	2.,100											603		298		305		63

Service Area E

								P		% IN	VEI			H-MI				CESS		STING
ROADWAY	FROM	то	LENGTH	LENGTH		(IST	TYPE		AK	SERVICE	-	ACITY		PPLY		IAND			DEFICI	
			(ft)	(mi)	LA	NES			UR	AREA		-HR		-HR		-HR		(-HR		-HR
									OL			LN		TAL	TO.			H-MI		H-MI
					NB/EB	SB/WB		NB/EB	SB/WB		NB/EB			SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/V
US HIGHWAY 380	THROCKMORTON ST	AIRPORT DR	2452	0.46	3	3	6D	1515	1515	100%	780	780	1,087	1,087	703	703	383	383		
US HIGHWAY 380	STATE HIGHWAY 5	THROCKMORTON ST	2595	0.49	3	3	6D	1492	1492	100%	780	780	1,150	1,150	733	733	417	417		
US HIGHWAY 380	TENNESSEE ST	STATE HIGHWAY 5	683	0.13	3	3	6D	1638	1638	100%	780	780	303	303	212	212	91	91	<u> </u>	
REDBUD BLVD	US HIGHWAY 380	WHITE AVE	3,146	0.60	2	2	4D	208	276	100%	700	700	834	834	124	164	710	670		
US HIGHWAY 380	GRAVES ST	TENNESSEE ST	4,618	0.87	3	3	6D	2024	2024	100%	780	780	2,047	2,047	1,770	1,770	277	277	<u> </u>	
TENNESSEE ST	STATE HIGHWAY 5	US HIGHWAY 380	1,405	0.27	2	2	4U	194	270	100%	525	525	279	279	52	72	228	208	<u> </u>	
STATE HIGHWAY 5	TENNESSEE ST	US HIGHWAY 380	1,785	0.34	2	2	4D	651	651	100%	700	700	473	473	220	220	253	253	<u> </u>	
US HIGHWAY 380	US HIGHWAY 75	REDBUD BLVD	1,479	0.28	3	3	6D	1935	1935	100%	780	780	655	655	542	542	114	114	<u> </u>	
REDBUD BLVD	BRAY CENTRAL DR	US HIGHWAY 380	2,846	0.54	2	2	4D	322	370	100%	700	700	755	755	174	199	581	555		
BRAY CENTRAL DR	US HIGHWAY 75	REDBUD BLVD	2,300	0.44	2	2	4U	171	171	100%	525	525	457	457	75	75	383	383		
UNNAMED C	WILMETH RD	2,615' S OF WILMETH RD	2,613	0.49	1	1	2U	53	53	50%	475	475	118	118	13	13	104	104		
REDBUD BLVD	WILMETH RD	BRAY CENTRAL DR	2,383	0.45	2	2	4D	232	268	100%	700	700	632	632	105	121	527	511		
WILMETH RD	US HIGHWAY 75	REDBUD BLVD	1,536	0.29	2	2	4D	481	481	100%	700	700	407	407	140	140	267	267		
STATE HIGHWAY 5	WILMETH RD	TENNESSEE ST	4,843	0.92	1	1	2U	534	534	100%	475	475	436	436	490	490	-54	-54	54	54
WILMETH RD	2,570' E OF REDBUD BLVD	STATE HIGHWAY 5	2,146	0.41	1	1	2U	462	462	100%	475	475	193	193	188	188	5	5	1	
STATE HIGHWAY 5	AIRPORT DR	1,965' S OF AIRPORT DR	1,967	0.37	1	1	2U	497	497	100%	475	475	177	177	185	185	-8	-8	8	8
REDBUD BLVD	BLOOMDALE RD	2,930' S OF BLOOMDALE RD	2,931	0.56	2	2	4D	75	87	100%	700	700	777	777	41	48	736	729	1	
BLOOMDALE RD	US HIGHWAY 75	REDBUD BLVD	2,521	0.48	2	2	4D	183	183	100%	700	700	668	668	87	87	581	581		
BLOOMDALE RD	REDBUD BLVD	LAUD HOWELL PKWY	2,693	0.51	1	1	2U	66	66	100%	475	475	242	242	34	34	208	208		
LAUD HOWELL PKWY	BLOOMDALE RD	STATE HIGHWAY 5	871	0.16	1	1	2U	166	166	100%	475	475	78	78	27	27	51	51		
LAUD HOWELL PKWY	US HIGHWAY 75	2,620' S OF US HIGHWAY 75	2,622	0.50	1	1	2U	100	100	50%	475	475	118	118	25	25	93	93		
STATE HIGHWAY 5	4,700' N OF AIRPORT DR	3,995' N OF AIRPORT DR	706	0.13	1	1	2U	337	337	50%	475	475	32	32	23	23	9	9		
STATE HIGHWAY 5	1,915' N OF AIRPORT DR	AIRPORT DR	1,915	0.36	1	1	2U	337	337	100%	475	475	172	172	122	122	50	50		
STATE HIGHWAY 5	1,965' S OF AIRPORT DR	WILMETH RD	1,452	0.27	1	1	3U	497	497	100%	525	525	144	144	137	137	8	8		
LAUD HOWELL PKWY	2,620' S OF US HIGHWAY 75	BLOOMDALE RD	1,635	0.31	1	1	2U	100	100	100%	475	475	147	147	31	31	116	116		
AIRPORT DR	WOODLAWN RD (N)	WOODLAWN RD (S)	1,536	0.29	1	1	2U	431	431	100%	475	475	138	138	126	126	13	13		
WILMETH RD	UNNAMED C	400' E OF UNNAMED C	399	0.08	1	1	2U	117	117	50%	475	475	18	18	4	4	14	14		
WILMETH RD	1,150' W OF UNNAMED C	UNNAMED C	1,150	0.22	1	1	2U	117	117	50%	475	475	52	52	13	13	39	39		
WILMETH RD	AIRPORT DR	235' E OF AIRPORT DR	236	0.04	1	1	2U	51	51	50%	475	475	11	11	1	1	9	9		
WILMETH RD	980' W OF AIRPORT DR	AIRPORT DR	981	0.19	1	1	2U	51	51	50%	475	475	44	44	5	5	39	39		
WILMETH RD	2,100' E OF SH 5	980' W OF AIRPORT DR	1,346	0.25	1	1	2U	51	51	100%	475	475	121	121	13	13	108	108		
WILMETH RD	REDBUD BLVD	1,340' E OF REDBUD BLVD	1,343	0.25	2	2	4D	462	462	100%	700	700	356	356	117	117	239	239		
WILMETH RD	1,340' E OF REDBUD BLVD	2,570' E OF REDBUD BLVD	1,228	0.23	2	2	4D	462	462	100%	700	700	325	325	107	107	218	218		
REDBUD BLVD	2,930' S OF BLOOMDALE RD	WILMETH RD	1,645	0.31	1	1	2U	75	87	100%	475	475	148	148	23	27	125	121		
US HIGHWAY 380	REDBUD BLVD	GRAVES ST	854	0.16	3	3	6D	1911	1911	100%	780	780	378	378	309	309	69	69		
US HIGHWAY 380	AIRPORT DR	940' E OF AIRPORT DR	939	0.18	2	2	4D	2249	2249	100%	700	700	249	249	400	400	-151	-151	151	15
SUBTOTAL			67,800	12.84				,					14,223	14,223	7,371	7,484	6,852	6,739	213	21

Service Area F	10/7/2020
----------------	-----------

ROADWAY	FROM	то	LENGTH (ft)	LENGTH (mi)	EXIST LANES	TYPE	PM PEAK HOUR	% IN SERVICE AREA	VEH-MI CAPACITY PK-HR	VEH-MI SUPPLY PK-HR	VEH-MI DEMAND PK-HR	EXCESS CAPACITY PK-HR	EXISTING DEFICIENCIES PK-HR
			(11)	` ,	NB/EB SB/WB		VOL NB/EB SB/WB		PER LN	TOTAL	TOTAL	VEH-MI	VEH-MI NB/EB SB/WB
		No Thoroughfare Roa	adways w	thin City L	L		<u>, , , , , , , , , , , , , , , , , , , </u>	ı	1 1 1				
SUBTOTAL			0	0.00						0 0	0 0	0 0	0 0
•										0	0	0	0

Service Area G

									M	% IN	VEI	I-MI	VEH		VEI		_	ESS	EXIST	
ROADWAY	FROM	то	LENGTH	LENGTH	EX	IST	TYPE	PE	AK	SERVICE	CAPA	CITY	SUP	PLY	DEM	AND	CAP	ACITY	DEFICIE	ENCIE
			(ft)	(mi)	LA	NES		HO	UR	AREA	PK-	-HR	PK-	-HR	PK-	HR	PK	-HR	PK-	·HR
								V	)L		PEF	RLN	TO	ΓAL	TO.	ΓAL	VEI	H-MI	VEH	I-MI
					NB/EB	SB/WB		NB/EB	SB/WB		NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WE
ELDORADO PKWY	ALMA DR	RIDGE RD	5325	1.01	2	2	4D	1092	1092	100%	700	700	1,412	1,412	1,102	1,102	310	310	i I	i
ELDORADO PKWY	STONEBRIDGE DR	ALMA DR	2035	0.39	2	2	4D	1119	1072	100%	700	700	540	540	431	413	108	126	1	1
ELDORADO PKWY	CUSTER RD	STONEBRIDGE DR	3,471	0.66	2	2	4D	865	813	100%	700	700	920	920	568	535	352	386	1	L
STONEBRIDGE DR	ALMA DR	ELDORADO PKWY	1,607	0.30	2	2	4D	572	619	100%	700	700	426	426	174	189	252	238	1	1
ALMA DR	STONEBRIDGE DR	ELDORADO PKWY	2,285	0.43	2	2	4D	277	277	100%	700	700	606	606	120	120	486	486	1	1
COIT RD	WESTRIDGE BLVD	2,595' S OF WESTRIDGE BLVD	2,595	0.49	2	2	4D	551	576	50%	700	700	344	344	135	142	209	202	i i	i
WESTRIDGE BLVD	1,635' E OF COIT RD	INDEPENDENCE PKWY	3,710	0.70	2	2	4D	357	293	100%	700	700	984	984	251	206	733	778	i i	i
INDEPENDENCE PKWY	WESTRIDGE BLVD	2,690' S OF WESTRIDGE BLVD	2,689	0.51	2	2	4D	537	567	100%	700	700	713	713	274	289	440	424	1	1
WESTRIDGE BLVD	INDEPENDENCE PKWY	2,720' E OF INDEPENDENCE PKWY	2,722	0.52	2	2	4D	298	319	100%	700	700	722	722	154	165	568	557	i i	i
CUSTER RD	WESTRIDGE BLVD	ELDORADO PKWY	5,381	1.02	3	3	6D	1583	1708	50%	780	780	1,192	1,192	807	870	386	322	i l	i
RIDGE RD	GLEN OAKS DR	ELDORADO PKWY	5,719	1.08	2	2	4D	641	641	100%	700	700	1,516	1,516	695	695	822	822	i l	i
STONEBRIDGE DR	GLEN OAKS DR	ALMA DR	5,966	1.13	2	2	4D	687	709	100%	700	700	1,582	1,582	776	801	806	781	i l	i
GLEN OAKS DR	STONEBRIDGE DR	RIDGE RD	4,733	0.90	2	2	4D	366	366	100%	700	700	1,255	1,255	328	328	927	927	i I	i
RIDGE RD	VIRGINIA PKWY	GLEN OAKS DR	3,912	0.74	2	2	4D	592	592	100%	700	700	1,037	1,037	438	438	599	599	i l	i
STONEBRIDGE DR	VIRGINIA PKWY	GLEN OAKS DR	2,716	0.51	2	2	4D	749	753	100%	700	700	720	720	385	387	335	333	i l	i
VIRGINIA PKWY	STONEBRIDGE DR	RIDGE RD	3,422	0.65	3	3	6D	1402	1402	100%	780	780	1,517	1,517	909	909	608	608	i l	ī
INDEPENDENCE PKWY	VIRGINIA PKWY	WESTRIDGE BLVD	5,349	1.01	2	2	4D	394	370	100%	700	700	1,418	1,418	399	375	1,019	1,044	i l	ī
COIT RD	VIRGINIA PKWY	2,610' S OF VIRGINIA PKWY	2,608	0.49	2	2	4D	456	477	50%	700	700	346	346	113	118	233	228	i l	i
VIRGINIA PKWY	COIT RD	500' W OF INDEPENDENCE PKWY	4,737	0.90	2	2	4D	598	599	100%	700	700	1,256	1,256	537	537	719	719	i l	ī
CUSTER RD	VIRGINIA PKWY	WESTRIDGE BLVD	5,277	1.00	3	3	6D	1396	1424	100%	780	780	2,339	2,339	1,395	1,423	943	915	i l	ī
VIRGINIA PKWY	935' W OF VIRGINIA HILLS DR	CUSTER RD	2,684	0.51	2	2	4D	803	818	100%	700	700	712	712	408	416	304	296	i l	ī
VIRGINIA PKWY	VIRGINIA PARKLANDS BLVD	STONEBRIDGE DR	3,226	0.61	3	3	6D	929	1011	100%	780	780	1,430	1,430	568	618	862	812	i l	ī
COIT RD	US HIGHWAY 380	VIRGINIA PKWY	5,467	1.04	2	2	4D	456	477	50%	700	700	725	725	236	247	489	478	i l	ī
US HIGHWAY 380	COIT RD	3,730' E OF COIT RD	3,729	0.71	3	3	6D	1819	1761	50%	780	780	826	826	642	622	184	204	i l	ī
INDEPENDENCE PKWY	2,380' S OF US HIGHWAY 380	4,465' S OF US HIGHWAY 380	2,085	0.39	2	2	4D	113	117	100%	700	700	553	553	45	46	508	507	i l	ī
US HIGHWAY 380	2,705' W OF CUSTER RD	CUSTER RD	2,706	0.51	3	3	6D	1832	1771	50%	780	780	600	600	469	454	130	146	i l	ī
CUSTER RD	US HIGHWAY 380	VIRGINIA PKWY	5,445	1.03	3	3	6D	1243	1319	100%	780	780	2,413	2,413	1,282	1,360	1,131	1,053		
RIDGE RD	US HIGHWAY 380	CREEKSIDE DR	6,874	1.30	2	2	4D	281	281	50%	700	700	911	911	183	183	729	729	i l	ī
US HIGHWAY 380	CUSTER RD	STONEBRIDGE DR	3,371	0.64	3	3	6D	1679	1731	100%	780	780	1,494	1,494	1,072	1,105	422	389	i l	i
STONEBRIDGE DR	US HIGHWAY 380	VIRGINIA PKWY	10,791	2.04	2	2	4D	296	282	100%	700	700	2,861	2,861	605	576	2,256	2,285		
US HIGHWAY 380	STONEBRIDGE DR	RIDGE RD	7,516	1.42	3	3	6D	1913	1913	100%	780	780	3,331	3,331	2,724	2,724	608	608		
RIDGE RD	CREEKSIDE DR	VIRGINIA PKWY	1,013	0.19	2	2	4D	281	281	100%	700	700	269	269	54	54	215	215	i i	1
VIRGINIA PKWY	500' W OF INDEPENDENCE PKWY	INDEPENDENCE PKWY	511	0.10	2	2	4D	598	599	50%	700	700	68	68	29	29	39	39		
VIRGINIA PKWY	INDEPENDENCE PKWY	325' E OF FORKHORN DR	1,227	0.23	2	2	4D	907	848	50%	700	700	163	163	105	99	57	64		
VIRGINIA PKWY	325' E OF FORKHORN DR	935' W OF VIRGINIA HILLS DR	1,467	0.28	2	2	4D	907	848	50%	700	700	195	195	126	118	68	77	i İ	i
VIRGINIA PKWY	CUSTER RD	410' E OF DANBURY RD	2,592	0.49	2	2	4D	867	840	100%	700	700	687	687	425	412	262	275	i İ	i
VIRGINIA PKWY	410' E OF DANBURY RD	VIRGINIA PARKLANDS BLVD	2,049	0.39	3	2	5D	867	840	100%	700	700	815	543	336	326	479	217		<del></del>
WESTRIDGE BLVD	COIT RD	1,635' E OF COIT RD	1,637	0.31	2	2	4D	322	289	50%	700	700	217	217	50	45	167	172	1	
WESTRIDGE BLVD	2,720' E OF INDEPENDENCE PKW	CUSTER RD	2,617	0.50	1	1	2U	374	385	50%	475	475	118	118	93	95	25	22	i İ	i
SUBTOTAL			143,268	27.13							İ		39.231	38.960	19.444	19.567	19,787	19,393	0	0
	-		,			1					1		78,	,	39.	- ,	.,.	180	ہنے	

Service Area H

								P	PM	% IN	VEH	I-MI	VEI	н-мі	VEI	I-MI	EXC	ESS	EXIS	STING
ROADWAY	FROM	то	LENGTH	LENGTH	EX	IST	TYPE	PE	AK	SERVICE	CAPA	CITY	SUF	PPLY	DEM	AND	CAP	ACITY	DEFICIE	ENCIE
	1.1.5		(ft)	(mi)		NES			DUR	AREA	PK-			-HR		HR.		-HR		-HR
			(,	()					OL	7		LN		TAL	TO			H-MI		H-MI
					NB/EB	SB/WB		NB/EB	SB/WB		NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/W
CUSTER RD	ROLATOR RD	STATE HIGHWAY 121	4,547	0.86	3	3	6D	2150	2406	50%	780	780	1,007	1,007	926	1,036	82	-28		28
COLLIN MCKINNEY PKWY	CUSTER RD	COLLIN MCKINNEY PKWY	3,807	0.72	2	2	4D	251	251	100%	700	700	1,009	1,009	181	181	828	828		
COLLIN MCKINNEY PKWY	WEISKOPF AVE	ALMA RD	4,167	0.79	2	1	3U	221	30	100%	525	525	829	414	174	24	654	391		
ALMA DR	COLLIN MCKINNEY PKWY	STATE HIGHWAY 121	3,861	0.73	3	3	6D	766	807	100%	780	780	1,711	1,711	560	590	1,151	1,121		
COLLIN MCKINNEY PKWY	WEISKOPF AVE	ALMA RD	3,873	0.73	1	2	3U	16	114	100%	525	525	385	770	12	84	374	687		
COLLIN MCKINNEY PKWY	ALMA RD	STACY RD	4,647	0.88	2	2	4D	102	102	100%	700	700	1,232	1,232	90	90	1,142	1,142		
COLLIN MCKINNEY PKWY	ALMA RD	STACY RD	4,647	0.88	2	2	4D	134	134	100%	700	700	1,232	1,232	118	118	1,114	1,114		
STACY RD	COLLIN MCKINNEY PKWY	STATE HIGHWAY 121	2,198	0.42	3	3	6D	1110	1507	50%	780	780	487	487	231	314	256	173		1
STACY RD	RIDGE RD	COLLIN MCKINNEY PKWY	2,152	0.41	3	3	6D	1124	1555	50%	780	780	477	477	229	317	248	160		
STACY RD	MCKINNEY RANCH PKWY	RIDGE RD	1,343	0.25	2	2	4D	874	884	100%	700	700	356	356	222	225	134	131		1
CUSTER RD	STACY RD	ROLATOR RD	5,319	1.01	3	3	6D	1960	2036	50%	780	780	1,179	1,179	987	1,025	191	153		1
CUSTER RD	STACY RD	ROLATOR RD	5,319	1.01	3	3	6D	2260	2107	50%	780	780	1,179	1,179	1,138	1,061	40	117		1
ALMA DR	STACY RD	COLLIN MCKINNEY PKWY	3,608	0.68	3	3	6D	712	712	100%	780	780	1,599	1,599	487	487	1,112	1,112		
STACY RD	CUSTER RD	ALMA DR	5,334	1.01	2	2	4D	1045	1020	100%	700	700	1,414	1,414	1,056	1,031	358	384		1
STACY RD	ALMA DR	MCKINNEY RANCH PKWY	4,039	0.77	2	2	4D	920	938	100%	700	700	1,071	1,071	704	717	367	354		
MCKINNEY RANCH PKWY	STACY RD	SILVERADO TRL	2,392	0.45	2	2	4D	343	311	100%	700	700	634	634	155	141	479	494		
CUSTER RD	SILVERADO TRL	STACY RD	2,635	0.50	3	3	6D	2214	2268	50%	780	780	584	584	553	566	31	18		
SILVERADO TRL	BURNETT DR	ALMA DR	3,378	0.64	2	2	4D	209	209	100%	700	700	896	896	134	134	762	762		
ALMA DR	SILVERADO TRL	STACY RD	2,623	0.50	2	2	4D	821	821	100%	700	700	696	696	408	408	288	288		
SILVERADO TRL	ALFALFA DR	145' W OF IRONSTONE LN	1,493	0.28	2	2	4D	211	213	100%	700	700	396	396	60	60	336	336		
MCKINNEY RANCH PKWY	SILVERADO TRL	RIDGE RD	1,684	0.32	2	2	4D	243	243	100%	700	700	446	446	77	77	369	369		
RIDGE RD	MCKINNEY RANCH PKWY	STACY RD	3,647	0.69	2	2	4D	704	704	100%	700	700	967	967	486	486	481	481		
CUSTER RD	STONEBRIDGE DR	SILVERADO TRL	3,351	0.63	3	3	6D	2115	2196	50%	780	780	743	743	671	697	72	46		
CUSTER RD	ELDORADO PKWY	STONEBRIDGE DR	2,042	0.39	3	3	6D	1672	1744	50%	780	780	452	452	323	337	129	115		
ALMA DR	ELDORADO PKWY	805' S OF BEAVER CREEK DR	3,465	0.66	2	2	4D	698	698	100%	700	700	919	919	458	458	461	461		
RIDGE RD	ELDORADO PKWY	MCKINNEY RANCH PKWY	5,706	1.08	2	2	4D	796	796	50%	700	700	756	756	430	430	326	326		
ELDORADO PKWY	ALMA DR	RIDGE RD	5,325	1.01	2	2	4D	1092	1092	100%	700	700	1,412	1,412	1,102	1,102	310	310		
STONEBRIDGE DR	ELDORADO PKWY	CUSTER RD	4,478	0.85	2	2	4D	548	522	100%	700	700	1,187	1,187	465	443	722	745		
ELDORADO PKWY	STONEBRIDGE DR	ALMA DR	2,035	0.39	2	2	4D	1119	1072	100%	700	700	540	540	431	413	108	126		
ELDORADO PKWY	CUSTER RD	STONEBRIDGE DR	3,471	0.66	2	2	4D	865	813	100%	700	700	920	920	568	535	352	386		
ALMA DR	805' S OF BEAVER CREEK DR	SILVERADO TRL	1,958	0.37	2	2	4D	698	698	100%	700	700	519	519	259	259	260	260		
COLLIN MCKINNEY PKWY	COLLIN MCKINNEY PKWY	WEISKOPF AVE	908	0.17	0	2	2UO	251	0	100%	475	475	0	163	43	0	-43	163	43	
COLLIN MCKINNEY PKWY	COLLIN MCKINNEY PKWY	WEISKOPF AVE	867	0.16	2	0	2UO	0	251	100%	475	475	156	0	0	41	156	-41		41
SILVERADO TRL	CUSTER RD	BURNETT DR	1,930	0.37	1	1	2U	251	146	100%	475	475	174	174	92	53	82	120		
SILVERADO TRL	145' W OF IRONSTONE LN	MCKINNEY RANCH PKWY	2,553	0.48	2	2	4D	211	213	100%	700	700	677	677	102	103	575	574		
SILVERADO TRL	ALMA DR	ALFALFA DR	1,168	0.22	2	2	4D	211	213	100%	700	700	310	310	47	47	263	263		
SUBTOTAL			115,971	21.96									28,552	28,530	13,979	14,089	14,573	14,441	43	70
													57.	,081	28,	068	29	014	1′	13

Service Area I

									M	% IN	VEH			H-MI		I-MI		CESS	_	STING
ROADWAY	FROM	то	LENGTH	LENGTH		IST	TYPE		AK	SERVICE	CAPA			PLY		IAND	_		DEFICI	
			(ft)	(mi)	LA	NES			UR	AREA	PK-			-HR		-HR		-HR		(-HR
									OL			LN		TAL	TO.			H-MI		H-MI
					NB/EB	SB/WB		NB/EB	SB/WB		NB/EB			SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/W
STACY RD	COLLIN MCKINNEY PKWY	STATE HIGHWAY 121	2,198	0.42	3	3	6D	1110	1507	50%	780	780	487	487	231	314	256	173		
STACY RD	RIDGE RD	COLLIN MCKINNEY PKWY	2,152	0.41	3	3	6D	1124	1555	50%	780	780	477	477	229	317	248	160		
COLLIN MCKINNEY PKWY	STACY RD	VILLAGE PARK	2,900	0.55	2	2	4D	136	136	100%	700	700	769	769	75	75	694	694		
LAKE FOREST DR	COLLIN MCKINNEY PKWY	STATE HIGHWAY 121	2,145	0.41	3	3	6D	1460	1460	100%	780	780	950	950	593	593	357	357		
COLLIN MCKINNEY PKWY	COTTONWOOD CREEK	1110' E OF TINA DR	2,929	0.55	1	1	2U	100	100	100%	475	475	264	264	55	55	208	208		
HARDIN BLVD	COLLIN MCKINNEY PKWY	STATE HIGHWAY 121	1,162	0.22	3	3	6D	961	961	100%	780	780	515	515	212	212	304	304		
RIDGE RD	MCKINNEY RANCH PKWY	STACY RD	3,647	0.69	2	2	4D	704	704	100%	700	700	967	967	486	486	481	481		
MCKINNEY RANCH PKWY	RIDGE RD	LAKE FOREST DR	4,204	0.80	2	2	4D	452	452	100%	700	700	1,115	1,115	360	360	755	755		
LAKE FOREST DR	MCKINNEY RANCH PKWY	COLLIN MCKINNEY PKWY	3,220	0.61	3	3	6D	1318	1318	100%	780	780	1,427	1,427	804	804	623	623		
MCKINNEY RANCH PKWY	LAKE FOREST DR	HARDIN BLVD	5,310	1.01	2	2	4D	335	335	100%	700	700	1,408	1,408	337	337	1,071	1,071		
HARDIN BLVD	MCKINNEY RANCH PKWY	COLLIN MCKINNEY PKWY	1,863	0.35	3	3	6D	961	961	100%	780	780	826	826	339	339	487	487		
HARDIN BLVD	ELDORADO PKWY	MCKINNEY RANCH PKWY	3,255	0.62	2	2	4D	948	948	100%	700	700	863	863	584	584	279	279		
LAKE FOREST DR	ELDORADO PKWY	MCKINNEY RANCH PKWY	5,751	1.09	2	2	4D	1040	1040	100%	700	700	1,525	1,525	1,133	1,133	392	392		
ELDORADO PKWY	LAKE FOREST DR	HARDIN BLVD	6,709	1.27	2	2	4D	1400	1400	100%	700	700	1,779	1,779	1,779	1,779	0	0	0	0
RIDGE RD	ELDORADO PKWY	MCKINNEY RANCH PKWY	5,706	1.08	2	2	4D	796	796	50%	700	700	756	756	430	430	326	326		
ELDORADO PKWY	850' E OF RIDGE RD	LAKE FOREST DR	3,350	0.63	2	2	4D	1273	1273	100%	700	700	888	888	808	808	80	80		
LAKE FOREST DR	GLEN OAKS DR	ELDORADO PKWY	5,760	1.09	2	2	4D	1010	1010	100%	700	700	1,527	1,527	1,102	1,102	425	425		
RIDGE RD	GLEN OAKS DR	ELDORADO PKWY	5,719	1.08	2	2	4D	641	641	100%	700	700	1,516	1,516	695	695	822	822		
GLEN OAKS DR	RIDGE RD	LAKE FOREST DR	2,445	0.46	2	2	4D	390	390	100%	700	700	648	648	181	181	467	467		
HARDIN BLVD	VIRGINIA PKWY	ELDORADO PKWY	10,688	2.02	2	2	4D	997	997	100%	700	700	2,834	2,834	2,017	2,017	817	817		
LAKE FOREST DR	VIRGINIA PKWY	GLEN OAKS DR	4,475	0.85	2	2	4D	930	930	100%	700	700	1,187	1,187	788	788	399	399		
VIRGINIA PKWY	LAKE FOREST DR	1355' W OF HARDIN BLVD	3,138	0.59	3	3	6D	1316	1316	100%	780	780	1,391	1,391	782	782	608	608		
RIDGE RD	VIRGINIA PKWY	GLEN OAKS DR	3,912	0.74	2	2	4D	592	592	100%	700	700	1,037	1,037	438	438	599	599		
VIRGINIA PKWY	1035' E OF RIDGE RD	LAKE FOREST DR	4,427	0.84	3	3	6D	1401	1401	100%	780	780	1,962	1,962	1,175	1,175	787	787		
VIRGINIA PKWY	1035' E OF RIDGE RD	LAKE FOREST DR	4,427	0.84	3	3	6D	1248	1248	100%	780	780	1,962	1,962	1,046	1,046	916	916		
HARDIN BLVD	WHITE AVE	VIRGINIA PKWY	5,297	1.00	2	2	4D	701	701	50%	700	700	702	702	352	352	351	351		
HARDIN BLVD	US HIGHWAY 380	WHITE AVE	3,041	0.58	2	2	4D	536	536	50%	700	700	403	403	154	154	249	249		
RIDGE RD	US HIGHWAY 380	CREEKSIDE DR	6,874	1.30	2	2	4D	281	281	50%	700	700	911	911	183	183	729	729		
LAKE FOREST DR	US HIGHWAY 380	VIRGINIA PKWY	7,574	1.43	2	2	4D	799	799	100%	700	700	2,008	2,008	1,146	1,146	862	862		
US HIGHWAY 380	LAKE FOREST DR	HARDIN BLVD	5,496	1.04	3	3	6D	2583	2583	100%	780	780	2,436	2,436	2,689	2,689	-253	-253	253	253
US HIGHWAY 380	RIDGE RD	LAKE FOREST DR	5,517	1.04	3	3	6D	2025	2025	100%	780	780	2,445	2,445	2,116	2,116	329	329		
RIDGE RD	CREEKSIDE DR	VIRGINIA PKWY	1,013	0.19	2	2	4D	281	281	100%	700	700	269	269	54	54	215	215		
COLLIN MCKINNEY PKWY	VILLAGE PARK	LAKE FOREST DR	1,729	0.33	2	2	4D	156	156	100%	700	700	459	459	51	51	407	407		
ELDORADO PKWY	RIDGE RD	850' E OF RIDGE RD	849	0.16	2	2	4D	1163	1163	100%	700	700	225	225	187	187	38	38		1
VIRGINIA PKWY	RIDGE RD	1035' E OF RIDGE RD	1,042	0.20	3	3	6D	1248	1248	100%	780	780	462	462	246	246	215	215		
VIRGINIA PKWY	1355' W OF HARDIN BLVD	HARDIN BLVD	1,378	0.26	3	3	6D	1370	1370	100%	780	780	611	611	357	357	253	253		
SUBTOTAL			141,304	26.76									40,011	40,011	24,215	24,386	15,796	15,625	254	25
	•	•			•	•	-	•	•		•		80	022	48.	601	31	421	5	07

Service Area J

ROADWAY	FROM	то	LENGTH (ft)	LENGTH (mi)		IST NES	TYPE	PE HC	M AK OUR OL	% IN SERVICE AREA	CAPA PK		SUP PK	H-MI PPLY -HR TAL	VEI DEM PK	AND -HR	CAP	ESS ACITY -HR H-MI	DEFICI	-HR
					NB/EB	SB/WB			SB/WB				NB/EB							
HARDIN BLVD	COLLIN MCKINNEY PKWY	STATE HIGHWAY 121	1,162	0.22	3	3	6D	961	961	100%	780	780	515	515	212	212	304	304		
COLLIN MCKINNEY PKWY	HARDIN BLVD	985' E OF HARDIN BLVD	983	0.19	2	2	4D	100	100	100%	700	700	261	261	19	19	242	242		
HARDIN BLVD	MCKINNEY RANCH PKWY	COLLIN MCKINNEY PKWY	1,863	0.35	3	3	6D	961	961	100%	780	780	826	826	339	339	487	487		
MCKINNEY RANCH PKWY	515' E OF HARDIN BLVD	COLLIN MCKINNEY PKWY	2,595	0.49	2	2	4D	275	226	100%	700	700	688	688	135	111	553	577		
MCKINNEY RANCH PKWY	COLLIN MCKINNEY PKWY	STATE HIGHWAY 121	2,197	0.42	2	2	4D	60	124	100%	700	700	583	583	25	51	558	531		
MEDICAL CENTER DR	STATE HIGHWAY 121	1,685' S OF STATE HIGHWAY 121	1,684	0.32	1	1	3U	380	380	100%	525	525	167	167	121	121	46	46		
COLLIN MCKINNEY PKWY	720' W OF TEST DR	CRAIG DR	2,252	0.43	2	2	4U	174	174	100%	525	525	448	448	74	74	374	374		
HARDIN BLVD	ELDORADO PKWY	MCKINNEY RANCH PKWY	3,255	0.62	2	2	4D	948	948	100%	700	700	863	863	584	584	279	279		
STATE HIGHWAY 5	STATE HIGHWAY 121	4,520' S OF STATE HIGHWAY 121	4,519	0.86	1	1	2U	640	640	100%	475	475	407	407	548	548	-142	-142	142	142
ELDORADO PKWY	HARDIN BLVD	495' W OF US HIGHWAY 75	7,277	1.38	2	2	4D	1194	1194	100%	700	700	1,930	1,930	1,646	1,646	283	283		
ELDORADO PKWY	US HIGHWAY 75	710' E OF US HIGHWAY 75	711	0.13	3	3	6D	976	976	100%	780	780	315	315	131	131	184	184		
MEDICAL CENTER DR	ELDORADO PKWY	STATE HIGHWAY 121	4,022	0.76	2	2	4D	361	361	100%	700	700	1,066	1,066	275	275	792	792		
STATE HIGHWAY 5	HARRY MCKILLOP BLVD / FM 546	STATE HIGHWAY 121	3,109	0.59	2	2	4D	2071	2071	100%	700	700	824	824	1,219	1,219	-395	-395	395	395
ELDORADO PKWY	MEDICAL CENTER DR	370' E OF BARRANCA WAY	4.308	0.82	2	2	4D	826	826	100%	700	700	1.142	1.142	674	674	469	469		
HARDIN BLVD	VIRGINIA PKWY	ELDORADO PKWY	10.688	2.02	2	2	4D	997	997	100%	700	700	2,834	2,834	2.017	2,017	817	817		
LOUISIANA ST	WILSON CREEK PKWY	VIRGINIA STREET	557	0.11	2	2	4D	0	802	100%	700	700	148	148	0	85	148	63		
LOUISIANA ST	US HIGHWAY 75	WILSON CREEK PKWY	1.228	0.23	2	3	5D	977	1018	100%	700	700	326	488	227	237	98	252		
VIRGINIA PKWY	HARDIN BLVD	US HIGHWAY 75	8.472	1.60	3	3	6D	1082	1082	100%	780	780	3.755	3.755	1.735	1.735	2.019	2.019		
HARDIN BLVD	WHITE AVE	VIRGINIA PKWY	5.297	1.00	2	2	4D	701	701	50%	700	700	702	702	352	352	351	351		
WHITE AVE	BOIS D'ARC RD	COMMUNITY AVE	4.929	0.93	2	2	4D	357	357	100%	700	700	1.307	1.307	333	333	974	974		
WHITE AVE	COMMUNITY AVE	US HIGHWAY 75	2.562	0.49	2	2	4D	398	398	100%	700	700	679	679	193	193	486	486		
WHITE AVE	US HIGHWAY 75	REDBUD BLVD	1,061	0.20	1	1	2U	279	316	100%	475	475	95	95	56	63	39	32		ļ —
COMMUNITY AVE	US HIGHWAY 380	2,055' S OF US HIGHWAY 380	2,055	0.39	2	2	4U	344	344	100%	525	525	409	409	134	134	275	275		
US HIGHWAY 380	COMMUNITY AVE	US HIGHWAY 75	2,357	0.45	3	3	6D	2441	2441	100%	780	780	1,044	1,044	1,090	1,090	-45	-45	45	45
HARDIN BLVD	US HIGHWAY 380	WHITE AVE	3,041	0.58	2	2	4D	536	536	50%	700	700	403	403	154	154	249	249		
US HIGHWAY 380	HARDIN BLVD	COMMUNITY AVE	5,281	1.00	3	3	6D	2169	2169	100%	780	780	2,340	2,340	2,170	2,170	171	171		l
COMMUNITY AVE	2,055' S OF US HIGHWAY 380	WHITE AVE	1,165	0.22	2	2	4U	453	453	100%	525	525	232	232	100	100	132	132		
US HIGHWAY 380	REDBUD BLVD	GRAVES ST	854	0.16	3	3	6D	1911	1911	100%	780	780	378	378	309	309	69	69		
WHITE AVE	HARDIN BLVD	BOIS D'ARC RD	904	0.17	2	2	4D	312	312	100%	700	700	240	240	53	53	186	186		<b> </b>
WHITE AVE	REDBUD BLVD	GRAVES ST	1,865	0.35	1	1	2U	263	258	100%	475	475	168	168	93	91	75	77		
VIRGINIA STREET	LOUISIANA ST	GRAVES ST	989	0.19	0	2	2UO	0	802	100%	475	475	0	178	0	150	0	28		
LOUISIANA ST	VIRGINIA STREET	GRAVES ST	1,050	0.20	2	0	2UO	631	0	100%	475	475	189	0	126	0	63	0		
ELDORADO PKWY	710' E OF US HIGHWAY 75	MEDICAL CENTER DR	559	0.11	2	2	4D	976	976	100%	700	700	148	148	103	103	45	45		
ELDORADO PKWY	495' W OF US HIGHWAY 75	US HIGHWAY 75	494	0.09	3	3	6D	979	979	100%	780	780	219	219	92	92	127	127		
ELDORADO PKWY	370' E OF BARRANCA WAY	1,180' E OF BARRANCA WAY	812	0.15	2	2	4D	656	656	100%	700	700	215	215	101	101	114	114		
MCKINNEY RANCH PKWY	HARDIN BLVD	515' E OF HARDIN BLVD	512	0.10	2	2	4D	275	226	100%	700	700	136	136	27	22	109	114		
COLLIN MCKINNEY PKWY	985' E OF HARDIN BLVD	2,100' E OF HARDIN BLVD	1,118	0.21	1	1	3U	100	100	100%	525	525	111	111	21	21	90	90		
COLLIN MCKINNEY PKWY	MCKINNEY RANCH PKWY	720' W OF TEST DR	1,943	0.37	2	2	4U	86	86	100%	525	525	386	386	32	32	355	355		
SUBTOTAL			99,731	18.89	_	<u> </u>					020	020	26.500	26,652	15.520	15.643	10.979	11,009	582	582
	1	ı	00,.01							·	1			151	31.			988	1,1	

Service Area K

10/7/202	

ROADWAY	FROM	то	LENGTH (ft)	LENGTH (mi)	LAI	IST NES	TYPE	PE HC V	PM EAK OUR OL	% IN SERVICE AREA		ACITY -HR R LN	SUF PK- TO	TAL	DEM PK TO	I-MI IAND -HR TAL	CAPA PK VEI	CESS ACITY I-HR H-MI	DEFICI PK- VEH	STING IENCIES K-HR IH-MI
AUDDOOT DO	ATTACK OF THE PROPERTY OF PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY	LUADOVANO (CLASSICO CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR CO	468	0.09	NB/EB	SB/WB			SB/WB	50%			NB/EB	SB/WB	NB/EB	SB/WB		SB/WB	NB/EB	SB/WB
AIRPORT DR STATE HIGHWAY 5	470' N OF HARRY MCKILLOP BLVD / FM 546	HARRY MCKILLOP BLVD / FM 546	4,519	0.09	1	1	2U 2U	22	22	100%	475 475	475 475	407	407	548	548	-142	-142		1.10
STATE HIGHWAY 5	STATE HIGHWAY 121 HARRY MCKILLOP BLVD / FM 546	4,520' S OF STATE HIGHWAY 121 STATE HIGHWAY 121	3,109	0.59	2	1	4D	640	640	100%	700	700	824	824	1,219	1,219	-395	-395	142	142
HARRY MCKILLOP BLVD / FM 5		AIRPORT DR	7.696	1.46	2	2	4D	2,071	2,071	100%	700	700	2.041	2.041	285	285	1.756	1,756	395	395
AIRPORT DR	INDUSTRIAL BLVD	FM 546	2,266	0.43	2	2	4D	195 191	195 191	50%	700	700	300	300	41	41	260	260		
STATE HIGHWAY 5	INDUSTRIAL BLVD	HARRY MCKILLOP BLVD / FM 546	1,456	0.43	2	2	4D	2,070	2,070	100%	700	700	386	386	571	571	-185	-185	405	405
	STATE HIGHWAY 5	AIRPORT DR	6,296	1.19	2	2	4D	912	912	100%	700	700	1,669	1,669	1,088	1,088	581	581	185	185
INDUSTRIAL BLVD	TENNESSEE ST	INDUSTRIAL BLVD	537	0.10	2	2	4D	1,505	1,505	100%	700	700	142	142	153	153	-11		- 44	- 44
STATE HIGHWAY 5	WILSON CREEK PKWY	385' N OF INDUSTRIAL BLVD	2,105	0.10	2	2	4D	843	843	50%	700	700	279	279	168	168	111	-11 111	11	11
	WILSON CREEK PKWY	TENNESSEE ST	2,105	0.40	2	2	5U	1,253	1,253	100%	625	625	487	487	488	488	-1	-1		1
STATE HIGHWAY 5 ELM ST	ROCKWALL ST	AIRPORT DR	3.314	0.63	0	0	4U	227	269	100%	525	525	0	0	143	169	-143	-169	143	169
	WILSON CREEK PKWY	STATE HIGHWAY 5	1,635	0.83	1	1	2U	152	165	100%	475	475	147	147	47	51	100	96	143	169
TENNESSEE ST FLM ST	TENNESSEE ST	525' TENNESSEE ST	527	0.31	2	2	4U	145	185	100%	525	525	105	105	14	18	90	86		+
GREENVILLE RD	LOUISIANA ST	AIRPORT DR	1.451	0.10	1	1	2U	165	155	100%	475	475	131	131	45	43	85	88		
AIRPORT DR	LOUISIANA ST	WILSON CREEK PKWY	4,197	0.27	2	2	4D	923	923	50%	700	700	556	556	367	367	189	189		-
GREENVILLE RD	THROCKMORTON ST	LOUISIANA ST	1,996	0.79	- 4	1	2U	165	155	100%	475	475	180	180		59	117	121		+
GREENVILLE RD	LOUISIANA ST			0.36	1			165	155				34	34	62					-
		THROCKMORTON ST	373		1	1	2U 2U			100%	475 475	475			12	11	22	23	<u> </u>	+
TENNESSEE ST LOUISIANA ST	DAVIS ST TENNESSEE ST	WILSON CREEK PKWY STATE HIGHWAY 5	3,874 791	0.73 0.15	2	0	200	172 279	125	100% 100%	475	475 475	349 142	349 0	126 42	91	223 101	257	₩	+-
					_	-												-		
STATE HIGHWAY 5	LOUISIANA ST	WILSON CREEK PKWY	4,415	0.84	2	2	5U	1,317	1,317	100%	625	625	1,045	1,045	1,102	1,102	-56	-56	56	56
LOUISIANA ST LOUISIANA ST	STATE HIGHWAY 5 GREENVILLE RD	GREENVILLE RD THROCKMORTON ST	830 389	0.16	1	1	2U	165 100	155 100	100%	475 475	475 475	75	75	26 7	24	49	50		
					1	1	2U			100%			35	35		7	28	28		
THROCKMORTON ST	LOUISIANA ST	GREENVILLE RD	249	0.05	1	1	2U	118	118	100%	475	475	22	22	6	6	17	17		
LOUISIANA ST	THROCKMORTON ST	GREENVILLE RD	2,259	0.43	1	1	2U	100	100	100%	475	475	203	203	43	43	160	160		
LOUISIANA ST	GRAVES ST	TENNESSEE ST	4,525	0.86	2	0	200	479	0	100%	475	475	814	0	410	0	404	0		
TENNESSEE ST	VIRGINIA STREET	LOUISIANA ST	249	0.05	2	0	2UO	283	0	100%	475	475	45	0	13	0	31	0		
VIRGINIA STREET	GRAVES ST	TENNESSEE ST	4,512	0.85	0	2	2UO 4D	0	599 344	100%	475 700	475	0	812	0	512	0	300		↓
WILSON CREEK PKWY	1,445' S OF LOUISIANA ST	TENNESSEE ST	9,000	1.70	2	2		273		100%		700	2,386	2,386	465	587	1,921	1,799		—
LOUISIANA ST	WILSON CREEK PKWY	VIRGINIA STREET	557	0.11	2	2	4D	0	802	100%	700	700	148	148	0	85	148	63		—
VIRGINIA STREET STATE HIGHWAY 5	TENNESSEE ST	STATE HIGHWAY 5	841 260	0.16	0	2	2UO 5U	0	250 1,337	100%	475	475 625	0	151	0	40	0	111		<del></del>
LOUISIANA ST	VIRGINIA STREET US HIGHWAY 75	LOUISIANA ST WILSON CREEK PKWY		0.05	2	2	5D	1,337		100%	625 700	700	61	61	66	66	-4 98	-4	4	4
			1,228	0.23	2	-		977	1,018	100%			326	488	227	237		252		
VIRGINIA STREET	STATE HIGHWAY 5	THROCKMORTON ST	1,108	0.21	1	1	2U	79	112	100%	475	475	100	100	17	24	83	76		—
THROCKMORTON ST	VIRGINIA STREET	LOUISIANA ST	267	0.05	1	1	2U	118	118	100%	475	475	24	24	6	6	18	18		
VIRGINIA STREET	THROCKMORTON ST	225' W OF AIRPORT DR GREENVILLE RD	2,661	0.50		2	2U 4D	79	112	100%	475	475	239 276	239 276	40	57	199	183		
AIRPORT DR	VIRGINIA STREET		1,042	0.20	2			920	920	100%	700	700			182	182	95	95		
AIRPORT DR	355' S OF US HIGHWAY 380	VIRGINIA STREET	1,863	0.35	2	2	4D	920	920	50%	700	700	247	247	162	162	85	85		
THROCKMORTON ST	US HIGHWAY 380	VIRGINIA STREET	3,783	0.72	1	1	2U	118	118	100%	475	475	340	340	84	84	256	256		
US HIGHWAY 380	THROCKMORTON ST	AIRPORT DR	2,452	0.46	3	3	6D	1,515	1,515	100%	780	780	1,087	1,087	703	703	383	383		—
TENNESSEE ST WHITE AVE	WHITE AVE GRAVES ST	LAMAR ST TENNESSEE ST	3,154	0.60	1	1	2U 2U	122 136	115 102	100%	475 475	475 475	284 370	284 370	73	69 79	211 264	215 291		
STATE HIGHWAY 5	US HIGHWAY 380	VIRGINIA STREET	4,118 4,974	0.78	2	2	2U 5U	1.289	1.289	100% 100%	625	625	1.177	1.177	106 1.214	1.214	-36	-36		
	STATE HIGHWAY 5		2,595	0.94					1,289										36	36
US HIGHWAY 380 TENNESSEE ST	US HIGHWAY 380	THROCKMORTON ST WHITE AVE	1,267	0.49	3	3	6D 2U	1,492 225	1,492	100% 100%	780 475	780 475	1,150 114	1,150	733 54	733 48	417 60	417 66		+
US HIGHWAY 380	TENNESSEE ST	STATE HIGHWAY 5	683	0.24	3	3	6D	1.638	1.638	100%	780	780	303	303	212	212	91	91		
	GRAVES ST	TENNESSEE ST			-	3	6D	2,024			780	780	2,047	2,047						
US HIGHWAY 380 US HIGHWAY 380	US HIGHWAY 75	REDBUD BLVD	4,618 1,479	0.87 0.28	3	3	6D	1,935	1,935	100% 100%	780	780	655	655	1,770 542	1,770 542	277	277		+
TENNESSEE ST	LAMAR ST	VIRGINIA STREET	953	0.28	2	0	2UO	161	0	100%	475	475	171	0	29	0	114	114		
TENNESSEE ST	LAMAR ST			0.18	2	0	2UO	141	0		475	475	171	0	25	0	146	0		
TENNESSEE ST	LOUISIANA ST	VIRGINIA STREET DAVIS ST	953 468	0.18	2	0	200	162	0	100% 100%	475	475	84	0	14	0	70	0		+
AIRPORT DR	US HIGHWAY 380		354	0.09	2	2	4D	920	920	100%	700	700	94	94	62	62	32	32		-
AIRPORT DR		355' S OF US HIGHWAY 380					4D													
AIRPORT DR	385' N OF INDUSTRIAL BLVD FM 546	INDUSTRIAL BLVD 470' N OF HARRY MCKILLOP BLVD /	387 1.656	0.07	2	2	4D 4D	843 22	843 22	100% 50%	700 700	700 700	103 220	103 220	62	62	41 216	41 216	₩	+
	VIRGINIA STREET	GRAVES ST				0	4D 2UO		0		475	475				3		216	<u> </u>	+
LOUISIANA ST			1,050	0.20	2	-		631		100%			189	0	126	0	63	-	<b>├</b>	+
WILSON CREEK PKWY	LOUISIANA ST	1,445' S OF LOUISIANA ST	1,444	0.27	2	2	4U	218	330	100%	525	525	287	287	60	90	228	197	—	+
ELM ST	525' TENNESSEE ST	STATE HIGHWAY 5	436	0.08	1	1	2U	145	185	100%	475	475	39	39	12	15	27	24	<u> </u>	1
ELM ST	STATE HIGHWAY 5	ROCKWALL ST	1,507	0.29	1	1	2U	227	269	100%	475	475	136	136	65	77	71	59	<u> </u>	1
ELDORADO PKWY	1,600' E OF BARRANCA WAY	STATE HIGHWAY 5	1,690	0.32	2	2	4D	625	625	100%	700	700	448	448	200	200	248	248	Ь—	
ELDORADO PKWY	1,180' E OF BARRANCA WAY	1,600' E OF BARRANCA WAY	419	0.08	2	2	4D	656	656	100%	700	700	111	111	52	52	59	59	<u> </u>	1
HARRY MCKILLOP BLVD / FM 5	AIRPURTUR	975' E OF AIRPORT DR	978	0.19	2	2	4D	195	195	100%	700	700	259	259 <b>23.595</b>	36 14.430	36 14.560	223 9.657	223 9.035	ь	
SUBTOTAL			126.338	23.93															973	999

Service Area L

								P	M	% IN	VE	H-MI	VE	Н-МІ	VE	H-MI	EXC	ESS	EXIS	STING
ROADWAY	FROM	то	LENGTH	LENGTH	EX	IST	TYPE	PE	AK	SERVICE	CAP	ACITY	SUF	PPLY	DEN	IAND	CAPA	ACITY	DEFICI	ENCIE
			(ft)	(mi)	LAI	NES		HC	DUR	AREA	PK	-HR	PK	-HR	PK	-HR	PK	-HR	PK	-HR
									OL			R LN		TAL		TAL		H-MI		н-мі
					NB/EB	SB/WB		NB/EB	SB/WB		NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WB	NB/EB	SB/WI
AIRPORT DR	470' N OF HARRY MCKILLOP BLVI	HARRY MCKILLOP BLVD / FM 546	468	0.09	1	1	2U	22	22	50%	475	475	21	21	1	1	20	20		
AIRPORT DR	INDUSTRIAL BLVD	FM 546	2,266	0.43	2	2	4D	191	191	50%	700	700	300	300	41	41	260	260		
INDUSTRIAL BLVD	AIRPORT DR	585' E OF AIRPORT DR	587	0.11	2	2	4D	33	33	100%	700	700	156	156	4	4	152	152		
AIRPORT DR	WILSON CREEK PKWY	385' N OF INDUSTRIAL BLVD	2,105	0.40	2	2	4D	843	843	50%	700	700	279	279	168	168	111	111		
AIRPORT DR	LOUISIANA ST	WILSON CREEK PKWY	4,197	0.79	2	2	4D	923	923	50%	700	700	556	556	367	367	189	189		
AIRPORT DR	VIRGINIA STREET	GREENVILLE RD	1,042	0.20	2	2	4D	920	920	100%	700	700	276	276	182	182	95	95		
AIRPORT DR	355' S OF US HIGHWAY 380	VIRGINIA STREET	1,863	0.35	2	2	4D	920	920	50%	700	700	247	247	162	162	85	85		
AIRPORT DR	US HIGHWAY 380	355' S OF US HIGHWAY 380	354	0.07	2	2	4D	920	920	100%	700	700	94	94	62	62	32	32		
AIRPORT DR	385' N OF INDUSTRIAL BLVD	INDUSTRIAL BLVD	387	0.07	2	2	4D	843	843	100%	700	700	103	103	62	62	41	41		
AIRPORT DR	FM 546	470' N OF HARRY MCKILLOP BLVD	1,656	0.31	2	2	4D	22	22	50%	700	700	220	220	3	3	216	216		
US HIGHWAY 380	AIRPORT DR	940' E OF AIRPORT DR	939	0.18	2	2	4D	2249	2249	100%	700	700	249	249	400	400	-151	-151	151	151
HARRY MCKILLOP BLVD / FM	AIRPORT DR	975' E OF AIRPORT DR	978	0.19	2	2	4D	195	195	100%	700	700	259	259	36	36	223	223		
SUBTOTAL			16,843	3.19									2,760	2,760	1,488	1,488	1,273	1,273	151	151
													5.	521	2.9	975	2.5	545	3/	02

Service Area M	10/7/2020
Service Area IVI	10///2020

00. 1.00 / 1.0u iii													
							PM	% IN	VEH-MI	VEH-MI	VEH-MI	EXCESS	EXISTING
ROADWAY	FROM	то	LENGTH	LENGTH	EXIST	TYPE	PEAK	SERVICE	CAPACITY	SUPPLY	DEMAND	CAPACITY	DEFICIENCIES
			(ft)	(mi)	LANES		HOUR	AREA	PK-HR	PK-HR	PK-HR	PK-HR	PK-HR
							VOL		PER LN	TOTAL	TOTAL	VEH-MI	VEH-MI
					NB/EB SB/WB		NB/EB SB/WB		NB/EB SB/WB	NB/EB SB/WB	NB/EB SB/WB	NB/EB SB/WB	NB/EB SB/WB
		No Thoroughfare Ro	adways w	ithin City L	imits Currentl	y Pres	ent within Ser	vice Area N	Л				
SUBTOTAL			0	0.00						0 0	0 0	0 0	0 0
•										0	0	0	0





# Appendix D – Plan for Awarding the Roadway Impact Fee Credit Summary

AS PREPARED BY NEWGEN STRATEGIES & SOLUTIONS, LLC

#### **SUMMARY OF ROADWAY IMPACT FEE DETERMINATION**

Service Area B

Recoverable Impact Fee CIP Costs	\$ 9,638,193	Line 16, Maximum Fee Calculation Table
Financing Costs	2,272,855	See Detail Below
Existing Fund Balance	-	Page 1 of Appendix E - Service Area B
Interest Earnings	(1,349,526)	Page 5 of Appendix E - Service Area B
Pre Credit Recoverable Cost for Impact Fee	\$ 10,561,522	Sum of Above
Credit for Ad Valorem Revenues	(82,337)	Page 8 of Appendix E - Service Area B
Maximum Recoverable Cost for Impact Fee	\$ 10,479,185	

## Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area B column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 7,091,951 (Page 3 of Appendix E - Service Area B)
Existing Annual Debt Service	- (Page 3 of Appendix E - Service Area B)
Principal Component	 (4,819,097) (Page 4 of Appendix E - Service Area B)
Financing Costs	\$ 2,272,855

#### Existing Fund Balance:

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area B.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area B.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

#### Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area B.

#### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

This is the maximum cost that can be recovered through impact fees.

#### **SUMMARY OF ROADWAY IMPACT FEE DETERMINATION**

Service Area C

Recoverable Impact Fee CIP Costs	\$ 42,187,190	Line 16, Maximum Fee Calculation Table
Financing Costs	9,640,068	See Detail Below
Existing Fund Balance	(1,784,813)	Page 1 of Appendix E - Service Area C
Interest Earnings	(5,688,458)	Page 5 of Appendix E - Service Area C
Pre Credit Recoverable Cost for Impact Fee	\$ 44,353,987	Sum of Above
Credit for Ad Valorem Revenues	(601,239)	Page 8 of Appendix E - Service Area C
Maximum Recoverable Cost for Impact Fee	\$ 43,752,749	

## Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area C column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 27,286,745 (Page 3 of Appendix E - Service Area C)
Existing Annual Debt Service	5,836,214 (Page 3 of Appendix E - Service Area C)
Principal Component	 (23,482,891) (Page 4 of Appendix E - Service Area C)
Financing Costs	\$ 9,640,068

#### **Existing Fund Balance:**

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area C.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area C.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

#### Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area C.

#### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

This is the maximum cost that can be recovered through impact fees.

Service Area D

Recoverable Impact Fee CIP Costs	\$ 132,127,064	Line 16, Maximum Fee Calculation Table
Financing Costs	32,193,283	See Detail Below
Existing Fund Balance	(131,981)	Page 1 of Appendix E - Service Area D
Interest Earnings	(17,212,335)	Page 5 of Appendix E - Service Area D
Pre Credit Recoverable Cost for Impact Fee	\$ 146,976,031	Sum of Above
Credit for Ad Valorem Revenues	(5,004,090)	Page 8 of Appendix E - Service Area D
Maximum Recoverable Cost for Impact Fee	\$ 141,971,941	

## Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area D column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 88,915,117 (Page 3 of Appendix E - Service Area D)
Existing Annual Debt Service	13,336,896 (Page 3 of Appendix E - Service Area D)
Principal Component	 (70,058,730) (Page 4 of Appendix E - Service Area D)
Financing Costs	\$ 32,193,283

#### Existing Fund Balance:

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area D.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area D.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

#### Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area D.

### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

Service Area E

Recoverable Impact Fee CIP Costs	\$ 36,477,811	Line 16, Maximum Fee Calculation Table
Financing Costs	8,560,746	See Detail Below
Existing Fund Balance	(129,689)	Page 1 of Appendix E - Service Area E
Interest Earnings	(5,036,323)	Page 5 of Appendix E - Service Area E
Pre Credit Recoverable Cost for Impact Fee	\$ 39,872,546	Sum of Above
Credit for Ad Valorem Revenues	(578,212)	Page 8 of Appendix E - Service Area E
Maximum Recoverable Cost for Impact Fee	\$ 39,294,334	

# Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area E column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 26,604,431 (Page 3 of Appendix E - Service Area E)
Existing Annual Debt Service	157,395 (Page 3 of Appendix E - Service Area E)
Principal Component	 (18,201,079) (Page 4 of Appendix E - Service Area E)
Financing Costs	\$ 8,560,746

#### **Existing Fund Balance:**

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area E.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area E.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

# Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area E.

### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

Service Area G

Recoverable Impact Fee CIP Costs	\$ 8,041,653	Line 16, Maximum Fee Calculation Table
Financing Costs	2,552,974	See Detail Below
Existing Fund Balance	(448,086)	Page 1 of Appendix E - Service Area G
Interest Earnings	(1,137,019)	Page 5 of Appendix E - Service Area G
Pre Credit Recoverable Cost for Impact Fee	\$ 9,009,522	Sum of Above
Credit for Ad Valorem Revenues	(67,194)	Page 8 of Appendix E - Service Area G
Maximum Recoverable Cost for Impact Fee	\$ 8,942,328	

#### Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area G column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 4,050,969 (Page 3 of Appendix E - Service Area G)
Existing Annual Debt Service	3,628,688 (Page 3 of Appendix E - Service Area G)
Principal Component	 (5,126,683) (Page 4 of Appendix E - Service Area G)
Financing Costs	\$ 2,552,974

#### **Existing Fund Balance:**

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area G.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area G.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

# Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area G.

### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

Service Area H

Recoverable Impact Fee CIP Costs	\$ 10,213,823	Line 16, Maximum Fee Calculation Table
Financing Costs	2,942,747	See Detail Below
Existing Fund Balance	(293,933)	Page 1 of Appendix E - Service Area H
Interest Earnings	(1,231,934)	Page 5 of Appendix E - Service Area H
Pre Credit Recoverable Cost for Impact Fee	\$ 11,630,704	Sum of Above
Credit for Ad Valorem Revenues	(333,123)	Page 8 of Appendix E - Service Area H
Maximum Recoverable Cost for Impact Fee	\$ 11,297,580	

## Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area H column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 4,752,546 (Page 3 of Appendix E - Service Area H)
Existing Annual Debt Service	5,016,542 (Page 3 of Appendix E - Service Area H)
Principal Component	(6,826,340) (Page 4 of Appendix E - Service Area H)
Financing Costs	\$ 2,942,747

#### Existing Fund Balance:

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area H.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area H.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

#### Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area H.

### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

Service Area I

Recoverable Impact Fee CIP Costs	\$ 25,021,841	Line 16, Maximum Fee Calculation Table
Financing Costs	7,106,451	See Detail Below
Existing Fund Balance	(5,189,258)	Page 1 of Appendix E - Service Area I
Interest Earnings	(3,301,274)	Page 5 of Appendix E - Service Area I
Pre Credit Recoverable Cost for Impact Fee	\$ 23,637,760	Sum of Above
Credit for Ad Valorem Revenues	(449,003)	Page 8 of Appendix E - Service Area I
Maximum Recoverable Cost for Impact Fee	\$ 23,188,757	

#### Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area I column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 9,394,797 (Page 3 of Appendix E - Service Area I)
Existing Annual Debt Service	12,937,528 (Page 3 of Appendix E - Service Area I)
Principal Component	(15,225,874) (Page 4 of Appendix E - Service Area I)
Financing Costs	\$ 7,106,451

#### Existing Fund Balance:

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area I.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area I.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

#### Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area I.

### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

Service Area J

Recoverable Impact Fee CIP Costs	\$ 9,621,608	Line 16, Maximum Fee Calculation Table
Financing Costs	2,915,731	See Detail Below
Existing Fund Balance	(2,179,356)	Page 1 of Appendix E - Service Area J
Interest Earnings	(1,467,153)	Page 5 of Appendix E - Service Area J
Pre Credit Recoverable Cost for Impact Fee	\$ 8,890,830	Sum of Above
Credit for Ad Valorem Revenues	(257,003)	Page 8 of Appendix E - Service Area J
Maximum Recoverable Cost for Impact Fee	\$ 8,633,827	

# Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area J column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 4,864,097 (Page 3 of Appendix E - Service Area J)
Existing Annual Debt Service	4,346,705 (Page 3 of Appendix E - Service Area J)
Principal Component	 (6,295,072) (Page 4 of Appendix E - Service Area J)
Financing Costs	\$ 2,915,731

#### Existing Fund Balance:

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area J.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area J.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

#### Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area J.

### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

Service Area K

Recoverable Impact Fee CIP Costs	\$ 9,904,669	Line 16, Maximum Fee Calculation Table
Financing Costs	2,590,329	See Detail Below
Existing Fund Balance	(779,111)	Page 1 of Appendix E - Service Area K
Interest Earnings	(1,427,017)	Page 5 of Appendix E - Service Area K
Pre Credit Recoverable Cost for Impact Fee	\$ 10,288,870	Sum of Above
Credit for Ad Valorem Revenues	(80,502)	Page 8 of Appendix E - Service Area K
Maximum Recoverable Cost for Impact Fee	\$ 10,208,369	

## Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area K column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 6,321,850 (Page 3 of Appendix E - Service Area K)
Existing Annual Debt Service	1,724,071 (Page 3 of Appendix E - Service Area K)
Principal Component	 (5,455,592) (Page 4 of Appendix E - Service Area K)
Financing Costs	\$ 2,590,329

#### Existing Fund Balance:

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area K.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area K.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

#### Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area K.

### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

Service Area L

Recoverable Impact Fee CIP Costs	\$ 3,542,826	Line 16, Maximum Fee Calculation Table
Financing Costs	829,021	See Detail Below
Existing Fund Balance	(5,532)	Page 1 of Appendix E - Service Area L
Interest Earnings	(491,577)	Page 5 of Appendix E - Service Area L
Pre Credit Recoverable Cost for Impact Fee	\$ 3,874,737	Sum of Above
Credit for Ad Valorem Revenues	(5,956)	Page 8 of Appendix E - Service Area L
Maximum Recoverable Cost for Impact Fee	\$ 3,868,782	

## Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area L column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 2,536,809 (Page 3 of Appendix E - Service Area L)
Existing Annual Debt Service	73,147 (Page 3 of Appendix E - Service Area L)
Principal Component	 (1,780,935) (Page 4 of Appendix E - Service Area L)
Financing Costs	\$ 829,021

#### Existing Fund Balance:

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area L.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area L.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

#### Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area L.

### Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.

Service Area M

Recoverable Impact Fee CIP Costs	\$ 668,610	Line 16, Maximum Fee Calculation Table
Financing Costs	157,670	See Detail Below
Existing Fund Balance	-	Page 1 of Appendix E - Service Area M
Interest Earnings	(94,613)	Page 5 of Appendix E - Service Area M
Pre Credit Recoverable Cost for Impact Fee	\$ 731,667	Sum of Above
Credit for Ad Valorem Revenues	(181)	Page 8 of Appendix E - Service Area M
Maximum Recoverable Cost for Impact Fee	\$ 731,486	

## Recoverable Impact Fee CIP Costs:

Represents the portion of capital improvement costs that are eligible for funding through impact fees.

Reference is Service Area M column, line 16 on the Max Fee Calculation Table.

#### Financing Costs:

Represents the interest costs associated with debt financing the new impact fee project costs. Interests costs are derived from existing debt issues and forecasted debt issues.

New Annual Debt Service	\$ 491,975 (Page 3 of Appendix E - Service Area M)
Existing Annual Debt Service	- (Page 3 of Appendix E - Service Area M)
Principal Component	 (334,305) (Page 4 of Appendix E - Service Area M)
Financing Costs	\$ 157,670

#### Existing Fund Balance:

Represents impact fee revenue collected but not yet expended. Some projects that are included in the 2020 Impact Fee Update were also included in prior Impact Fee Updates. To avoid charging twice for the same project, the impact fee revenues collected but yet to be expended (i.e. fund balance) are credited against the recoverable costs. Reference is page 1 of Appendix E - Service Area M.

#### Interest Earnings:

Represents the interest earned on cash flows and assumes a 2.00% annual interest rate. The Impact Fee Statute states that interest earnings are funds of the impact fee account and are held to the same restrictions as impact fee revenues. Therefore in order to recognize that interest earnings are used to fund capital improvements, interest earnings are credited against the recoverable costs. Reference is the sum of recoverable costs. Reference is page 1 of Appendix E - Service Area M.

#### Pre Credit Recoverable Cost for Impact Fee

Represents Recoverable Impact Fee CIP Costs plus Financing Costs less Interest Earnings.

# Credit for Ad Valorem Revenues:

In 2001, the Impact Fee Statute was amended to include a credit for ad valorem and/or utility revenues generated by new service units during the ten-year timeframe that are used to fund impact fee eligible projects for which the new service units were charged an impact fee. The intent of this amendment is to avoid double-charging the new service units for impact fee capital improvements. The credit recognizes ad valorem revenues used to fund the debt service of debt financed impact fee eligible projects and assumes that all non-debt funded impact fee eligible project costs will be funded solely through impact fee revenues or non-ad valorem revenue sources. Reference is page 6 of Appendix E - Service Area M.

## Maximum Recoverable Cost for Impact Fee:

Represents Pre Credit Recoverable Cost for Impact Fee less Credit for Ad Valorem Revenues.





# Appendix E – Plan for Awarding the Roadway Impact Fee Credit Summary Supporting Exhibits

AS PREPARED BY NEWGEN STRATEGIES & SOLUTIONS, LLC

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area B

#### I. General Assumptions

Annual Interest Rate on Deposits (1)
Annual Vehicle Mile Growth (2)
Existing Fund Balance (3)

2.00% 958 \$ -

Portion of Projects Funded by Existing Debt⁽⁴⁾ Non-debt Funded Project Cost⁽⁵⁾ New Project Cost Funded Through New Debt⁽⁶⁾ \$ -4,819,097 4,819,097 \$ 9,638,193

# Total Recoverable Project Cost (7)

#### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	<u>Term</u>	
1	\$ 481,910	4.00%	20
2	481,910	4.00%	20
3	481,910	4.00%	20
4	481,910	4.00%	20
5	481,910	4.00%	20
6	481,910	4.00%	20
7	481,910	4.00%	20
8	481,910	4.00%	20
9	481,910	4.00%	20
10	481,910	4.00%	20
Total	\$ 4,819,097		

## III. Capital Expenditure Assumptions

<u>Year</u>	Exp	Annual Capital enditures ⁽¹⁰⁾
1	\$	481,910
2		642,546
3		803,183
4		963,819
5		963,819
6		963,819
7		963,819
8		963,819
9		963,819
10		963,819
11		481,910
12		321,273
13		160,637
Total	\$	9,638,193

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Total

# City of McKinney - 2019 Roadway Impact Fee Study

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area B

#### I. New Debt Service Detail

Year	Series <u>1</u>	Series	Series <u>3</u>	Series <u>4</u>	Series <u>5</u>	Series	Series 7	Series	Series	Series	Annual New Debt Service
1	\$ 35,460	\$ -	\$ -	\$ -	\$ - \$	- \$	- \$	- \$	- \$	- :	\$ 35,460
2	35,460	35,460	-	-	-	-	-	-	-	-	70,920
3	35,460			-	-	-	-	-	-	-	106,379
4	35,460			35,460	-	-	-	-	-	-	141,839
5	35,460			35,460	35,460	-	-	-	-	-	177,299
6	35,460			35,460	35,460	35,460	-	-	-	-	212,759
7	35,460			35,460	35,460	35,460	35,460	-	-	-	248,218
8	35,460			35,460	35,460	35,460	35,460	35,460	-	-	283,678
9	35,460			35,460	35,460	35,460	35,460	35,460	35,460	-	319,138
10	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
11	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
12	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
13	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
14	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
15	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
16	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
17	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
18	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
19	35,460			35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
20	35,460	35,460	35,460	35,460	35,460	35,460	35,460	35,460	35,460	35,460	354,598
21	-	35,460	35,460	35,460	35,460	35,460	35,460	35,460	35,460	35,460	319,138
22	-	-	35,460	35,460	35,460	35,460	35,460	35,460	35,460	35,460	283,678
23	-	-	-	35,460	35,460	35,460	35,460	35,460	35,460	35,460	248,218
24	-	-	-	-	35,460	35,460	35,460	35,460	35,460	35,460	212,759
25	-	-	-	-	-	35,460	35,460	35,460	35,460	35,460	177,299
26	-	-	-	-	-	-	35,460	35,460	35,460	35,460	141,839
27	-	-	-	-	-	-	-	35,460	35,460	35,460	106,379
28	-	-	-	-	-	-	-	-	35,460	35,460	70,920
29	-	-	-	-	-	-	-	-	-	35,460	35,460
	\$ 709,195	\$ 709,195	5 \$ 709,195	\$ 709,195	\$ 709,195 \$	709,195 \$	709,195 \$	709,195 \$	709,195 \$	709,195	\$ 7,091,951

## II. Summary of Annual Expenses

<u>Year</u>	:	New Annual Debt Service ⁽¹⁾	<u>Ex</u>	Annual Capital penditures ⁽²⁾	<u>P</u>	Annual Bond 'roceeds ⁽²⁾	Existing Annual Debt Service ⁽³⁾	Annual <u>Credit⁽⁴⁾</u>	Total <u>Expense</u>
1	\$	35,460	\$	481,910	\$	(481,910)	\$ -	\$ (56) \$	35,404
2		70,920		642,546		(481,910)	-	(218)	231,338
3		106,379		803,183		(481,910)	-	(476)	427,176
4		141,839		963,819		(481,910)	-	(824)	622,924
5		177,299		963,819		(481,910)	-	(1,254)	657,954
6		212,759		963,819		(481,910)	-	(1,760)	692,908
7		248,218		963,819		(481,910)	-	(2,336)	727,792
8		283,678		963,819		(481,910)	-	(2,977)	762,611
9		319,138		963,819		(481,910)	-	(3,678)	797,369
10		354,598		963,819		(481,910)	-	(4,436)	832,071
11		354,598		481,910		-	-	(4,436)	832,071
12		354,598		321,273		-	-	(4,436)	671,435
13		354,598		160,637		-	-	(4,436)	510,798
14		354,598		-		-	-	(4,436)	350,162
15		354,598		-		-	-	(4,436)	350,162
16		354,598		-		-	-	(4,436)	350,162
17		354,598		-		-	-	(4,436)	350,162
18		354,598		-		-	-	(4,436)	350,162
19		354,598		-		-	-	(4,436)	350,162
20		354,598		-		-	-	(4,436)	350,162
21		319,138		-		-	-	(3,992)	315,145
22		283,678		-		-	-	(3,549)	280,129
23		248,218		-		-	-	(3,105)	245,113
24		212,759		-		-	-	(2,662)	210,097
25		177,299		-		-	-	(2,218)	175,081
26		141,839		-		-	-	(1,774)	140,065
27		106,379		-		-	-	(1,331)	105,048
28		70,920		-		-	-	(887)	70,032
29		35,460				-	-	(444)	35,016
	\$	7,091,951	\$	9,638,193	\$	(4,819,097)	\$ -	\$ (82,337) \$	11,828,711

⁽¹⁾ Appendix E - Service Area B, Page 2 Section I
(2) Appendix E - Service Area B, Page 1

⁽³⁾ Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area B, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area B

<u>Year</u>	Impact <u>Fee</u>	Vehicle <u>Miles</u>	Impact Fee <u>Revenue</u>	Annual <u>Expenses</u>	Sub-Total	Accumulated Interest	Estimated Fund <u>Balance</u>
Initial							\$ -
1	\$ 1,09	4 958	\$ 1,047,918	\$ 35,404	\$ 1,012,515	\$ 10,125	1,022,640
2	1,09	4 958	1,047,918	231,338	816,580	28,619	1,867,839
3	1,09		1,047,918	427,176	620,743	43,564	2,532,146
4	1,09	4 958	1,047,918	622,924	424,994	54,893	3,012,032
5	1,09	4 958	1,047,918	657,954	389,964	64,140	3,466,137
6	1,09	4 958	1,047,918	692,908	355,010	72,873	3,894,020
7	1,09	4 958	1,047,918	727,792	320,126	81,082	4,295,228
8	1,09	4 958	1,047,918	762,611	285,308	88,758	4,669,294
9	1,09		1,047,918	797,369	250,549	95,891	5,015,734
10	1,09	4 958	1,047,918	832,071	215,847	102,473	5,334,055
11	-	-	-	832,071	(832,071)	98,360	4,600,344
12	-	-	-	671,435	(671,435)	85,293	4,014,202
13	-	-	-	510,798	(510,798)	75,176	3,578,579
14	-	-	-	350,162	(350,162)	68,070	3,296,488
15	-	-	-	350,162	(350,162)	62,428	3,008,754
16	-	-	-	350,162	(350,162)	56,673	2,715,266
17	-	-	-	350,162	(350,162)	50,804	2,415,908
18	-	-	-	350,162	(350,162)	44,817	2,110,563
19	-	-	-	350,162	(350,162)	38,710	1,799,111
20	-	-	-	350,162	(350,162)	32,481	1,481,430
21	-	-	-	315,145	(315,145)	26,477	1,192,762
22	-	-	-	280,129	(280,129)	21,054	933,687
23	-	-	-	245,113	(245,113)	16,223	704,796
24	-	-	-	210,097	(210,097)	11,995	506,694
25	-	-	-	175,081	(175,081)	8,383	339,996
26	-	-	-	140,065	(140,065)	5,399	205,331
27	-	-	-	105,048	(105,048)	3,056	103,339
28	-	-	-	70,032	(70,032)	1,366	34,673
29	-	-		35,016	(35,016)	343	-
			\$ 10,479,185	\$ 11,828,711		\$ 1,349,526	

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area B

	Number of	Interest	Recovery						
	Years to	Rate	Fee	Annual Vel	hicle Miles		Annual	Ехр	ense
<u>Year</u>	<b>End of Period</b>	<u>Factor</u>	<u>Factor</u>	<u>Actual</u>	Escalated		<u>Actual</u>	-	<b>Escalated</b>
' <u></u> '									
1	29	1.7584	1.0000	958	1,684	\$	35,404	\$	62,255
2	28	1.7240	1.0000	958	1,651		231,338		398,817
3	27	1.6902	1.0000	958	1,619		427,176		721,992
4	26	1.6570	1.0000	958	1,587		622,924		1,032,193
5	25	1.6245	1.0000	958	1,556		657,954		1,068,861
6	24	1.5927	1.0000	958	1,525		692,908		1,103,573
7	23	1.5614	1.0000	958	1,496		727,792		1,136,403
8	22	1.5308	1.0000	958	1,466		762,611		1,167,422
9	21	1.5008	1.0000	958	1,437		797,369		1,196,697
10	20	1.4714	1.0000	958	1,409		832,071		1,224,292
11	19	1.4425	1.0000	-	-		832,071		1,200,287
12	18	1.4142	1.0000	-	-		671,435		949,572
13	17	1.3865	1.0000	-	-		510,798		708,229
14	16	1.3593	1.0000	-	-		350,162		475,984
15	15	1.3327	1.0000	-	-		350,162		466,651
16	14	1.3065	1.0000	-	-		350,162		457,501
17	13	1.2809	1.0000	-	-		350,162		448,530
18	12	1.2558	1.0000	-	-		350,162		439,736
19	11	1.2312	1.0000	-	-		350,162		431,113
20	10	1.2070	1.0000	-	-		350,162		422,660
21	9	1.1834	1.0000	_	_		315,145		372,936
22	8	1.1602	1.0000	_	_		280,129		324,998
23	7	1.1374	1.0000	_	_		245,113		278,798
24	6	1.1151	1.0000	_	_		210,097		234,284
25	5	1.0933	1.0000	_	_		175,081		191,408
26	4	1.0718	1.0000	_	_		140,065		150,124
27	3	1.0508	1.0000	_	_		105,048		110,385
28	2	1.0302	1.0000	_	_		70,032		72,147
29	1	1.0100	1.0000	_	_		35,016		35,366
20	·	1.0100	1.0000		15,431		00,010	\$	16,883,217
					10, 101			Ψ	10,000,217
		Annual Interest Ra	te:				2.00%		
		, umaar mitoroot i ta					2.0070		
	Present Value of Initial Impact Fee Fund Balance						-		
		T. (-) E		District		Φ.	40.000.04=		
		Total Escalated Ex	•			\$	16,883,217		
		Less Future Value	of Initial Impact I	ee Fund Balance	,	Φ.	-	•	
		Sub-Total				\$	16,883,217		
		Total Escalated Ve	hicle Miles				15,431	•	
		Impact Fee For Se	ervice Area B			\$	1,094		

Capital Improvement Plan for Impact Fees
Appendix E - Impact Fee Calculation Assumptions
Service Area B

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	Ser	Cost In vice Area ⁽¹⁾	<u>R</u>	Impact Fee Recoverable Cost ⁽²⁾	Debt F Existing	ed ⁽³⁾ Proposed	Non-Debt Funded ⁽³⁾	<u> </u>	Impact Fee Recoverable Cost
UNNAMED 5 (4)	B-1, D-2	\$	2,452,100	\$	2,433,532	\$ -	\$ 1,216,766	\$ 1,216,766	\$	2,433,532
HARDIN BLVD (1)	B-2		438,900		435,577	-	217,788	217,788		435,577
HARDIN BLVD (2)	B-3		2,418,500		2,400,187	-	1,200,093	1,200,093		2,400,187
HARDIN BLVD (3)	B-4		4,090,450		4,059,477	-	2,029,738	2,029,738		4,059,477
Signal	1		150,000		148,864	-	74,432	74,432		148,864
Signal	3		150,000		148,864	-	74,432	74,432		148,864
Impact Fee Study			11,692		11,692	-	5,846	5,846		11,692
Total		\$	9,711,642	\$	9,638,193	\$ -	\$ 4,819,097	\$ 4,819,097	\$	9,638,193

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area B

<u>Year</u>	Eligible Debt <u>Service⁽¹⁾</u>	Annual Vehicle <u>Miles</u>	Eligible Debt Service per <u>Vehicle Mile</u>	Annual Growth in Vehicle Miles (Cumulative)	edit for Annual Ad Valorem <u>Revenues</u>
1	\$ 35,460	606,072	\$ 0.06	958	\$ 56
2	70,920	623,802	0.11	1,916	218
3	106,379	641,531	0.17	2,873	476
4	141,839	659,260	0.22	3,831	824
5	177,299	676,990	0.26	4,789	1,254
6	212,759	694,719	0.31	5,747	1,760
7	248,218	712,448	0.35	6,705	2,336
8	283,678	730,177	0.39	7,662	2,977
9	319,138	747,907	0.43	8,620	3,678
10	354,598	765,636	0.46	9,578	4,436
11	354,598	765,636	0.46	9,578	4,436
12	354,598	765,636	0.46	9,578	4,436
13	354,598	765,636	0.46	9,578	4,436
14	354,598	765,636	0.46	9,578	4,436
15	354,598	765,636	0.46	9,578	4,436
16	354,598	765,636	0.46	9,578	4,436
17	354,598	765,636	0.46	9,578	4,436
18	354,598	765,636	0.46	9,578	4,436
19	354,598	765,636	0.46	9,578	4,436
20	354,598	765,636	0.46	9,578	4,436
21	319,138	765,636	0.42	9,578	3,992
22	283,678	765,636	0.37	9,578	3,549
23	248,218	765,636	0.32	9,578	3,105
24	212,759	765,636	0.28	9,578	2,662
25	177,299	765,636	0.23	9,578	2,218
26	141,839	765,636	0.19	9,578	1,774
27	106,379	765,636	0.14	9,578	1,331
28	70,920	765,636	0.09	9,578	887
29	 35,460	765,636	0.05	9,578	444
Total	\$ 7,091,951				\$ 82,337

2019 Vehicle Miles (2)

Ten Year Growth in Vehicle Miles in Service Area (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

167,715

10 years

Annual Growth in Vehicle Miles

16,772

Credit Amount

\$ 82,337

- (1) Appendix E Service Area B, Page 2 Section II
- (2) Per Kimley-Horn Impact Fee Study
- (3) Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area C

#### I. General Assumptions

Annual Interest Rate on Deposits (1)

Annual Vehicle Mile Growth (2)

Existing Fund Balance (3) \$

Portion of Projects Funded by Existing Debt⁽⁴⁾
Non-debt Funded Project Cost⁽⁵⁾
New Project Cost Funded Through New Debt⁽⁶⁾
Total Recoverable Project Cost⁽⁷⁾

\$ 4,941,103 18,704,299 18,541,789 \$ 42,187,190

2.00%

1,558

1,784,813

## II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>		
1	\$ 1,854,179	4.00%	20		
'					
2	1,854,179	4.00%	20		
3	1,854,179	4.00%	20		
4	1,854,179	4.00%	20		
5	1,854,179	4.00%	20		
6	1,854,179	4.00%	20		
7	1,854,179	4.00%	20		
8	1,854,179	4.00%	20		
9	1,854,179	4.00%	20		
10	1,854,179	4.00%	20		
Total	\$ 18,541,789				

### III. Capital Expenditure Assumptions

<u>Year</u>	Annual Capital <u>Expenditures⁽¹⁰⁾</u>
1	\$ 1,870,430
2	2,488,489
3	3,106,549
4	3,724,609
5	3,724,609
6	3,724,609
7	3,724,609
8	3,724,609
9	3,724,609
10	3,724,609
11	1,854,179
12	1,236,119
13	618,060
Total	\$ 37.246.087

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Total

# City of McKinney - 2019 Roadway Impact Fee Study

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area C

#### I. New Debt Service Detail

<u>Year</u>	Series	Series	Series	Series <u>4</u>	Series <u>5</u>	Series	Series	Series	Series	Series 10	Annual New Debt <u>Service</u>
1 \$	136,434	- 9	- 9	- \$	- \$	- \$	- \$	- \$	- \$	-	\$ 136,434
2	136,434	136,434	-	-	-	-	-	-	-	-	272,867
3	136,434	136,434	136,434	-	-	-	-	-	-	-	409,301
4	136,434	136,434	136,434	136,434	-	-	-	-	-	-	545,735
5	136,434	136,434	136,434	136,434	136,434	-	-	-	-	-	682,169
6	136,434	136,434	136,434	136,434	136,434	136,434	-	-	-	-	818,602
7	136,434	136,434	136,434	136,434	136,434	136,434	136,434	-	-	-	955,036
8	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	-	-	1,091,470
9	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	-	1,227,904
10	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
11	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
12	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
13	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
14	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
15	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
16	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
17	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
18	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
19	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
20	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,364,337
21	-	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,227,904
22	-	-	136,434	136,434	136,434	136,434	136,434	136,434	136,434	136,434	1,091,470
23	-	-	-	136,434	136,434	136,434	136,434	136,434	136,434	136,434	955,036
24	-	-	-	-	136,434	136,434	136,434	136,434	136,434	136,434	818,602
25	-	-	-	-	-	136,434	136,434	136,434	136,434	136,434	682,169
26	-	-	-	-	-	-	136,434	136,434	136,434	136,434	545,735
27	-	-	-	-	-	-	-	136,434	136,434	136,434	409,301
28	-	-	-	-	-	-	-	-	136,434	136,434	272,867
29	-	-	-	-	-	-	-	-	-	136,434	136,434
9	2,728,675	2,728,675	\$ 2,728,675	2,728,675 \$	2,728,675 \$	2,728,675 \$	2,728,675 \$	2,728,675 \$	2,728,675 \$	2,728,675	\$ 27,286,745

# II. Summary of Annual Expenses

	New			Existing		
	Annual	Annual	Annual	Annual		
	Debt	Capital	Bond	Debt	Annual	Total
Year	Service ⁽¹⁾	Expenditures (2)	Proceeds ⁽²⁾	Service ⁽³⁾	Credit ⁽⁴⁾	Expense
1	\$ 136,434	\$ 1,870,430	\$ (1,854,179) \$	573,496 \$	(1,825)	724,355
2	272,867	2,488,489	(1,854,179)	441,988	(3,571)	1,345,595
3	409,301	3,106,549	(1,854,179)	333,872	(5,415)	1,990,129
4	545,735	3,724,609	(1,854,179)	327,296	(8,254)	2,735,206
5	682,169	3,724,609	(1,854,179)	320,670	(11,541)	2,861,727
6	818,602	3,724,609	(1,854,179)	314,098	(15,243)	2,987,887
7	955,036	3,724,609	(1,854,179)	307,472	(19,329)	3,113,609
8	1,091,470	3,724,609	(1,854,179)	300,895	(23,770)	3,239,024
9	1,227,904	3,724,609	(1,854,179)	294,259	(28,542)	3,364,051
10	1,364,337	3,724,609	(1,854,179)	287,667	(33,621)	3,488,813
11	1,364,337	1,854,179	-	281,062	(33,487)	3,466,091
12	1,364,337	1,236,119	-	277,083	(33,406)	2,844,134
13	1,364,337	618,060	-	273,138	(33,325)	2,222,209
14	1,364,337	-	-	269,170	(33,245)	1,600,262
15	1,364,337	-	-	263,906	(33,138)	1,595,106
16	1,364,337	-	-	259,602	(33,050)	1,590,890
17	1,364,337	-	-	217,620	(32,196)	1,549,762
18	1,364,337	-	-	212,590	(32,093)	1,544,834
19	1,364,337	-	-	208,151	(32,003)	1,540,485
20	1,364,337	-	-	72,179	(29,236)	1,407,281
21	1,227,904	-	-	-	(24,990)	1,202,914
22	1,091,470		-	-	(22,213)	1,069,257
23	955,036	-	-	-	(19,437)	935,599
24	818,602	-	-	-	(16,660)	801,942
25	682,169	-	-	-	(13,883)	668,285
26	545,735	-	-	-	(11,107)	534,628
27	409,301	-	-	-	(8,330)	400,971
28	272,867	-	-	-	(5,553)	267,314
29	136,434	-	-	-	(2,777)	133,657
	\$ 27,286,745	\$ 37,246,087	\$ (18,541,789) \$	5,836,214 \$	(601,239)	51,226,020

⁽¹⁾ Appendix E - Service Area C, Page 2 Section I
(2) Appendix E - Service Area C, Page 1

⁽³⁾ Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area C, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area C

<u>Year</u>	Impact <u>Fee</u>	Vehicle <u>Miles</u>	Impact Fee <u>Revenue</u>	Annual <u>Expenses</u>	Sub-Total	Accumulated Interest	Estimated Fund <u>Balance</u>
Initial							\$ 1,784,813
1	\$ 2,808	1,558	\$ 4,375,275	\$ 724,355	\$ 3,650,920	\$ 72,205	5,507,938
2	2,808	1,558	4,375,275	1,345,595	3,029,680	140,456	8,678,073
3	2,808	1,558	4,375,275	1,990,129	2,385,146	197,413	11,260,632
4	2,808	1,558	4,375,275	2,735,206	1,640,068	241,613	13,142,314
5	2,808	1,558	4,375,275	2,861,727	1,513,548	277,982	14,933,844
6	2,808	1,558	4,375,275	2,987,887	1,387,388	312,551	16,633,782
7	2,808	1,558	4,375,275	3,113,609	1,261,665	345,292	18,240,740
8	2,808	1,558	4,375,275	3,239,024	1,136,250	376,177	19,753,168
9	2,808	1,558	4,375,275	3,364,051	1,011,224	405,176	21,169,567
10	2,808	1,558	4,375,275	3,488,813	886,462	432,256	22,488,285
11	-	-	-	3,466,091	(3,466,091)	415,105	19,437,299
12	-	-	-	2,844,134	(2,844,134)	360,305	16,953,470
13	-	-	-	2,222,209	(2,222,209)	316,847	15,048,107
14	-	-	-	1,600,262	(1,600,262)	284,960	13,732,805
15	-	-	-	1,595,106	(1,595,106)	258,705	12,396,404
16	-	-	-	1,590,890	(1,590,890)	232,019	11,037,533
17	-	-	-	1,549,762	(1,549,762)	205,253	9,693,024
18	-	-	-	1,544,834	(1,544,834)	178,412	8,326,602
19	-	-	-	1,540,485	(1,540,485)	151,127	6,937,245
20	-	-	-	1,407,281	(1,407,281)	124,672	5,654,636
21	-	-	-	1,202,914	(1,202,914)	101,064	4,552,786
22	-	-	-	1,069,257	(1,069,257)	80,363	3,563,892
23	-	-	-	935,599	(935,599)	61,922	2,690,215
24	-	-	-	801,942	(801,942)	45,785	1,934,057
25	-	-	-	668,285	(668,285)	31,998	1,297,770
26	-	-	-	534,628	(534,628)	20,609	783,751
27	-	-	-	400,971	(400,971)	11,665	394,445
28	-	-	-	267,314	(267,314)	5,216	132,347
29	-	-		133,657	(133,657)	1,310	-
			\$ 43,752,749	\$ 51,226,020		\$ 5,688,458	

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area C

	Number of	Interest	Recovery					
	Years to	Rate	Fee	Annual Ve	hicle Miles	Annual	Ехр	ense
<u>Year</u>	<b>End of Period</b>	<u>Factor</u>	<u>Factor</u>	<u>Actual</u>	Escalated	<u>Actual</u>	-	Escalated
			· <u> </u>	·	· <u> </u>		•	
1	29	1.7584	1.0000	1,558	2,740	\$ 724,355	\$	1,273,731
2	28	1.7240	1.0000	1,558	2,686	1,345,595		2,319,746
3	27	1.6902	1.0000	1,558	2,634	1,990,129		3,363,620
4	26	1.6570	1.0000	1,558	2,582	2,735,206		4,532,270
5	25	1.6245	1.0000	1,558	2,531	2,861,727		4,648,938
6	24	1.5927	1.0000	1,558	2,482	2,987,887		4,758,713
7	23	1.5614	1.0000	1,558	2,433	3,113,609		4,861,713
8	22	1.5308	1.0000	1,558	2,385	3,239,024		4,958,373
9	21	1.5008	1.0000	1,558	2,339	3,364,051		5,048,791
10	20	1.4714	1.0000	1,558	2,293	3,488,813		5,133,367
11	19	1.4425	1.0000	-	-	3,466,091		4,999,936
12	18	1.4142	1.0000	-	-	2,844,134		4,022,299
13	17	1.3865	1.0000	-	-	2,222,209		3,081,124
14	16	1.3593	1.0000	-	-	1,600,262		2,175,280
15	15	1.3327	1.0000	-	-	1,595,106		2,125,755
16	14	1.3065	1.0000	-	-	1,590,890		2,078,565
17	13	1.2809	1.0000	-	-	1,549,762		1,985,128
18	12	1.2558	1.0000	-	-	1,544,834		1,940,015
19	11	1.2312	1.0000	-	-	1,540,485		1,896,621
20	10	1.2070	1.0000	-	-	1,407,281		1,698,649
21	9	1.1834	1.0000	-	-	1,202,914		1,423,499
22	8	1.1602	1.0000	-	-	1,069,257		1,240,522
23	7	1.1374	1.0000	-	-	935,599		1,064,173
24	6	1.1151	1.0000	-	-	801,942		894,263
25	5	1.0933	1.0000	-	-	668,285		730,607
26	4	1.0718	1.0000	-	-	534,628		573,025
27	3	1.0508	1.0000	-	-	400,971		421,342
28	2	1.0302	1.0000	-	-	267,314		275,387
29	1	1.0100	1.0000	-	-	133,657		134,994
					25,104		\$	73,660,447
		Annual Interest Ra	te:			2.00%		
		Present Value of Ir	nitial Impact Fee	Fund Balance		\$ 1,784,813		
		Total Escalated Ex	pense for Entire	Period		\$ 73,660,447		
		Less Future Value	of Initial Impact	Fee Fund Balance		3,169,551	_	
		Sub-Total				\$ 70,490,896		
		Total Escalated Ve	hicle Miles			25,104		
		Impact Fee For Se	ervice Area C			\$ 2,808		

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area C

Impact Fee Project Name ⁽¹⁾	Total <u>Project Cost⁽¹⁾</u>	Cost In Service Area ⁽¹⁾	Impact Fee Recoverable Cost ⁽²⁾	Debt Fu Existing	ınded ⁽³⁾ <u>Proposed</u>	Non-Debt Funded ⁽³⁾	Impact Fee Recoverable Cost
UNNAMED 5 (1)	\$ 7,715,900	\$ 3,857,950	\$ 1,392,232	\$ -	\$ 696,116	\$ 696,116	\$ 1,392,232
UNNAMED 5 (2)	3,137,400	1,568,700	566,102	-	283,051	283,051	566,102
LAUD HOWELL PKWY (1)	665,000	332,500	119,990	_	59,995	59,995	119.990
LAUD HOWELL PKWY (2)	1,171,800	1,171,800	422,871	_	211,436	211,436	422,871
LAUD HOWELL PKWY (3)	808,500	404,250	145,883	_	72,942	72,942	145,883
LAUD HOWELL PKWY (4)	2,859,500	1,429,750	515,959	_	257,979	257,979	515,959
LAUD HOWELL PKWY (5)	3,073,000	1,536,500	554,482	_	277,241	277,241	554,482
BLOOMDALE RD (1)	3,179,400	3,179,400	1,147,361	_	573,680	573,680	1,147,361
BLOOMDALE RD (2)	4,838,400	2,419,200	873,025	_	436,512	436,512	873,025
BLOOMDALE RD (3)	13,314,000	13,314,000	4,804,669	_	2,402,334	2,402,334	4,804,669
BLOOMDALE RD (4)	3,292,800	1,646,400	594,142	_	297,071	297,071	594,142
BLOOMDALE RD (5)	1,453,200	1,453,200	524,421	_	262,211	262,211	524,421
BLOOMDALE RD (6)	4,650,800	2,325,400	839,175	_	419,588	419,588	839,175
WILMETH RD (1)	8,845,850	8,845,850	3,192,232	_	1,596,116	1,596,116	3,192,232
WILMETH RD (2)	6,200,600	3,100,300	1,118,816	_	559,408	559,408	1,118,816
WILMETH RD (3)	1,593,000	1,593,000	574,871	558,447	(0)		574,871
WILMETH RD (4)	708,000	708,000	255,498	248,198	-	7,300	255,498
CUSTER RD (1)	1,834,000	917,000	330,921	- 10,100	165,460	165,460	330.921
CUSTER RD (2)	2,869,825	2,869,825	1,035,644	_	517,822	517,822	1,035,644
CUSTER RD (3)	8,071,300	4,035,650	1,456,359	150,074	630,744	675,542	1,456,359
STONEBRIDGE DR (2)	2,763,650	2,763,650	997,328	-	498,664	498,664	997,328
STONEBRIDGE DR (3)	14,194,900	14,194,900	5,122,562	_	2,561,281	2,561,281	5,122,562
STONEBRIDGE DR (4)	2,117,300	1,058,650	382,039	_	191,019	191,019	382,039
STONEBRIDGE DR (5)	8,232,050	8,232,050	2,970,728	_	1,485,364	1,485,364	2,970,728
STONEBRIDGE DR (6)	1,030,750	1,030,750	371,970	_	185,985	185,985	371,970
RIDGE RD (1)	3,095,400	1,547,700	558,524	_	279,262	279,262	558,524
RIDGE RD (2)	7,267,950	7,267,950	2,622,810	_	1,311,405	1,311,405	2.622.810
RIDGE RD (3)	9,144,800	4,572,400	1,650,058	_	825,029	825,029	1,650,058
RIDGE RD (4)	3,756,200	1,878,100	677,756	_	338,878	338,878	677,756
RIDGE RD (5)	7,411,200	7,411,200	2,674,505	2,233,786	187,510	253,209	2,674,505
RIDGE RD (6)	1,455,000	727,500	262,535	217,174	19,487	25,875	262,535
RIDGE RD (7)	2,857,200	2,857,200	1,031,088	744,595	132,296	154,196	1,031,088
LAKE FOREST DR (2)	5,008,981	2,504,491	903,804	458,631	222,587	222,587	903,804
LAKE FOREST DR (3)	2,350,800	1,175,400	424,171	-100,001	212,085	212,085	424,171
Signal	300,000	75,000	27,066	_	13,533	13,533	27,066
Signal	300,000	225,000	81,197	_	40,598	40,598	81,197
Signal	300,000	150,000	54,131	_	27,066	27,066	54,131
Intersection Improvement	150,000	75,000	27,066	_	13,533	13,533	27,066
Signal	300,000	300,000	108,262		54,131	54,131	108,262
Signal	300,000	150,000	54,131		27,066	27,066	54,131
Signal	300,000	75,000	27,066	_	13,533	13,533	27,066
Signal	300,000	300,000	108,262		54,131	54,131	108,262
Signal	300,000	300,000	108,262	-	54,131	54,131	108,262
Roundabout	1,830,000	915,000	330,199	330,199	J4, IJ I	J4, I3 I	330,199
Signal Mod	150,000	75,000	27,066	330,199	13,533	13,533	27,066
Signal Wood	300,000	150,000	54,131	-	27,066	27,066	54,131
Signal	300,000	150,000	54,131	-	27,066	27,066	54,131
Impact Fee Study	11,692	11,692	11,692	-	5,846	5,846	11,692
Total	\$ 156,110,148						
iviai	÷ 100,110,140	ψ 110,002,000	Ψ 72,107,130	Ψ ¬,υ¬1,100	\$ 10,0 <del>1</del> 1,709	\$ 10,10 <del>4</del> ,205	Ψ ¬≥,101,100

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area C

<u>Year</u>	E	Eligible Debt <u>Service⁽¹⁾</u>	Annual Vehicle <u>Miles</u>	Eligible Debt Service per Vehicle Mile	Annual Growth in Vehicle Miles (Cumulative)	Δ	dit for Annual ad Valorem Revenues
1	\$	709,930	606,072	\$ 1.17	1,558	\$	1,825
2		714,856	623,802	1.15	3,116		3,571
3		743,174	641,531	1.16	4,675		5,415
4		873,030	659,260	1.32	6,233		8,254
5		1,002,838	676,990	1.48	7,791		11,541
6		1,132,700	694,719	1.63	9,349		15,243
7		1,262,508	712,448	1.77	10,907		19,329
8		1,392,365	730,177	1.91	12,466		23,770
9		1,522,163	747,907	2.04	14,024		28,542
10		1,652,004	765,636	2.16	15,582		33,621
11		1,645,399	765,636	2.15	15,582		33,487
12		1,641,420	765,636	2.14	15,582		33,406
13		1,637,475	765,636	2.14	15,582		33,325
14		1,633,507	765,636	2.13	15,582		33,245
15		1,628,243	765,636	2.13	15,582		33,138
16		1,623,940	765,636	2.12	15,582		33,050
17		1,581,957	765,636	2.07	15,582		32,196
18		1,576,927	765,636	2.06	15,582		32,093
19		1,572,488	765,636	2.05	15,582		32,003
20		1,436,517	765,636	1.88	15,582		29,236
21		1,227,904	765,636	1.60	15,582		24,990
22		1,091,470	765,636	1.43	15,582		22,213
23		955,036	765,636	1.25	15,582		19,437
24		818,602	765,636	1.07	15,582		16,660
25		682,169	765,636	0.89	15,582		13,883
26		545,735	765,636	0.71	15,582		11,107
27		409,301	765,636	0.53	15,582		8,330
28		272,867	765,636	0.36	15,582		5,553
29		136,434	765,636	0.18	15,582		2,777
Total	\$	33,122,960				\$	601,239

2019 Vehicle Miles (2)

Ten Year Growth in Vehicle Miles in Service Area (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

161,711

10 years

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

161,711

Credit Amount

\$ 601,239

⁽¹⁾ Appendix E - Service Area C, Page 2 Section II

⁽²⁾ Per Kimley-Horn Impact Fee Study

⁽³⁾ Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area D

#### I. General Assumptions

Annual Interest Rate on Deposits (1)
Annual Vehicle Mile Growth (2)
Existing Fund Balance (3)

2.00%
4,130
\$ 131,981

Portion of Projects Funded by Existing Debt ⁽⁴⁾ Non-debt Funded Project Cost ⁽⁵⁾ New Project Cost Funded Through New Debt ⁽⁶⁾ Total Recoverable Project Cost ⁽⁷⁾

\$ 9,639,457
62,068,334
60,419,273

⁷⁾ \$ 132,127,064

#### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>
1	\$ 6,041,927	4.00%	20
2	6,041,927	4.00%	20
3	6,041,927	4.00%	20
4	6,041,927	4.00%	20
5	6,041,927	4.00%	20
6	6,041,927	4.00%	20
7	6,041,927	4.00%	20
8	6,041,927	4.00%	20
9	6,041,927	4.00%	20
10	6,041,927	4.00%	20
Total	\$ 60,419,273		

### III. Capital Expenditure Assumptions

<u>Year</u>	Annual Capital <u>Expenditures⁽¹⁰⁾</u>
1	\$ 6,206,833
2	8,220,809
3	10,234,785
4	12,248,761
5	12,248,761
6	12,248,761
7	12,248,761
8	12,248,761
9	12,248,761
10	12,248,761
11	6,041,927
12	4,027,952
13	2,013,976
Total	\$ 122,487,607

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area D

#### I. New Debt Service Detail

<u>Year</u>	Series	s	Series <u>2</u>	;	Series	Series	Series <u>5</u>	Series	Series	Series	Series	Series	Ne	Total Annual ew Debt Service
1	\$ 444,576	\$	-	\$	-	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$	444,576
2	444,576		444,576		-	-	-	-	-	-	-	-		889,151
3	444,576		444,576		444,576	-	-	-	-	-	-	-		1,333,727
4	444,576		444,576		444,576	444,576	-	-	-	-	-	-		1,778,302
5	444,576		444,576		444,576	444,576	444,576	-	-	-	-	-	- 2	2,222,878
6	444,576		444,576		444,576	444,576	444,576	444,576	-	-	-	-	- 2	2,667,454
7	444,576		444,576		444,576	444,576	444,576	444,576	444,576	-	-	-	:	3,112,029
8	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	-	-	;	3,556,605
9	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	-		4,001,180
10	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
11	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
12	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
13	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
14	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
15	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
16	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576		4,445,756
17	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
18	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
19	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
20	444,576		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,445,756
21	-		444,576		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	4	4,001,180
22	-		-		444,576	444,576	444,576	444,576	444,576	444,576	444,576	444,576	;	3,556,605
23	-		-		-	444,576	444,576	444,576	444,576	444,576	444,576	444,576	;	3,112,029
24	-		-		-	-	444,576	444,576	444,576	444,576	444,576	444,576		2,667,454
25	-		-		-	-	-	444,576	444,576	444,576	444,576	444,576	- 2	2,222,878
26	-		-		-	-	-	-	444,576	444,576	444,576	444,576		1,778,302
27	-		-		-	-	-	-	-	444,576	444,576	444,576		1,333,727
28	-		-		-	-	-	-	-	-	444,576	444,576		889,151
29	-		-		-	-	-	-	-	-	-	444,576		444,576
	\$ 8,891,512	\$ 8	3,891,512	\$	8,891,512	\$ 8,891,512	\$ 8,891,512	\$ 8,891,512	\$ 8,891,512	\$ 8,891,512	\$ 8,891,512	\$ 8,891,512	\$ 88	3,915,117

#### II. Summary of Annual Expenses

<u>Year</u>	New Annual Debt Service ⁽¹⁾	Annual Capital Expenditures ⁽²⁾	Annual Bond <u>Proceeds⁽²⁾</u>	Existing Annual Debt Service ⁽³⁾	Annual <u>Credit⁽⁴⁾</u>	Total <u>Expense</u>
1	\$ 444,576	\$ 6,206,833	\$ (6,041,927)	\$ 770,423	\$ (8,279)	\$ 1,371,625
2	889,151	8,220,809	(6,041,927)	761,935	(21,862)	3,808,106
3	1,333,727	10,234,785	(6,041,927)	754,379	(40,327)	6,240,637
4	1,778,302	12,248,761	(6,041,927)	754,261	(63,460)	8,675,936
5	2,222,878	12,248,761	(6,041,927)	753,586	(90,788)	9,092,510
6	2,667,454	12,248,761	(6,041,927)	753,526	(122,020)	9,505,793
7	3,112,029	12,248,761	(6,041,927)	752,852	(156,827)	9,914,888
8	3,556,605	12,248,761	(6,041,927)	752,733	(194,990)	10,321,182
9	4,001,180	12,248,761	(6,041,927)	751,942	(236,218)	10,723,737
10	4,445,756	12,248,761	(6,041,927)	751,648	(280, 352)	11,123,885
11	4,445,756	6,041,927	-	751,208	(280, 328)	10,958,563
12	4,445,756	4,027,952	-	750,768	(280,305)	8,944,171
13	4,445,756	2,013,976	-	750,708	(280,301)	6,930,139
14	4,445,756	-	-	750,386	(280,284)	4,915,858
15	4,445,756	-	-	750,267	(280,278)	4,915,746
16	4,445,756	-	-	749,864	(280, 256)	4,915,364
17	4,445,756	-	-	321,768	(257,164)	4,510,359
18	4,445,756	-	-	321,432	(257,146)	4,510,042
19	4,445,756	-	-	321,136	(257,130)	4,509,762
20	4,445,756	-	-	312,072	(256,641)	4,501,187
21	4,001,180	-	-	-	(215,827)	3,785,354
22	3,556,605	-	-	-	(191,846)	3,364,759
23	3,112,029	-	-	-	(167,865)	2,944,164
24	2,667,454	-	-	-	(143,885)	2,523,569
25	2,222,878	-	-	-	(119,904)	2,102,974
26	1,778,302	-	-	-	(95,923)	1,682,379
27	1,333,727	-	-	-	(71,942)	1,261,785
28	889,151	-	-	-	(47,962)	841,190
29	444,576	-	-	-	(23,981)	420,595
	\$ 88,915,117	\$122,487,607	\$ (60,419,273)	\$ 13,336,896	\$ (5,004,090)	\$159,316,257

⁽¹⁾ Appendix E - Service Area D, Page 2 Section I
(2) Appendix E - Service Area D, Page 1
(3) Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area D, Page 6

Capital Improvement Plan for Impact Fees
Appendix E - Impact Fee Calculation Assumptions
Service Area D

<u>Year</u>	Impact <u>Fee</u>	Vehicle <u>Miles</u>	Impact Fee <u>Revenue</u>	Annual <u>Expenses</u>	Sub-Total	Accumulated Interest	Estimated Fund <u>Balance</u>
Initial							\$ 131,981
1	\$ 3,438	4,130	\$ 14,197,194	\$ 1,371,625	\$ 12,825,569	\$ 130,895	13,088,445
2	3,438	4,130	14,197,194	3,808,106	10,389,088	365,660	23,843,193
3	3,438	4,130	14,197,194	6,240,637	7,956,557	556,429	32,356,180
4	3,438	4,130	14,197,194	8,675,936	5,521,258	702,336	38,579,774
5	3,438	4,130	14,197,194	9,092,510	5,104,684	822,642	44,507,101
6	3,438	4,130	14,197,194	9,505,793	4,691,401	937,056	50,135,558
7	3,438	4,130	14,197,194	9,914,888	4,282,307	1,045,534	55,463,399
8	3,438	4,130	14,197,194	10,321,182	3,876,013	1,148,028	60,487,440
9	3,438	4,130	14,197,194	10,723,737	3,473,457	1,244,483	65,205,380
10	3,438	4,130	14,197,194	11,123,885	3,073,309	1,334,841	69,613,529
11	-	-	-	10,958,563	(10,958,563)	1,282,685	59,937,652
12	-	-	-	8,944,171	(8,944,171)	1,109,311	52,102,792
13	-	-	-	6,930,139	(6,930,139)	972,754	46,145,408
14	-	-	-	4,915,858	(4,915,858)	873,750	42,103,300
15	-	-	-	4,915,746	(4,915,746)	792,909	37,980,462
16	-	-	-	4,915,364	(4,915,364)	710,456	33,775,554
17	-	-	-	4,510,359	(4,510,359)	630,407	29,895,602
18	-	-	-	4,510,042	(4,510,042)	552,812	25,938,371
19	-	-	-	4,509,762	(4,509,762)	473,670	21,902,279
20	-	-	-	4,501,187	(4,501,187)	393,034	17,794,125
21	-	-	-	3,785,354	(3,785,354)	318,029	14,326,801
22	-	-	-	3,364,759	(3,364,759)	252,888	11,214,930
23	-	-	-	2,944,164	(2,944,164)	194,857	8,465,623
24	-	-	-	2,523,569	(2,523,569)	144,077	6,086,131
25	-	-	-	2,102,974	(2,102,974)	100,693	4,083,850
26	-	-	-	1,682,379	(1,682,379)	64,853	2,466,324
27	-	-	-	1,261,785	(1,261,785)	36,709	1,241,248
28	-	-	-	841,190	(841,190)	16,413	416,471
29	-	-	-	420,595	(420,595)	4,123	
			\$ 141,971,941	\$159,316,257		\$ 17,212,335	

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area D

Year	Number of Years to End of Period	Interest Rate <u>Factor</u>	Recovery Fee Factor	Annual Vehicle Miles <u>Actual Escalated</u>		Annual   Actual	Expense Escalated		
<u></u>		<u> </u>		<u>- 10000</u>		- 1010.U.			
1	29	1.7584	1.0000	4,130	7,262	\$ 1,371,625	\$	2,411,913	
2	28	1.7240	1.0000	4,130	7,120	3,808,106		6,565,005	
3	27	1.6902	1.0000	4,130	6,980	6,240,637		10,547,627	
4	26	1.6570	1.0000	4,130	6,843	8,675,936		14,376,130	
5	25	1.6245	1.0000	4,130	6,709	9,092,510		14,770,979	
6	24	1.5927	1.0000	4,130	6,578	9,505,793		15,139,574	
7	23	1.5614	1.0000	4,130	6,449	9,914,888		15,481,497	
8	22	1.5308	1.0000	4,130	6,322	10,321,182		15,799,902	
9	21	1.5008	1.0000	4,130	6,198	10,723,737		16,094,259	
10	20	1.4714	1.0000	4,130	6,077	11,123,885		16,367,454	
11	19	1.4425	1.0000	-	-	10,958,563		15,808,041	
12	18	1.4142	1.0000	-	-	8,944,171		12,649,239	
13	17	1.3865	1.0000	-	-	6,930,139		9,608,731	
14	16	1.3593	1.0000	-	-	4,915,858		6,682,258	
15	15	1.3327	1.0000	-	-	4,915,746		6,551,084	
16	14	1.3065	1.0000	-	-	4,915,364		6,422,133	
17	13	1.2809	1.0000	-	-	4,510,359		5,777,429	
18	12	1.2558	1.0000	-	-	4,510,042		5,663,747	
19	11	1.2312	1.0000	-	-	4,509,762		5,552,349	
20	10	1.2070	1.0000	-	-	4,501,187		5,433,129	
21	9	1.1834	1.0000	-	-	3,785,354		4,479,496	
22	8	1.1602	1.0000	-	-	3,364,759		3,903,701	
23	7	1.1374	1.0000	-	-	2,944,164		3,348,763	
24 25	6	1.1151	1.0000	-	-	2,523,569		2,814,086	
25 26	5	1.0933 1.0718	1.0000 1.0000	-	-	2,102,974 1,682,379		2,299,090	
26 27	4	1.0508	1.0000	-	-			1,803,208	
28	2	1.0308	1.0000	_	_	1,261,785 841,190		1,325,888 866,594	
29	1	1.0100	1.0000	_	_	420,595		424,801	
23	'	1.0100	1.0000		66,538	420,000	\$	228,968,108	
		Annual Interest Ra	ite:			2.00%			
		Present Value of Ir	nitial Impact Fee	Fund Balance		\$ 131,981			
		Total Escalated Ex	pense for Entire	Period		\$ 228,968,108			
		Less Future Value	of Initial Impact	Fee Fund Balance	_	234,378			
		Sub-Total			_	\$ 228,733,730			
		Total Escalated Ve	ehicle Miles			66,538			
		Impact Fee For Se	ervice Area D			\$ 3,438			

Capital Improvement Plan for Impact Fees
Appendix E - Impact Fee Calculation Assumptions
Service Area D

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	Cost In Service Area (1)	Impact Fee Recoverable Cost ⁽²⁾	Debt Fu <u>Existing</u>	ınded ⁽³⁾ <u>Proposed</u>	Non-Debt <u>Funded⁽³⁾</u>	Impact Fee Recoverable Cost
UNNAMED 5 (3)	A-2, D-1	\$ 3,758,750	\$ 2,627,229	\$ -	\$ 1,313,615	\$ 1,313,615	\$ 2,627,229
UNNAMED 5 (4)	B-1, D-2	2,452,100	1,713,928	-	856,964	856,964	1,713,928
LAUD HOWELL PKWY (6)	D-3	39,497,100	27,607,032	-	13,803,516	13,803,516	27,607,032
LAUD HOWELL PKWY (7)	D-4	8,774,550	6,133,090	-	3,066,545	3,066,545	6,133,090
LAUD HOWELL PKWY (8)	D-5	2,220,027	1,551,718	438,978	314,534	798,207	1,551,718
TRINITY FALLS PKWY (1)	D-6	3,243,800	2,267,298	-	1,133,649	1,133,649	2,267,298
TRINITY FALLS PKWY (2)	D-7	650,300	454,536	-	227,268	227,268	454,536
TRINITY FALLS PKWY (3)	D-8	2,988,400	2,088,783	-	1,044,391	1,044,391	2,088,783
TRINITY FALLS PKWY (4)	D-9	8,418,050	5,883,910	-	2,941,955	2,941,955	5,883,910
TRINITY FALLS PKWY (5)	D-10	7,622,400	5,327,780	3,497,455	881,533	948,792	5,327,780
BLOOMDALE RD (7)	D-11	1,899,800	1,327,891	-	663,945	663,945	1,327,891
BLOOMDALE RD (8)	D-12	3,206,000	2,240,877	-	1,120,439	1,120,439	2,240,877
BLOOMDALE RD (9)	D-13	1,500,800	1,049,004		524,502	524,502	1,049,004
BLOOMDALE RD (10)	D-14	5,885,810	4,113,966	1,939,066	1,021,605	1,153,295	4,113,966
BLOOMDALE RD (11)	D-15	5,165,390	3,610,419	2,544,347	446,637	619,435	3,610,419
WILMETH RD (5)	D-16	5,495,525	3,841,172	-	1,920,586	1,920,586	3,841,172
WILMETH RD (6)	D-17	1,401,400	979,527	-	489,764 143,847	489,764	979,527 287,693
WILMETH RD (9)	D-18 D-19	411,600	287,693	-		143,847	,
WILMETH RD (8)	D-19 D-20	1,901,900 2,799,600	1,329,359 1,956,818	-	664,679 978,409	664,679 978,409	1,329,359 1,956,818
WILMETH RD (9) LAKE FOREST DR (1)	D-20 D-21	3,224,200	2,253,598	-	1,126,799	1,126,799	2,253,598
LAKE FOREST DR (3)	C-34, D-22	1,175,400	821,562	_	410,781	410,781	821,562
UNNAMED A (1)	D-23	17,435,950	12,187,093	_	6,093,547	6,093,547	12,187,093
UNNAMED A (2)	D-24	2,299,425	1,607,214	_	803,607	803,607	1,607,214
UNNAMED A (3)	D-25	938,000	655,628	_	327,814	327,814	655,628
UNNAMED A (4)	D-26	5,969,050	4,172,148	-	2,086,074	2,086,074	4,172,148
TAYLOR-BURK DR (1)	D-27	2,038,250	1,424,662	-	712,331	712,331	1,424,662
HARDIN BLVD (4)	D-28	1,633,700	1,141,897	-	570,948	570,948	1,141,897
HARDIN BLVD (5)	D-29	21,290,800	14,881,493	-	7,440,746	7,440,746	14,881,493
HARDIN BLVD (6)	D-30	2,051,000	1,433,574	-	716,787	716,787	1,433,574
HARDIN BLVD (7)	D-31	4,538,400	3,172,176	-	1,586,088	1,586,088	3,172,176
HARDIN BLVD (8)	D-32	1,070,400	748,171	-	374,085	374,085	748,171
HARDIN BLVD (9)	D-33	1,124,900	786,264	-	393,132	393,132	786,264
HARDIN BLVD (10)	D-34	2,904,000	2,029,790	-	1,014,895	1,014,895	2,029,790
COMMUNITY AVE (1)	D-35	2,164,400	1,512,837	-	756,418	756,418	1,512,837
COMMUNITY AVE (2)	D-36	1,960,000	1,369,969	-	684,984	684,984	1,369,969
COMMUNITY AVE (3)	D-37	1,174,600	821,003	-	410,501	410,501	821,003
Signal	3	150,000	104,845	-	52,422	52,422	104,845
Signal	6	150,000	104,845	-	52,422	52,422	104,845
Signal	7	300,000	209,689	-	104,845	104,845	209,689
Signal	8	300,000	209,689	-	104,845	104,845	209,689
Signal	9	225,000	157,267	-	78,633	78,633	157,267
Roundabout	10	100,000	69,896	-	34,948	34,948	69,896
Interchange Signals	11	300,000	209,689	-	104,845	104,845	209,689
Signal	16 17	75,000 300,000	52,422 209,689	-	26,211 104,845	26,211 104,845	52,422 209,689
Signal	18	300,000	209,689	-	104,845	104,845	209,689
Signal Interchange Signals	19	300,000	209,689	-	104,845	104,845	209,689
Roundabout	25	915,000	639,552	-	104,040	639,552	639,552
Roundabout	26 26	150,000	104,845	-	52,422	52,422	104,845
Roundabout	26 27	1,575,000	1,100,868	1,034,148	-	66,719	1,100,868
Roundabout	32	1,200,000	838,756	-,504,140	419,378	419,378	838,756
Under Construction	36	390,341	272,834	185,464	- 10,570	87,370	272,834
Impact Fee Study	50	11,692	11,692	-	5,846	5,846	11,692
Total		\$ 189,027,810		\$ 9,639,457		\$ 62,068,334	

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area D

<u>Year</u>	E	Eligible Debt <u>Service⁽¹⁾</u>	Annual Vehicle <u>Miles</u>	Eligible Debt Service per Vehicle Mile	Annual Growth in Vehicle Miles (Cumulative)	-	dit for Annual Ad Valorem <u>Revenues</u>
1	\$	1,214,998	606,072	\$ 2.00	4,130	\$	8,279
2		1,651,086	623,802	2.65	8,260		21,862
3		2,088,106	641,531	3.25	12,390		40,327
4		2,532,563	659,260	3.84	16,520		63,460
5		2,976,464	676,990	4.40	20,650		90,788
6		3,420,980	694,719	4.92	24,779		122,020
7		3,864,881	712,448	5.42	28,909		156,827
8		4,309,338	730,177	5.90	33,039		194,990
9		4,753,122	747,907	6.36	37,169		236,218
10		5,197,404	765,636	6.79	41,299		280,352
11		5,196,964	765,636	6.79	41,299		280,328
12		5,196,524	765,636	6.79	41,299		280,305
13		5,196,464	765,636	6.79	41,299		280,301
14		5,196,142	765,636	6.79	41,299		280,284
15		5,196,023	765,636	6.79	41,299		280,278
16		5,195,620	765,636	6.79	41,299		280,256
17		4,767,523	765,636	6.23	41,299		257,164
18		4,767,188	765,636	6.23	41,299		257,146
19		4,766,892	765,636	6.23	41,299		257,130
20		4,757,828	765,636	6.21	41,299		256,641
21		4,001,180	765,636	5.23	41,299		215,827
22		3,556,605	765,636	4.65	41,299		191,846
23		3,112,029	765,636	4.06	41,299		167,865
24		2,667,454	765,636	3.48	41,299		143,885
25		2,222,878	765,636	2.90	41,299		119,904
26		1,778,302	765,636	2.32	41,299		95,923
27		1,333,727	765,636	1.74	41,299		71,942
28		889,151	765,636	1.16	41,299		47,962
29		444,576	765,636	0.58	41,299		23,981
Total	\$	102,252,013				\$	5,004,090

2019 Vehicle Miles⁽²⁾

588,343

Ten Year Growth in Vehicle Miles in Service Area (3)

41,299 10 years 4,130

Annual Growth in Vehicle Miles

135,994

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

10 years 13,599

Annual Growth in Vehicle Miles

Credit Amount

\$ 5,004,090

⁽¹⁾ Appendix E - Service Area D, Page 2 Section II

⁽²⁾ Per Kimley-Horn Impact Fee Study

⁽³⁾ Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area E

#### I. General Assumptions

Annual Interest Rate on Deposits (1)
Annual Vehicle Mile Growth (2)
Existing Fund Balance (3)

2.00%
1,785
\$ 129,689

Portion of Projects Funded by Existing Debt⁽⁴⁾ Non-debt Funded Project Cost⁽⁵⁾ New Project Cost Funded Through New Debt⁽⁶⁾

\$ 122,934
18,276,732
18,078,145

Total Recoverable Project Cost (7)

#### \$ 36,477,811

#### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>
1	\$ 1,807,814	4.00%	20
2	1,807,814	4.00%	20
3	1,807,814	4.00%	20
4	1,807,814	4.00%	20
5	1,807,814	4.00%	20
6	1,807,814	4.00%	20
7	1,807,814	4.00%	20
8	1,807,814	4.00%	20
9	1,807,814	4.00%	20
10	1,807,814	4.00%	20

Total \$ 18,078,145

## III. Capital Expenditure Assumptions

<u>Year</u>	<u>Ex</u> j	Annual Capital <u>penditures⁽¹⁰⁾</u>
1	\$	1,827,673
2		2,430,278
3		3,032,883
4		3,635,488
5		3,635,488
6		3,635,488
7		3,635,488
8		3,635,488
9		3,635,488
10		3,635,488
11		1,807,814
12		1,205,210
13		602,605
Total	\$	36,354,877

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area E

#### I. New Debt Service Detail

<u>Year</u>	Series <u>1</u>	Series	Series <u>3</u>	Series <u>4</u>	Series <u>5</u>	Series <u>6</u>	Series <u>7</u>	Series <u>8</u>	Series <u>9</u>	Series 10	Total Annual New Debt <u>Service</u>
1	\$ 133,022	\$ -	\$ -	\$ - 9	- \$	- \$	- 9	\$ - \$	\$ - \$		\$ 133,022
2	133,022	133,022	-	-	-	-	-	-	-	-	266,044
3	133,022	133,022	133,022	-	-	-	-	-	-	-	399,066
4	133,022	133,022	133,022	133,022	-	-	-	-	-	-	532,089
5	133,022	133,022	133,022	133,022	133,022	-	-	-	-	-	665,111
6	133,022	133,022	133,022	133,022	133,022	133,022	-	-	-	-	798,133
7	133,022	133,022	133,022	133,022	133,022	133,022	133,022	-	-	-	931,155
8	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	-	-	1,064,177
9	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	-	1,197,199
10	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
11	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
12	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
13	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
14	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
15	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
16	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
17	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
18	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
19	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
20	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,330,222
21	-	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,197,199
22	-	-	133,022	133,022	133,022	133,022	133,022	133,022	133,022	133,022	1,064,177
23	-	-	-	133,022	133,022	133,022	133,022	133,022	133,022	133,022	931,155
24	-	-	-	-	133,022	133,022	133,022	133,022	133,022	133,022	798,133
25	-	-	-	-	-	133,022	133,022	133,022	133,022	133,022	665,111
26	-	-	-	-	-	-	133,022	133,022	133,022	133,022	532,089
27	-	-	-	-	-	-	-	133,022	133,022	133,022	399,066
28	-	-	-	-	-	-	-	-	133,022	133,022	266,044
29					· · · · · · ·					133,022	133,022
	\$ 2,660,443	\$ 2,660,443	\$ 2,660,443	\$ 2,660,443	\$ 2,660,443 \$	2,660,443 \$	2,660,443	\$ 2,660,443	\$ 2,660,443 \$	2,660,443	\$ 26,604,431

### II. Summary of Annual Expenses

<u>Year</u>	New Annual Debt Service ⁽¹⁾	Annual Capital <u>Expenditures⁽²⁾</u>	Annual Bond <u>Proceeds⁽²⁾</u>	Existing Annual Debt Service ⁽³⁾	Annual <u>Credit⁽⁴⁾</u>	Total Expense
1	\$ 133,022	\$ 1,827,673	\$ (1,807,814)	\$ 9,832	\$ (421)	\$ 162,292
2	266,044	2,430,278	(1,807,814)	9,838	(1,578)	896,768
3	399,066	3,032,883	(1,807,814)	9,830	(3,412)	1,630,553
4	532,089	3,635,488	(1,807,814)	9,838	(5,868)	2,363,732
5	665,111	3,635,488	(1,807,814)	9,832	(8,896)	2,493,721
6	798,133	3,635,488	(1,807,814)	9,841	(12,452)	2,623,195
7	931,155	3,635,488	(1,807,814)	9,836	(16,499)	2,752,165
8	1,064,177	3,635,488	(1,807,814)	9,843	(20,999)	2,880,695
9	1,197,199	3,635,488	(1,807,814)	9,835	(25,920)	3,008,788
10	1,330,222	3,635,488	(1,807,814)	9,838	(31,233)	3,136,500
11	1,330,222	1,807,814	-	9,838	(31,233)	3,116,641
12	1,330,222	1,205,210	-	9,834	(31,233)	2,514,032
13	1,330,222	602,605	-	9,839	(31,233)	1,911,432
14	1,330,222	-	-	9,838	(31,233)	1,308,826
15	1,330,222	-	-	9,843	(31,233)	1,308,831
16	1,330,222	-	-	9,840	(31,233)	1,308,828
17	1,330,222	-	-	-	(31,004)	1,299,218
18	1,330,222	-	-	-	(31,004)	1,299,218
19	1,330,222	-	-	-	(31,004)	1,299,218
20	1,330,222	-	-	-	(31,004)	1,299,218
21	1,197,199	-	-	-	(27,904)	1,169,296
22	1,064,177	-	-	-	(24,803)	1,039,374
23	931,155	-	-	-	(21,703)	909,452
24	798,133	-	-	-	(18,602)	779,531
25	665,111	-	-	-	(15,502)	649,609
26	532,089	-	-	-	(12,402)	519,687
27	399,066	-	-	-	(9,301)	389,765
28	266,044	-	-	-	(6,201)	259,844
29	133,022	-	-	-	(3,100)	129,922
	\$ 26,604,431	\$ 36,354,877	\$ (18,078,145)	\$ 157,395	\$ (578,212)	\$ 44,460,346

⁽¹⁾ Appendix E - Service Area E, Page 2 Section I
(2) Appendix E - Service Area E, Page 1
(3) Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area E, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area E

<u>Year</u>	Impact Vehicle <u>Fee Miles</u>					Annual Expenses	<u> </u>	Sub-Total	Accumulated Interest		Estimated Fund <u>Balance</u>	
Initial												129,689
1	\$	2,202	1,785	\$	3,929,433	\$	162,292	\$	3,767,141	\$ 40,265		3,937,096
2		2,202	1,785		3,929,433		896,768		3,032,666	109,069		7,078,830
3		2,202	1,785		3,929,433		1,630,553		2,298,881	164,565		9,542,276
4		2,202	1,785		3,929,433		2,363,732		1,565,702	206,503		11,314,480
5		2,202	1,785		3,929,433		2,493,721		1,435,713	240,647		12,990,840
6		2,202	1,785		3,929,433		2,623,195		1,306,239	272,879		14,569,958
7		2,202	1,785		3,929,433		2,752,165		1,177,268	303,172		16,050,398
8		2,202	1,785		3,929,433		2,880,695		1,048,739	331,495		17,430,632
9		2,202	1,785		3,929,433		3,008,788		920,646	357,819		18,709,097
10		2,202	1,785		3,929,433		3,136,500		792,934	382,111		19,884,142
11		-	-		-		3,116,641		(3,116,641)	366,516		17,134,017
12		-	-		-		2,514,032		(2,514,032)	317,540		14,937,525
13		-	-		-		1,911,432		(1,911,432)	279,636		13,305,729
14		-	-		-		1,308,826		(1,308,826)	253,026		12,249,930
15		-	-		-		1,308,831		(1,308,831)	231,910		11,173,009
16		-	-		-		1,308,828		(1,308,828)	210,372		10,074,552
17		-	-		-		1,299,218		(1,299,218)	188,499		8,963,834
18		-	-		-		1,299,218		(1,299,218)	166,285		7,830,901
19		-	-		-		1,299,218		(1,299,218)	143,626		6,675,309
20		-	-		-		1,299,218		(1,299,218)	120,514		5,496,606
21		-	-		-		1,169,296		(1,169,296)	98,239		4,425,549
22		-	-		-		1,039,374		(1,039,374)	78,117		3,464,292
23		-	-		-		909,452		(909,452)	60,191		2,615,031
24		-	-		-		779,531		(779,531)	44,505		1,880,006
25		-	-		-		649,609		(649,609)	31,104		1,261,501
26		-	-		-		519,687		(519,687)	20,033		761,847
27		-	-		-		389,765		(389,765)	11,339		383,422
28		-	-		-		259,844		(259,844)	5,070		128,648
29		-	-		<u> </u>		129,922		(129,922)	1,274		-
				\$	39,294,334	\$	44,460,346			\$ 5,036,323		

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area E

	Number of	Interest	Recovery					
	Years to	Rate	Fee	Annual Ve	hicle Miles	Annual	Ехр	ense
<u>Year</u>	<b>End of Period</b>	<u>Factor</u>	Factor	<u>Actual</u>	<b>Escalated</b>	<u>Actual</u>	-	<b>Escalated</b>
				<u></u> -				
1	29	1.7584	1.0000	1,785	3,138	\$ 162,292	\$	285,380
2	28	1.7240	1.0000	1,785	3,076	896,768		1,545,987
3	27	1.6902	1.0000	1,785	3,016	1,630,553		2,755,883
4	26	1.6570	1.0000	1,785	2,957	2,363,732		3,916,732
5	25	1.6245	1.0000	1,785	2,899	2,493,721		4,051,103
6	24	1.5927	1.0000	1,785	2,842	2,623,195		4,177,879
7	23	1.5614	1.0000	1,785	2,786	2,752,165		4,297,339
8	22	1.5308	1.0000	1,785	2,732	2,880,695		4,409,834
9	21	1.5008	1.0000	1,785	2,678	3,008,788		4,515,609
10	20	1.4714	1.0000	1,785	2,626	3,136,500		4,614,981
11	19	1.4425	1.0000	-	-	3,116,641		4,495,844
12	18	1.4142	1.0000	-	-	2,514,032		3,555,455
13	17	1.3865	1.0000	-	-	1,911,432		2,650,226
14	16	1.3593	1.0000	-	-	1,308,826		1,779,122
15	15	1.3327	1.0000	-	-	1,308,831		1,744,245
16	14	1.3065	1.0000	-	-	1,308,828		1,710,040
17	13	1.2809	1.0000	-	-	1,299,218		1,664,199
18	12	1.2558	1.0000	-	-	1,299,218		1,631,568
19	11	1.2312	1.0000	-	_	1,299,218		1,599,576
20	10	1.2070	1.0000	-	-	1,299,218		1,568,212
21	9	1.1834	1.0000	_	_	1,169,296		1,383,717
22	8	1.1602	1.0000	-		1,039,374		1,205,853
23	7	1.1374	1.0000	-	_	909,452		1,034,433
24	6	1.1151	1.0000	_	-	779,531		869,271
25	5	1.0933	1.0000	_	_	649,609		710,189
26	4	1.0718	1.0000	-	-	519,687		557,011
27	3	1.0508	1.0000	_	_	389,765		409,567
28	2	1.0302	1.0000	_	_	259,844		267,691
29	1	1.0100	1.0000	_	_	129,922		131,221
				_	28,750	,	\$	63,538,166
					,		•	,,
		Annual Interest Ra	te:			2.00%		
		Present Value of Ir	nitial Impact Fee	Fund Balance		\$ 129,689		
		Total Escalated Ex	pense for Entire	Period		\$ 63,538,166		
		Less Future Value	of Initial Impact F	Fee Fund Balance		230,308	_	
		Sub-Total				\$ 63,307,859		
		Total Escalated Ve	hicle Miles			28,750		
		Impact Fee For Se	ervice Area E			\$ 2,202		

Capital Improvement Plan for Impact Fees

Appendix E - Impact Fee Calculation Assumptions

Service Area E

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	Se	Cost In	Impact Fee				Funded ⁽³⁾ <u>Proposed</u>			Non-Debt Funded ⁽³⁾		Impact Fee
<del></del>													
BLOOMDALE RD (12)	E-1	\$	955,200			\$	-	\$ 2	36,244	\$	236,244	\$	472,488
BLOOMDALE RD (13)	E-2		3,361,400	1,662,7	'10		-	8	31,355		831,355		1,662,710
WILMETH RD (10)	E-3		1,935,600	957,4			-		78,720		478,720		957,441
WILMETH RD (11)	E-4		2,608,200	1,290,	41		-	6	45,070		645,070		1,290,141
WILMETH RD (12)	E-5		5,068,500	2,507,	23		-	1,2	53,562		1,253,562		2,507,123
WILMETH RD (13)	E-6		2,804,200	1,387,0	92		-	6	93,546		693,546		1,387,092
WILMETH RD (14)	E-7		1,708,700	845,2	205		-	4:	22,603		422,603		845,205
WILMETH RD (15)	E-8		1,614,900	798,8	807		-	3	99,404		399,404		798,807
REDBUD BLVD (1)	E-9		650,000	321,	21		122,934		-		198,587		321,521
REDBUD BLVD (2)	E-10		852,600	421,7	37		-	2	10,868		210,868		421,737
LAUD HOWELL PKWY (9)	E-11		1,954,750	966,9	913		-	4	83,457		483,457		966,913
LAUD HOWELL PKWY (10)	E-12		1,876,700	928,3	806		-	4	64,153		464,153		928,306
LAUD HOWELL PKWY (11)	E-13		861,000	425,8	392		-	2	12,946		212,946		425,892
STATE HIGHWAY 5 (1)	E-14		347,550	171,9	15		-		85,957		85,957		171,915
STATE HIGHWAY 5 (2)	E-15		13,994,400	6,922,3	802		-	3,4	61,151		3,461,151		6,922,302
AIRPORT DR (1)	E-16		9,379,050	4,639,3	328		-	2,3	19,664		2,319,664		4,639,328
AIRPORT DR (2)	E-17		6,582,850	3,256,	94		-	1,6	28,097		1,628,097		3,256,194
AIRPORT DR (3)	E-18		3,648,400	1,804,6	74		-	9	02,337		902,337		1,804,674
AIRPORT DR (4)	E-19		8,952,800	4,428,4	85		-	2,2	14,242		2,214,242		4,428,485
UNNAMED C (1)	E-20		986,400	487,9	21		-	2	43,960		243,960		487,921
UNNAMED C (2)	E-21		1,403,150	694,0	65		-	3-	47,033		347,033		694,065
Interchange Signals	11		300,000	148,3	894		-		74,197		74,197		148,394
Interchange Signals	19		300,000	148,3	394		-		74,197		74,197		148,394
Signal	20		300,000	148,3	394		-		74,197		74,197		148,394
Signal	21		300,000	148,3	394		-		74,197		74,197		148,394
Signal Mod	22		150,000	74,	97		-	:	37,099		37,099		74,197
Signal	28		300,000	148,3	394		-		74,197		74,197		148,394
Signal Mod	29		150,000	74,	97		-	:	37,099		37,099		74,197
Signal	30		150,000	74,	97		-	:	37,099		37,099		74,197
Signal	31		150,000	74,	97		-	:	37,099		37,099		74,197
Signal Mod	41		75,000	37,0	99		-		18,549		18,549		37,099
Impact Fee Study			11,692	11,6	92		-		5,846		5,846		11,692
Total		\$	73,733,042	\$ 36,477,	811	\$	122,934	\$ 18,0	78,145	\$	18,276,732	\$	36,477,811

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area E

<u>Year</u>	Eligible Debt <u>Service⁽¹⁾</u>		Annual Vehicle <u>Miles</u>		Eligible Debt Service per <u>Vehicle Mile</u>	Annual Growth in Vehicle Miles (Cumulative)	Credit for Annua Ad Valorem <u>Revenues</u>		
1	\$	142,854	606,072	\$	0.24	1,785	\$	421	
2	•	275,883	623,802	•	0.44	3,569	*	1,578	
3		408,897	641,531		0.64	5,354		3,412	
4		541,926	659,260		0.82	7,138		5,868	
5		674,943	676,990		1.00	8,923		8,896	
6		807,974	694,719		1.16	10,707		12,452	
7		940,991	712,448		1.32	12,492		16,499	
8		1,074,020	730,177		1.47	14,276		20,999	
9		1,207,034	747,907		1.61	16,061		25,920	
10		1,340,060	765,636		1.75	17,845		31,233	
11		1,340,060	765,636		1.75	17,845		31,233	
12		1,340,056	765,636		1.75	17,845		31,233	
13		1,340,060	765,636		1.75	17,845		31,233	
14		1,340,059	765,636		1.75	17,845		31,233	
15		1,340,065	765,636		1.75	17,845		31,233	
16		1,340,062	765,636		1.75	17,845		31,233	
17		1,330,222	765,636		1.74	17,845		31,004	
18		1,330,222	765,636		1.74	17,845		31,004	
19		1,330,222	765,636		1.74	17,845		31,004	
20		1,330,222	765,636		1.74	17,845		31,004	
21		1,197,199	765,636		1.56	17,845		27,904	
22		1,064,177	765,636		1.39	17,845		24,803	
23		931,155	765,636		1.22	17,845		21,703	
24		798,133	765,636		1.04	17,845		18,602	
25		665,111	765,636		0.87	17,845		15,502	
26		532,089	765,636		0.69	17,845		12,402	
27		399,066	765,636		0.52	17,845		9,301	
28		266,044	765,636		0.35	17,845		6,201	
29		133,022	765,636		0.17	17,845		3,100	
Total	\$	26,761,826					\$	578,212	

2019 Vehicle Miles (2)

Ten Year Growth in Vehicle Miles in Service Area (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

⁽¹⁾ Appendix E - Service Area E, Page 2 Section II

⁽²⁾ Per Kimley-Horn Impact Fee Study

⁽³⁾ Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area G

#### I. General Assumptions

Annual Interest Rate on Deposits ⁽¹⁾	2.00
Annual Vehicle Mile Growth ⁽²⁾	77
Existing Fund Balance ⁽³⁾	\$ 448,08

Portion of Projects Funded by Existing Debt⁽⁴⁾ Non-debt Funded Project Cost⁽⁵⁾ New Project Cost Funded Through New Debt⁶⁾ Total Recoverable Project Cost⁽⁷⁾

\$ 2,373,984
2,914,970
2,752,700
•

8,041,653

#### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>
1	\$ 275,270	4.00%	20
2	275,270	4.00%	20
3	275,270	4.00%	20
4	275,270	4.00%	20
5	275,270	4.00%	20
6	275,270	4.00%	20
7	275,270	4.00%	20
8	275,270	4.00%	20
9	275,270	4.00%	20
10	275,270	4.00%	20
Total	¢ 2.752.700		•

Total 2.752.700

#### III. Capital Expenditure Assumptions

<u>Year</u>	Exp	Annual Capital enditures ⁽¹⁰⁾
1	\$	291,497
2		383,254
3		475,010
4		566,767
5		566,767
6		566,767
7		566,767
8		566,767
9		566,767
10		566,767
11		275,270
12		183,513
13		91,757
Total	\$	5,667,669

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- (5) This assumes 50% of new project costs funded through sources other than debt, unless specified otherwise
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area G

#### I. New Debt Service Detail

Year	Series		Series	Series <u>3</u>	Series <u>4</u>	Series <u>5</u>		Series	s	Series <u>7</u>	Series	S	eries <u>9</u>	Series	N	Total Annual lew Debt Service
1	\$ 20,	255	\$ -	\$ -	\$ -	\$ -	\$	-	\$	-	\$ -	\$	-	\$ -	\$	20,255
2	20,	255	20,255	-	-	-		-		-	-		-	-		40,510
3	20,		20,255	20,255	-	-		-		-	-		-	-		60,765
4	20,	255	20,255	20,255	20,255	-		-		-	-		-	-		81,019
5	20,	255	20,255	20,255	20,255	20,25	5	-		-	-		-	-		101,274
6	20,	255	20,255	20,255	20,255	20,25	5	20,255		-	-		-	-		121,529
7	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	-		-	-		141,784
8	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		-	-		162,039
9	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	-		182,294
10	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
11	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
12	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
13	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
14	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
15	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
16	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
17	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
18	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
19	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
20	20,	255	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		202,548
21		-	20,255	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		182,294
22		-	-	20,255	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		162,039
23		-	-	-	20,255	20,25	5	20,255		20,255	20,255		20,255	20,255		141,784
24		-	-	-	-	20,25	5	20,255		20,255	20,255		20,255	20,255		121,529
25		-	-	-	-	-		20,255		20,255	20,255		20,255	20,255		101,274
26		-	-	-	-	-		-		20,255	20,255		20,255	20,255		81,019
27		-	-	-	-	-		-		-	20,255		20,255	20,255		60,765
28		-	-	-	-	-		-		-	-		20,255	20,255		40,510
29		-	-	-	-	-		-		-	-		-	20,255		20,255
-	\$ 405,	097	\$ 405,097	\$ 405,097	\$ 405,097	\$ 405,09	7 \$	405,097	\$	405,097	\$ 405,097	\$	405,097	\$ 405,097	\$	4,050,969

#### II. Summary of Annual Expenses

<u>Year</u>	New Annual Debt <u>Service⁽¹⁾</u>			Annual Capital penditures ⁽²⁾	Ē	Annual Bond Proceeds ⁽²⁾	Existing Annual Debt Service ⁽³⁾	Annual Credit ⁽⁴⁾	Total <u>Expense</u>		
1	\$	20,255	\$	291,497	\$	(275,270)	\$ 182,760	\$ (259)	\$	218,983	
2		40,510		383,254		(275,270)	182,765	(554)		330,704	
3		60,765		475,010		(275,270)	182,759	(882)		442,382	
4		81,019		566,767		(275,270)	182,764	(1,239)		554,041	
5		101,274		566,767		(275,270)	182,760	(1,624)		573,908	
6		121,529		566,767		(275,270)	182,766	(2,035)		593,758	
7		141,784		566,767		(275,270)	182,763	(2,469)		613,575	
8		162,039		566,767		(275,270)	182,768	(2,925)		633,379	
9		182,294		566,767		(275,270)	182,762	(3,401)		653,152	
10		202,548		566,767		(275,270)	182,765	(3,896)		672,914	
11		202,548		275,270		-	182,765	(3,896)		656,687	
12		202,548		183,513		-	182,762	(3,896)		564,927	
13		202,548		91,757		-	182,765	(3,896)		473,174	
14		202,548		-		-	182,764	(3,896)		381,416	
15		202,548		-		-	182,768	(3,896)		381,420	
16		202,548		-		-	182,766	(3,896)		381,418	
17		202,548		-		-	176,117	(3,829)		374,836	
18		202,548		-		-	176,117	(3,829)		374,836	
19		202,548		-		-	176,117	(3,829)		374,836	
20		202,548		-		-	176,117	(3,829)		374,836	
21		182,294		-		-	-	(1,843)		180,450	
22		162,039		-		-	-	(1,639)		160,400	
23		141,784		-		-	-	(1,434)		140,350	
24		121,529		-		-	-	(1,229)		120,300	
25		101,274		-		-	-	(1,024)		100,250	
26		81,019		-		-	-	(819)		80,200	
27		60,765		-		-	-	(614)		60,150	
28		40,510		-		-	-	(410)		40,100	
29		20,255		-		-	-	(205)		20,050	
	\$	4,050,969	\$	5,667,669	\$	(2,752,700)	\$ 3,628,688	\$ (67,194)	\$ 10	,527,433	

⁽¹⁾ Appendix E - Service Area G, Page 2 Section I
(2) Appendix E - Service Area G, Page 1
(3) Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area G, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area G

<u>Year</u>	Impact <u>Fee</u>	Vehicle <u>Miles</u>	Impact Fee <u>Revenue</u>		Annual <u>Expenses</u>		<u>Sub-Total</u>		Accumulated <u>Interest</u>		Estimated Fund <u>Balance</u>
Initial											\$ 448,086
1	\$ 1,155	774	\$	894,233	\$	218,983	\$	675,250	\$	15,714	1,139,050
2	1,155	774		894,233		330,704		563,529		28,416	1,730,996
3	1,155	774		894,233		442,382		451,850		39,138	2,221,985
4	1,155	774		894,233		554,041		340,191		47,842	2,610,018
5	1,155	774		894,233		573,908		320,325		55,404	2,985,746
6	1,155	774		894,233		593,758		300,475		62,720	3,348,941
7	1,155	774		894,233		613,575		280,658		69,785	3,699,384
8	1,155	774		894,233		633,379		260,854		76,596	4,036,835
9	1,155	774		894,233		653,152		241,081		83,148	4,361,063
10	1,155	774		894,233		672,914		221,319		89,434	4,671,817
11	-	-		-		656,687		(656,687)		86,869	4,101,999
12	-	-		-		564,927		(564,927)		76,391	3,613,463
13	-	-		-		473,174		(473,174)		67,538	3,207,826
14	-	-		-		381,416		(381,416)		60,342	2,886,752
15	-	-		-		381,420		(381,420)		53,921	2,559,253
16	-	-		-		381,418		(381,418)		47,371	2,225,206
17	-	-		-		374,836		(374,836)		40,756	1,891,126
18	-	-		-		374,836		(374,836)		34,074	1,550,364
19	-	-		-		374,836		(374,836)		27,259	1,202,786
20	-	-		-		374,836		(374,836)		20,307	848,258
21	-	-		-		180,450		(180,450)		15,161	682,968
22	-	-		-		160,400		(160,400)		12,055	534,623
23	-	-		-		140,350		(140,350)		9,289	403,562
24	-	-		-		120,300		(120,300)		6,868	290,130
25	-	-		-		100,250		(100,250)		4,800	194,680
26	-	-		-		80,200		(80,200)		3,092	117,571
27	-	-		-		60,150		(60,150)		1,750	59,171
28	-	-		-		40,100		(40,100)		782	19,853
29	-	-				20,050		(20,050)		197	-
			\$	8,942,328	\$ 1	10,527,433			\$	1,137,019	

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area G

	Number of Years to	Interest Rate					Annual	Ехр	pense	
<u>Year</u>	<b>End of Period</b>	<u>Factor</u>	<u>Factor</u>	<u>Actual</u>	<b>Escalated</b>		<u>Actual</u>		<u>Escalated</u>	
1	29	1.7584	1.0000	774	1,361	\$	218,983	\$	385,067	
2	28	1.7240	1.0000	774	1,335	Ψ	330,704	Ψ	570,118	
3	27	1.6902	1.0000	774	1,309		442,382		747,693	
4	26	1.6570	1.0000	774	1,283		554,041		918,053	
5	25	1.6245	1.0000	774	1,258		573,908		932,325	
6	24	1.5927	1.0000	774	1,233		593,758		945,659	
7	23	1.5614	1.0000	774	1,209		613,575		958,060	
8	22	1.5308	1.0000	774	1,185		633,379		969,591	
9	21	1.5008	1.0000	774	1,162		653,152		980,255	
10	20	1.4714	1.0000	774	1,139		672,914		990,111	
11	19	1.4425	1.0000	-	-		656,687		947,289	
12	18	1.4142	1.0000	-	-		564,927		798,945	
13	17	1.3865	1.0000	-	-		473,174		656,062	
14	16	1.3593	1.0000	-	-		381,416		518,470	
15	15	1.3327	1.0000	-	-		381,420		508,308	
16	14	1.3065	1.0000	-	-		381,418		498,339	
17	13	1.2809	1.0000	-	-		374,836		480,137	
18	12	1.2558	1.0000	-	-		374,836		470,722	
19	11	1.2312	1.0000	-	-		374,836		461,492	
20	10	1.2070	1.0000	-	-		374,836		452,444	
21	9	1.1834	1.0000	-	-		180,450		213,541	
22	8	1.1602	1.0000	-	-		160,400		186,092	
23	7	1.1374	1.0000	-	-		140,350		159,638	
24	6	1.1151	1.0000	-	-		120,300		134,149	
25	5	1.0933	1.0000	-	-		100,250		109,599	
26	4	1.0718	1.0000	-	-		80,200		85,960	
27	3	1.0508	1.0000	-	-		60,150		63,206	
28	2	1.0302	1.0000	-	-		40,100		41,311	
29	1	1.0100	1.0000	-	-		20,050		20,251	
					12,473			\$	15,202,888	
		Annual Interest Ra	ite:				2.00%			
			\$	448,086						
		Total Escalated Ex	pense for Entire	Period		\$	15,202,888			
	Total Escalated Expense for Entire Period  Less Future Value of Initial Impact Fee Fund Balance					*	795,731			
		•	\$	14,407,157	•					
	Total Escalated Vehicle Miles						12,473	•		
			\$	1,155						

Capital Improvement Plan for Impact Fees
Appendix E - Impact Fee Calculation Assumptions
Service Area G

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	Cost In Service Area (1)	Impact Fee Recoverable Cost ⁽²⁾	Debt Fund Existing	ded ⁽³⁾ <u>Proposed</u>	Non-Debt Funded ⁽³⁾	Impact Fee Recoverable Cost	
VIRGINIA PKWY (1)	G-1	\$ 2,158,80	573,853	\$ - \$	286,926	\$ 286,926	\$ 573,853	
VIRGINIA PKWY (2)	G-2	397,200	105,584		52,792	52,792	105,584	
VIRGINIA PKWY (3)	G-3	456,598	121,373	32,536	44,419	44,419	121,373	
VIRGINIA PKWY (4)	G-4	1,661,860	441,757	116,074	162,841	162,841	441,757	
VIRGINIA PKWY (5)	G-5	1,182,000	314,200	-	157,100	157,100	314,200	
VIRGINIA PKWY (6)	G-6	392,400	104,308	-	52,154	52,154	104,308	
WESTRIDGE BLVD (1)	G-7	372,600	99,045	-	49,522	49,522	99,045	
WESTRIDGE BLVD (2)	G-8	2,931,600	779,279	-	389,639	389,639	779,279	
WESTRIDGE BLVD (3)	G-9	596,400	158,535	-	79,268	79,268	158,535	
ELDORADO PKWY (1)	H-1, G-10	2,601,000	691,398	-	345,699	345,699	691,398	
COIT RD (1)	G-11	1,840,800	489,322	-	244,661	244,661	489,322	
COIT RD (2)	G-12	592,200	157,419	-	78,709	78,709	157,419	
INDEPENDENCE PKWY (1)	G-13	951,600	252,955	-	126,477	126,477	252,955	
INDEPENDENCE PKWY (2)	G-14	3,666,000	974,497	-	487,248	487,248	974,497	
CUSTER RD (4)	G-15	3,260,94	866,825	826,396	-	40,430	866,825	
CUSTER RD (5)	G-16	1,476,398	392,456	374,152	-	18,305	392,456	
RIDGE RD (8)	G-17, I-8	275,407	73,209	11,207	-	62,002	73,209	
Signal Mod	33	75,000	19,937	-	9,968	9,968	19,937	
Signal	34	150,000	39,873	-	19,937	19,937	39,873	
Signal	37	300,000	79,746	-	39,873	39,873	79,746	
Signal	38	171,500	45,588	45,588	-	-	45,588	
Signal	43	40,000	10,633	10,633	-	-	10,633	
Under Construction	44	195,17	51,880	35,267	-	16,614	51,880	
Signal	47	300,000	79,746	-	39,873	39,873	79,746	
Under Construction	48	292,756	77,820	52,900	-	24,921	77,820	
Roundabout	49	1,950,000	518,349	518,349	-	-	518,349	
Roundabout	50	1,320,000	350,883	350,883	-	-	350,883	
Signal	55	300,000	79,746	-	39,873	39,873	79,746	
Signal	56	150,000	39,873	-	19,937	19,937	39,873	
Signal	57	150,000	39,873	-	19,937	19,937	39,873	
Impact Fee Study		11,692		-	5,846	5,846	11,692	
Total		\$ 30,219,929	8,041,653	\$ \$ 2,373,984 \$	2,752,700	\$ 2,914,970	\$ 8,041,653	

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area G

<u>Year</u>	Eligible Debt <u>Service⁽¹⁾</u>		Annual Vehicle <u>Miles</u>	Eligible Debt Service per Vehicle Mile	Annual Growth in Vehicle Miles (Cumulative)	edit for Annual Ad Valorem <u>Revenues</u>
1	\$	203,015	606,072	\$ 0.33	774	\$ 259
2		223,274	623,802	0.36	1,548	554
3		243,524	641,531	0.38	2,323	882
4		263,783	659,260	0.40	3,097	1,239
5		284,035	676,990	0.42	3,871	1,624
6		304,295	694,719	0.44	4,645	2,035
7		324,547	712,448	0.46	5,419	2,469
8		344,807	730,177	0.47	6,194	2,925
9		365,056	747,907	0.49	6,968	3,401
10		385,313	765,636	0.50	7,742	3,896
11		385,313	765,636	0.50	7,742	3,896
12		385,310	765,636	0.50	7,742	3,896
13		385,313	765,636	0.50	7,742	3,896
14		385,313	765,636	0.50	7,742	3,896
15		385,316	765,636	0.50	7,742	3,896
16		385,314	765,636	0.50	7,742	3,896
17		378,665	765,636	0.49	7,742	3,829
18		378,665	765,636	0.49	7,742	3,829
19		378,665	765,636	0.49	7,742	3,829
20		378,665	765,636	0.49	7,742	3,829
21		182,294	765,636	0.24	7,742	1,843
22		162,039	765,636	0.21	7,742	1,639
23		141,784	765,636	0.19	7,742	1,434
24		121,529	765,636	0.16	7,742	1,229
25		101,274	765,636	0.13	7,742	1,024
26		81,019	765,636	0.11	7,742	819
27		60,765	765,636	0.08	7,742	614
28		40,510	765,636	0.05	7,742	410
29		20,255	765,636	0.03	7,742	 205
Total	\$	7,679,657				\$ 67,194

2019 Vehicle Miles (2) 588,343

Ten Year Growth in Vehicle Miles in Service Area (3) 7,742

Annual Growth in Vehicle Miles 774

Ten Year Growth in Vehicle Miles In Other Service Areas (3) 169,551

Annual Growth in Vehicle Miles 16,955

Credit Amount

67,194

⁽¹⁾ Appendix E - Service Area G, Page 2 Section II

⁽²⁾ Per Kimley-Horn Impact Fee Study

⁽³⁾ Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area H

### I. General Assumptions

Annual Interest Rate on Deposits (1)
Annual Vehicle Mile Growth (2)
Existing Fund Balance (3)

2.00%
3,132
\$ 293,933

Portion of Projects Funded by Existing Debt ⁽⁴⁾ Non-debt Funded Project Cost ⁽⁵⁾ New Project Cost Funded Through New Debt ⁽⁶⁾ Total Recoverable Project Cost ⁽⁷⁾

\$ 3,596,908
3,387,483
3,229,433

10,213,823

### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>
1	\$ 322,943	4.00%	20
2	322,943	4.00%	20
3	322,943	4.00%	20
4	322,943	4.00%	20
5	322,943	4.00%	20
6	322,943	4.00%	20
7	322,943	4.00%	20
8	322,943	4.00%	20
9	322,943	4.00%	20
10	322,943	4.00%	20
Total	\$ 3,229,433		

### III. Capital Expenditure Assumptions

<u>Year</u>	<u>Exp</u>	Annual Capital enditures ⁽¹⁰⁾
1	\$	338,748
2		446,396
3		554,044
4		661,692
5		661,692
6		661,692
7		661,692
8		661,692
9		661,692
10		661,692
11		322,943
12		215,296
13		107,648
Total	\$	6,616,916

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Total

### City of McKinney - 2019 Roadway Impact Fee Study

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area H

#### I. New Debt Service Detail

Year	Series <u>1</u>	Series	Series	Series	Series <u>5</u>	Series	Series	Series <u>8</u>	Series	Series	Annual New Debt Service
1	\$ 23,763	\$ -	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- 9	-,
2	23,763	23,763	-	-	-	-	-	-	-	-	47,525
3	23,763	23,763	23,763	-	-	-	-	-	-	-	71,288
4	23,763	23,763	23,763	23,763	-	-	-	-	-	-	95,051
5	23,763	23,763	23,763	23,763	23,763	-	-	-	-	-	118,814
6	23,763	23,763	23,763	23,763	23,763	23,763	-	-	-	-	142,576
7	23,763	23,763	23,763	23,763	23,763	23,763	23,763	-	-	-	166,339
8	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	-	-	190,102
9	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763		213,865
10	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
11	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
12	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
13	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
14	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
15	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
16	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
17	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
18	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
19	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
20	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	237,627
21	-	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	213,865
22	-	-	23,763	23,763	23,763	23,763	23,763	23,763	23,763	23,763	190,102
23	-	-	-	23,763	23,763	23,763	23,763	23,763	23,763	23,763	166,339
24	-	-	-	-	23,763	23,763	23,763	23,763	23,763	23,763	142,576
25	-	-	-	-	-	23,763	23,763	23,763	23,763	23,763	118,814
26	-	-	-	-	-	-	23,763	23,763	23,763	23,763	95,051
27	-	-	-	-	-	-	-	23,763	23,763	23,763	71,288
28	-	-	-	-	-	-	-	-	23,763	23,763	47,525
29				-			-		-	23,763	23,763
	\$ 475,255	\$ 475,255	\$ 475,255 \$	475,255 \$	475,255 \$	475,255 \$	475,255 \$	475,255 \$	475,255 \$	475,255	4,752,546

### II. Summary of Annual Expenses

		New Annual		Annual		Annual	Existing Annual		
		Debt		Capital		Bond	Debt	Annual	Total
Year	•	Service ⁽¹⁾	Fxr	enditures ⁽²⁾	Р	roceeds ⁽²⁾	Service ⁽³⁾	Credit ⁽⁴⁾	Expense
<u>r cur</u>	2	OCI VIOC		ociiditaico	-	rooccus	OCI VIOC	Orcuit	Expense
1	\$	23,763	\$	338,748	\$	(322,943)	\$ 484,617	\$ (2,627) \$	521,557
2		47,525		446,396		(322,943)	256,422	(3,053)	424,347
3		71,288		554,044		(322,943)	255,033	(4,780)	552,642
4		95,051		661,692		(322,943)	252,784	(6,611)	679,973
5		118,814		661,692		(322,943)	302,645	(9,750)	750,457
6		142,576		661,692		(322,943)	221,614	(9,853)	693,086
7		166,339		661,692		(322,943)	290,705	(14,066)	781,726
8		190,102		661,692		(322,943)	384,185	(19,709)	893,326
9		213,865		661,692		(322,943)	360,904	(21,665)	891,852
10		237,627		661,692		(322,943)	301,468	(22,056)	855,788
11		237,627		322,943		-	197,442	(17,800)	740,213
12		237,627		215,296		-	197,373	(17,797)	632,499
13		237,627		107,648		-	197,511	(17,803)	524,983
14		237,627		-		-	197,489	(17,802)	417,314
15		237,627		-		-	197,558	(17,804)	417,381
16		237,627		-		-	197,523	(17,803)	417,348
17		237,627		-		-	180,255	(17,097)	400,785
18		237,627		-		-	180,342	(17,100)	400,869
19		237,627		-		-	180,361	(17,101)	400,887
20		237,627		-		-	180,311	(17,099)	400,839
21		213,865		-		-	-	(8,750)	205,115
22		190,102		-		-	-	(7,778)	182,324
23		166,339		-		-	-	(6,805)	159,534
24		142,576		-		-	-	(5,833)	136,743
25		118,814		-		-	-	(4,861)	113,953
26		95,051		-		-	-	(3,889)	91,162
27		71,288		-		-	-	(2,917)	68,372
28		47,525		-		-	-	(1,944)	45,581
29		23,763		-		-	-	(972)	22,791
	\$	4,752,546	\$	6,616,916	\$	(3,229,433)	\$ 5,016,542	\$ (333,123) \$	12,823,447

⁽¹⁾ Appendix E - Service Area H, Page 2 Section I
(2) Appendix E - Service Area H, Page 1

⁽³⁾ Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area H, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area H

<u>Year</u>	lmp <u>Fe</u>		Vehicle <u>Miles</u>		Impact Fee <u>Revenue</u>		Annual Expenses		Sub-Total		Accumulated Interest		Estimated Fund <u>Balance</u>
Initial												\$	293,933
1	\$	361	3,132	\$	1,129,758	\$	521,557	\$	608,201	\$	11,961		914,095
2		361	3,132		1,129,758		424,347		705,411		25,336		1,644,841
3		361	3,132		1,129,758		552,642		577,116		38,668		2,260,626
4		361	3,132		1,129,758		679,973		449,785		49,710		2,760,121
5		361	3,132		1,129,758		750,457		379,301		58,995		3,198,418
6		361	3,132		1,129,758		693,086		436,672		68,335		3,703,426
7		361	3,132		1,129,758		781,726		348,032		77,549		4,129,007
8		361	3,132		1,129,758		893,326		236,432		84,944		4,450,383
9		361	3,132		1,129,758		891,852		237,906		91,387		4,779,676
10		361	3,132		1,129,758		855,788		273,970		98,333		5,151,979
11		-	-		-		740,213		(740,213)		95,637		4,507,403
12		-	-		-		632,499		(632,499)		83,823		3,958,727
13		-	-		-		524,983		(524,983)		73,925		3,507,669
14		-	-		-		417,314		(417,314)		65,980		3,156,335
15		-	-		-		417,381		(417,381)		58,953		2,797,907
16		-	-		-		417,348		(417,348)		51,785		2,432,344
17		-	-		-		400,785		(400,785)		44,639		2,076,197
18		-	-		-		400,869		(400,869)		37,515		1,712,843
19		-	-		-		400,887		(400,887)		30,248		1,342,204
20		-	-		-		400,839		(400,839)		22,836		964,200
21		-	-		-		205,115		(205,115)		17,233		776,318
22		-	-		-		182,324		(182,324)		13,703		607,697
23		-	-		-		159,534		(159,534)		10,559		458,722
24		-	-		-		136,743		(136,743)		7,807		329,786
25		-	-		-		113,953		(113,953)		5,456		221,289
26		-	-		-		91,162		(91,162)		3,514		133,641
27		-	-		-		68,372		(68,372)		1,989		67,259
28		-	-		-		45,581		(45,581)		889		22,567
29		-	-	_	<u>-</u>		22,791		(22,791)		223		-
				\$	11,297,581	\$ 1	12,823,447		•	\$	1,231,934		

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area H

	Number of	Interest			Annual Expense					
	Years to	Rate	Fee	Annual Vel				-		
<u>Year</u>	End of Period	<u>Factor</u>	<u>Factor</u>	<u>Actual</u>	<u>Escalated</u>		<u>Actual</u>		<u>Escalated</u>	
1	29	1.7584	1.0000	3,132	5,508	\$	521,557	\$	917,124	
2	28	1.7240	1.0000	3,132	5,400		424,347		731,556	
3	27	1.6902	1.0000	3,132	5,294		552,642		934,049	
4	26	1.6570	1.0000	3,132	5,190		679,973		1,126,723	
5	25	1.6245	1.0000	3,132	5,089		750,457		1,219,133	
6	24	1.5927	1.0000	3,132	4,989		693,086		1,103,856	
7	23	1.5614	1.0000	3,132	4,891		781,726		1,220,618	
8	22	1.5308	1.0000	3,132	4,795		893,326		1,367,524	
9	21	1.5008	1.0000	3,132	4,701		891,852		1,338,497	
10	20	1.4714	1.0000	3,132	4,609		855,788		1,259,189	
11	19	1.4425	1.0000	-	-		740,213		1,067,779	
12	18	1.4142	1.0000	-	-		632,499		894,507	
13	17	1.3865	1.0000	-	-		524,983		727,897	
14	16	1.3593	1.0000	_	-		417,314		567,267	
15	15	1.3327	1.0000	-	-		417,381		556,232	
16	14	1.3065	1.0000	_	-		417,348		545,282	
17	13	1.2809	1.0000	-	-		400,785		513,376	
18	12	1.2558	1.0000	-	-		400,869		503,415	
19	11	1.2312	1.0000	-	-		400,887		493,566	
20	10	1.2070	1.0000	-	-		400,839		483,831	
21	9	1.1834	1.0000	-	-		205,115		242,728	
22	8	1.1602	1.0000	-	-		182,324		211,528	
23	7	1.1374	1.0000	-	-		159,534		181,458	
24	6	1.1151	1.0000	-	-		136,743		152,485	
25	5	1.0933	1.0000	-	-		113,953		124,580	
26	4	1.0718	1.0000	-	-		91,162		97,709	
27	3	1.0508	1.0000	-	-		68,372		71,845	
28	2	1.0302	1.0000	-	-		45,581		46,958	
29	1	1.0100	1.0000	-	-		22,791		23,018	
					50,467			\$	18,723,729	
		Annual Interest Ra	te:				2.00%			
			\$	293,933						
Total Escalated Expense for Entire Period Less Future Value of Initial Impact Fee Fund Balance						\$	18,723,729 521,979			
	Sub-Total					\$	18,201,750	•		
	Total Escalated Vehicle Miles						50,467			
Impact Fee For Service Area H							361			

Capital Improvement Plan for Impact Fees
Appendix E - Impact Fee Calculation Assumptions
Service Area H

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	Cost In vice Area ⁽¹⁾	act Fee rable Cost ⁽²⁾	Debt Fu Existing	ed ⁽³⁾ Proposed	Non-Debt Funded ⁽³⁾	Re	Impact Fee ecoverable Cost
ELDORADO PKWY (1)	H-1, G-10	\$ 2,601,000	\$ 1,618,857	\$ -	\$ 809,429	\$ 809,429	\$	1,618,857
SILVERADO TRL (1)	H-2	2,746,293	1,709,287	-	784,657	924,630		1,709,287
SILVERADO TRL (2)	H-3	141,088	87,813	87,813	-	-		87,813
STACY RD (1)	H-4	4,479,991	2,788,338	2,788,338	(0)	(0)		2,788,338
CUSTER RD (6)	H-5	622,725	387,583	369,505	-	18,078		387,583
ALMA DR (1)	H-6	239,850	149,282	149,282	-	-		149,282
ALMA DR (2)	H-7	1,522,102	947,353	201,969	372,692	372,692		947,353
RIDGE RD (9)	H-8, I-9	831,000	517,213	-	258,606	258,606		517,213
MCKINNEY RANCH PKWY (1)	H-9	1,857,600	1,156,167	-	578,083	578,083		1,156,167
Signal	65	150,000	93,360	-	46,680	46,680		93,360
Signal	66	300,000	186,719	-	93,360	93,360		186,719
Signal	71	300,000	186,719	-	93,360	93,360		186,719
Signal	75	150,000	93,360	-	46,680	46,680		93,360
Signal	76	150,000	93,360	-	46,680	46,680		93,360
Signal	77	300,000	186,719	-	93,360	93,360		186,719
Impact Fee Study		11,692	11,692	-	5,846	5,846		11,692
Total		\$ 16.403.341	\$ 10.213.823	\$ 3.596.908	\$ 3.229.433	\$ 3.387.483	\$	10.213.823

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area H

<u>Year</u>	Eligible Debt Annual Vehicle Service ⁽¹⁾ Miles  \$ 508,379 606,07		Eligible Debt Service per Vehicle Mile	Annual Growth in Vehicle Miles (Cumulative)	edit for Annual Ad Valorem <u>Revenues</u>
1	\$ 508,379	606,072	\$ 0.84	3,132	\$ 2,627
2	303,947	623,802	0.49	6,265	3,053
3	326,321	641,531	0.51	9,397	4,780
4	347,835	659,260	0.53	12,530	6,611
5	421,459	676,990	0.62	15,662	9,750
6	364,190	694,719	0.52	18,794	9,853
7	457,044	712,448	0.64	21,927	14,066
8	574,287	730,177	0.79	25,059	19,709
9	574,769	747,907	0.77	28,192	21,665
10	539,096	765,636	0.70	31,324	22,056
11	435,070	765,636	0.57	31,324	17,800
12	435,000	765,636	0.57	31,324	17,797
13	435,138	765,636	0.57	31,324	17,803
14	435,116	765,636	0.57	31,324	17,802
15	435,185	765,636	0.57	31,324	17,804
16	435,151	765,636	0.57	31,324	17,803
17	417,882	765,636	0.55	31,324	17,097
18	417,969	765,636	0.55	31,324	17,100
19	417,988	765,636	0.55	31,324	17,101
20	417,938	765,636	0.55	31,324	17,099
21	213,865	765,636	0.28	31,324	8,750
22	190,102	765,636	0.25	31,324	7,778
23	166,339	765,636	0.22	31,324	6,805
24	142,576	765,636	0.19	31,324	5,833
25	118,814	765,636	0.16	31,324	4,861
26	95,051	765,636	0.12	31,324	3,889
27	71,288	765,636	0.09	31,324	2,917
28	47,525	765,636	0.06	31,324	1,944
29	 23,763	765,636	0.03	31,324	972
Total	\$ 9,769,088				\$ 333,123

2019 Vehicle Miles (2)

Ten Year Growth in Vehicle Miles in Service Area (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

145,969

10 years

Annual Growth in Vehicle Miles

14,597

Credit Amount

\$ 333,123

⁽¹⁾ Appendix E - Service Area H, Page 2 Section II

⁽²⁾ Per Kimley-Horn Impact Fee Study

⁽³⁾ Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area I

### I. General Assumptions

Annual Interest Rate on Deposits (1)
Annual Vehicle Mile Growth (2)
Existing Fund Balance (3)

2.00%
1,833
\$ 5,189,258

Portion of Projects Funded by Existing Debt ⁽⁴⁾ Non-debt Funded Project Cost ⁽⁵⁾ New Project Cost Funded Through New Debt ⁽⁶⁾ Total Recoverable Project Cost ⁽⁷⁾

\$ 8,841,956
9,795,967
6,383,918

25,021,841

### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>				
1	\$ 638,392	4.00%	20				
2	638,392	4.00%	20				
3	638,392	4.00%	20				
4	638,392	4.00%	20				
5	638,392	4.00%	20				
6	638,392	4.00%	20				
7	638,392	4.00%	20				
8	638,392	4.00%	20				
9	638,392	4.00%	20				
10	638,392	4.00%	20				
Total	\$ 6,383,918						

### III. Capital Expenditure Assumptions

	Annual Capital
<u>Year</u>	Expenditures (10)
1	\$ 979,597
2	1,192,394
3	1,405,191
4	1,617,988
5	1,617,988
6	1,617,988
7	1,617,988
8	1,617,988
9	1,617,988
10	1,617,988
11	638,392
12	425,595
13	212,797
Total	\$ 16,179,885

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Total

### City of McKinney - 2019 Roadway Impact Fee Study

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area I

#### I. New Debt Service Detail

Year	Series <u>1</u>		Series	Series <u>3</u>	Series	S	eries <u>5</u>	Series	Series 7	Series <u>8</u>	Series	Series	Ne	Annual ew Debt Service
1		74 \$	-	\$ -	\$ -	\$	- \$	-	\$ -	\$ -	\$ -	\$ -	\$	46,974
2	46,9	74	46,974	-	-		-	-	-	-	-	-		93,948
3	46,9		46,974	46,974	-		-	-	-	-	-	-		140,922
4	46,9		46,974	46,974	46,974		-	-	-	-	-	-		187,896
5	46,9		46,974	46,974	46,974		46,974	-	-	-	-	-		234,870
6	46,9		46,974	46,974	46,974		46,974	46,974	-	-	-	-		281,844
7	46,9		46,974	46,974	46,974		46,974	46,974	46,974	-	-	-		328,818
8	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	-	-		375,792
9	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	-		422,766
10	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
11	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
12	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
13	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
14	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
15	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
16	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
17	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
18	46,9		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
19	46,9	74	46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
20	46,9	74	46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		469,740
21	-		46,974	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		422,766
22	-		-	46,974	46,974		46,974	46,974	46,974	46,974	46,974	46,974		375,792
23	-		-	-	46,974		46,974	46,974	46,974	46,974	46,974	46,974		328,818
24	-		-	-	-		46,974	46,974	46,974	46,974	46,974	46,974		281,844
25	-		-	-	-		-	46,974	46,974	46,974	46,974	46,974		234,870
26	-		-	-	-		-	-	46,974	46,974	46,974	46,974		187,896
27	-		-	-	-		-	-	-	46,974	46,974	46,974		140,922
28	-		-	-	-		-	-	-	-	46,974	46,974		93,948
29	-			-	-		-	-	-	-	-	46,974		46,974
_	\$ 939,4	30 \$	939,480	\$ 939,480	\$ 939,480	\$	939,480 \$	939,480	\$ 939,480	\$ 939,480	\$ 939,480	\$ 939,480	\$	9,394,797

### II. Summary of Annual Expenses

<u>Year</u>	<u> </u>	New Annual Debt Service ⁽¹⁾	<u>Ex</u>	Annual Capital penditures ⁽²⁾	P	Annual Bond Proceeds ⁽²⁾	Existing Annual Debt Service ⁽³⁾	Annual <u>Credit⁽⁴⁾</u>	Total <u>Expense</u>
1	\$	46,974	\$	979,597	\$	(638,392)	\$ 848,125	\$ (2,707) \$	1,233,596
2		93,948		1,192,394		(638,392)	666,815	(4,471)	1,310,293
3		140,922		1,405,191		(638,392)	665,648	(6,914)	1,566,455
4		187,896		1,617,988		(638,392)	663,919	(9,475)	1,821,937
5		234,870		1,617,988		(638,392)	703,504	(12,705)	1,905,265
6		281,844		1,617,988		(638,392)	639,172	(14,582)	1,886,030
7		328,818		1,617,988		(638,392)	694,041	(18,423)	1,984,032
8		375,792		1,617,988		(638,392)	768,394	(22,981)	2,100,801
9		422,766		1,617,988		(638,392)	749,827	(25,867)	2,126,322
10		469,740		1,617,988		(638,392)	702,616	(28,070)	2,123,883
11		469,740		638,392		-	619,940	(26,091)	1,701,981
12		469,740		425,595		-	619,853	(26,089)	1,489,099
13		469,740		212,797		-	620,000	(26,092)	1,276,445
14		469,740		-		-	619,972	(26,091)	1,063,620
15		469,740		-		-	620,069	(26,094)	1,063,715
16		469,740		-		-	620,020	(26,093)	1,063,668
17		469,740		-		-	528,854	(23,910)	974,684
18		469,740		-		-	528,924	(23,911)	974,752
19		469,740		-		-	528,939	(23,912)	974,767
20		469,740		-		-	528,899	(23,911)	974,728
21		422,766		-		-	-	(10,122)	412,643
22		375,792		-		-	-	(8,998)	366,794
23		328,818		-		-	-	(7,873)	320,945
24		281,844		-		-	-	(6,748)	275,096
25		234,870		-		-	-	(5,624)	229,246
26		187,896		-		-	-	(4,499)	183,397
27		140,922		-		-	-	(3,374)	137,548
28		93,948		-		-	-	(2,249)	91,699
29		46,974		-		-	-	(1,125)	45,849
	\$	9,394,797	\$	16,179,885	\$	(6,383,918)	\$ 12,937,528	\$ (449,003) \$	31,679,290

⁽¹⁾ Appendix E - Service Area I, Page 2 Section I (2) Appendix E - Service Area I, Page 1

⁽³⁾ Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area I, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area I

<u>Year</u>	Impact <u>Fee</u>	Vehicle <u>Miles</u>	Impact Fee <u>Revenue</u>	Annual <u>Expenses</u>	<u>Sub-Total</u>	Accumulated Interest	Estimated Fund <u>Balance</u>
Initial							\$ 5,189,258
1	\$ 1,265	1,833	\$ 2,318,876	\$ 1,233,596	\$ 1,085,279	\$ 114,638	6,389,175
2	1,265	1,833	2,318,876	1,310,293	1,008,582	137,869	7,535,627
3	1,265	1,833	2,318,876	1,566,455	752,421	158,237	8,446,285
4	1,265	1,833	2,318,876	1,821,937	496,939	173,895	9,117,119
5	1,265	1,833	2,318,876	1,905,265	413,610	186,478	9,717,208
6	1,265	1,833	2,318,876	1,886,030	432,846	198,673	10,348,726
7	1,265	1,833	2,318,876	1,984,032	334,844	210,323	10,893,893
8	1,265	1,833	2,318,876	2,100,801	218,074	220,059	11,332,026
9	1,265	1,833	2,318,876	2,126,322	192,553	228,566	11,753,145
10	1,265	1,833	2,318,876	2,123,883	194,993	237,013	12,185,151
11	-	-	-	1,701,981	(1,701,981)	226,683	10,709,853
12	-	-	-	1,489,099	(1,489,099)	199,306	9,420,061
13	-	-	-	1,276,445	(1,276,445)	175,637	8,319,253
14	-	-	-	1,063,620	(1,063,620)	155,749	7,411,381
15	-	-	-	1,063,715	(1,063,715)	137,590	6,485,257
16	-	-	-	1,063,668	(1,063,668)	119,068	5,540,658
17	-	-	-	974,684	(974,684)	101,066	4,667,040
18	-	-	-	974,752	(974,752)	83,593	3,775,881
19	-	-	-	974,767	(974,767)	65,770	2,866,884
20	-	-	-	974,728	(974,728)	47,590	1,939,747
21	-	-	-	412,643	(412,643)	34,669	1,561,772
22	-	-	-	366,794	(366,794)	27,568	1,222,545
23	-	-	-	320,945	(320,945)	21,241	922,842
24	-	-	-	275,096	(275,096)	15,706	663,452
25	-	-	-	229,246	(229,246)	10,977	445,183
26	-	-	-	183,397	(183,397)	7,070	268,855
27	-	-	-	137,548	(137,548)	4,002	135,309
28	-	-	-	91,699	(91,699)	1,789	45,400
29	-	-	-	45,849	(45,849)	450	-
			\$ 23,188,757	\$ 31,679,290		\$ 3,301,274	

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area I

	Number of Years to	Interest Rate	Recovery Fee	Annual Vel	hicle Miles		Annual	Expense		
<u>Year</u>	End of Period	<u>Factor</u>	<u>Factor</u>	<u>Actual</u>	<b>Escalated</b>		<u>Actual</u>	1	<u>Escalated</u>	
1	29	1.7584	1.0000	1,833	3,224	\$	1,233,596	\$	2,169,199	
2	28	1.7240	1.0000	1,833	3,160	Ψ	1,310,293	Ψ	2,258,887	
3	27	1.6902	1.0000	1,833	3,098		1,566,455		2,647,547	
4	26	1.6570	1.0000	1,833	3,038		1,821,937		3,018,971	
5	25	1.6245	1.0000	1,833	2,978		1,905,265		3,095,145	
6	24	1.5927	1.0000	1,833	2,920		1,886,030		3,003,820	
7	23	1.5614	1.0000	1,833	2,862		1,984,032		3,097,946	
8	22	1.5308	1.0000	1,833	2,806		2,100,801		3,215,955	
9	21	1.5008	1.0000	1,833	2,751		2,126,322		3,191,199	
10	20	1.4714	1.0000	1,833	2,697		2,123,883		3,125,037	
11	19	1.4425	1.0000	-	-		1,701,981		2,455,156	
12	18	1.4142	1.0000	-	-		1,489,099		2,105,949	
13	17	1.3865	1.0000	-	-		1,276,445		1,769,808	
14	16	1.3593	1.0000	-	-		1,063,620		1,445,807	
15	15	1.3327	1.0000	-	-		1,063,715		1,417,585	
16	14	1.3065	1.0000	-	-		1,063,668		1,389,727	
17	13	1.2809	1.0000	-	-		974,684		1,248,497	
18	12	1.2558	1.0000	-	-		974,752		1,224,102	
19	11	1.2312	1.0000	-	-		974,767		1,200,117	
20	10	1.2070	1.0000	-	-		974,728		1,176,539	
21	9	1.1834	1.0000	-	-		412,643		488,312	
22	8	1.1602	1.0000	-	-		366,794		425,544	
23	7	1.1374	1.0000	-	-		320,945		365,050	
24	6	1.1151	1.0000	-	-		275,096		306,765	
25 26	5 4	1.0933 1.0718	1.0000 1.0000	-	-		229,246		250,625	
26 27	3	1.0508	1.0000	-	-		183,397 137,548		196,569 144,536	
28	2	1.0308	1.0000	_	_		91,699		94,468	
29	1	1.0100	1.0000	_	_		45,849		46,308	
23	,	1.0100	1.0000	_	29,535		40,040	\$	46,575,170	
		Annual Interest Ra	te:				2.00%			
		Present Value of Ir	nitial Impact Fee	Fund Balance		\$	5,189,258			
		Total Escalated Ex	pense for Entire	Period		\$	46,575,170			
		Less Future Value	-			*	9,215,316			
		Sub-Total	,		•	\$	37,359,854			
		Total Escalated Ve	hicle Miles				29,535			
		Impact Fee For Se	ervice Area I			\$	1,265			

Capital Improvement Plan for Impact Fees

Appendix E - Impact Fee Calculation Assumptions

Service Area I

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	Ç.	Cost In rvice Area ⁽¹⁾	Impact Fee Recoverable Cost ⁽²⁾		Debt Funded ⁽³⁾ <u>Existing</u> <u>Proposed</u>			Non-Debt Funded ⁽³⁾		В	Impact Fee
impact ree Project Name*	Project No.	<u>3e</u>	rvice Area	<u>K</u>	ecoverable Cost	Existing		roposeu		-unaea ·	<u>K</u>	ecoverable Cost
VIRGINIA PKWY (7)	I-1	\$	2,567,378	\$	1,804,697	\$ 886,767	\$	-	\$	917,931	\$	1,804,697
VIRGINIA PKWY (8)	I-2		531,979		373,946	373,946		-		-		373,946
ELDORADO PKWY (2)	I-3		4,857,600		3,414,572	-		1,707,286		1,707,286		3,414,572
MCKINNEY RANCH PKWY (2)	I-4		4,338,000		3,049,328	-		1,524,664		1,524,664		3,049,328
COLLIN MCKINNEY PKWY (2)	I-5		1,777,105		1,249,188	595,943		-		653,245		1,249,188
COLLIN MCKINNEY PKWY (3)	I-6		3,221,002		2,264,152	1,080,146		-		1,184,006		2,264,152
COLLIN MCKINNEY PKWY (4)	I-7		1,101,893		774,558	369,514		-		405,044		774,558
RIDGE RD (8)	G-17, I-8		275,407		193,593	29,636		-		163,957		193,593
RIDGE RD (9)	H-8, I-9		831,000		584,138	-		292,069		292,069		584,138
HARDIN BLVD (11)	I-10, J-6		6,792,049		4,774,362	2,935,487		919,438		919,438		4,774,362
HARDIN BLVD (12)	I-11, J-7		3,104,400		2,182,188	-		1,091,094		1,091,094		2,182,188
Signal	35		150,000		105,440	-		52,720		52,720		105,440
Under Construction	36		195,171		137,192	93,259		-		43,933		137,192
Signal	38		171,500		120,553	120,553		-		-		120,553
Under Construction	44		195,171		137,192	93,259		-		43,933		137,192
Signal	45		300,000		210,880	-		105,440		105,440		210,880
Signal	46		300,000		210,880	-		105,440		105,440		210,880
Roundabout	50		1,320,000		927,873	927,873		-		-		927,873
Roundabout	51		1,900,000		1,335,575	1,335,575		-		-		1,335,575
Signal	56		150,000		105,440	-		52,720		52,720		105,440
Signal	57		150,000		105,440	-		52,720		52,720		105,440
Signal	58		150,000		105,440	-		52,720		52,720		105,440
Signal	59		300,000		210,880	-		105,440		105,440		210,880
Signal	60		300,000		210,880	-		105,440		105,440		210,880
Signal	72		300,000		210,880	-		105,440		105,440		210,880
Signal	73		150,000		105,440	-		52,720		52,720		105,440
Signal	76		150,000		105,440	-		52,720		52,720		105,440
Impact Fee Study			11,692		11,692	-		5,846		5,846		11,692
Total		\$	35,591,345	\$	25,021,841	\$ 8,841,956	\$	6,383,918	\$	9,795,967	\$	25,021,841

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area I

<u>Year</u>	E	Eligible Debt Annual Vo		Eligible Debt Service per Vehicle Mile	Annual Growth in Vehicle Miles (Cumulative)		edit for Annual Ad Valorem <u>Revenues</u>
1	\$	895,099	606,072	\$ 1.48	1,833	\$	2,707
2		760,763	623,802	1.22	3,666		4,471
3		806,570	641,531	1.26	5,500		6,914
4		851,815	659,260	1.29	7,333		9,475
5		938,374	676,990	1.39	9,166		12,705
6		921,016	694,719	1.33	10,999		14,582
7		1,022,859	712,448	1.44	12,832		18,423
8		1,144,185	730,177	1.57	14,666		22,981
9		1,172,593	747,907	1.57	16,499		25,867
10		1,172,356	765,636	1.53	18,332		28,070
11		1,089,680	765,636	1.42	18,332		26,091
12		1,089,593	765,636	1.42	18,332		26,089
13		1,089,740	765,636	1.42	18,332		26,092
14		1,089,711	765,636	1.42	18,332		26,091
15		1,089,809	765,636	1.42	18,332		26,094
16		1,089,760	765,636	1.42	18,332		26,093
17		998,594	765,636	1.30	18,332		23,910
18		998,664	765,636	1.30	18,332		23,911
19		998,678	765,636	1.30	18,332		23,912
20		998,639	765,636	1.30	18,332		23,911
21		422,766	765,636	0.55	18,332		10,122
22		375,792	765,636	0.49	18,332		8,998
23		328,818	765,636	0.43	18,332		7,873
24		281,844	765,636	0.37	18,332		6,748
25		234,870	765,636	0.31	18,332		5,624
26		187,896	765,636	0.25	18,332		4,499
27		140,922	765,636	0.18	18,332		3,374
28		93,948	765,636	0.12	18,332		2,249
29		46,974	765,636	0.06	18,332	_	1,125
Total	\$	22,332,326				\$	449,003

2019 Vehicle Miles⁽²⁾ 588,343

Ten Year Growth in Vehicle Miles in Service Area (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

18,332 10 years 1,833

Annual Growth in Vehicle Miles

158,961 _____10_years

15,896

Annual Growth in Vehicle Miles

\$ 449,003

(1) Appendix E - Service Area I, Page 2 Section II

(2) Per Kimley-Horn Impact Fee Study

Credit Amount

(3) Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area J

### I. General Assumptions

Annual Interest Rate on Deposits (1)
Annual Vehicle Mile Growth (2)
Existing Fund Balance (3)

2.00%
2,486
\$ 2,179,356

Portion of Projects Funded by Existing Debt⁽⁴⁾
Non-debt Funded Project Cost⁽⁵⁾
New Project Cost Funded Through New Debt⁽⁶⁾
Total Recoverable Project Cost⁽⁷⁾

\$ 2,989,838
3,326,536
3,305,234
\$ 9,621,608

### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>			
1	\$ 330,523	4.00%	20			
2	330,523	4.00%	20			
3	330,523	4.00%	20			
4	330,523	4.00%	20			
5	330,523	4.00%	20			
6	330,523	4.00%	20			
7	330,523	4.00%	20			
8	330,523	4.00%	20			
9	330,523	4.00%	20			
10	330,523	4.00%	20			
Total	\$ 3,305,234					

### III. Capital Expenditure Assumptions

<u>Year</u>	Annual Capital <u>Expenditures⁽¹⁰</u>	)
1	\$ 332,654	_
2	442,828	,
3	553,003	,
4	663,177	,
5	663,177	,
6	663,177	,
7	663,177	,
8	663,177	,
9	663,177	
10	663,177	,
11	330,523	,
12	220,349	,
13	110,174	
Total	\$ 6,631,770	)

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Total

### City of McKinney - 2019 Roadway Impact Fee Study

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area J

#### I. New Debt Service Detail

<u>Year</u>	Series	Series	Series	Series	Series <u>5</u>	Series	Series	Series <u>8</u>	Series	Series	Annual New Debt Service
1	\$ 24,320 \$		- \$	- \$	- \$	- \$	- \$	- \$	- \$	- 9	,
2	24,320	24,320	-	-	-	-	-	-	-	-	48,641
3	24,320	24,320	24,320	-	-	-	-	-	-	-	72,961
4	24,320	24,320	24,320	24,320	-	-	-	-	-	-	97,282
5	24,320	24,320	24,320	24,320	24,320	-	-	-	-	-	121,602
6	24,320	24,320	24,320	24,320	24,320	24,320	-	-	-	-	145,923
7	24,320	24,320	24,320	24,320	24,320	24,320	24,320	-	-	-	170,243
8	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	-	-	194,564
9	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	-	218,884
10	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
11	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
12	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
13	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
14	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
15	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
16	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
17	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
18	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
19	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
20	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	243,205
21	-	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	218,884
22	-	-	24,320	24,320	24,320	24,320	24,320	24,320	24,320	24,320	194,564
23	-	-	-	24,320	24,320	24,320	24,320	24,320	24,320	24,320	170,243
24	-	-	-	-	24,320	24,320	24,320	24,320	24,320	24,320	145,923
25	-	-	-	-	-	24,320	24,320	24,320	24,320	24,320	121,602
26	-	-	-	-	-	-	24,320	24,320	24,320	24,320	97,282
27	-	-	-	-	-	-	-	24,320	24,320	24,320	72,961
28	-	-	-	-	-	-	-	-	24,320	24,320	48,641
29	-	-	-	-	-	-	-	-	-	24,320	24,320
	\$ 486,410 \$	486,410	\$ 486,410 \$	486,410 \$	486,410 \$	486,410 \$	486,410 \$	486,410 \$	486,410 \$	486,410	4,864,097

### II. Summary of Annual Expenses

<u>Year</u>		New Annual Debt ervice ⁽¹⁾	<u>Ex</u>	Annual Capital penditures ⁽²⁾	<u>P</u>	Annual Bond Proceeds ⁽²⁾		Existing Annual Debt Service ⁽³⁾		Annual <u>Credit⁽⁴⁾</u>	Ē	Total Expense
1	\$	24,320	\$	332,654	\$	(330,523)	\$	232,863	\$	(1,055) \$	:	258,259
2	•	48,641	Ψ.	442,828	Ψ	(330,523)	•	232,914	~	(2,244)		391,615
3		72,961		553,003		(330,523)		232,850		(3,556)		524,735
4		97,282		663,177		(330,523)		232,909		(4,981)		657,863
5		121,602		663,177		(330,523)		232,866		(6,509)		680,613
6		145,923		663,177		(330,523)		232,935		(8,136)		703,376
7		170,243		663,177		(330,523)		232,893		(9,848)		725,941
8		194,564		663,177		(330,523)		232,951		(11,646)		748,523
9		218,884		663,177		(330,523)		232,888		(13,517)		770,908
10		243,205		663,177		(330,523)		232,914		(15,462)		793,311
11		243,205		330,523				232,914		(15,462)		791,180
12		243,205		220,349		-		232,882		(15,461)		680,975
13		243,205		110,174		-		232,919		(15,462)		570,837
14		243,205		· -		-		232,909		(15,462)		460,652
15		243,205		-		-		232,951		(15,463)		460,693
16		243,205		-		-		232,930		(15,462)		460,672
17		243,205		-		-		155,054		(12,933)		385,325
18		243,205		-		-		155,054		(12,933)		385,325
19		243,205		-		-		155,054		(12,933)		385,325
20		243,205		-		-		155,054		(12,933)		385,325
21		218,884		-		-		-		(7,108)		211,776
22		194,564		-		-		-		(6,318)		188,245
23		170,243		-		-		-		(5,529)		164,715
24		145,923		-		-		-		(4,739)		141,184
25		121,602		-		-		-		(3,949)		117,653
26		97,282		-		-		-		(3,159)		94,123
27		72,961		-		-		-		(2,369)		70,592
28		48,641		-		-		-		(1,580)		47,061
29		24,320		-	_	<u>-</u>	_	-		(790)		23,531
	\$	4.864.097	\$	6.631.770	\$	(3.305.234)	\$	4.346,705	\$	(257.003) \$	; ′	12.280.336

⁽¹⁾ Appendix E - Service Area J, Page 2 Section I
(2) Appendix E - Service Area J, Page 1

⁽³⁾ Eligible outstanding debt funded projects as a percent of outstanding principal times outstanding annual debt service

⁽⁴⁾ Appendix E - Service Area J, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area J

<u>Year</u>	npact <u>Fee</u>	Vehicle <u>Miles</u>	Impact Fee <u>Revenue</u>		Annual Expenses		Sub-Total		Accumulated Interest			Estimated Fund <u>Balance</u>
Initial											\$	2,179,356
1	\$ 347	2,486	\$	863,383	\$	258,259	\$	605,124	\$	49,638		2,834,118
2	347	2,486		863,383		391,615		471,767		61,400		3,367,286
3	347	2,486		863,383		524,735		338,648		70,732		3,776,666
4	347	2,486		863,383		657,863		205,520		77,589		4,059,774
5	347	2,486		863,383		680,613		182,770		83,023		4,325,567
6	347	2,486		863,383		703,376		160,006		88,111		4,573,685
7	347	2,486		863,383		725,941		137,441		92,848		4,803,974
8	347	2,486		863,383		748,523		114,860		97,228		5,016,062
9	347	2,486		863,383	770,908		92,474			101,246		5,209,782
10	347	2,486		863,383		793,311		70,072		104,896		5,384,751
11	-	-		-		791,180		(791,180)		99,783		4,693,354
12	-	-		-		680,975		(680,975)		87,057		4,099,436
13	-	-		-		570,837	(570,837)		76,280			3,604,880
14	-	-		-	460,652		(460,652)		67,491			3,211,719
15	-	-		-	460,693		(460,693)			59,627		2,810,653
16	-	-		-		460,672	(460,672)			51,606		2,401,587
17	-	-		-		385,325		(385, 325)		44,178		2,060,440
18	-	-		-		385,325		(385, 325)		37,356		1,712,470
19	-	-		-		385,325		(385, 325)		30,396		1,357,541
20	-	-		-		385,325		(385,325)		23,298		995,514
21	-	-		-		211,776		(211,776)		17,793		801,530
22	-	-		-		188,245		(188,245)		14,148		627,433
23	-	-		-		164,715		(164,715)		10,902		473,619
24	-	-		-		141,184		(141,184)		8,061		340,496
25	-	-		-		117,653		(117,653)		5,633		228,476
26	-	-		-		94,123		(94,123)		3,628		137,981
27	-	-		-		70,592		(70,592)		2,054		69,443
28	-	-		-		47,061		(47,061)	918			23,300
29	-	-		-		23,531		(23,531)		231		-
			\$	8,633,827	\$ 1	12,280,336			\$	1,467,153		

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area J

	Number of	Interest	Recovery					
	Years to	Rate	Fee	Annual Ve	hicle Miles	Annual	Ехр	ense
<u>Year</u>	<b>End of Period</b>	<u>Factor</u>	Factor	Actual	Escalated	Actual		Escalated
							•	
1	29	1.7584	1.0000	2,486	4,372	\$ 258,259	\$	454,131
2	28	1.7240	1.0000	2,486	4,286	391,615		675,127
3	27	1.6902	1.0000	2,486	4,202	524,735		886,882
4	26	1.6570	1.0000	2,486	4,120	657,863		1,090,087
5	25	1.6245	1.0000	2,486	4,039	680,613		1,105,670
6	24	1.5927	1.0000	2,486	3,960	703,376		1,120,245
7	23	1.5614	1.0000	2,486	3,882	725,941		1,133,514
8	22	1.5308	1.0000	2,486	3,806	748,523		1,145,856
9	21	1.5008	1.0000	2,486	3,732	770,908		1,156,985
10	20	1.4714	1.0000	2,486	3,658	793,311		1,167,261
11	19	1.4425	1.0000	-	-	791,180		1,141,300
12	18	1.4142	1.0000	-	-	680,975		963,065
13	17	1.3865	1.0000	-	-	570,837		791,473
14	16	1.3593	1.0000	-	-	460,652		626,177
15	15	1.3327	1.0000	-	-	460,693		613,953
16	14	1.3065	1.0000	-	-	460,672		601,888
17	13	1.2809	1.0000	-	-	385,325		493,572
18	12	1.2558	1.0000	-	-	385,325		483,895
19	11	1.2312	1.0000	-	-	385,325		474,406
20	10	1.2070	1.0000	-	-	385,325		465,104
21	9	1.1834	1.0000	-	-	211,776		250,611
22	8	1.1602	1.0000	-	-	188,245		218,397
23	7	1.1374	1.0000	-	-	164,715		187,351
24	6	1.1151	1.0000	-	-	141,184		157,437
25	5	1.0933	1.0000	-	-	117,653		128,625
26	4	1.0718	1.0000	-	-	94,123		100,883
27	3	1.0508	1.0000	-	-	70,592		74,178
28	2	1.0302	1.0000	-	-	47,061		48,483
29	1	1.0100	1.0000	-	-	23,531		23,766
				_	40,059		\$	17,780,324
		Annual Interest Ra	te:			2.00%		
		Present Value of Ir	nitial Impact Fee	Fund Balance		\$ 2,179,356		
		Total Escalated Ex				\$ 17,780,324		
		Less Future Value	of Initial Impact I	Fee Fund Balance		3,870,198		
		Sub-Total				\$ 13,910,126		
		Total Escalated Ve	hicle Miles			40,059	•	
		Impact Fee For Se	ervice Area J			\$ 347		

Capital Improvement Plan for Impact Fees
Appendix E - Impact Fee Calculation Assumptions
Service Area J

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	Sei	Cost In rvice Area ⁽¹⁾	<u>F</u>	Impact Fee Recoverable Cost ⁽²⁾		Debt Fo		d ⁽³⁾ roposed		lon-Debt unded ⁽³⁾		mpact Fee overable Cost
WHITE AVE (1)	J-1	\$	981,328	\$	334.478	\$	334.478	\$	_	\$	_	\$	334,478
WHITE AVE (1)	J-2	Ψ	213,991	Ψ	72,937	Ψ	72,937	Ψ	_	Ψ	_	Ψ	72,937
VIRGINIA PKWY (9)	J-3		3,267,873		1,113,829		1,113,829		_		_		1,113,829
ELDORADO PKWY (3)	J-4		4,047,600		1,379,593		-,,		689,797		689,797		1,379,593
COLLIN MCKINNEY PKWY (5)	J-5		1,953,000		665,665		_		332,832		332,832		665,665
HARDIN BLVD (11)	I-10, J-6		6,792,049		2,315,017		1,423,374		445,822		445,822		2,315,017
HARDIN BLVD (12)	I-11, J-7		3,104,400		1,058,111		-		529,055		529,055		1,058,111
MEDICAL CENTER DR	J-8		2,240,000		763,487		_		381,743		381,743		763,487
STATE HIGHWAY 5 (4)	J-9, K-7		2,323,650		791,998		_		395,999		395,999		791,998
STATE HIGHWAY 5 (5)	J-10, K-8		1,111,600		378,880		-		189,440		189,440		378,880
STATE HIGHWAY 5 (6)	J-11		313,950		107,007		-		53,504		53,504		107,007
Under Construction	36		195,171		66,522		45,220		-		21,303		66,522
Signal	39		300,000		102,253		-		51,126		51,126		102,253
Signal	58		150,000		51,126		-		25,563		25,563		51,126
Intersection Improvements	61		150,000		51,126		-		25,563		25,563		51,126
Signal	62		150,000		51,126		-		25,563		25,563		51,126
Signal	67		300,000		102,253		-		51,126		51,126		102,253
Signal	68		300,000		102,253		-		51,126		51,126		102,253
Signal	69		150,000		51,126		-		25,563		25,563		51,126
Signal	73		150,000		51,126		-		25,563		25,563		51,126
Impact Fee Study			11,692		11,692		-		5,846		5,846		11,692
Total		\$	28,206,303	\$	9,621,608	\$	2,989,838	\$	3,305,234	\$	3,326,536	\$	9,621,608

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area J

<u>Year</u>	Eligible Debt <u>Service⁽¹⁾</u>		Annual Vehicle <u>Miles</u>		Eligible Debt Service per <u>Vehicle Mile</u>	Annual Growth in Vehicle Miles (Cumulative)	Credit for Annual Ad Valorem <u>Revenues</u>		
1	\$	257,184	606,072	\$	0.42	2,486	\$ 1,055		
2		281,555	623,802		0.45	4,973	2,244		
3		305,812	641,531		0.48	7,459	3,556		
4		330,191	659,260		0.50	9,946	4,981		
5		354,469	676,990		0.52	12,432	6,509		
6		378,858	694,719		0.55	14,918	8,136		
7		403,136	712,448		0.57	17,405	9,848		
8		427,515	730,177		0.59	19,891	11,646		
9		451,772	747,907		0.60	22,378	13,517		
10		476,119	765,636		0.62	24,864	15,462		
11		476,119	765,636		0.62	24,864	15,462		
12		476,087	765,636		0.62	24,864	15,461		
13		476,124	765,636		0.62	24,864	15,462		
14		476,114	765,636		0.62	24,864	15,462		
15		476,156	765,636		0.62	24,864	15,463		
16		476,135	765,636		0.62	24,864	15,462		
17		398,259	765,636		0.52	24,864	12,933		
18		398,259	765,636		0.52	24,864	12,933		
19		398,259	765,636		0.52	24,864	12,933		
20		398,259	765,636		0.52	24,864	12,933		
21		218,884	765,636		0.29	24,864	7,108		
22		194,564	765,636		0.25	24,864	6,318		
23		170,243	765,636		0.22	24,864	5,529		
24		145,923	765,636		0.19	24,864	4,739		
25		121,602	765,636		0.16	24,864	3,949		
26		97,282	765,636		0.13	24,864	3,159		
27		72,961	765,636		0.10	24,864	2,369		
28		48,641	765,636		0.06	24,864	1,580		
29		24,320	765,636		0.03	24,864	 790		
Total	\$	9,210,803					\$ 257,003		

2019 Vehicle Miles (2)

Ten Year Growth in Vehicle Miles in Service Area (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

152,429

10 years

Annual Growth in Vehicle Miles

15,243

Credit Amount

\$ 257,003

⁽¹⁾ Appendix E - Service Area J, Page 2 Section II

⁽²⁾ Per Kimley-Horn Impact Fee Study

⁽³⁾ Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area K

### I. General Assumptions

Annual Interest Rate on Deposits (1)
Annual Vehicle Mile Growth (2)
Existing Fund Balance (3)

2.00%
853
\$ 779,111

Portion of Projects Funded by Existing Debt ⁽⁴⁾ Non-debt Funded Project Cost ⁽⁵⁾ New Project Cost Funded Through New Debt ⁽⁶⁾ Total Recoverable Project Cost ⁽⁷⁾

\$ 1,159,792
4,449,077
4,295,800
\$ 9,904,669

### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>
1	\$ 429,580	4.00%	20
2	429,580	4.00%	20
3	429,580	4.00%	20
4	429,580	4.00%	20
5	429,580	4.00%	20
6	429,580	4.00%	20
7	429,580	4.00%	20
8	429,580	4.00%	20
9	429,580	4.00%	20
10	429,580	4.00%	20
Total	\$ 4,295,800		

### III. Capital Expenditure Assumptions

<u>Year</u>	C	nnual apital nditures ⁽¹⁰⁾
1	\$	444,908
2		588,101
3		731,294
4		874,488
5		874,488
6		874,488
7		874,488
8		874,488
9		874,488
10		874,488
11		429,580
12		286,387
13		143,193
Total	\$	8.744.877

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area K

### I. New Debt Service Detail

<u>Year</u>	s	eries <u>1</u>	Series	s	Series <u>3</u>	;	Series	Series <u>5</u>	Series	Series <u>7</u>	Series <u>8</u>	Series <u>9</u>	Series	N	Total Annual lew Debt Service
1	\$	31,609	\$ -	\$	-	\$	-	\$ -	\$ - 9	\$ -	\$ -	\$ -	\$ -	\$	31,609
2		31,609	31,609		-		-	-	-	-	-	-	-		63,218
3		31,609	31,609		31,609		-	-	-	-	-	-	-		94,828
4		31,609	31,609		31,609		31,609	-	-	-	-	-	-		126,437
5		31,609	31,609		31,609		31,609	31,609	-	-	-	-	-		158,046
6		31,609	31,609		31,609		31,609	31,609	31,609	-	-	-	-		189,655
7		31,609	31,609		31,609		31,609	31,609	31,609	31,609	-	-	-		221,265
8		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	-	-		252,874
9		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	-		284,483
10		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
11		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
12		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
13		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
14		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
15		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
16		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
17		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
18		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
19		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
20		31,609	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		316,092
21		-	31,609		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		284,483
22		-	-		31,609		31,609	31,609	31,609	31,609	31,609	31,609	31,609		252,874
23		-	-		-		31,609	31,609	31,609	31,609	31,609	31,609	31,609		221,265
24		-	-		-		-	31,609	31,609	31,609	31,609	31,609	31,609		189,655
25		-	-		-		-	-	31,609	31,609	31,609	31,609	31,609		158,046
26		-	-		-		-	-	-	31,609	31,609	31,609	31,609		126,437
27		-	-		-		-	-	-	-	31,609	31,609	31,609		94,828
28		-	-		-		-	-	-	-	-	31,609	31,609		63,218
29		-	-		-		-	-	-	-	-	-	31,609		31,609
	\$	632,185	\$ 632,185	\$	632,185	\$	632,185	\$ 632,185	\$ 632,185	\$ 632,185	\$ 632,185	\$ 632,185	\$ 632,185	\$	6,321,850

### II. Summary of Annual Expenses

<u>Year</u>	New Annual Debt <u>Service⁽¹</u>		Annual Capital xpenditures ⁽²⁾	<u>F</u>	Annual Bond Proceeds ⁽²⁾	Existing Annual Debt Service ⁽³⁾	Annual Credit ⁽⁴⁾	!	Total Expense
1	\$ 31,6	09 \$	444,908	\$	(429,580)	\$ 89,873	\$ (171)	\$	136,639
2	63,2	18	588,101		(429,580)	89,885	(419)		311,206
3	94,8	328	731,294		(429,580)	89,870	(737)		485,675
4	126,4	37	874,488		(429,580)	89,884	(1,120)		660,109
5	158,0	146	874,488		(429,580)	89,874	(1,562)		691,266
6	189,6	555	874,488		(429,580)	89,890	(2,059)		722,394
7	221,2	65	874,488		(429,580)	89,880	(2,608)		753,445
8	252,8	74	874,488		(429,580)	89,894	(3,203)		784,472
9	284,4	83	874,488		(429,580)	89,879	(3,843)		815,427
10	316,0	192	874,488		(429,580)	89,885	(4,523)		846,362
11	316,0	92	429,580		-	89,885	(4,523)		831,035
12	316,0	92	286,387		-	89,878	(4,523)		687,834
13	316,0	92	143,193		-	89,886	(4,523)		544,649
14	316,0	92	-		-	89,884	(4,523)		401,453
15	316,0	92	-		-	89,894	(4,523)		401,463
16	316,0	92	-		-	89,889	(4,523)		401,458
17	316,0	92	-		-	71,485	(4,318)		383,260
18	316,0	92	-		-	71,485	(4,318)		383,260
19	316,0	92	-		-	71,485	(4,318)		383,260
20	316,0	92	-		-	71,485	(4,318)		383,260
21	284,4	83	-		-	-	(3,169)		281,314
22	252,8	374	-		-	-	(2,817)		250,057
23	221,2	265	-		-	-	(2,465)		218,800
24	189,6	555	-		-	-	(2,113)		187,543
25	158,0	146	-		-	-	(1,761)		156,285
26	126,4	137	-		-	-	(1,409)		125,028
27	94,8	28	-		-	-	(1,056)		93,771
28	63,2	18	-		-	-	(704)		62,514
29	31,6	609	-		-	-	(352)		31,257
	\$ 6,321,8	50 \$	8,744,877	\$	(4,295,800)	\$ 1,724,071	\$ (80,502)	\$	12,414,496

⁽¹⁾ Appendix E - Service Area K, Page 2 Section I
(2) Appendix E - Service Area K, Page 1
(3) Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area K, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area K

<u>Year</u>	Impact <u>Fee</u>	Vehicle <u>Miles</u>	Impact Fee <u>Revenue</u>		Annual <u>Expenses</u>		<u>Sub-Total</u>	Accumulated <u>Interest</u>			Estimated Fund <u>Balance</u>
Initial										\$	779,111
1	\$ 1,197	853	\$ 1,020,837	\$	136,639	\$	884,198	\$	24,424		1,687,733
2	1,197	853	1,020,837		311,206		709,631		40,851		2,438,215
3	1,197	853	1,020,837		485,675		535,162		54,116		3,027,492
4	1,197	853	1,020,837		660,109		360,728		64,157		3,452,377
5	1,197	853	1,020,837		691,266		329,571		72,343		3,854,292
6	1,197	853	1,020,837		722,394		298,443		80,070		4,232,805
7	1,197	853	1,020,837		753,445		267,392		87,330		4,587,527
8	1,197	853	1,020,837		784,472		236,365		94,114		4,918,006
9	1,197	853	1,020,837		815,427		205,410		100,414		5,223,830
10	1,197	853	1,020,837		846,362		174,475		106,221		5,504,526
11	-	-	-		831,035		(831,035)		101,780		4,775,272
12	-	-	-		687,834		(687,834)		88,627		4,176,065
13	-	-	-		544,649		(544,649)		78,075		3,709,490
14	-	-	-		401,453		(401,453)		70,175		3,378,212
15	-	-	-		401,463		(401,463)		63,550		3,040,299
16	-	-	-		401,458		(401,458)		56,791		2,695,632
17	-	-	-		383,260		(383,260)		50,080		2,362,452
18	-	-	-		383,260		(383,260)		43,416		2,022,609
19	-	-	-		383,260		(383,260)		36,620		1,675,968
20	-	-	-		383,260		(383,260)		29,687		1,322,395
21	-	-	-		281,314		(281,314)		23,635		1,064,716
22	-	-	-		250,057		(250,057)		18,794		833,453
23	-	-	-		218,800		(218,800)		14,481		629,135
24	-	-	-		187,543		(187,543)		10,707		452,299
25	-	-	-		156,285		(156,285)		7,483		303,497
26	-	-	-		125,028		(125,028)		4,820		183,288
27	-	-	-		93,771		(93,771)		2,728		92,245
28	-	-	-		62,514		(62,514)		1,220		30,951
29	-	-	 		31,257	_	(31,257)		306		-
			\$ 10,208,369	\$	12,414,496	-		\$	1,427,017	-	

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area K

	Number of	Interest	Recovery				_	
	Years to	Rate	Fee	Annual Ve		Annual	-	
<u>Year</u>	End of Period	<u>Factor</u>	<u>Factor</u>	<u>Actual</u>	<u>Escalated</u>	<u>Actual</u>		<u>Escalated</u>
1	29	1.7584	1.0000	853	1,500	\$ 136,639	\$	240,271
2	28	1.7240	1.0000	853	1,471	311,206		536,505
3	27	1.6902	1.0000	853	1,442	485,675		820,865
4	26	1.6570	1.0000	853	1,413	660,109		1,093,809
5	25	1.6245	1.0000	853	1,386	691,266		1,122,976
6	24	1.5927	1.0000	853	1,359	722,394		1,150,534
7	23	1.5614	1.0000	853	1,332	753,445		1,176,458
8	22	1.5308	1.0000	853	1,306	784,472		1,200,888
9	21	1.5008	1.0000	853	1,280	815,427		1,223,799
10	20	1.4714	1.0000	853	1,255	846,362		1,245,320
11	19	1.4425	1.0000	-	-	831,035		1,198,791
12	18	1.4142	1.0000	-	-	687,834		972,765
13	17	1.3865	1.0000	-	-	544,649		755,163
14	16	1.3593	1.0000	-	-	401,453		545,706
15	15	1.3327	1.0000	-	-	401,463		535,020
16	14	1.3065	1.0000	-	-	401,458		524,522
17	13	1.2809	1.0000	-	-	383,260		490,927
18	12	1.2558	1.0000	-	-	383,260		481,301
19	11	1.2312	1.0000	-	-	383,260		471,864
20	10	1.2070	1.0000	-	-	383,260		462,611
21	9	1.1834	1.0000	-	-	281,314		332,900
22	8	1.1602	1.0000	-	-	250,057		290,109
23	7	1.1374	1.0000	-	-	218,800		248,868
24	6	1.1151	1.0000	-	-	187,543		209,133
25	5	1.0933	1.0000	-	-	156,285		170,860
26	4	1.0718	1.0000	-	-	125,028		134,008
27	3	1.0508	1.0000	-	-	93,771		98,535
28	2	1.0302	1.0000	-	-	62,514		64,402
29	1	1.0100	1.0000		-	31,257	_	31,570
					13,743		\$	17,830,480
		Annual Interest Ra	te:			2.00%		
		Present Value of Ir	nitial Impact Fee	Fund Balance		\$ 779,111		
		Total Escalated Ex	•			\$ 17,830,480		
		Less Future Value Sub-Total	of Initial Impact	Fee Fund Balance		\$ 1,383,580 16,446,899		
		Total Escalated Ve	hicle Miles			13,743		
						=		
		Impact Fee For Se	ervice Area K			\$ 1,197		

Capital Improvement Plan for Impact Fees
Appendix E - Impact Fee Calculation Assumptions
Service Area K

Impact Fee			Cost In		Impact Fee		Debt Fu	ınde	ed ⁽³⁾	1	Non-Debt		Impact Fee
Impact Fee Project Name ⁽¹⁾	Project No. (1)	Ser	vice Area ⁽¹⁾	Re	ecoverable Cost ⁽²⁾		Existing	<u> </u>	roposed	Į	Funded ⁽³⁾	<u> </u>	Recoverable Cost
		_		_		_				_			
VIRGINIA STREET	K-1	\$	779,650	\$	398,340	\$	-	\$	199,170	\$	199,170	\$	398,340
ELDORADO PKWY (4)	K-2		1,699,200		868,158		-		434,079		434,079		868,158
HARRY MCKILLOP BLVD / FM 546 (1)	K-3		1,839,600		939,892		-		469,946		469,946		939,892
HARRY MCKILLOP BLVD / FM 546 (2)	K-4, L-1		117,300		59,931		-		29,966		29,966		59,931
HARRY MCKILLOP BLVD / FM 546 (3)	K-5, L-2		1,633,700		834,693		-		417,346		417,346		834,693
STATE HIGHWAY 5 (3)	K-6		2,064,300		1,054,696		-		527,348		527,348		1,054,696
STATE HIGHWAY 5 (4)	J-9, K-7		2,323,650		1,187,203		-		593,602		593,602		1,187,203
STATE HIGHWAY 5 (5)	J-10, K-8		1,111,600		567,941		-		283,970		283,970		567,941
AIRPORT DR (5)	K-9, L-6		3,161,400		1,615,228		-		807,614		807,614		1,615,228
AIRPORT DR (6)	K-10, L-7		1,462,600		747,274		229,915		182,041		335,318		747,274
Signal	40		300,000		153,277		-		76,638		76,638		153,277
Signal Mod	41		75,000		38,319		-		19,160		19,160		38,319
Roundabout	52		1,820,000		929,877		929,877		-		-		929,877
Signal	53		300,000		153,277		-		76,638		76,638		153,277
Signal	54		150,000		76,638		-		38,319		38,319		76,638
Signal	62		150,000		76,638		-		38,319		38,319		76,638
Signal	63		225,000		114,957		-		57,479		57,479		114,957
Signal	69		150,000		76,638		-		38,319		38,319		76,638
Impact Fee Study			11,692		11,692		-		5,846		5,846		11,692
Total		\$	19,374,692	\$	9,904,669	\$	1,159,792	\$	4,295,800	\$	4,449,077	\$	9,904,669

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area K

<u>Year</u>	E	ligible Debt <u>Service⁽¹⁾</u>	Annual Vehicle <u>Miles</u>	Eligible Debt Service per Vehicle Mile	Annual Growth in Vehicle Miles (Cumulative)	edit for Annual Ad Valorem <u>Revenues</u>
1	\$	121,482	606,072	\$ 0.20	853	\$ 171
2		153,104	623,802	0.25	1,706	419
3		184,698	641,531	0.29	2,559	737
4		216,321	659,260	0.33	3,412	1,120
5		247,920	676,990	0.37	4,265	1,562
6		279,546	694,719	0.40	5,118	2,059
7		311,145	712,448	0.44	5,971	2,608
8		342,768	730,177	0.47	6,824	3,203
9		374,362	747,907	0.50	7,677	3,843
10		405,978	765,636	0.53	8,530	4,523
11		405,978	765,636	0.53	8,530	4,523
12		405,970	765,636	0.53	8,530	4,523
13		405,979	765,636	0.53	8,530	4,523
14		405,976	765,636	0.53	8,530	4,523
15		405,986	765,636	0.53	8,530	4,523
16		405,981	765,636	0.53	8,530	4,523
17		387,578	765,636	0.51	8,530	4,318
18		387,578	765,636	0.51	8,530	4,318
19		387,578	765,636	0.51	8,530	4,318
20		387,578	765,636	0.51	8,530	4,318
21		284,483	765,636	0.37	8,530	3,169
22		252,874	765,636	0.33	8,530	2,817
23		221,265	765,636	0.29	8,530	2,465
24		189,655	765,636	0.25	8,530	2,113
25		158,046	765,636	0.21	8,530	1,761
26		126,437	765,636	0.17	8,530	1,409
27		94,828	765,636	0.12	8,530	1,056
28		63,218	765,636	0.08	8,530	704
29		31,609	765,636	0.04	8,530	352
Total	\$	8,045,921				\$ 80,502

2019 Vehicle Miles (2)

Ten Year Growth in Vehicle Miles in Service Area (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

10 years

16,876

Credit Amount

\$ 80,502

⁽¹⁾ Appendix E - Service Area K, Page 2 Section II

⁽²⁾ Per Kimley-Horn Impact Fee Study

⁽³⁾ Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area L

### I. General Assumptions

Annual Interest Rate on Deposits ⁽¹⁾	
Annual Vehicle Mile Growth ⁽²⁾	
Existing Fund Balance ⁽³⁾	\$

Portion of Projects Funded by Existing Debt⁽⁴⁾
Non-debt Funded Project Cost⁽⁵⁾
New Project Cost Funded Through New Debt⁽⁶⁾
Total Recoverable Project Cost⁽⁷⁾

\$ 57,132
1,761,891
1,723,803
\$ 3,542,826

2.00% 189 5,532

#### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>
1	\$ 172,380	4.00%	20
2	172,380	4.00%	20
3	172,380	4.00%	20
4	172,380	4.00%	20
5	172,380	4.00%	20
6	172,380	4.00%	20
7	172,380	4.00%	20
8	172,380	4.00%	20
9	172,380	4.00%	20
10	172,380	4.00%	20
Total	\$ 1,723,803		

### III. Capital Expenditure Assumptions

<u>Year</u>	Exp	Annual Capital enditures ⁽¹⁰⁾
1	\$	176,189
2		233,649
3		291,109
4		348,569
5		348,569
6		348,569
7		348,569
8		348,569
9		348,569
10		348,569
11		172,380
12		114,920
13		57,460
Total	\$	3,485,694

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- (5) This assumes 50% of new project costs funded through sources other than debt, unless specified otherwise
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area L

#### I. New Debt Service Detail

Year	Series	Series	Series <u>3</u>	Series	Series <u>5</u>	Series <u>6</u>	Series <u>7</u>	Series	Series	Series <u>10</u>	Total Annual New Debt <u>Service</u>
1	\$ 12,684	\$ -	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-	\$ 12,684
2	12,684	12,684	-	-	-	-	-	-	-	-	25,368
3	12,684	12,684	12,684	-	-	-	-	-	-	-	38,052
4	12,684	12,684	12,684	12,684	-	-	-	-	-	-	50,736
5	12,684	12,684	12,684	12,684	12,684	-	-	-	-	-	63,420
6	12,684	12,684	12,684	12,684	12,684	12,684	-	-	-	-	76,104
7	12,684	12,684	12,684	12,684	12,684	12,684	12,684	-	-	-	88,788
8	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	-	-	101,472
9	12,684	12,684	12,684	12,684	12,684	12,684 12,684 12,684 12,684		-	114,156		
10	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
11	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
12	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
13	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
14	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
15	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
16	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
17	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
18	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
19	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
20	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	126,840
21	-	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	114,156
22	-	-	12,684	12,684	12,684	12,684	12,684	12,684	12,684	12,684	101,472
23	-	-	-	12,684	12,684	12,684	12,684	12,684	12,684	12,684	88,788
24	-	-	-	-	12,684	12,684	12,684	12,684	12,684	12,684	76,104
25	-	-	-	-	-	12,684	12,684	12,684	12,684	12,684	63,420
26	-	-	-	-	-	-	12,684	12,684	12,684	12,684	50,736
27	-	-	-	-	-	-	-	12,684	12,684	12,684	38,052
28	-	-	-	-	-	-	-	-	12,684	12,684	25,368
29	-	-	-	-	-	-	-	-	-	12,684	12,684
_	\$ 253,681	\$ 253,681	\$ 253,681 \$	253,681 \$	253,681 \$	253,681 \$	253,681 \$	253,681 \$	253,681 \$	253,681	\$ 2,536,809

### II. Summary of Annual Expenses

<u>Year</u>		New Annual Debt <u>Service⁽¹⁾</u>		Annual Capital <u>Expenditures⁽²⁾</u>		Annual Bond Proceeds ⁽²⁾		Existing Annual Debt <u>Service⁽³⁾</u>		Annual <u>Credit⁽⁴⁾</u>		Total Expense	
1	\$	12,684	\$	176,189	\$	(172,380)	\$	4,569	\$	(5)	\$	21,057	
2	Ψ.	25,368	Ψ	233,649	Ψ	(172,380)	•	4,572	•	(18)	Ψ	91,191	
3		38,052		291,109		(172,380)		4,568		(38)		161,312	
4		50,736		348,569		(172,380)		4,572		(64)		231,434	
5		63,420		348,569		(172,380)		4,569		(95)		244,084	
6		76,104		348,569		(172,380)		4,573		(132)		256,735	
7		88,788		348,569		(172,380)		4,571		(174)		269,375	
8		101,472		348,569		(172,380)		4,574		(220)		282,016	
9		114,156		348,569		(172,380)		4,571		(270)		294,646	
10		126,840		348,569		(172,380)		4,572		(325)		307,277	
11		126,840		172,380		- 1		4,572		(325)		303,468	
12		126,840		114,920		-		4,570		(325)		246,006	
13		126,840		57,460		-		4,573		(325)		188,548	
14		126,840		-		-		4,572		(325)		131,087	
15		126,840		-		-		4,574		(325)		131,090	
16		126,840		-		-		4,573		(325)		131,089	
17		126,840		-		-		-		(314)		126,527	
18		126,840		-		-		-		(314)		126,527	
19		126,840		-		-		-		(314)		126,527	
20		126,840		-		-		-		(314)		126,527	
21		114,156		-		-		-		(282)		113,874	
22		101,472		-		-		-		(251)		101,221	
23		88,788		-		-		-		(220)		88,569	
24		76,104		-		-		-		(188)		75,916	
25		63,420		-		-		-		(157)		63,263	
26		50,736		-		-		-		(125)		50,611	
27		38,052		-		-		-		(94)		37,958	
28		25,368		-		-		-		(63)		25,305	
29		12,684		-		-		-		(31)		12,653	
	\$	2,536,809	\$	3,485,694	\$	(1,723,803)	\$	73,147	\$	(5,956)	\$	4,365,891	

⁽¹⁾ Appendix E - Service Area L, Page 2 Section I

⁽¹⁾ Appendix E - Service Area L, Page 1
(3) Eligible debt funded projects as a percent of total principal times original annual debt service

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area L

<u>Year</u>	Impact <u>Fee</u>				Impact Fee <u>Revenue</u>		Annual Expenses		Sub-Total		Accumulated <u>Interest</u>		Estimated Fund <u>Balance</u>
Initial												\$	5,532
1	\$	2,044	189	\$	386,878	\$	21,057	\$	365,822	\$	3,769		375,122
2		2,044	189		386,878		91,191		295,687		10,459		681,269
3		2,044	189		386,878		161,312		225,566		15,881		922,716
4		2,044	189		386,878		231,434		155,445		20,009		1,098,169
5	2,044 189			386,878		244,084		142,795		23,391		1,264,355	
6	2,044 189			386,878		256,735		130,143		26,589		1,421,087	
7		2,044	189		386,878		269,375		117,503		29,597		1,568,187
8		2,044	189		386,878		282,016		104,862		32,412		1,705,462
9		2,044	189		386,878		294,646		92,232		35,032		1,832,726
10		2,044	189		386,878		307,277		79,601		37,451		1,949,778
11		-	-		-		303,468		(303,468)		35,961		1,682,271
12		-	-		-		246,006		(246,006)		31,185		1,467,450
13		-	-		-		188,548		(188,548)		27,464		1,306,365
14		-	-		-		131,087		(131,087)		24,816		1,200,094
15		-	-		-		131,090		(131,090)		22,691		1,091,696
16		-	-		-		131,089		(131,089)		20,523		981,130
17		-	-		-		126,527		(126,527)		18,357		872,960
18		-	-		-		126,527		(126,527)		16,194		762,628
19		-	-		-		126,527		(126,527)		13,987		650,088
20		-	-		-		126,527		(126,527)		11,736		535,298
21		-	-		-		113,874		(113,874)		9,567		430,991
22		-	-		-		101,221		(101,221)		7,608		337,377
23		-	-		-		88,569		(88,569)		5,862		254,670
24		-	-		-		75,916		(75,916)		4,334		183,088
25		-	-		-		63,263		(63,263)		3,029		122,854
26		-	-		-		50,611		(50,611)		1,951		74,194
27		-	-		-		37,958		(37,958)		1,104		37,340
28		-	-		-		25,305	5 (25,305			494		12,529
29		-	-		-		12,653	in	(12,653)		124		-
				\$	3,868,782	\$	4,365,891			\$	491,577		

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area L

	Number of Years to	Interest Rate	Recovery Fee	Annual Vel			Annual		
<u>Year</u>	End of Period	<u>Factor</u>	<u>Factor</u>	<u>Actual</u>	<b>Escalated</b>		<u>Actual</u>	<u> </u>	<u>scalated</u>
1	29	1.7584	1.0000	189	333	\$	21,057	\$	37,027
2	28	1.7240	1.0000	189	326	•	91,191	Ť	157,209
3	27	1.6902	1.0000	189	320		161,312		272,642
4	26	1.6570	1.0000	189	314		231,434		383,488
5	25	1.6245	1.0000	189	308		244,084		396,519
6	24	1.5927	1.0000	189	301		256,735		408,894
7	23	1.5614	1.0000	189	296		269,375		420,612
8	22	1.5308	1.0000	189	290		282,016		431,716
9	21	1.5008	1.0000	189	284		294,646		442,206
10	20	1.4714	1.0000	189	279		307,277		452,121
11	19	1.4425	1.0000	-	-		303,468		437,761
12	18	1.4142	1.0000	-	-		246,006		347,913
13	17	1.3865	1.0000	-	-		188,548		261,425
14 15	16 15	1.3593 1.3327	1.0000	-	-		131,087		178,191
16	14	1.3065	1.0000 1.0000	-	-		131,090 131,089		174,700 171,273
17	13	1.2809	1.0000	_	_		126,527		162,071
18	12	1.2558	1.0000	_	_		126,527		158,893
19	11	1.2312	1.0000	_	_		126,527		155,778
20	10	1.2070	1.0000	_	_		126,527		152,723
21	9	1.1834	1.0000	-	-		113,874		134,756
22	8	1.1602	1.0000	-	-		101,221		117,434
23	7	1.1374	1.0000	-	-		88,569		100,740
24	6	1.1151	1.0000	-	-		75,916		84,656
25	5	1.0933	1.0000	-	-		63,263		69,163
26	4	1.0718	1.0000	-	-		50,611		54,246
27	3	1.0508	1.0000	-	-		37,958		39,886
28	2	1.0302	1.0000	-	-		25,305		26,070
29	1	1.0100	1.0000				12,653		12,779
					3,050			\$	6,242,892
		Annual laterest De	4				2.000/		
		Annual Interest Ra	te:				2.00%		
		Present Value of Ir	nitial Impact Fee	Fund Balance		\$	5,532		
		Total Escalated Ex	pense for Entire	Period		\$	6,242,892		
		Less Future Value	of Initial Impact F	Fee Fund Balance	_		9,824		
		Sub-Total			•	\$	6,233,068		
		Total Escalated Ve	ehicle Miles				3,050	ı	
			\$	2,044					

Capital Improvement Plan for Impact Fees

Appendix E - Impact Fee Calculation Assumptions

Service Area L

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	Cost In Service Area (1)			Impact Fee ecoverable Cost ⁽²⁾	Debt Funded ⁽³⁾ <u>Existing</u> <u>Proposed</u>				Non-Debt Funded ⁽³⁾		Impact Fee Recoverable Cost	
HARRY MCKILLOP BLVD / FM 546 (2)	K-4, L-1	\$	117,300	\$	14,892	\$	-	\$	7,446	\$	7,446	\$	14,892
HARRY MCKILLOP BLVD / FM 546 (3)	K-5, L-2		1,633,700		207,415		-		103,707		103,707		207,415
HARRY MCKILLOP BLVD / FM 546 (S) (1)	L-3		2,153,725		273,437		-		136,719		136,719		273,437
HARRY MCKILLOP BLVD / FM 546 (S) (2)	L-4		3,843,225		487,937		-		243,968		243,968		487,937
HARRY MCKILLOP BLVD / FM 546 (N) (1)	L-5		2,166,900		275,110		-		137,555		137,555		275,110
AIRPORT DR (5)	K-9, L-6		3,161,400		401,372		-		200,686		200,686		401,372
AIRPORT DR (6)	K-10, L-7		1,462,600		185,692		57,132		45,236		83,324		185,692
UNNAMED C (3)	L-8		5,807,850		737,366		-		368,683		368,683		737,366
UNNAMED C (4)	L-9, M-5		1,415,150		179,668		-		89,834		89,834		179,668
UNNAMED C (5)	L-10, M-6		5,001,075		634,937		-		317,469		317,469		634,937
Signal Mod	41		75,000		9,522		-		4,761		4,761		9,522
Signal	42		150,000		19,044		-		9,522		9,522		19,044
Signal	54		150,000		19,044		-		9,522		9,522		19,044
Signal	63		225,000		28,566		-		14,283		14,283		28,566
Signal	70		300,000		38,088		-		19,044		19,044		38,088
Signal	74		150,000		19,044		-		9,522		9,522		19,044
Impact Fee Study			11,692		11,692		-		5,846		5,846		11,692
Total		\$	27,824,617	\$	3,542,826	\$	57,132	\$	1,723,803	\$	1,761,891	\$	3,542,826

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area L

<u>Year</u>	Eligible Debt Service ⁽¹⁾ \$ 17.253		Annual Vehicle <u>Miles</u>	Eligible Debt Service per Vehicle Mile	Annual Growth in Vehicle Miles (Cumulative)	Credit for Annual Ad Valorem <u>Revenues</u>			
1	\$	17,253	606,072	\$ 0.03	189	\$	5		
2		29,940	623,802	0.05	379		18		
3		42,621	641,531	0.07	568		38		
4		55,308	659,260	0.08	757		64		
5	67,990 676,990		0.10	947		95			
6	80,678 694,719		0.12	1,136		132			
7		93,359	712,448	0.13	1,325		174		
8		106,047	730,177	0.15	1,514		220		
9		118,727	747,907	0.16	1,704		270		
10		131,413	765,636	0.17	1,893		325		
11		131,413	765,636	0.17	1,893		325		
12		131,411	765,636	0.17	1,893		325		
13		131,413	765,636	0.17	1,893		325		
14		131,412	765,636	0.17	1,893		325		
15		131,415	765,636	0.17	1,893		325		
16		131,414	765,636	0.17	1,893		325		
17		126,840	765,636	0.17	1,893		314		
18		126,840	765,636	0.17	1,893		314		
19		126,840	765,636	0.17	1,893		314		
20		126,840	765,636	0.17	1,893		314		
21		114,156	765,636	0.15	1,893		282		
22		101,472	765,636	0.13	1,893		251		
23		88,788	765,636	0.12	1,893		220		
24		76,104	765,636	0.10	1,893		188		
25		63,420	765,636	0.08	1,893		157		
26		50,736	765,636	0.07	1,893		125		
27		38,052	765,636	0.05	1,893		94		
28		25,368	765,636	0.03	1,893		63		
29	12,684 765,636		0.02	1,893		31			
Total	\$	2,609,956				\$	5,956		

2019 Vehicle Miles (2)

Ten Year Growth in Vehicle Miles in Service Area (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

- (1) Appendix E Service Area L, Page 2 Section II
- (2) Per Kimley-Horn Impact Fee Study
- (3) Line 8 of the Max Fee Table Report

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area M

### I. General Assumptions

Annual Interest Rate on Deposits (1)
Annual Vehicle Mile Growth (2)
Existing Fund Balance (3)

2.00% 30 \$ -

Portion of Projects Funded by Existing Debt ⁽⁴⁾ Non-debt Funded Project Cost ⁽⁵⁾ New Project Cost Funded Through New Debt ⁽⁶⁾ Total Recoverable Project Cost ⁽⁷⁾

\$ -
334,305
334,305
\$ 668,610

### II. New Debt Issues Assumptions

<u>Year</u>	Principal ⁽⁸⁾	Interest ⁽⁹⁾	<u>Term</u>
1	\$ 33,430	4.00%	20
2	33,430	4.00%	20
3	33,430	4.00%	20
4	33,430	4.00%	20
5	33,430	4.00%	20
6	33,430	4.00%	20
7	33,430	4.00%	20
8	33,430	4.00%	20
9	33,430	4.00%	20
10	33,430	4.00%	20
Total	¢ 224.20E	·	·

### III. Capital Expenditure Assumptions

<u>Year</u>	(	Annual Capital <u>nditures⁽¹⁰⁾</u>
1	\$	33,430
2		44,574
3		55,717
4		66,861
5		66,861
6		66,861
7		66,861
8		66,861
9		66,861
10		66,861
11		33,430
12		22,287
13		11,143
Total	\$	668,610

- (1) Per discussions with City Staff and City files
- (2) Derived from Kimley-Horn Impact Fee Study
- (3) Per discussions with City Staff and City files
- (4) Per discussions with City Staff and City files
- $(5) \quad \text{This assumes 50\% of new project costs funded through sources other than debt, unless specified otherwise}$
- (6) This assumes 50% of new project costs funded through new debt issues, unless specified otherwise
- (7) Per Kimley-Horn Impact Fee Study
- (8) Assumes new debt issued in equal annual amounts
- (9) Per discussions with City Staff and City files
- (10) Assumes new debt proceeds expended over a 3-year timeframe.

Non-debt funded capital expenditures allocated per discussions with City Staff

Total

### City of McKinney - 2019 Roadway Impact Fee Study

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area M

#### I. New Debt Service Detail

Year	Series	Series	Series <u>3</u>	Series	Series <u>5</u>	Series	Series 7	Series	Series	Series	Annual New Debt Service
1	\$ 2,460	\$ -	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-	\$ 2,460
2	2,460	2,460	-	-	-	-	-	-	-	-	4,920
3	2,460	2,460	2,460	-	-	-	-	-	-	-	7,380
4	2,460	2,460	2,460	2,460	-	-	-	-	-	-	9,839
5	2,460	2,460	2,460	2,460	2,460	-	-	-	-	-	12,299
6	2,460	2,460	2,460	2,460	2,460	2,460	-	-	-	-	14,759
7	2,460	2,460	2,460	2,460	2,460	2,460	2,460	-	-	-	17,219
8	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	-	-	19,679
9	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	-	22,139
10	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
11	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
12	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
13	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
14	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
15	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
16	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
17	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
18	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
19	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
20	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	24,599
21	-	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	22,139
22	-	-	2,460	2,460	2,460	2,460	2,460	2,460	2,460	2,460	19,679
23	-	-	-	2,460	2,460	2,460	2,460	2,460	2,460	2,460	17,219
24	-	-	-	-	2,460	2,460	2,460	2,460	2,460	2,460	14,759
25	-	-	-	-	-	2,460	2,460	2,460	2,460	2,460	12,299
26	-	-	-	-	-	-	2,460	2,460	2,460	2,460	9,839
27	-	-	-	-	-	-	-	2,460	2,460	2,460	7,380
28	-	-	-	-	-	-	-	-	2,460	2,460	4,920
29	-	-	-	-	-	-	-	-	-	2,460	2,460
	\$ 49,197	\$ 49,197	\$ 49,197 \$	49,197 \$	49,197 \$	49,197 \$	49,197 \$	49,197 \$	49,197 \$	49,197	\$ 491,975

### II. Summary of Annual Expenses

<u>Year</u>	New Annual Debt <u>Year</u> <u>Service⁽¹⁾</u>		Annual Capital Expenditures ⁽²⁾			Annual Bond Proceeds ⁽²⁾		Existing Annual Debt Service ⁽³⁾	Annual <u>Credit⁽⁴⁾</u>		Total <u>Expense</u>	
1	\$	2,460	\$	33,430	\$	(33,430)	\$	_	\$	(0) \$	2,460	
2	•	4,920	•	44,574		(33,430)	•	-	•	(0)	16,063	
3		7,380		55,717		(33,430)		-		(1)	29,666	
4		9,839		66,861		(33,430)		-		(2)	43,268	
5		12,299		66,861		(33,430)		-		(3)	45,727	
6		14,759		66,861		(33,430)		-		(4)	48,186	
7		17,219		66,861		(33,430)		-		(5)	50,644	
8		19,679		66,861		(33,430)		-		(7)	53,103	
9		22,139		66,861		(33,430)		-		(8)	55,561	
10		24,599		66,861		(33,430)		-		(10)	58,019	
11		24,599		33,430		-		-		(10)	58,019	
12		24,599		22,287		-		-		(10)	46,876	
13		24,599		11,143		-		-		(10)	35,732	
14		24,599		-		-		-		(10)	24,589	
15		24,599		-		-		-		(10)	24,589	
16		24,599		-		-		-		(10)	24,589	
17		24,599		-		-		-		(10)	24,589	
18		24,599		-		-		-		(10)	24,589	
19		24,599		-		-		-		(10)	24,589	
20		24,599		-		-		-		(10)	24,589	
21		22,139		-		-		-		(9)	22,130	
22		19,679		-		-		-		(8)	19,671	
23		17,219		-		-		-		(7)	17,212	
24		14,759		-		-		-		(6)	14,753	
25		12,299		-		-		-		(5)	12,294	
26		9,839		-		-		-		(4)	9,836	
27		7,380		-		-		-		(3)	7,377	
28		4,920		-		-		-		(2)	4,918	
29		2,460		-		-		-		(1)	2,459	
	\$	491,975	\$	668,610	\$	(334,305)	\$	-	\$	(181) \$	826,099	

⁽¹⁾ Appendix E - Service Area M, Page 2 Section I (2) Appendix E - Service Area M, Page 1

⁽³⁾ Eligible debt funded projects as a percent of total principal times original annual debt service

⁽⁴⁾ Appendix E - Service Area M, Page 6

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area M

<u>Year</u>	Impact <u>Fee</u>	Vehicle <u>Miles</u>	mpact Fee <u>evenue</u>	Annual Expenses		Sub-Total	Accumulated <u>Interest</u>	Estimated Fund <u>Balance</u>
Initial								\$ -
1	\$ 2,406	30	\$ 73,149	\$ 2,460	\$	70,689	\$ 707	71,396
2	2,406	30	73,149	16,063		57,086	1,999	130,480
3	2,406	30	73,149	29,666		43,483	3,044	177,008
4	2,406	30	73,149	43,268		29,880	3,839	210,727
5	2,406	30	73,149	45,727		27,421	4,489	242,637
6	2,406	30	73,149	48,186		24,963	5,102	272,703
7	2,406	30	73,149	50,644		22,504	5,679	300,886
8	2,406	30	73,149	53,103		20,046	6,218	327,150
9	2,406	30	73,149	55,561		17,587	6,719	351,456
10	2,406	30	73,149	58,019		15,129	7,180	373,765
11	-	-	-	58,019		(58,019)	6,895	322,641
12	-	-	-	46,876		(46,876)	5,984	281,749
13	-	-	-	35,732		(35,732)	5,278	251,294
14	-	-	-	24,589		(24,589)	4,780	231,485
15	-	-	-	24,589		(24,589)	4,384	211,280
16	-	-	-	24,589		(24,589)	3,980	190,671
17	-	-	-	24,589		(24,589)	3,568	169,649
18	-	-	-	24,589		(24,589)	3,147	148,208
19	-	-	-	24,589		(24,589)	2,718	126,337
20	-	-	-	24,589		(24,589)	2,281	104,029
21	-	-	-	22,130		(22,130)	1,859	83,758
22	-	-	-	19,671		(19,671)	1,478	65,565
23	-	-	-	17,212		(17,212)	1,139	49,492
24	-	-	-	14,753		(14,753)	842	35,581
25	-	-	-	12,294		(12,294)	589	23,875
26	-	-	-	9,836		(9,836)	379	14,419
27	-	-	-	7,377		(7,377)	215	7,257
28	-	-	-	4,918		(4,918)	96	2,435
29	-	-	 -	2,459	_	(2,459)	24	_
			\$ 731,486	\$ 826,099	_	•	\$ 94,613	<del>-</del>

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area M

	Number of	Interest	Recovery						
	Years to	Rate	Fee	Annual Ve	hicle Miles		Annual	Ехрє	ense
<u>Year</u>	End of Period	<u>Factor</u>	<u>Factor</u>	<u>Actual</u>	<b>Escalated</b>		<u>Actual</u>	<u> </u>	<b>Escalated</b>
1	29	1.7584	1.0000	30	53	\$	2,460	\$	4,325
2	28	1.7240	1.0000	30	52		16,063		27,691
3	27	1.6902	1.0000	30	51		29,666		50,139
4	26	1.6570	1.0000	30	50		43,268		71,696
5	25	1.6245	1.0000	30	49		45,727		74,285
6	24	1.5927	1.0000	30	48		48,186		76,744
7	23	1.5614	1.0000	30	47		50,644		79,078
8	22	1.5308	1.0000	30	47		53,103		81,291
9	21	1.5008	1.0000	30	46		55,561		83,387
10	20	1.4714	1.0000	30	45		58,019		85,369
11	19	1.4425	1.0000	-	-		58,019		83,695
12	18	1.4142	1.0000	-	-		46,876		66,294
13	17	1.3865	1.0000	-	-		35,732		49,544
14	16	1.3593	1.0000	-	-		24,589		33,424
15	15	1.3327	1.0000	-	_		24,589		32,769
16	14		1.0000	-	_		24,589		32,127
17	13	1.2809	1.0000	_	_		24,589		31,497
18	12		1.0000	_	_		24,589		30,879
19	11	1.2312	1.0000	_	_		24,589		30,274
20	10	1.2070	1.0000	_	_		24,589		29,680
21	9	1.1834	1.0000	_	_		22,130		26,188
22	8	1.1602	1.0000	_	_		19,671		22,822
23	7		1.0000	_	_		17,212		19,578
24	6	1.1151	1.0000	_	_		14,753		16,452
25	5	1.0933	1.0000	-	-		12,294		13,441
26	4			-	-				
			1.0000	-	-		9,836		10,542
27	3		1.0000	-	-		7,377		7,751
28	2		1.0000	-	-		4,918		5,066
29	1	1.0100	1.0000		- 400		2,459	Ф.	2,483
					490			\$	1,178,511
		A I I - ( I D -					0.000/		
		Annual Interest Ra	te:				2.00%		
		Danie a (Value a)		E I Dala		•			
		Present Value of Ir	ittai impact Fee	Fund Balance		\$	-		
		Tatal Canalatad Cu		Daviad		Φ	4 470 544		
		Total Escalated Ex	-			\$	1,178,511		
		Less Future Value	of Initial Impact I	ee Fund Balance		_	- 4 470 544	-	
		Sub-Total				\$	1,178,511		
		Total Escalated Ve	hicle Miles				490	_	
						_		•	
		Impact Fee For So	ervice Area M			\$	2,406		

Capital Improvement Plan for Impact Fees
Appendix E - Impact Fee Calculation Assumptions
Service Area M

Impact Fee Project Name ⁽¹⁾	Impact Fee Project No. ⁽¹⁾	<u>Sei</u>	Cost In rvice Area (1)	R	Impact Fee ecoverable Cost ⁽²⁾	Debt F Existing	ed ⁽³⁾ Proposed	 lon-Debt unded ⁽³⁾	<u>R</u>	Impact Fee Recoverable Cost
HARRY MCKILLOP BLVD / FM 546 (N) (2)	M-1	\$	98,038	\$	8,200	\$ -	\$ 4,100	\$ 4,100	\$	8,200
HARRY MCKILLOP BLVD / FM 546 (N) (3)	M-2		180,575		15,103	-	7,551	7,551		15,103
HARRY MCKILLOP BLVD / FM 546 (N) (4)	M-3		139,500		11,667	-	5,834	5,834		11,667
HARRY MCKILLOP BLVD / FM 546 (S) (3)	M-4		719,975		60,217	-	30,109	30,109		60,217
UNNAMED C (4)	L-9, M-5		1,415,150		118,360	-	59,180	59,180		118,360
UNNAMED C (5)	L-10, M-6		5,001,075		418,279	-	209,140	209,140		418,279
Signal	64		150,000		12,546	-	6,273	6,273		12,546
Signal	74		150,000		12,546	-	6,273	6,273		12,546
Impact Fee Study			11,692		11,692	-	5,846	5,846		11,692
Total		\$	7,866,005	\$	668,610	\$ -	\$ 334,305	\$ 334,305	\$	668,610

⁽¹⁾ Per Kimley-Horn Impact Fee Study

⁽²⁾ Line 11 of the Max Fee Table Report

⁽³⁾ Per discussions with City staff. For existing debt funding that does not have a specific bond identified, a 4.5% rate is used to coincide with the water and wastewater calculations.

Capital Improvement Plan for Impact Fees Appendix E - Impact Fee Calculation Assumptions Service Area M

<u>Year</u>	ı	Eligible Debt <u>Service⁽¹⁾</u>	Annual Vehicle <u>Miles</u>	Eligible Debt Service per Vehicle Mile	Annual Growth in Vehicle Miles (Cumulative)	A	dit for Annual Ad Valorem <u>Revenues</u>
1	\$	2,460	606,072	\$ 0.00	30	\$	0
2		4,920	623,802	0.01	61		0
3		7,380	641,531	0.01	91		1
4		9,839	659,260	0.01	122		2
5		12,299	676,990	0.02	152		3
6		14,759	694,719	0.02	182		4
7		17,219	712,448	0.02	213		5
8		19,679	730,177	0.03	243		7
9		22,139	747,907	0.03	274		8
10		24,599	765,636	0.03	304		10
11		24,599	765,636	0.03	304		10
12		24,599	765,636	0.03	304		10
13		24,599	765,636	0.03	304		10
14		24,599	765,636	0.03	304		10
15		24,599	765,636	0.03	304		10
16		24,599	765,636	0.03	304		10
17		24,599	765,636	0.03	304		10
18		24,599	765,636	0.03	304		10
19		24,599	765,636	0.03	304		10
20		24,599	765,636	0.03	304		10
21		22,139	765,636	0.03	304		9
22		19,679	765,636	0.03	304		8
23		17,219	765,636	0.02	304		7
24		14,759	765,636	0.02	304		6
25		12,299	765,636	0.02	304		5
26		9,839	765,636	0.01	304		4
27		7,380	765,636	0.01	304		3
28		4,920	765,636	0.01	304		2
29		2,460	765,636	0.00	304		1
Total	\$	491,975				\$	181

2019 Vehicle Miles (2)

Ten Year Growth in Vehicle Miles in Service Area (3)

Annual Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

Ten Year Growth in Vehicle Miles In Other Service Areas (3)

176,989

10 years

Annual Growth in Vehicle Miles

17,699

Credit Amount

\$ 181

- (1) Appendix E Service Area M, Page 2 Section II
- (2) Per Kimley-Horn Impact Fee Study
- (3) Line 8 of the Max Fee Table Report

Land Use Category	Development Unit	Vehicle Miles (per development unit)	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
Single Family Detached	Dwelling Unit	2.85	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34	344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Multi-Family	Dwelling Unit	1.47	\$526.23	\$ 440.35	\$ 404.05	\$ -				84 \$ 353.34		\$ 350.72		\$ 506.34	344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Townhouse/Condominium	Dwelling Unit	1.74		\$ 440.35		+	+	+		84 \$ 353.34		\$ 350.72		\$ 506.34		\$ -	+				\$ 270.38		\$ -		\$ 490.32			\$ 424.72
Mobile Home Park	Dwelling Unit	1.68		\$ 440.35		+ -				84 \$ 353.34		\$ 350.72		+	344.93	\$ -	+				\$ 270.38		\$ -	<del></del>	\$ 490.32			\$ 424.72
Retirement Community	Dwelling Unit	0.84		\$ 440.35		<del> </del>	\$ 586.93			84 \$ 353.34		\$ 350.72	\$ -	+	344.93	\$ -	+				\$ 270.38	\$ -	\$ -	<del>+ · +</del>	\$ 490.32			\$ 424.72
Other Residential Not Specified	Dwelling Unit	2.85		\$ 440.35						84 \$ 353.34		\$ 350.72	\$ -	\$ 506.34		\$ -					\$ 270.38	\$ -	\$ -		\$ 490.32			\$ 424.72
General Office Building	1,000 SF GFA	3.19			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34		\$ -					\$ 270.38		\$ -		\$ 490.32			\$ 424.72
Office Park	1,000 SF GFA	3.52		\$ 440.35			+	+		84 \$ 353.34	+	\$ 350.72		\$ 506.34		\$ -	+				\$ 270.38		\$ -		\$ 490.32			\$ 424.72
Medical/Dental Office	1,000 SF GFA	6.53		\$ 440.35		<del> </del>	+			84 \$ 353.34		\$ 350.72		+	\$ 344.93	Φ -					\$ 270.38		Φ -		\$ 490.32			\$ 424.72
Business Park	1,000 SF GFA	3.55		\$ 440.35		+	\$ 586.93			84 \$ 353.34		\$ 350.72	ψ - Φ -		\$ 344.93	ψ - •	\$ 379.35 \$ 370.35		_		\$ 270.38	Φ -	Φ -		\$ 490.32		\$ 572.24	
Other Office Not Specified	1,000 SF GFA	3.19		\$ 440.35		φ -							φ -	+		φ -	¢ 270.25					φ -	φ -					
General Retail						<b>5 -</b>				84 \$ 353.34		\$ 350.72	<del>ф -</del>	\$ 506.34		Φ -	+ + +		\$ 401.61			ф -	<b>ф</b> -		\$ 490.32		\$ 572.24	+
	1,000 SF GFA	2.17			\$ 404.05	+	+	+		84 \$ 353.34		\$ 350.72		\$ 506.34		\$ -	+				\$ 270.38		<b>ъ</b> -	<del></del>	\$ 490.32		\$ 572.24	
Shopping Center	1,000 SF GFA	6.22	<del> </del>	\$ 440.35	<u> </u>	+ -				84 \$ 353.34		\$ 350.72		\$ 506.34		\$ -	+	_			\$ 270.38	\$ -	\$ -	<del> </del>	\$ 490.32		\$ 572.24	
Discount/Department Store	1,000 SF GFA	4.80		\$ 440.35		<del>+                                    </del>	+			84 \$ 353.34		\$ 350.72	\$ -	+	344.93	\$ -	\$ 379.35		-		\$ 270.38	\$ -	\$ -	<del></del>	\$ 490.32		\$ 572.24	
Supermarket	1,000 SF GFA	8.68		<del> </del>		<del>+                                    </del>	\$ 586.93			84 \$ 353.34		\$ 350.72	\$ -		344.93	\$ -	\$ 379.35			-	\$ 270.38	\$ -	\$ -		\$ 490.32		\$ 572.24	
Quality Restaurant	1,000 SF GFA	2.11		\$ 440.35			<del>-</del>	+		84 \$ 353.34		\$ 350.72		\$ 506.34	_	\$ -	+				\$ 270.38	\$ -	\$ -	+	\$ 490.32	-	\$ 572.24	
Fast Food Restaurant with Drive-Thru	1,000 SF GFA	2.01		\$ 440.35			+			84 \$ 353.34		\$ 350.72		\$ 506.34		\$ -	+				\$ 270.38	\$ -	\$ -		\$ 490.32		\$ 572.24	
High Turnover Restaurant	1,000 SF GFA	1.79		\$ 440.35		\$ -				84 \$ 353.34		\$ 350.72			\$ 344.93	\$ -			\$ 401.61			\$ -	\$ -		\$ 490.32		\$ 572.24	
Convenience Store without Gas	1,000 SF GFA	1.81	\$526.23	\$ 440.35	\$ 404.05	\$ -				84 \$ 353.34		\$ 350.72	\$ -	\$ 506.34	\$ 344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32		\$ 572.24	
Service Station	Pump	0.46	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34	\$ 344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Gas Station with Convenience Store	Pump	0.52	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34	\$ 344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Bank	1,000 SF GFA	1.74	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34	\$ 344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Hotel	Room	1.06	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34	\$ 344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Motel	Room	0.84	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34	\$ 344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
New Car Sales	1,000 SF GFA	2.20	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34	\$ 344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Auto Care Center	1,000 SF GFA	3.66	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34	\$ 344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Furniture Store	1,000 SF GFA	0.49	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	1 \$ -	\$ 350.72	\$ -	\$ 506.34	344.93	\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Apparel Store	1,000 SF GFA	2.73			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34		\$ -	\$ 379.35	\$ 334.62	\$ 401.61	\$ 324.39	\$ 270.38	\$ -	\$ -	\$ 264.28			\$ 572.24	
Building Material/Lumber Store	1,000 SF GFA	4.58			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34			\$ 379.35						\$ -	\$ 264.28			\$ 572.24	
Golf Course/Driving Range	Acre	1.17			\$ 404.05	-				84 \$ 353.34		\$ 350.72		\$ 506.34			\$ 379.35							\$ 264.28			\$ 572.24	
Hardware/Paint Store	1,000 SF GFA	6.82			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34							\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
Garden Center/Nursery	1,000 SF GFA	5.22			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34							\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
Entertainment Center	1,000 SF GFA	5.32			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34							\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
Other Commercial Not Specified	1,000 SF GFA	2.17			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34				-	-	-	\$ 270.38	•	\$ -		\$ 490.32		\$ 572.24	
Elementary School	Student	0.01			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34 \$			\$ 379.35						\$ -		\$ 490.32		\$ 572.24	
High School	Student	0.07			\$ 404.05			+		84 \$ 353.34		\$ 350.72		\$ 506.34 \$							\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
Junior/Community College	Student	0.13			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34	_						\$ 270.38		\$ -	-	\$ 490.32		\$ 572.24	
Day Care Center	Student	0.13			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34 \$							\$ 270.38		φ -		\$ 490.32		\$ 572.24	
· ·		2.07			\$ 404.05					84 \$ 353.34				\$ 506.34 \$							\$ 270.38		\$ -				\$ 572.24	
Hospital	Bed											\$ 350.72											_		\$ 490.32			
Nursing Home	Bed	0.29			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34			\$ 379.35						\$ -		\$ 490.32		\$ 572.24	
Church/Synagogue	1,000 SF GFA	0.50			\$ 404.05					84 \$ 353.34	_	\$ 350.72		\$ 506.34	-						\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
Other Institutional Not Specified	1,000 SF GFA	0.50			\$ 404.05					84 \$ 353.34	_	\$ 350.72		\$ 506.34							\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
General Light Industrial	1,000 SF GFA	0.77			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34							\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
Industrial Park	1,000 SF GFA	2.00			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34			\$ 379.35						\$ -		\$ 490.32		\$ 572.24	
Manufacturing	1,000 SF GFA				\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34							\$ 270.38		\$ -		\$ 490.32		\$ 572.24	+
Warehouse	1,000 SF GFA	1.78			\$ 404.05					84 \$ 353.34		\$ 350.72		\$ 506.34			_				\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
Mini-Warehouse	1,000 SF GFA				\$ 404.05			+		84 \$ 353.34		\$ 350.72		\$ 506.34							\$ 270.38		\$ -		\$ 490.32		\$ 572.24	
Outside Light Industrial	Acre	5.84	\$526.23	\$ 440.35	\$ 404.05	\$ -	\$ 586.93	\$ 387.70	\$ 353.8	84 \$ 353.34	4 \$ -	\$ 350.72	\$ -	\$ 506.34							\$ 270.38		\$ -	\$ 264.28	\$ 490.32	\$ -	\$ 572.24	\$ 424.72
Other Industrial Not Specified	1,000 SF GFA	2.00	\$526.23	\$ 440.35	\$ 404.05	Φ	¢ 586 03	\$ 387 70	¢ 353.9	84 \$ 353.34	1 0	\$ 350.72	Ф	\$ 506.34	1 244 02	Φ.	¢ 270 25	¢ 224 62	¢ 401 61	¢ 224 20	\$ 270.38	¢.	\$ -	\$ 264.28	¢ 400 22	¢.	\$ 572.24	¢ 424.70

				Servi	ce Area 'A'	Combined						
Schedule 1 Table B, Actual Roadway Impact	Final Pl	at Recorded Between: 9/1/	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	Recorded Between: 12/1	/20 - Present*
Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Development Ur
Land Use					PORT AND TERMI							
Truck Terminal	Acre	\$0	\$0	Acre	\$0	\$0	Acre	\$0	\$0	1,000 SF GFA	\$0	\$0
General Light Industrial	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
General Heavy Industrial Industrial Park	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$0	\$0
Warehousing	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0
	·				RESIDENTIAL							
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0
Multifamily Housing (High-Rise)		N/A			N/A	,		N/A		Dwelling Unit	\$0	\$0
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0
Mobile Home Park	Dwelling Unit	\$0	\$0	Dwelling Unit	\$0	\$0		N/A		Dwelling Unit	\$0	\$0
Retirement Community Others Not Specified	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0		N/A N/A			N/A N/A			N/A N/A	
Assisted Living		N/A N/A		Bed	\$0 N/A	\$0	Bed Dwelling Unit	\$0 \$0	\$0 \$0	Beds	\$0 \$0	\$0 \$0
Senior Adult Housing Congregate Care Facility		N/A N/A			N/A		Dwelling Unit  Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit  Dwelling Unit	\$0 \$0	\$0
Hotel	Room	\$0	\$0	Room	LODGING \$0	\$0	Room	\$0	\$0	Rooms	\$0	\$0
Motel/Other Lodging Facilities	Room	\$0 \$0	\$0 \$0	Room	\$0	\$0 \$0	Room	\$0 \$0	\$0	Rooms	\$0 \$0	\$0 \$0
Arena	Acre	\$0	\$0		RECREATIONA N/A			N/A			N/A	
Arena  Bowling Alley	1,000 SF GFA	\$0	\$0		N/A			N/A			N/A	
Driving Range Golf Course	Tee Acre	\$0 \$0	\$0 \$0	Tee Acre	\$0 \$0	\$0 \$0	Tee Acre	\$0 \$0	\$0 \$0	Driving Positions Holes	\$0 \$0	\$0 \$0
Health/Recreational Clubs and Facilities	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Ice Rink Live Theater	1,000 SF GFA Seat	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 0	\$0
Miniature Golf	Hole	\$0	\$0	Hole	\$0	\$0	Hole	\$0	\$0	Holes	\$0	\$0
Multiplex Movie Theater Tennis Courts	Seat Court	\$0 \$0	\$0 \$0	Screen Court	\$0 \$0	\$0 \$0	Screen Court	\$0 \$0	\$0 \$0	Screens Courts	\$0 \$0	\$0 \$0
Terrins Courts	Court	<del>, , , , , , , , , , , , , , , , , , , </del>	٥ڔ	Court	INSTITUTIONA	· ·	Court	, JO	Ų	Courts	ŢŪ	30
Church Day Care Center	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Primary/Middle School (1-8)	Student	\$0	\$0	Student	\$0	\$0 \$0	Student	\$0	\$0 \$0	Student	\$0 \$0	\$0 \$0
High School (9-12)  Jr/Community College	Student Student	\$0 \$0	\$0 \$0	Student Student	\$0 \$0	\$0 \$0	Student Student	\$0 \$0	\$0 \$0	Students Students	\$0 \$0	\$0 \$0
University/College	Student	\$0	\$0	Student	\$0	\$0	Student	\$0	\$0	Students	\$0 \$0	\$0
Clinic	1,000 SF GFA	\$0	\$0	1,000 SF GFA	MEDICAL \$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Hospital	Bed	\$0	\$0	Bed	\$0	\$0	Bed	\$0	\$0	Beds	\$0	\$0
Nursing Home Animal Hospital/Veterinary Clinic	Bed	\$0 N/A	\$0	Bed	\$0 N/A	\$0	Bed 1,000 SF GFA	\$0 \$0	\$0 \$0	Beds 1,000 SF GFA	\$0 \$0	\$0 \$0
					OFFICE		·	, , ,	70	·	Ψ.	, , ,
Corporate Headquarters Building General Office Building	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Medical/Dental Office	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Single Tenant Office Building Office Park	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Others Not Specified	1,000 SF GFA	\$0	\$0		N/A	·	_,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	N/A	70		N/A	75
					COMMERCIAL Automobile Rela							
Automobile Care Center	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GLA	\$0	\$0
Automobile Parts Sales Gasoline/Service Station w/ Convenience Market	1,000 SF GFA Fueling Position	\$0 \$0	\$0 \$0	1,000 SF GFA Fueling Position	\$0 \$0	\$0 \$0	1,000 SF GFA Fueling Position	\$0 \$0	\$0 \$0	1,000 SF GFA /ehicle Fueling Position	\$0 \$0	\$0 \$0
Convenience Market with 12 or More Fueling Positions	Fueling Position	\$0	\$0		N/A	, , ,		N/A	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		N/A	, ,,
Convenience Market with Less than 12 Fueling Positions  New and Used Car Sales	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$0	\$0
Quick Lubrication Vehicle Center	Service Position	\$0	\$0	Service Position	\$0	\$0	Service Position	\$0	\$0	Servicing Positions	\$0	\$0
Self-Service Car Wash Automated Car Wash	Stall	\$0 N/A	\$0	Stall 1,000 SF GFA	\$0 \$0	\$0 \$0	Stall	\$0 N/A	\$0	Stalls	\$0 N/A	\$0
Tire Store	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Fast Food Restaurant	1,000 SF GFA	\$0	\$0	1,000 SF GFA	Dining \$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Fast Food Restaurant without Drive-Thru	1,000 SF GFA	\$0	\$0		N/A			N/A			N/A	
High Turnover (Sit-down) Restaurant Sit-Down Restaurant	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Coffee / Donut Shop		N/A			N/A			N/A		1,000 SF GFA	\$0	\$0
Free-Standing Retail Store	1,000 SF GFA	\$0	\$0	1,000 SF GFA	Other Retail \$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Garden Center (Nursery)		N/A	•	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Home Improvement Superstore Pharmacy/Drugstore	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Shopping Center	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GLA	\$0	\$0
Supermarket  Video Arcade	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0
Video Rental Store	1,000 SF GFA	\$0	\$0		N/A	4-	4 222 57 1	N/A	1-		N/A	
Toy/Children's Superstore		N/A		1,000 SF GFA	\$0 Wholesale	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Wholesale Market	1,000 SF GFA	\$0	\$0		N/A			N/A			N/A	
Bank (Walk-In)	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$5 \$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Bank (Drive-In)	Drive-in Lanes	\$0	\$0	Drive-in Lane	\$0	\$0	Drive-in Lane	\$0	\$0	Drive-in Lanes	\$0	\$0
Personal Service		N/A			N/A			N/A		1,000 SF GFA	\$0	\$0

Truck Terminal  General Light Industrial  General Heavy Industrial  Industrial Park  Industrial Park  Warehousing  Mini-Warehouse  Others Not Specified  Single Family Detached Housing  Apartment/Multi-family  Multifamily Housing (High-Rise)  Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Dw  Retirement Community  Dw		\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$	Acre  1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA Dwelling Unit	Recorded Between: 11/10/  Maximum Assessable Fee Per Development Unit  PORT AND TERMI \$8,164  INDUSTRIAL \$1,215 \$841 \$1,059 \$405 \$327 N/A RESIDENTIAL	Actual Fee Charged Per Development Unit	Pinal Plat  Development Unit  Acre  1,000 SF GFA	Maximum Assessable Fee Per Development Unit		Development Unit	Maximum Assessable Fee Per Development Unit	
Fee Charged Per Development Unit  Land Use  Truck Terminal  General Light Industrial Industrial Park Industrial Park Warehousing Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Park Industrial Pa	Acre  .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$	Acre  1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA Dwelling Unit	Maximum Assessable Fee Per Development Unit  PORT AND TERMI \$8,164  INDUSTRIAL \$1,215 \$841 \$1,059 \$405 \$327 N/A	Actual Fee Charged Per Development Unit  NAL  \$2,658  \$547 \$841 \$568	Acre 1,000 SF GFA	Maximum Assessable Fee Per Development Unit \$4,512	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit
Truck Terminal  General Light Industrial  General Heavy Industrial  Industrial Park  Warehousing  Mini-Warehouse  Others Not Specified  Single Family Detached Housing  Apartment/Multi-family  Multifamily Housing (High-Rise)  Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Retirement Community  Others Not Specified  Assisted Living  Senior Adult Housing	Acre  .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA	\$0  \$0  \$0  \$0  \$0  \$0  \$0  \$0  \$0  \$0	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0	Acre  1,000 SF GFA  1,000 SF GFA  1,000 SF GFA  1,000 SF GFA  1,000 SF GFA  Dwelling Unit	Per Development Unit  PORT AND TERMI  \$8,164  INDUSTRIAL  \$1,215  \$841  \$1,059  \$405  \$327  N/A	\$2,658 \$547 \$841 \$568	Acre 1,000 SF GFA	Per Development Unit \$4,512	Development Unit		Per Development Unit	Development Unit
Truck Terminal  General Light Industrial  I,0  General Heavy Industrial  Industrial Park  I,0  Warehousing  Mini-Warehouse  I,0  Others Not Specified  Single Family Detached Housing  Apartment/Multi-family  Multifamily Housing (High-Rise)  Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Dw  Retirement Community  Dw  Assisted Living  Senior Adult Housing	.,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .)0welling Unit Dwelling Unit	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 N/A \$0 N/A	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA Dwelling Unit	\$8,164 INDUSTRIAL \$1,215 \$841 \$1,059 \$405 \$327 N/A	\$2,658 \$547 \$841 \$568	1,000 SF GFA		\$2,658	1,000 SF GFA	\$2,658	\$2,658
General Light Industrial 1,0 General Heavy Industrial 1,0 Industrial Park 1,0 Warehousing 1,0 Mini-Warehouse 1,0 Others Not Specified 1,0  Single Family Detached Housing Dw Apartment/Multi-family Dw Multifamily Housing (High-Rise) Residential Condominium/Townhouse Dw Mid-Rise Residential with 1st Floor Commercial Mobile Home Park Dw Retirement Community Dw Others Not Specified Dw Assisted Living Senior Adult Housing	.,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .,000 SF GFA .)0welling Unit Dwelling Unit	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 N/A \$0 N/A	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA Dwelling Unit	\$8,164 INDUSTRIAL \$1,215 \$841 \$1,059 \$405 \$327 N/A	\$2,658 \$547 \$841 \$568	1,000 SF GFA		\$2,658	1,000 SF GFA	\$2,658	\$2,658
General Heavy Industrial  Industrial Park  Warehousing  Mini-Warehouse  Others Not Specified  Single Family Detached Housing  Apartment/Multi-family  Multifamily Housing (High-Rise)  Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Retirement Community  Others Not Specified  Dw  Assisted Living  Senior Adult Housing	2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 N/A \$0 N/A	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA 1,000 SF GFA Dwelling Unit	\$1,215 \$841 \$1,059 \$405 \$327 N/A	\$841 \$568		¢C73				
Industrial Park  Warehousing  Mini-Warehouse  Others Not Specified  Single Family Detached Housing  Apartment/Multi-family  Multifamily Housing (High-Rise)  Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Dw  Retirement Community  Others Not Specified  Dw  Assisted Living  Senior Adult Housing	2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000 SF GFA 2,000	\$0 \$0 \$0 \$0 \$0 \$0 N/A \$0 N/A	\$0 \$0 \$0 \$0 \$0 \$0	1,000 SF GFA 1,000 SF GFA 1,000 SF GFA Dwelling Unit	\$1,059 \$405 \$327 N/A	\$568		\$672	\$547	1,000 SF GFA	\$897	\$547
Warehousing  Mini-Warehouse  Others Not Specified  Single Family Detached Housing  Apartment/Multi-family  Multifamily Housing (High-Rise)  Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Dw  Retirement Community  Others Not Specified  Assisted Living  Senior Adult Housing	owelling Unit  Owelling Unit  Owelling Unit  Owelling Unit  Owelling Unit	\$0 \$0 \$0 \$0 \$0 N/A \$0 N/A	\$0 \$0 \$0 \$0 \$0 \$0	1,000 SF GFA 1,000 SF GFA  Dwelling Unit	\$405 \$327 N/A		1,000 SF GFA 1,000 SF GFA	\$465 \$585	\$464 \$568	1,000 SF GFA	N/A \$569	\$568
Others Not Specified 1,0  Single Family Detached Housing Dw Apartment/Multi-family Dw Multifamily Housing (High-Rise) Residential Condominium/Townhouse Dw Mid-Rise Residential with 1st Floor Commercial Mobile Home Park Dw Retirement Community Dw Others Not Specified Dw Assisted Living Senior Adult Housing	Owelling Unit Owelling Unit Owelling Unit Owelling Unit Owelling Unit	\$0 \$0 \$0 N/A \$0 N/A	\$0 \$0 \$0	Dwelling Unit	N/A	· ·	1,000 SF GFA	\$224	\$223	1,000 SF GFA	\$274	\$263
Apartment/Multi-family  Multifamily Housing (High-Rise)  Residential Condominium/Townhouse  Dw  Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Dw  Retirement Community  Others Not Specified  Assisted Living  Senior Adult Housing	Owelling Unit Owelling Unit Owelling Unit Owelling Unit	\$0 N/A \$0 N/A	\$0		RESIDENTIAL	\$212	1,000 SF GFA	\$181 N/A	\$180	1,000 SF GFA	\$241 N/A	\$212
Apartment/Multi-family  Multifamily Housing (High-Rise)  Residential Condominium/Townhouse  Dw  Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Dw  Retirement Community  Others Not Specified  Assisted Living  Senior Adult Housing	Owelling Unit Owelling Unit Owelling Unit Owelling Unit	\$0 N/A \$0 N/A	\$0		\$1,262	\$811	Dwelling Unit	\$689	\$688	Dwelling Unit	\$1,411	\$811
Residential Condominium/Townhouse Dw Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park Dw Retirement Community Dw Others Not Specified Dw Assisted Living Senior Adult Housing	Owelling Unit Owelling Unit	\$0 N/A		Dwelling Unit	\$779	\$507	Dwelling Unit	\$431	\$430	Dwelling Unit	\$624	\$507
Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park  Dw  Retirement Community  Others Not Specified  Assisted Living  Senior Adult Housing	Owelling Unit Owelling Unit	N/A	\$0	Dwelling Unit	N/A \$654	\$426	Dwelling Unit	N/A \$362	\$361	Dwelling Unit Dwelling Unit	\$514 \$799	\$507 \$426
Retirement Community Dw Others Not Specified Dw Assisted Living Senior Adult Housing	Welling Unit	SO I	•		N/A			N/A		Dwelling Unit	\$514	\$507
Assisted Living Senior Adult Housing	)welling Unit	\$0	\$0 \$0	Dwelling Unit	\$732 N/A	\$656		N/A N/A		Dwelling Unit	\$656 N/A	\$656
Senior Adult Housing		\$0 N/A	\$0	Bed	N/A \$280	\$182	Bed	N/A \$155	\$154	Beds	N/A \$372	\$182
Congregate Care Facility		N/A		Deu	N/A	. γ102	Dwelling Unit	\$172	\$172	Dwelling Unit	\$372	\$202
		N/A			N/A LODGING		Dwelling Unit	\$121	\$120	Dwelling Unit	\$252	\$142
	Room	\$0	\$0 \$0	Room	\$732	\$487	Room	\$413	\$413	Rooms	\$853	\$487
Motel/Other Lodging Facilities	Room	\$0	\$0	Room	\$592 RECREATIONA	\$385 L	Room	\$327	\$327	Rooms	\$536	\$385
Arena  Bowling Alley 1,0	Acre .,000 SF GFA	\$0 \$0	\$0 \$0		N/A N/A			N/A N/A			N/A N/A	
Driving Range	Tee	\$0	\$0	Tee	\$1,558	\$1,014	Tee	\$861	\$861	Driving Positions	\$1,783	\$1,014
Golf Course  Health/Recreational Clubs and Facilities 1,0	Acre .,000 SF GFA	\$0 \$0	\$0 \$0	Acre 1,000 SF GFA	\$374 \$2,041	\$243 \$2,040	Acre 1,000 SF GFA	\$207 \$1,886	\$206 \$1,885	Holes 1,000 SF GFA	\$4,135 \$3,282	\$243 \$2,222
Ice Rink 1,0	,000 SF GFA	\$0	\$0	1,000 SF GFA	\$2,945	\$1,892	1,000 SF GFA	\$1,627	\$1,627	1,000 SF GFA	\$1,893	\$1,892
Live Theater  Miniature Golf	Seat Hole	\$0 \$0	\$0 \$0	Hole	N/A \$405	\$263	Hole	N/A \$224	\$223	Holes	N/A \$470	\$263
Multiplex Movie Theater Tennis Courts	Seat Court	\$0 \$0	\$0 \$0	Screen Court	\$16,998 \$4,175	\$10,258 \$2,719	Screen Court	\$9,394 \$2,307	\$9,393 \$2,307	Screens Courts	\$19,528 \$5,437	\$10,258 \$2,719
Termis Courts	Court	Ş0	Ş0	Court	INSTITUTIONA	<u> </u>	Court	\$2,307	\$2,307	Courts	\$5,437	\$2,719
·	,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$826 \$16,421	\$446 \$5,017	1,000 SF GFA 1,000 SF GFA	\$379 \$4,761	\$378 \$4,761	1,000 SF GFA 1,000 SF GFA	\$700 \$8,861	\$446 \$5,017
Primary/Middle School (1-8)	Student	\$0	\$0	Student	\$187	\$130	Student	\$112	\$111	Student	\$241	\$130
· ,	Student Student	\$0 \$0	\$0 \$0	Student Student	\$171 \$156	\$101 \$101	Student Student	\$86 \$86	\$86 \$86	Students Students	\$197 \$153	\$101 \$101
University/College S	Student	\$0	\$0	Student	\$265 MEDICAL	\$141	Student	\$121	\$120	Students	\$219	\$141
Clinic 1,0	.,000 SF GFA	\$0	\$0	1,000 SF GFA	\$6,450	\$4,201	1,000 SF GFA	\$3,565	\$3,564	1,000 SF GFA	\$4,660	\$4,201
Hospital  Nursing Home	Bed Bed	\$0 \$0	\$0 \$0	Bed Bed	\$1,620 \$280	\$1,156 \$181	Bed Bed	\$982 \$155	\$981 \$154	Beds Beds	\$2,691 \$317	\$1,156 \$181
Animal Hospital/Veterinary Clinic		N/A	7-		N/A	, , , , ,	1,000 SF GFA	\$2,273	\$2,273	1,000 SF GFA	\$3,512	\$2,679
Corporate Headquarters Building 1,0	.,000 SF GFA	\$0	\$0	1,000 SF GFA	<b>OFFICE</b> \$1,745	\$853	1,000 SF GFA	\$973	\$853	1,000 SF GFA	\$853	\$853
	.,000 SF GFA .,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$1,854 \$4,643	\$1,207 \$2,902	1,000 SF GFA 1,000 SF GFA	\$1,025 \$2,462	\$1,024 \$2,462	1,000 SF GFA 1,000 SF GFA	\$1,641 \$4,923	\$1,207 \$2,902
Single Tenant Office Building 1,0	,000 SF GFA	\$0	\$0	1,000 SF GFA	\$2,150	\$1,410	1,000 SF GFA	\$1,197	\$1,196	1,000 SF GFA	\$2,429	\$1,410
	,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$1,870 N/A	\$1,197	1,000 SF GFA	\$1,016 N/A	\$1,015	1,000 SF GFA	\$1,521 N/A	\$1,197
	,	·			COMMERCIAL			·				
Automobile Care Center 1,0	,000 SF GFA	\$0	\$0	1,000 SF GFA	Automobile Rela \$2,524	\$1,522	1,000 SF GFA	\$1,292	\$1,291	1,000 SF GLA	\$2,658	\$1,522
	,000 SF GFA eling Position	\$0 \$0	\$0 \$0	1,000 SF GFA Fueling Position	\$4,253 \$5,500	\$2,770 \$1,115	1,000 SF GFA Fueling Position	\$2,351 \$3,065	\$2,350 \$1,115	1,000 SF GFA 'ehicle Fueling Position	\$3,982 1 \$4,048	\$2,770 \$1,115
Convenience Market with 12 or More Fueling Positions Fuel	eling Position	\$0	\$0	i deinig FOSILION	N/A	, 1,11J	i ucillig FUSIUUII	N/A	ر 1,11,	emole ruelling Position	N/A	γ1,113
	.,000 SF GFA .,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$2,633	\$1,704	1,000 SF GFA	N/A \$1,446	\$1,446	1,000 SF GFA	N/A \$2,757	\$1,704
Quick Lubrication Vehicle Center Serv	rvice Position	\$0	\$0	Service Position	\$3,879	\$2,453	Service Position	\$2,144	\$2,143	Servicing Positions	\$4,135	\$2,453
Self-Service Car Wash Automated Car Wash	Stall	\$0 N/A	\$0	Stall 1,000 SF GFA	\$3,100 \$6,528	\$2,019 \$869	Stall	\$1,713 N/A	\$1,713	Stalls	\$2,177 N/A	\$2,019
Tire Store 1,0	.,000 SF GFA	\$0	\$0	1,000 SF GFA	\$4,518 <b>Dining</b>	\$2,425	1,000 SF GFA	\$2,058	\$2,057	1,000 SF GFA	\$4,081	\$2,425
·	.,000 SF GFA	\$0	\$0	1,000 SF GFA	\$21,594	\$12,038	1,000 SF GFA	\$11,245	\$11,244	1,000 SF GFA	\$23,237	\$12,038
·	.,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$7,759	\$4,119	1,000 SF GFA	N/A \$3,866	\$3,865	1,000 SF GFA	N/A \$7,921	\$4,119
Sit-Down Restaurant 1,0	,000 SF GFA	\$0	\$0	1,000 SF GFA	\$5,219	\$3,399	1,000 SF GFA	\$2,884	\$2,884	1,000 SF GFA	\$6,214	\$3,399
Coffee / Donut Shop		N/A			N/A Other Retail			N/A		1,000 SF GFA	\$18,500	\$4,119
Free-Standing Retail Store 1,0 Garden Center (Nursery)	,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA 1,000 SF GFA	\$4,409 \$3,319	\$2,831 \$3,318	1,000 SF GFA 1,000 SF GFA	\$2,402 \$3,349	\$2,402 \$3,349	1,000 SF GFA 1,000 SF GFA	\$4,803 \$6,914	\$2,831 \$3,699
Home Improvement Superstore		N/A		1,000 SF GFA	\$2,150	\$984	1,000 SF GFA	\$835	\$835	1,000 SF GFA	\$1,925	\$984
7, 9	.,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$5,484 \$3,085	\$4,099 \$1,989	1,000 SF GFA 1,000 SF GFA	\$3,478 \$1,688	\$3,478 \$1,687	1,000 SF GFA 1,000 SF GLA	\$7,472 \$3,566	\$4,099 \$1,989
Supermarket 1,0	,000 SF GFA	\$0	\$0	1,000 SF GFA	\$8,335	\$4,931	1,000 SF GFA	\$4,184	\$4,184	1,000 SF GFA	\$8,402	\$4,931
·	.,000 SF GFA .,000 SF GFA	\$0 \$0	\$0 \$0		N/A N/A			N/A N/A			N/A N/A	
Toy/Children's Superstore		N/A		1,000 SF GFA	\$4,347 Wholesale	\$2,831	1,000 SF GFA	\$2,402	\$2,402	1,000 SF GFA	\$4,978	\$2,831
Wholesale Market 1,0	,000 SF GFA	\$0	\$0		N/A			N/A			N/A	
Bank (Walk-In) 1,0	.,000 SF GFA	\$0	\$0	1,000 SF GFA	\$ <b>ERVICES</b> \$24,788	\$427	1,000 SF GFA	\$5,011	\$427	1,000 SF GFA	\$10,349	\$427
Bank (Drive-In) Dri	Orive-in Lane	\$0	\$0	Drive-in Lane	\$30,210	\$427	Drive-in Lane	\$12,140	\$427	Drive-in Lanes	\$25,107	\$427
Personal Service		N/A			N/A plat is within the listed da		l	N/A		1,000 SF GFA	\$1,455	\$427

				Servi	ce Area 'C'	Combined						
chedule 1 Table B, Actual Roadway Impact	Final Pla	at Recorded Between: 9/1/0	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	/08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	t Recorded Between: 12/1	/20 - Present*
Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Development Un
Land Use					PORT AND TERMI	NAL						
Truck Terminal	Acre	\$17,456	\$14,952	Acre	\$31,156 INDUSTRIAL	\$14,952	Acre	\$30,465	\$14,952	1,000 SF GFA	\$21,004	\$14,952
General Light Industrial	1,000 SF GFA	\$2,613	\$1,879	1,000 SF GFA	\$4,663	\$1,879	1,000 SF GFA	\$4,515	\$1,879	1,000 SF GFA	\$7,076	\$1,879
General Heavy Industrial Industrial Park	1,000 SF GFA 1,000 SF GFA	\$1,814 \$2,450	\$1,814 \$2,351	1,000 SF GFA 1,000 SF GFA	\$3,237 \$4,096	\$890 \$2,351	1,000 SF GFA 1,000 SF GFA	\$3,165 \$3,960	\$890 \$2,351	1,000 SF GFA	N/A \$4,493	\$2,351
Warehousing Mini-Warehouse	1,000 SF GFA 1,000 SF GFA	\$1,624 \$774	\$1,624 \$716	1,000 SF GFA 1,000 SF GFA	\$2,807 \$1,243	\$1,742 \$716	1,000 SF GFA 1,000 SF GFA	\$1,485 \$1,215	\$1,485 \$716	1,000 SF GFA 1,000 SF GFA	\$2,134 \$1,909	\$1,742 \$716
Others Not Specified	1,000 SF GFA	\$2,613	\$2,612	1,000 SF GFA	N/A	·	1,000 SF GFA	N/A	\$710	1,000 SF GFA	N/A	\$/10
Single Family Detached Housing	Dwelling Unit	\$2,690	\$2,690	Dwelling Unit	\$4,801	\$4,484	Dwelling Unit	\$4,650	\$4,484	Dwelling Unit	\$11,120	\$4,484
Apartment/Multi-family	Dwelling Unit	\$1,650	\$1,650	Dwelling Unit	\$2,945	\$2,945	Dwelling Unit	\$2,880	\$2,880	Dwelling Unit	\$4,942	\$3,398
Multifamily Housing (High-Rise) Residential Condominium/Townhouse	Dwelling Unit	N/A \$1,435	\$1,435	Dwelling Unit	N/A \$2,470	\$2,469	Dwelling Unit	N/A \$2,415	\$2,415	Dwelling Unit  Dwelling Unit	\$4,044 \$6,290	\$3,398 \$2,848
Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park	Dwelling Unit	N/A \$1,496	\$1,495	Dwelling Unit	N/A \$2,807	\$2,807		N/A N/A		Dwelling Unit Dwelling Unit	\$4,044 \$5,167	\$3,398 \$4,484
Retirement Community	Dwelling Unit	\$722	\$1,495 \$722	Dwelling Offit	N/A	\$2,807		N/A		Dwelling Offic	N/A	34,464
Others Not Specified  Assisted Living	Dwelling Unit	\$2,690 N/A	\$2,690	Bed	N/A \$1,043	\$1,043	Bed	N/A \$1,020	\$1,020	Beds	N/A \$2,920	\$1,203
Senior Adult Housing		N/A		Dea	N/A	<b>V1,043</b>	Dwelling Unit	\$1,170	\$1,170	Dwelling Unit	\$2,920	\$1,380
Congregate Care Facility		N/A			N/A LODGING		Dwelling Unit	\$795	\$795	Dwelling Unit	\$2,022	\$937
Hotel	Room	\$1,624	\$1,438	Room	\$2,807	\$1,438	Room	\$2,790	\$1,438	Rooms	\$5,419	\$1,438
Motel/Other Lodging Facilities	Room	\$1,255	\$1,254	Room	\$2,240 RECREATIONA	\$1,371 L	Room	\$2,190	\$1,371	Rooms	\$3,426	\$1,371
Arena Povelin - Allen	Acre	\$88,804	\$88,803		N/A			N/A			N/A	
Bowling Alley Driving Range	1,000 SF GFA Tee	\$9,429 \$3,335	\$9,428 \$2,352	Tee	N/A \$5,952	\$2,352	Tee	N/A \$5,820	\$2,352	Driving Positions	N/A \$13,787	\$2,352
Golf Course  Health/Recreational Clubs and Facilities	Acre 1,000 SF GFA	\$1,040 \$4,667	\$969 \$1,494	Acre 1,000 SF GFA	\$1,427 \$7,793	\$969 \$1,494	Acre 1,000 SF GFA	\$1,395 \$12,735	\$969 \$1,494	Holes 1,000 SF GFA	\$32,124 \$25,497	\$969 \$1,494
Ice Rink	1,000 SF GFA	\$4,667	\$1,494	1,000 SF GFA 1,000 SF GFA	\$11,229	\$1,494	1,000 SF GFA 1,000 SF GFA	\$12,735	\$1,494	1,000 SF GFA 1,000 SF GFA	\$25,497	\$1,494
Live Theater  Miniature Golf	Seat Hole	\$52 \$877	\$52 \$835	Hole	N/A \$1,565	\$835	Hole	N/A \$1,530	\$835	Holes	N/A \$3,650	\$835
Multiplex Movie Theater	Seat	\$370	\$369	Screen	\$64,858	\$12,385	Screen	\$63,420	\$12,385	Screens	\$154,215	\$12,385
Tennis Courts	Court	\$10,340	\$1,443	Court	\$15,938 INSTITUTIONA	\$1,443 I	Court	\$15,585	\$1,443	Courts	\$42,148	\$1,443
Church	1,000 SF GFA	\$1,195	\$1,050	1,000 SF GFA	\$2,132	\$1,050	1,000 SF GFA	\$1,740	\$1,050	1,000 SF GFA	\$5,504	\$1,050
Day Care Center Primary/Middle School (1-8)	1,000 SF GFA Student	\$23,825 \$292	\$4,860 \$207	1,000 SF GFA Student	\$42,461 \$491	\$4,860 \$207	1,000 SF GFA Student	\$21,765 \$510	\$4,860 \$207	1,000 SF GFA Student	\$30,607 \$842	\$4,860 \$207
High School (9-12)	Student	\$275	\$207	Student	\$445	\$207	Student	\$405	\$207	Students	\$702	\$207
Jr/Community College University/College	Student Student	\$309 \$378	\$202 \$323	Student Student	\$384 \$675	\$202 \$323	Student Student	\$375 \$540	\$202 \$323	Students Students	\$1,236 \$1,685	\$202 \$323
					MEDICAL							
Clinic Hospital	1,000 SF GFA Bed	\$13,804 \$3,249	\$4,821 \$2,269	1,000 SF GFA Bed	\$24,636 \$6,182	\$4,821 \$2,269	1,000 SF GFA Bed	\$24,090 \$6,600	\$4,821 \$2,269	1,000 SF GFA Beds	\$36,841 \$21,228	\$4,821 \$2,269
Nursing Home	Bed	\$456	\$455	Bed	\$1,043	\$527	Bed	\$1,020	\$527	Beds	\$2,471	\$527
Animal Hospital/Veterinary Clinic		N/A			N/A <b>OFFICE</b>		1,000 SF GFA	\$15,345	\$4,821	1,000 SF GFA	\$27,743	\$4,821
Corporate Headquarters Building General Office Building	1,000 SF GFA 1,000 SF GFA	\$3,704 \$3,971	\$2,670 \$2,850	1,000 SF GFA 1,000 SF GFA	\$6,658 \$7,087	\$2,670 \$2,850	1,000 SF GFA 1,000 SF GFA	\$6,555 \$6,930	\$2,670 \$2,850	1,000 SF GFA 1,000 SF GFA	\$6,739 \$12,917	\$2,670 \$2,850
Medical/Dental Office	1,000 SF GFA	\$9,755	\$5,618	1,000 SF GFA	\$17,687	\$5,618	1,000 SF GFA	\$16,605	\$5,618	1,000 SF GFA	\$38,863	\$5,618
Single Tenant Office Building Office Park	1,000 SF GFA 1,000 SF GFA	\$4,581 \$3,997	\$3,297 \$2,863	1,000 SF GFA 1,000 SF GFA	\$8,222 \$7,133	\$3,297 \$2,863	1,000 SF GFA 1,000 SF GFA	\$8,085 \$6,885	\$3,297 \$2,863	1,000 SF GFA 1,000 SF GFA	\$19,207 \$12,018	\$3,297 \$2,863
Others Not Specified	1,000 SF GFA	\$3,971	\$3,970	1,000 31 017	N/A		1,000 31 017	N/A	72,003	1,000 31 3171	N/A	72,003
				_	COMMERCIAL Automobile Rela		_					
Automobile Care Center	1,000 SF GFA	\$5,406	\$3,856	1,000 SF GFA	\$9,649	\$3,856	1,000 SF GFA	\$8,700	\$3,856	1,000 SF GLA	\$11,709	\$3,856
Automobile Parts Sales Gasoline/Service Station w/ Convenience Market	1,000 SF GFA Fueling Position	\$9,085 \$4,358	\$6,018 \$900	1,000 SF GFA Fueling Position	\$16,214 \$5,415	\$6,018 \$900	1,000 SF GFA Fueling Position	\$15,855 \$5,340	\$6,018 \$900	1,000 SF GFA ehicle Fueling Position	\$17,522 \$10,390	\$6,018 \$900
Convenience Market with 12 or More Fueling Positions	Fueling Position	\$2,991	\$2,991	<u> </u>	N/A		<u> </u>	N/A	· ·		N/A	
Convenience Market with Less than 12 Fueling Positions  New and Used Car Sales	1,000 SF GFA 1,000 SF GFA	\$3,034 \$5,965	\$3,034 \$3,498	1,000 SF GFA	N/A \$10,032	\$3,498	1,000 SF GFA	N/A \$9,765	\$3,498	1,000 SF GFA	N/A \$15,247	\$3,498
Quick Lubrication Vehicle Center Self-Service Car Wash	Service Position Stall	\$8,294 \$1,788	\$2,117 \$489	Service Position Stall	\$14,788 \$3,053	\$2,117 \$489	Service Position Stall	\$14,460 \$2,985	\$2,117 \$489	Servicing Positions Stalls	\$18,224 \$5,588	\$2,117 \$489
Automated Car Wash	Stall	N/A	Ş469	1,000 SF GFA	\$6,427	\$323	Stall	\$2,985 N/A	Ş469	Stalls	N/A	\$469
Tire Store	1,000 SF GFA	\$7,907	\$6,030	1,000 SF GFA	\$17,211 Dining	\$6,030	1,000 SF GFA	\$13,905	\$6,030	1,000 SF GFA	\$17,971	\$6,030
Fast Food Restaurant	1,000 SF GFA	\$34,457	\$9,508	1,000 SF GFA	\$63,630	\$9,508	1,000 SF GFA	\$58,785	\$9,508	1,000 SF GFA	\$129,393	\$9,508
Fast Food Restaurant without Drive-Thru High Turnover (Sit-down) Restaurant	1,000 SF GFA 1,000 SF GFA	\$26,911 \$12,746	\$26,910 \$3,578	1,000 SF GFA	N/A \$22,857	\$3,578	1,000 SF GFA	N/A \$20,190	\$3,578	1,000 SF GFA	N/A \$44,114	\$3,578
Sit-Down Restaurant	1,000 SF GFA	\$8,638	\$4,729	1,000 SF GFA	\$15,401	\$4,729	1,000 SF GFA	\$15,090	\$4,729	1,000 SF GFA	\$34,595	\$4,729
Coffee / Donut Shop		N/A			N/A Other Retail			N/A		1,000 SF GFA	\$103,026	\$3,578
Free-Standing Retail Store	1,000 SF GFA	\$7,907	\$4,824	1,000 SF GFA	\$16,828	\$4,824	1,000 SF GFA	\$16,230	\$4,824	1,000 SF GFA	\$26,564	\$4,824
Garden Center (Nursery)  Home Improvement Superstore		N/A N/A		1,000 SF GFA 1,000 SF GFA	\$12,656 \$8,176	\$3,527 \$4,558	1,000 SF GFA 1,000 SF GFA	\$22,605 \$5,625	\$3,527 \$4,558	1,000 SF GFA 1,000 SF GFA	\$38,217 \$10,614	\$3,527 \$4,558
Pharmacy/Drugstore	1,000 SF GFA	\$14,130	\$3,719	1,000 SF GFA	\$20,924	\$3,719	1,000 SF GFA	\$23,490	\$3,719	1,000 SF GFA	\$41,278	\$3,719
Shopping Center Supermarket	1,000 SF GFA 1,000 SF GFA	\$6,575 \$19,631	\$5,021 \$6,861	1,000 SF GFA 1,000 SF GFA	\$11,796 \$31,815	\$5,021 \$6,861	1,000 SF GFA 1,000 SF GFA	\$11,400 \$28,230	\$5,021 \$6,861	1,000 SF GLA 1,000 SF GFA	\$19,740 \$46,472	\$5,021 \$6,861
Video Arcade	1,000 SF GFA	\$14,173	\$14,173		N/A			N/A			N/A	
Video Rental Store Toy/Children's Superstore	1,000 SF GFA	\$18,118 N/A	\$18,118	1,000 SF GFA	N/A \$16,598	\$4,626	1,000 SF GFA	N/A \$16,230	\$4,626	1,000 SF GFA	N/A \$27,518	\$4,626
	1 000 07 55		AFFO		Wholesale N/A			N/A				
and the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of the same of th	CE CEA	CELO	. CEEN		NI / A			N/A			NI / A	
Wholesale Market	1,000 SF GFA	\$559	\$559		SERVICES			IV/A			N/A	
Wholesale Market  Bank (Walk-In)  Bank (Drive-In)	1,000 SF GFA  1,000 SF GFA  Drive-in Lane	\$28,974 \$42,287	\$7,762 \$12,450	1,000 SF GFA Drive-in Lane		\$7,762 \$12,450	1,000 SF GFA Drive-in Lane	\$18,570 \$44,925	\$7,762 \$12,450	1,000 SF GFA Drive-in Lanes	\$45,574 \$110,523	\$7,762 \$12,450

				Servi	ce Area 'D'	Combined						
Sahadula 1 Tabla D. Astual Daaduusu leenast	Final Pl	at Recorded Between: 9/1/0	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	t Recorded Between: 12/1	/20 - Present*
chedule 1 Table B, Actual Roadway Impact Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Development Ur
Land Use					PORT AND TERMI	NΔI		·	·			
Truck Terminal	Acre	\$25,813	\$11,326	Acre	\$45,587	\$11,326	Acre	\$56,155	\$11,326	1,000 SF GFA	\$32,214	\$11,326
General Light Industrial	1,000 SF GFA	\$3,862	\$1,736	1,000 SF GFA	\$6,820	\$1,736	1,000 SF GFA	\$8,315	\$1,736	1,000 SF GFA	\$10,864	\$1,736
General Heavy Industrial  Industrial Park	1,000 SF GFA 1,000 SF GFA	\$2,682 \$3,626	\$2,681 \$2,173	1,000 SF GFA 1,000 SF GFA	\$4,736 \$5,987	\$509 \$2,173	1,000 SF GFA 1,000 SF GFA	\$5,835 \$7,289	\$509 \$2,173	1,000 SF GFA	N/A \$6,876	\$2,173
Warehousing	1,000 SF GFA	\$2,595	\$1,683	1,000 SF GFA	\$4,431	\$1,683	1,000 SF GFA	\$2,960	\$1,683	1,000 SF GFA	\$3,266	\$1,683
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$1,235 \$3,862	\$974 \$3,861	1,000 SF GFA	\$1,958 N/A	\$974	1,000 SF GFA	\$2,413 N/A	\$974	1,000 SF GFA	\$2,922 N/A	\$974
		44.600			RESIDENTIAL	Å4.404	5 H: 11 ii	40.004	44.404	6 III II II	446.674	44.404
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit Dwelling Unit	\$4,609 \$2,831	\$4,484 \$2,831	Dwelling Unit Dwelling Unit	\$8,140 \$5,000	\$4,484 \$5,000	Dwelling Unit Dwelling Unit	\$9,924 \$6,160	\$4,484 \$5,121	Dwelling Unit Dwelling Unit	\$16,674 \$7,426	\$4,484 \$5,121
Multifamily Housing (High-Rise)	Duralling Unit	N/A	¢2.461	Dualling Unit	N/A	¢4.000	Duralling Unit	N/A	¢4.000	Dwelling Unit	\$6,051	\$5,121
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$2,462 N/A	\$2,461	Dwelling Unit	\$4,195 N/A	\$4,088	Dwelling Unit	\$5,167 N/A	\$4,088	Dwelling Unit  Dwelling Unit	\$9,420 \$6,051	\$4,088 \$5,121
Mobile Home Park	Dwelling Unit	\$2,556	\$2,556	Dwelling Unit	\$4,750	\$4,484		N/A		Dwelling Unit	\$7,736	\$4,484
Retirement Community Others Not Specified	Dwelling Unit Dwelling Unit	\$1,235 \$4,609	\$1,235 \$4,608		N/A N/A			N/A N/A			N/A N/A	
Assisted Living		N/A		Bed	\$1,778	\$1,777	Bed	\$2,190	\$2,190	Beds	\$4,366	\$2,275
Senior Adult Housing Congregate Care Facility		N/A N/A			N/A N/A		Dwelling Unit  Dwelling Unit	\$2,481 \$1,694	\$2,319 \$1,693	Dwelling Unit Dwelling Unit	\$4,366 \$3,025	\$2,319 \$1,997
		A4.542	44.006		LODGING	Å4.20C		40.000	44.006		45.505	
Hotel  Motel/Other Lodging Facilities	Room Room	\$1,542 \$1,188	\$1,306 \$1,089	Room Room	\$2,639 \$2,097	\$1,306 \$1,089	Room Room	\$3,302 \$2,584	\$1,306 \$1,089	Rooms Rooms	\$6,635 \$4,194	\$1,306 \$1,089
					RECREATIONA							. ,
Arena  Bowling Alley	Acre 1,000 SF GFA	\$84,281 \$8,950	\$84,281 \$8,950		N/A N/A			N/A N/A			N/A N/A	
Driving Range	Tee	\$3,162	\$2,106	Tee	\$5,584	\$2,106	Tee	\$6,895	\$2,106	Driving Positions	\$16,881	\$2,106
Golf Course  Health/Recreational Clubs and Facilities	Acre 1,000 SF GFA	\$983 \$4,428	\$851 \$1,272	Acre 1,000 SF GFA	\$1,333 \$7,320	\$851 \$1,272	Acre 1,000 SF GFA	\$1,660 \$15,091	\$851 \$1,272	Holes 1,000 SF GFA	\$39,331 \$31,217	\$851 \$1,272
Ice Rink	1,000 SF GFA	\$5,970	\$2,290	1,000 SF GFA	\$10,543	\$2,290	1,000 SF GFA	\$13,004	\$2,290	1,000 SF GFA	\$17,981	\$2,290
Live Theater  Miniature Golf	Seat Hole	\$47 \$834	\$47 \$759	Hole	N/A \$1,472	\$759	Hole	N/A \$1,814	\$759	Holes	N/A \$4,469	\$759
Multiplex Movie Theater	Seat	\$354	\$353	Screen	\$60,908	\$11,165	Screen	\$75,147	\$11,165	Screens	\$283,222	\$11,165
Tennis Courts	Court	\$9,808	\$1,236	Court	\$14,960 INSTITUTIONA	\$1,236 L	Court	\$18,462	\$1,236	Courts	\$51,604	\$1,236
Church	1,000 SF GFA	\$1,093	\$932	1,000 SF GFA	\$1,931	\$932	1,000 SF GFA	\$1,985	\$932	1,000 SF GFA	\$7,014	\$932
Day Care Center Primary/Middle School (1-8)	1,000 SF GFA Student	\$21,802 \$267	\$5,403 \$186	1,000 SF GFA Student	\$38,448 \$444	\$5,403 \$186	1,000 SF GFA Student	\$24,827 \$582	\$5,403 \$186	1,000 SF GFA Student	\$37,474 \$1,031	\$5,403 \$186
High School (9-12)	Student	\$252	\$184	Student	\$403	\$184	Student	\$462	\$184	Students	\$860	\$184
Jr/Community College University/College	Student Student	\$283 \$346	\$177 \$286	Student Student	\$347 \$611	\$177 \$286	Student Student	\$428 \$616	\$177 \$286	Students Students	\$1,960 \$2,682	\$177 \$286
Oniversity/ conege	Student	<b>43 10</b>	<b>7200</b>	Student	MEDICAL	<b>7250</b>	Student			Stadents		
Clinic Hospital	1,000 SF GFA Bed	\$15,376 \$3,626	\$4,815 \$2,308	1,000 SF GFA Bed	\$27,155 \$6,820	\$4,815 \$2,308	1,000 SF GFA Bed	\$33,501 \$9,188	\$4,815 \$2,308	1,000 SF GFA Beds	\$55,592 \$32,042	\$4,815 \$2,308
Nursing Home	Bed	\$503	\$503	Bed	\$1,153	\$554	Bed	\$1,420	\$554	Beds	\$3,713	\$554
Animal Hospital/Veterinary Clinic		N/A			N/A OFFICE		1,000 SF GFA	\$21,336	\$4,815	1,000 SF GFA	\$41,875	\$4,815
Corporate Headquarters Building	1,000 SF GFA	\$5,970	\$3,534	1,000 SF GFA	\$10,612	\$3,534	1,000 SF GFA	\$13,175	\$3,534	1,000 SF GFA	\$12,377	\$3,534
General Office Building  Medical/Dental Office	1,000 SF GFA 1,000 SF GFA	\$6,402 \$15,714	\$3,770 \$5,318	1,000 SF GFA 1,000 SF GFA	\$11,306 \$28,211	\$3,770 \$5,318	1,000 SF GFA 1,000 SF GFA	\$13,928 \$33,347	\$3,770 \$5,318	1,000 SF GFA 1,000 SF GFA	\$23,722 \$58,652	\$3,770 \$5,318
Single Tenant Office Building	1,000 SF GFA	\$7,385	\$4,368	1,000 SF GFA	\$13,126	\$4,368	1,000 SF GFA	\$16,255	\$4,368	1,000 SF GFA	\$35,274	\$4,368
Office Park Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$6,441 \$6,402	\$3,788 \$6,402	1,000 SF GFA	\$11,376 N/A	\$3,788	1,000 SF GFA	\$13,825 N/A	\$3,788	1,000 SF GFA	\$22,072 N/A	\$3,788
Others Not Specified	1,000 31 GFA	\$0,402	70,402		COMMERCIAL			N/A			N/A	
Automobile Care Center	1,000 SF GFA	\$5,128	\$3,453	1,000 SF GFA	Automobile Rela	\$3,453	1,000 SF GFA	\$10,300	\$3,453	1,000 SF GLA	\$14,336	\$3,453
Automobile Care Center  Automobile Parts Sales	1,000 SF GFA 1,000 SF GFA	\$5,128	\$3,453 \$5,432	1,000 SF GFA 1,000 SF GFA	\$9,070 \$15,223	\$3,453	1,000 SF GFA 1,000 SF GFA	\$10,300	\$3,453	1,000 SF GFA	\$14,336	\$3,453
Gasoline/Service Station w/ Convenience Market	Fueling Position	\$3,988	\$798	Fueling Position	\$4,903	\$798	Fueling Position	\$6,091	\$798	ehicle Fueling Position		\$798
Convenience Market with 12 or More Fueling Positions Convenience Market with Less than 12 Fueling Positions	Fueling Position 1,000 SF GFA	\$2,737 \$2,776	\$2,737 \$3,271		N/A N/A			N/A N/A			N/A N/A	
New and Used Car Sales	1,000 SF GFA	\$5,663	\$3,181	1,000 SF GFA	\$9,417	\$3,181	1,000 SF GFA	\$11,566	\$3,181	1,000 SF GFA	\$18,668	\$3,181
Quick Lubrication Vehicle Center Self-Service Car Wash	Service Position Stall	\$7,873 \$1,636	\$1,980 \$435	Service Position Stall	\$13,890 \$2,764	\$1,980 \$435	Service Position Stall	\$17,127 \$3,405	\$1,980 \$435	Servicing Positions Stalls	\$22,313 \$6,842	\$1,980 \$435
Automated Car Wash	4 000 05 054	N/A		1,000 SF GFA	\$5,820	\$242	4 000 05 054	N/A		4 000 05 054	N/A	45.400
Tire Store	1,000 SF GFA	\$7,503	\$5,483	1,000 SF GFA	\$16,168 <b>Dining</b>	\$5,483	1,000 SF GFA	\$16,477	\$5,483	1,000 SF GFA	\$22,003	\$5,483
Fast Food Restaurant	1,000 SF GFA	\$31,531	\$8,538	1,000 SF GFA	\$57,616	\$8,538	1,000 SF GFA	\$67,054	\$8,538	1,000 SF GFA	\$158,423	\$8,538
Fast Food Restaurant without Drive-Thru High Turnover (Sit-down) Restaurant	1,000 SF GFA 1,000 SF GFA	\$24,625 \$11,664	\$24,625 \$3,177	1,000 SF GFA	N/A \$20,696	\$3,177	1,000 SF GFA	N/A \$23,030	\$3,177	1,000 SF GFA	N/A \$54,011	\$3,177
Sit-Down Restaurant	1,000 SF GFA	\$7,904	\$4,210	1,000 SF GFA	\$13,946	\$4,210	1,000 SF GFA	\$17,213	\$4,210	1,000 SF GFA	\$42,356	\$4,210
Coffee / Donut Shop		N/A		1	N/A Other Retail			N/A		1,000 SF GFA	\$126,140	\$3,177
Free-Standing Retail Store	1,000 SF GFA	\$7,503	\$3,282	1,000 SF GFA	\$15,807	\$3,282	1,000 SF GFA	\$19,232	\$3,282	1,000 SF GFA	\$32,523	\$3,282
Garden Center (Nursery)  Home Improvement Superstore	<b>_</b>	N/A N/A		1,000 SF GFA 1,000 SF GFA	\$11,876 \$7,681	\$3,308 \$4,281	1,000 SF GFA 1,000 SF GFA	\$26,777 \$6,673	\$3,308 \$4,281	1,000 SF GFA 1,000 SF GFA	\$46,791 \$12,996	\$3,308 \$4,281
Pharmacy/Drugstore	1,000 SF GFA	\$13,410	\$3,110	1,000 SF GFA	\$19,654	\$3,110	1,000 SF GFA	\$27,821	\$3,110	1,000 SF GFA	\$50,539	\$3,110
Shopping Center Supermarket	1,000 SF GFA 1,000 SF GFA	\$6,245 \$18,624	\$4,437 \$6,058	1,000 SF GFA 1,000 SF GFA	\$11,070 \$29,877	\$4,437 \$6,058	1,000 SF GFA 1,000 SF GFA	\$13,500 \$33,450	\$4,437 \$6,058	1,000 SF GLA 1,000 SF GFA	\$24,169 \$56,899	\$4,437 \$6,058
Video Arcade	1,000 SF GFA	\$13,449	\$13,449	1,000 3F GFA	\$29,877 N/A	٥٥٥,٥٠	1,000 3F GFA	N/A	٥٥٠,٥٥٠	1,000 SF GFA	N/A	۵۵۰٬۵۶
Video Rental Store Toy/Children's Superstore	1,000 SF GFA	\$17,193 N/A	\$17,192	1,000 SF GFA	N/A \$15,585	\$4,343	1,000 SF GFA	N/A \$19,232	\$4,343	1,000 SF GFA	N/A \$33,692	\$4,343
roy/ ciliuren 3 Juperstore		IV/A		1,000 3F GFA	Wholesale	د <del>ب</del> ربوب ا	1,000 3F GFA	1 713,434	د+ر+ب ا	1,000 OF GFA	J 33,032	1 24,343
Wholesale Market	1,000 SF GFA	\$535	\$535		N/A SERVICES			N/A			N/A	
Bank (Walk-In)	1,000 SF GFA	\$26,513	\$6,965	1,000 SF GFA	\$46,823	\$6,965	1,000 SF GFA	\$21,182	\$6,965	1,000 SF GFA	\$55,799	\$6,965
Bank (Drive-In)	Drive-in Lane	\$38,696	\$9,285	Drive-in Lane	\$57,074	\$9,285	Drive-in Lane	\$51,244	\$9,285	Drive-in Lanes	\$135,320	\$9,285
Personal Service	ı	N/A			N/A			N/A		1,000 SF GFA	\$11,242	\$3,110

				Servi	ce Area 'E'	Combined						
Schedule 1 Table B, Actual Roadway Impact	Final Pl	at Recorded Between: 9/1/0	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	/08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pl	at Recorded Between: 12/1/	20 - Present*
Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Development Uni
Land Use					PORT AND TERMI	NAI						
Truck Terminal	Acre	\$22,951	\$11,756	Acre	\$52,599	\$11,756	Acre	\$65,458	\$11,756	1,000 SF GFA	\$19,774	\$11,756
General Light Industrial	1,000 SF GFA	\$3,431	\$1,890	1,000 SF GFA	\$7,863	\$1,890	1,000 SF GFA	\$9,702	\$1,890	1,000 SF GFA	\$6,650	\$1,890
General Heavy Industrial	1,000 SF GFA	\$2,358	\$2,357	1,000 SF GFA	\$5,454	\$579	1,000 SF GFA	\$6,787	\$579	4 000 05 054	N/A	40.075
Industrial Park  Warehousing	1,000 SF GFA 1,000 SF GFA	\$3,227 \$2,139	\$2,375 \$1,720	1,000 SF GFA 1,000 SF GFA	\$6,909 \$4,735	\$2,375 \$1,720	1,000 SF GFA 1,000 SF GFA	\$8,495 \$3,206	\$2,375 \$1,720	1,000 SF GFA 1,000 SF GFA	\$4,228 \$2,004	\$2,375 \$1,720
Mini-Warehouse	1,000 SF GFA	\$1,015	\$1,013	1,000 SF GFA	\$2,091	\$1,013	1,000 SF GFA	\$2,603	\$1,013	1,000 SF GFA	\$1,806	\$1,013
Others Not Specified	1,000 SF GFA	\$3,431	\$3,431		N/A RESIDENTIAL			N/A			N/A	
Single Family Detached Housing	Dwelling Unit	\$3,541	\$3,540	Dwelling Unit	\$8,114	\$4,484	Dwelling Unit	\$9,994	\$4,484	Dwelling Unit	\$10,460	\$4,484
Apartment/Multi-family  Multifamily Housing (High-Rise)	Dwelling Unit	\$2,175 N/A	\$2,175	Dwelling Unit	\$4,986 N/A	\$4,646	Dwelling Unit	\$6,204 N/A	\$4,646	Dwelling Unit Dwelling Unit	\$4,646 \$3,809	\$4,646 \$3,809
Residential Condominium/Townhouse	Dwelling Unit	\$1,891	\$1,890	Dwelling Unit	\$4,183	\$4,073	Dwelling Unit	\$5,205	\$4,073	Dwelling Unit	\$5,923	\$4,073
Mid-Rise Residential with 1st Floor Commercial  Mobile Home Park	Dwelling Unit	N/A \$1,964	\$1,963	Dwelling Unit	N/A \$4,735	\$4,484		N/A N/A		Dwelling Unit Dwelling Unit	\$3,809 \$4,866	\$3,809 \$4,484
Retirement Community	Dwelling Unit	\$949	\$949	J	N/A	. ,		N/A		3	N/A	, ,
Others Not Specified Assisted Living	Dwelling Unit	\$3,541 N/A	\$4,172	Bed	N/A \$1,773	\$1,773	Bed	N/A \$2,207	\$2,206	Beds	N/A \$2,753	\$2,269
Senior Adult Housing		N/A			N/A		Dwelling Unit	\$2,498	\$2,311	Dwelling Unit	\$2,753	\$2,311
Congregate Care Facility		N/A			N/A LODGING		Dwelling Unit	\$1,707	\$1,707	Dwelling Unit	\$1,894	\$1,893
Hotel	Room	\$1,431	\$1,070	Room	\$3,179	\$1,070	Room	\$4,018	\$1,070	Rooms	\$4,250	\$1,070
Motel/Other Lodging Facilities	Room	\$1,102	\$1,102	Room	\$2,526 RECREATIONA	\$1,244 L	Room	\$3,144	\$1,244	Rooms	\$2,686	\$1,244
Arena	Acre	\$78,227	\$78,226		N/A			N/A			N/A	
Bowling Alley Driving Range	1,000 SF GFA Tee	\$8,307 \$2,935	\$8,307 \$2,363	Tee	N/A \$6,725	\$2,363	Tee	N/A \$8,390	\$2,363	Driving Positions	N/A \$10,812	\$2,363
Golf Course	Acre	\$913	\$912	Acre	\$1,606	\$933	Acre	\$2,020	\$933	Holes	\$25,191	\$933
Health/Recreational Clubs and Facilities Ice Rink	1,000 SF GFA	\$4,110 \$5,541	\$1,650 \$2,830	1,000 SF GFA	\$8,817 \$12,698	\$1,650 \$2,839	1,000 SF GFA	\$18,363 \$15,823	\$1,650	1,000 SF GFA	\$19,994	\$1,650 \$2,839
Live Theater	1,000 SF GFA Seat	\$5,541	\$2,839 \$44	1,000 SF GFA	\$12,698 N/A	\$2,839	1,000 SF GFA	\$15,823 N/A	\$2,839	1,000 SF GFA	\$11,516 N/A	\$2,839
Miniature Golf	Hole	\$774	\$773	Hole	\$1,773	\$869	Hole	\$2,207	\$869	Holes	\$2,863	\$869
Multiplex Movie Theater Tennis Courts	Seat Court	\$329 \$9,103	\$328 \$1,634	Screen Court	\$73,361 \$18,018	\$12,567 \$1,634	Screen Court	\$91,441 \$22,465	\$12,567 \$1,634	Screens Courts	\$145,112 \$33,052	\$12,567 \$1,634
Telling courts					INSTITUTIONA	L						
Church  Day Care Center	1,000 SF GFA 1,000 SF GFA	\$1,015 \$20,236	\$1,014 \$5,378	1,000 SF GFA 1,000 SF GFA	\$2,325 \$46,309	\$1,084 \$5,378	1,000 SF GFA 1,000 SF GFA	\$2,415 \$30,210	\$1,084 \$5,378	1,000 SF GFA 1,000 SF GFA	\$4,492 \$24,002	\$1,084 \$5,378
Primary/Middle School (1-8)	Student	\$20,236	\$224	Student	\$535	\$5,378	Student	\$30,210	\$5,378	Student	\$24,002	\$5,378 \$224
High School (9-12)	Student	\$234	\$218	Student	\$485	\$218	Student	\$562	\$218	Students	\$551	\$218
Jr/Community College University/College	Student Student	\$263 \$321	\$202 \$321	Student Student	\$418 \$736	\$202 \$336	Student Student	\$521 \$750	\$202 \$336	Students Students	\$1,167 \$1,585	\$202 \$336
					MEDICAL							
Clinic Hospital	1,000 SF GFA Bed	\$14,272 \$3,365	\$5,475 \$2,623	1,000 SF GFA Bed	\$32,707 \$8,214	\$5,475 \$2,623	1,000 SF GFA Bed	\$40,766 \$11,180	\$5,475 \$2,623	1,000 SF GFA Beds	\$34,659 \$19,972	\$5,475 \$2,623
Nursing Home	Bed	\$467	\$467	Bed	\$1,389	\$645	Bed	\$1,728	\$645	Beds	\$2,334	\$645
Animal Hospital/Veterinary Clinic		N/A			N/A OFFICE		1,000 SF GFA	\$25,963	\$5,475	1,000 SF GFA	\$26,116	\$5,475
Corporate Headquarters Building	1,000 SF GFA	\$4,869	\$3,621	1,000 SF GFA	\$11,243	\$3,621	1,000 SF GFA	\$14,095	\$3,621	1,000 SF GFA	\$6,342	\$3,621
General Office Building	1,000 SF GFA	\$5,220	\$3,858	1,000 SF GFA	\$11,962	\$3,858	1,000 SF GFA	\$14,886	\$3,858	1,000 SF GFA	\$12,155	\$3,858
Medical/Dental Office Single Tenant Office Building	1,000 SF GFA 1,000 SF GFA	\$12,826 \$6,030	\$5,366 \$4,472	1,000 SF GFA 1,000 SF GFA	\$29,880 \$13,886	\$5,366 \$4,472	1,000 SF GFA 1,000 SF GFA	\$35,685 \$17,385	\$5,366 \$4,472	1,000 SF GFA 1,000 SF GFA	\$36,575 \$18,078	\$5,366 \$4,472
Office Park	1,000 SF GFA	\$5,256	\$3,881	1,000 SF GFA	\$12,046	\$3,881	1,000 SF GFA	\$14,782	\$3,881	1,000 SF GFA	\$11,318	\$3,881
Others Not Specified	1,000 SF GFA	\$5,220	\$5,219		N/A COMMERCIAL			N/A			N/A	
					Automobile Rela							
Automobile Care Center  Automobile Parts Sales	1,000 SF GFA 1,000 SF GFA	\$4,760 \$8,001	\$3,869 \$5,052	1,000 SF GFA 1,000 SF GFA	\$10,925 \$18,336	\$3,869 \$5,052	1,000 SF GFA 1,000 SF GFA	\$12,534 \$22,860	\$3,869 \$5,052	1,000 SF GLA 1,000 SF GFA	\$9,182 \$13,740	\$3,869 \$5,052
Gasoline/Service Station w/ Convenience Market	Fueling Position	\$3,701	\$926	Fueling Position	\$5,906	\$926	Fueling Position	\$7,412		ehicle Fueling Positio	n \$8,147	\$926
Convenience Market with 12 or More Fueling Positions Convenience Market with Less than 12 Fueling Positions	Fueling Position 1,000 SF GFA	\$2,540 \$2,577	\$2,540 \$2,577		N/A N/A			N/A N/A			N/A N/A	
New and Used Car Sales	1,000 SF GFA	\$5,256	\$3,656	1,000 SF GFA	\$11,343	\$3,656	1,000 SF GFA	\$14,074	\$3,656	1,000 SF GFA	\$11,957	\$3,656
Quick Lubrication Vehicle Center Self-Service Car Wash	Service Position Stall	\$7,307 \$1,518	\$2,371 \$507	Service Position Stall	\$16,730 \$3,329	\$2,371 \$507	Service Position Stall	\$20,841 \$4,143	\$2,371 \$507	Servicing Positions Stalls	\$14,291 \$4,382	\$2,371 \$507
Automated Car Wash		N/A		1,000 SF GFA	\$3,329	\$200		N/A			\$4,382 N/A	
Tire Store	1,000 SF GFA	\$6,964	\$5,182	1,000 SF GFA	\$19,474	\$5,182	1,000 SF GFA	\$20,050	\$5,182	1,000 SF GFA	\$14,093	\$5,182
Fast Food Restaurant	1,000 SF GFA	\$29,266	\$10,124	1,000 SF GFA	\$69,396	\$10,124	1,000 SF GFA	\$81,594	\$10,124	1,000 SF GFA	\$101,468	\$10,124
Fast Food Restaurant without Drive-Thru	1,000 SF GFA	\$22,856	\$22,856		N/A			N/A			N/A	
High Turnover (Sit-down) Restaurant Sit-Down Restaurant	1,000 SF GFA 1,000 SF GFA	\$10,826 \$7,337	\$3,692 \$2,680	1,000 SF GFA 1,000 SF GFA	\$24,928 \$16,797	\$3,692 \$2,680	1,000 SF GFA 1,000 SF GFA	\$28,024 \$20,945	\$3,692 \$2,680	1,000 SF GFA 1,000 SF GFA	\$34,593 \$27,129	\$3,692 \$2,680
Coffee / Donut Shop		N/A			N/A			N/A		1,000 SF GFA	\$80,791	\$3,692
Free-Standing Retail Store	1,000 SF GFA	\$6,964	\$3,142	1,000 SF GFA	Other Retail \$19,039	\$3,142	1,000 SF GFA	\$23,402	\$3,142	1,000 SF GFA	\$20,831	\$3,142
Garden Center (Nursery)	1,000 31 GTA	N/A	Ι Υ ^Ο ,± <del>7</del> 4	1,000 SF GFA	\$14,304	\$3,987	1,000 SF GFA	\$32,583	\$3,987	1,000 SF GFA	\$29,969	\$3,987
Home Improvement Superstore	1,000 SF GFA	N/A \$12,447	\$3,053	1,000 SF GFA 1,000 SF GFA	\$9,252 \$23,673	\$5,156 \$3,053	1,000 SF GFA 1,000 SF GFA	\$8,120 \$33,853	\$5,156 \$3,053	1,000 SF GFA 1,000 SF GFA	\$8,324	\$5,156 \$3,053
Pharmacy/Drugstore Shopping Center	1,000 SF GFA 1,000 SF GFA	\$12,447	\$3,053 \$4,874	1,000 SF GFA 1,000 SF GFA	\$23,673	\$3,053 \$4,874	1,000 SF GFA 1,000 SF GFA	\$33,853	\$3,053 \$4,874	1,000 SF GFA 1,000 SF GLA	\$32,369 \$15,480	\$3,053 \$4,874
Supermarket	1,000 SF GFA	\$17,286	\$6,637	1,000 SF GFA	\$35,986	\$6,637	1,000 SF GFA	\$40,703	\$6,637	1,000 SF GFA	\$36,443	\$6,637
Video Arcade Video Rental Store	1,000 SF GFA 1,000 SF GFA	\$12,483 \$15,958	\$12,483 \$15,957		N/A N/A			N/A N/A			N/A N/A	
Toy/Children's Superstore		N/A		1,000 SF GFA	\$18,771	\$3,558	1,000 SF GFA	\$23,402	\$3,558	1,000 SF GFA	\$21,580	\$3,558
Wholesale Market	1,000 SF GFA	\$496	\$496		Wholesale N/A			N/A			N/A	
WITUICSAIC IVIAINEL	1,000 3F GFA	J450	J+30		SERVICES			IV/A			IV/A	
Bank (Walk-In)	1,000 SF GFA	\$24,608	\$8,251	1,000 SF GFA	\$56,397	\$8,251	1,000 SF GFA	\$25,775	\$8,251	1,000 SF GFA	\$35,738	\$8,251
Bank (Drive-In)  Personal Service	Drive-in Lane	\$35,916 N/A	\$13,293	Drive-in Lane	\$68,744 N/A	\$13,293	Drive-in Lane	\$62,356 N/A	\$13,293	Drive-in Lanes 1,000 SF GFA	\$86,671 \$7,201	\$13,293 \$3,053
7 Croonar Scrvice		14/11			14/1		<u> </u>			1,000 31 GIA	Y1,201	73,033

				Servi	ce Area 'F'	Combined						
Schoolule 4 Table D. Astual Deadway Immed	Final Pl	at Recorded Between: 9/1/0	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	/08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	Recorded Between: 12/1/	/20 - Present*
chedule 1 Table B, Actual Roadway Impact Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged
Land Use					PORT AND TERMI	·						
Truck Terminal	Acre	\$0	\$0	Acre	\$0	\$0	Acre	\$0	\$0	1,000 SF GFA	\$0	\$0
General Light Industrial	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
General Heavy Industrial Industrial Park	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$0	\$0
Warehousing	1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0 \$0	\$0
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0
Others Not Specified	1,000 31 G1A	, , , , , , , , , , , , , , , , , , ,	Ų.		RESIDENTIAL			Ny/X			14/7	
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0
Multifamily Housing (High-Rise)		N/A			N/A	·		N/A		Dwelling Unit	\$0	\$0
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0
Mobile Home Park	Dwelling Unit	\$0	\$0	Dwelling Unit	\$0	\$0		N/A		Dwelling Unit	\$0	\$0
Retirement Community Others Not Specified	Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0		N/A N/A			N/A N/A			N/A N/A	
Assisted Living		N/A		Dwelling Unit	\$0	\$0	Bed	\$0	\$0	Beds	\$0	\$0
Senior Adult Housing Congregate Care Facility		N/A N/A			N/A N/A		Dwelling Unit Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit  Dwelling Unit	\$0 \$0	\$0 \$0
	D	1 60	40		LODGING	I 40	2	40	<u> </u>		40	<b>A</b> 0
Hotel  Motel/Other Lodging Facilities	Room Room	\$0 \$0	\$0 \$0	Room Room	\$0 \$0	\$0 \$0	Room Room	\$0 \$0	\$0 \$0	Rooms Rooms	\$0 \$0	\$0 \$0
					RECREATIONA	Ĺ		21/2			21/2	
Arena  Bowling Alley	Acre 1,000 SF GFA	\$0 \$0	\$0 \$0		N/A N/A			N/A N/A			N/A N/A	
Driving Range	Tee	\$0	\$0	Tee	\$0	\$0	Tee	\$0	\$0	Driving Positions	\$0	\$0 \$0
Golf Course  Health/Recreational Clubs and Facilities	Acre 1,000 SF GFA	\$0 \$0	\$0 \$0	Acre 1,000 SF GFA	\$0 \$0	\$0 \$0	Acre 1,000 SF GFA	\$0 \$0	\$0 \$0	Holes 1,000 SF GFA	\$0 \$0	\$0 \$0
Ice Rink	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Live Theater  Miniature Golf	Seat Hole	\$0 \$0	\$0 \$0	Hole	N/A \$0	\$0	Hole	N/A \$0	\$0	Holes	N/A \$0	\$0
Multiplex Movie Theater	Seat	\$0	\$0	Screen	\$0	\$0	Screen	\$0	\$0	Screens	\$0	\$0
Tennis Courts	Court	\$0	\$0	Court	\$0 INSTITUTIONA	\$0 L	Court	\$0	\$0	Courts	\$0	\$0
Church	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Day Care Center Primary/Middle School (1-8)	1,000 SF GFA Student	\$0 \$0	\$0 \$0	1,000 SF GFA Student	\$0 \$0	\$0 \$0	1,000 SF GFA Student	\$0 \$0	\$0 \$0	1,000 SF GFA Student	\$0 \$0	\$0 \$0
High School (9-12)	Student	\$0	\$0	Student	\$0	\$0	Student	\$0	\$0	Students	\$0	\$0
Jr/Community College University/College	Student Student	\$0 \$0	\$0 \$0	Student Student	\$0 \$0	\$0 \$0	Student Student	\$0 \$0	\$0 \$0	Students Students	\$0 \$0	\$0 \$0
	1 000 55 651	1 40	40	4 000 55 654	MEDICAL		4.000.55.054		40	4 000 05 054	40	40
Clinic Hospital	1,000 SF GFA Bed	\$0 \$0	\$0 \$0	1,000 SF GFA Bed	\$0 \$0	\$0 \$0	1,000 SF GFA Bed	\$0 \$0	\$0 \$0	1,000 SF GFA Beds	\$0 \$0	\$0 \$0
Nursing Home	Bed	\$0	\$0	Bed	\$0	\$0	Bed	\$0	\$0	Beds	\$0	\$0 \$0
Animal Hospital/Veterinary Clinic		N/A			N/A OFFICE		1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Corporate Headquarters Building	1,000 SF GFA	\$0 \$0	\$0	1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0	\$0 \$0
General Office Building  Medical/Dental Office	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Single Tenant Office Building Office Park	1,000 SF GFA	\$0 \$0	\$0	1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA	\$0	\$0 60	1,000 SF GFA	\$0	\$0 \$0
Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	Ş0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0
					COMMERCIAL Automobile Rela							
Automobile Care Center	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GLA	\$0	\$0
Automobile Parts Sales Gasoline/Service Station w/ Convenience Market	1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA Fueling Position	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA /ehicle Fueling Position	\$0 \$0	\$0 \$0
Convenience Market with 12 or More Fueling Positions	Fueling Position Fueling Position	\$0	\$0 \$0	rueiling Position	N/A		Fueling Position	N/A	) ŞU	remide Fueiling Position	\$0 N/A	J \$0
Convenience Market with Less than 12 Fueling Positions  New and Used Car Sales	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$0	\$0
Quick Lubrication Vehicle Center	Service Position	\$0	\$0 \$0	Service Position	\$0	\$0	Service Position	\$0	\$0	Servicing Positions	\$0 \$0	\$0 \$0
Self-Service Car Wash Automated Car Wash	Stall	\$0 N/A	\$0	Stall 1,000 SF GFA	\$0 \$0	\$0 \$0	Stall	\$0 N/A	\$0	Stalls	\$0 N/A	\$0
Tire Store	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
East Food Doctorrest	1,000,00,000	Ć0	ćo	1,000 55 554	Dining	Ċ0.	1,000,00,000	Ć0	ćo	1,000 55 654	ćo	60
Fast Food Restaurant Fast Food Restaurant without Drive-Thru	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0
High Turnover (Sit-down) Restaurant Sit-Down Restaurant	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Coffee / Donut Shop	1,000 SF GFA	N/A	υ <b>ς</b>	1,000 3F GFA	N/A		1,000 SF GFA	N/A	ار 	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Eroo Standing Potail Store	1 000 55 654	ĊO	ćo	1,000 \$5,054	Other Retail	ćo	1,000,55,054	ĊO	ćo	1,000 55 654	ćo	ĊO
Free-Standing Retail Store Garden Center (Nursery)	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Home Improvement Superstore	1,000 SF GFA	N/A \$0	ćo	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0
Pharmacy/Drugstore Shopping Center	1,000 SF GFA 1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GLA	\$0 \$0	\$0 \$0
Supermarket Video Arcade	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0
Video Arcade Video Rental Store	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0		N/A N/A			N/A N/A			N/A N/A	
Toy/Children's Superstore		N/A		1,000 SF GFA	\$0 Wholesale	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0
Wholesale Market	1,000 SF GFA	\$0	\$0		N/A			N/A			N/A	
				1,000,05,051	SERVICES		1,000,05,051		40	1,000 55 551		40
Bank (Walk-In) Bank (Drive-In)	1,000 SF GFA Drive-in Lane	\$0 \$0	\$0 \$0	1,000 SF GFA Drive-in Lane	\$0 \$0	\$0 \$0	1,000 SF GFA Drive-in Lane	\$0 \$0	\$0 \$0	1,000 SF GFA Drive-in Lanes	\$0 \$0	\$0 \$0
		N/A			N/A		I	N/A		1,000 SF GFA	\$0	\$0

				Servi	ce Area 'G'	Combined						
Sahadula 1 Tabla D. Astual Daaduusu kunsat	Final Pl	at Recorded Between: 9/1/	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	/08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	t Recorded Between: 12/1	/20 - Present*
Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Development Ur
Land Use					PORT AND TERMI	NΔI			·			
Truck Terminal	Acre	\$10,880	\$10,205	Acre	\$22,777 INDUSTRIAL	\$10,205	Acre	\$20,841	\$10,205	1,000 SF GFA	\$10,822	\$10,205
General Light Industrial	1,000 SF GFA	\$1,628	\$1,355	1,000 SF GFA	\$3,408	\$1,355	1,000 SF GFA	\$3,086	\$1,355	1,000 SF GFA	\$3,650	\$1,355
General Heavy Industrial  Industrial Park	1,000 SF GFA 1,000 SF GFA	\$1,130 \$1,528	\$1,130 \$1,528	1,000 SF GFA 1,000 SF GFA	\$2,367 \$2,991	\$397 \$1,699	1,000 SF GFA 1,000 SF GFA	\$2,165 \$2,705	\$397 \$1,699	1,000 SF GFA	N/A \$2,310	\$1,699
Warehousing	1,000 SF GFA	\$1,094	\$1,093	1,000 SF GFA	\$2,214	\$1,097	1,000 SF GFA	\$1,099	\$1,097	1,000 SF GFA	\$1,097	\$1,097
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$520 \$1,628	\$520 \$1,628	1,000 SF GFA	\$979 N/A	\$549	1,000 SF GFA	\$895 N/A	\$549	1,000 SF GFA	\$982 N/A	\$549
Single Family Detached Housing	Dwelling Unit	\$2,009	\$2,008	Dwelling Unit	RESIDENTIAL \$4,206	\$4,205	Dwelling Unit	\$3,810	\$3,810	Dwelling Unit	\$5,602	\$4,484
Apartment/Multi-family	Dwelling Unit	\$1,233	\$1,233	Dwelling Unit	\$2,582	\$2,494	Dwelling Unit	\$2,362	\$2,362	Dwelling Unit	\$2,495	\$2,494
Multifamily Housing (High-Rise)  Residential Condominium/Townhouse	Dwelling Unit	N/A \$1,074	\$1,074	Dwelling Unit	N/A \$2,165	\$2,165	Dwelling Unit	N/A \$1,981	\$1,981	Dwelling Unit Dwelling Unit	\$2,033 \$3,165	\$2,032 \$2,334
Mid-Rise Residential with 1st Floor Commercial	Ţ	N/A		Ü	N/A		Dweining offic	N/A	Ÿ1,501	Dwelling Unit	\$2,033	\$2,032
Mobile Home Park  Retirement Community	Dwelling Unit Dwelling Unit	\$1,114 \$537	\$1,113 \$537	Dwelling Unit	\$2,457 N/A	\$2,456		N/A N/A		Dwelling Unit	\$2,599 N/A	\$2,598
Others Not Specified	Dwelling Unit	\$2,009	\$2,009		N/A	1		N/A	1		N/A	1
Assisted Living Senior Adult Housing		N/A N/A		Bed	\$916 N/A	\$916	Bed Dwelling Unit	\$838 \$953	\$838 \$952	Beds Dwelling Unit	\$1,467 \$1,467	\$987 \$1,122
Congregate Care Facility		N/A			N/A		Dwelling Unit	\$648	\$647	Dwelling Unit	\$1,016	\$763
Hotel	Room	\$650	\$649	Room	\$1,319	\$742	Room	\$1,226	\$742	Rooms	\$2,229	\$742
Motel/Other Lodging Facilities	Room	\$501	\$500	Room	\$1,048	\$617	Room	\$959	\$617	Rooms	\$1,409	\$617
Arena	Acre	\$35,524	\$35,524	T	RECREATIONA N/A	L		N/A			N/A	
Bowling Alley	1,000 SF GFA	\$3,772 \$1,333	\$3,772 \$1,332	Too	N/A \$2,790	\$1,636	Too	N/A \$2,559	\$1,636	Driving Positions	N/A \$5,671	\$1,636
Driving Range Golf Course	Tee Acre	\$1,333 \$414	\$1,332 \$414	Tee Acre	\$2,790 \$666	\$1,636 \$497	Tee Acre	\$2,559 \$616	\$1,636 \$497	Driving Positions Holes	\$5,671 \$13,213	\$1,636 \$497
Health/Recreational Clubs and Facilities  Ice Rink	1,000 SF GFA 1,000 SF GFA	\$1,866 \$2,516	\$1,342 \$1,912	1,000 SF GFA 1,000 SF GFA	\$3,657 \$5,267	\$1,342 \$1,912	1,000 SF GFA 1,000 SF GFA	\$5,601 \$4,826	\$1,342 \$1,912	1,000 SF GFA 1,000 SF GFA	\$10,487 \$6,041	\$1,342 \$1,912
Live Theater	Seat	\$2,516	\$20	1,000 SF GFA	35,267 N/A	\$1,912	1,000 SF GFA	N/A	\$1,912	1,000 SF GFA	N/A	\$1,912
Miniature Golf  Multiplex Movie Theater	Hole Seat	\$351 \$149	\$351 \$149	Hole Screen	\$736 \$30,432	\$430 \$6,409	Hole Screen	\$673 \$27,889	\$430 \$6,409	Holes Screens	\$1,502 \$95,149	\$430 \$6,409
Tennis Courts	Court	\$4,134	\$1,315	Court	\$7,474	\$1,315	Court	\$6,852	\$1,315	Courts	\$17,337	\$1,315
Church	1,000 SF GFA	\$461	\$460	1,000 SF GFA	\$965	\$523	1,000 SF GFA	\$737	\$523	1,000 SF GFA	\$2,356	\$523
Day Care Center	1,000 SF GFA	\$9,189	\$2,960	1,000 SF GFA	\$19,210	\$2,960	1,000 SF GFA	\$9,214	\$2,960	1,000 SF GFA	\$12,590	\$2,960
Primary/Middle School (1-8) High School (9-12)	Student Student	\$113 \$106	\$102 \$102	Student Student	\$222 \$201	\$102 \$102	Student Student	\$216 \$171	\$102 \$102	Student Students	\$347 \$289	\$102 \$102
Jr/Community College	Student	\$119	\$100	Student	\$174	\$100	Student	\$159	\$100	Students	\$658	\$100
University/College	Student	\$146	\$145	Student	\$305 MEDICAL	\$160	Student	\$229	\$160	Students	\$901	\$160
Clinic	1,000 SF GFA	\$6,481	\$4,815	1,000 SF GFA	\$13,568	\$4,815	1,000 SF GFA	\$12,433	\$4,815	1,000 SF GFA Beds	\$18,676	\$4,815 \$1,316
Hospital Nursing Home	Bed Bed	\$1,528 \$212	\$1,316 \$212	Bed Bed	\$3,408 \$576	\$1,316 \$310	Bed Bed	\$3,410 \$527	\$1,316 \$310	Beds	\$10,765 \$1,247	\$1,316
Animal Hospital/Veterinary Clinic		N/A			N/A <b>OFFICE</b>		1,000 SF GFA	\$7,918	\$4,815	1,000 SF GFA	\$14,068	\$4,815
Corporate Headquarters Building	1,000 SF GFA	\$2,516	\$2,009	1,000 SF GFA	\$5,302	\$2,009	1,000 SF GFA	\$4,890	\$2,009	1,000 SF GFA	\$4,158	\$2,009
General Office Building  Medical/Dental Office	1,000 SF GFA 1,000 SF GFA	\$2,698 \$6,623	\$2,145 \$5,127	1,000 SF GFA 1,000 SF GFA	\$5,649 \$14,095	\$2,145 \$5,127	1,000 SF GFA 1,000 SF GFA	\$5,169 \$12,376	\$2,145 \$5,127	1,000 SF GFA 1,000 SF GFA	\$7,970 \$19,704	\$2,145 \$5,127
Single Tenant Office Building	1,000 SF GFA	\$3,113	\$2,485	1,000 SF GFA	\$6,558	\$2,485	1,000 SF GFA	\$6,033	\$2,485	1,000 SF GFA	\$11,850	\$2,485
Office Park Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$2,715 \$2,698	\$2,154 \$2,698	1,000 SF GFA	\$5,684 N/A	\$2,154	1,000 SF GFA	\$5,131 N/A	\$2,154	1,000 SF GFA	\$7,415 N/A	\$2,154
	2,000 0. 0.71	<del>+</del> =/000	<del>+</del> 2,000		COMMERCIAL							
Automobile Care Center	1,000 SF GFA	\$2,161	\$1,988	1,000 SF GFA	Automobile Rela \$4,532	ted \$1,988	1,000 SF GFA	\$3,823	\$1,988	1,000 SF GLA	\$4,816	\$1,988
Automobile Parts Sales	1,000 SF GFA	\$3,633	\$3,098	1,000 SF GFA	\$7,606	\$3,098	1,000 SF GFA	\$6,972	\$3,098	1,000 SF GFA	\$7,207	\$3,098
Gasoline/Service Station w/ Convenience Market Convenience Market with 12 or More Fueling Positions	Fueling Position Fueling Position	\$1,681 \$1,154	\$381 \$1,153	Fueling Position	\$2,450 N/A	\$381	Fueling Position	\$2,261 N/A	\$381	ehicle Fueling Position	\$4,274 N/A	\$381
Convenience Market with Less than 12 Fueling Positions	1,000 SF GFA	\$1,170	\$1,170	1,000 SF GFA	N/A   \$4.705	Ć1 700	1 000 05 054	N/A 1 \$4.202	ć1 700	1,000 SF GFA	N/A \$6.272	Ć4 700
New and Used Car Sales  Quick Lubrication Vehicle Center	1,000 SF GFA Service Position	\$2,387 \$3,318	\$1,799 \$1,060	1,000 SF GFA Service Position	\$4,705 \$6,940	\$1,799 \$1,060	1,000 SF GFA Service Position	\$4,293 \$6,356	\$1,799 \$1,060	1,000 SF GFA Servicing Positions	\$6,272 \$7,496	\$1,799 \$1,060
Self-Service Car Wash Automated Car Wash	Stall	\$690 N/A	\$634	Stall 1,000 SF GFA	\$1,381 \$2,908	\$634 \$128	Stall	\$1,264 N/A	\$634	Stalls	\$2,298 N/A	\$634
Tire Store	1,000 SF GFA	\$3,163	\$3,104	1,000 SF GFA	\$8,078	\$3,104	1,000 SF GFA	\$6,115	\$3,104	1,000 SF GFA	\$7,392	\$3,104
Fast Food Restaurant	1,000 SF GFA	\$13,290	\$4,725	1,000 SF GFA	\$28,787	\$4,725	1,000 SF GFA	\$24,886	\$4,725	1,000 SF GFA	\$53,222	\$4,725
Fast Food Restaurant without Drive-Thru	1,000 SF GFA	\$10,379	\$10,379		N/A			N/A			N/A	
High Turnover (Sit-down) Restaurant Sit-Down Restaurant	1,000 SF GFA 1,000 SF GFA	\$4,916 \$3,332	\$1,785 \$2,357	1,000 SF GFA 1,000 SF GFA	\$10,341 \$6,968	\$1,785 \$2,357	1,000 SF GFA 1,000 SF GFA	\$8,547 \$6,388	\$1,785 \$2,357	1,000 SF GFA 1,000 SF GFA	\$18,145 \$14,230	\$1,785 \$2,357
Coffee / Donut Shop	, , , , , , , , , , , , , , , , , , , ,	N/A	, , , , , , , , , , , , , , , , , , , ,		N/A	. , , , , ,	, , , , , , , , , , , , , , , , , , , ,	N/A	, , , , , , , ,	1,000 SF GFA	\$42,377	\$1,785
Free-Standing Retail Store	1,000 SF GFA	\$3,163	\$2,769	1,000 SF GFA	Other Retail \$7,898	\$2,769	1,000 SF GFA	\$7,137	\$2,769	1,000 SF GFA	\$10,926	\$2,769
Garden Center (Nursery)	, , , , , , , , , , , , , , , , , , , ,	N/A		1,000 SF GFA	\$5,934	\$3,622	1,000 SF GFA	\$9,938	\$3,622	1,000 SF GFA	\$15,720	\$3,622
Home Improvement Superstore  Pharmacy/Drugstore	1,000 SF GFA	N/A \$5,652	\$3,635	1,000 SF GFA 1,000 SF GFA	\$3,838 \$9,820	\$2,342 \$3,635	1,000 SF GFA 1,000 SF GFA	\$2,477 \$10,325	\$2,342 \$3,635	1,000 SF GFA 1,000 SF GFA	\$4,366 \$16,979	\$2,342 \$3,635
Shopping Center	1,000 SF GFA	\$2,632	\$2,588	1,000 SF GFA	\$5,531	\$2,588	1,000 SF GFA	\$5,010	\$2,588	1,000 SF GLA	\$8,120	\$2,588
Supermarket Video Arcade	1,000 SF GFA 1,000 SF GFA	\$7,850 \$5,669	\$5,708 \$5,668	1,000 SF GFA	\$14,928 N/A	\$5,708	1,000 SF GFA	\$12,414 N/A	\$5,708	1,000 SF GFA	\$19,115 N/A	\$5,708
Video Rental Store	1,000 SF GFA	\$7,247 N/A	\$7,246	1,000 SF GFA	N/A \$7,787	\$2,894	1,000 SF GFA	N/A \$7,137	\$2,894	1,000 SF GFA	N/A	\$2,894
Toy/Children's Superstore		IV/A		1,000 SF GFA	\$7,787 Wholesale	J	1,000 SF GFA	] \$/,15/	J 32,894	1,000 SF GFA	\$11,319	\$2,894
Wholesale Market	1,000 SF GFA	\$225	\$225		N/A SERVICES			N/A			N/A	
Bank (Walk-In)	1,000 SF GFA	\$11,175	\$3,857	1,000 SF GFA	\$23,395	\$3,857	1,000 SF GFA	\$7,861	\$3,857	1,000 SF GFA	\$18,746	\$3,857
Bank (Drive-In)	Drive-in Lane	\$16,310 N/A	\$6,184	Drive-in Lane	\$28,516 N/A	\$6,184	Drive-in Lane	\$19,018 N/A	\$6,184	Drive-in Lanes	\$45,461 \$3,777	\$6,184 \$3,635
Personal Service		N/A			IN/A		L	N/A		1,000 SF GFA	\$3,777	\$3,635

				Servi	ce Area 'H'	Combined						
Sahadula 4 Tabla D. Astual Daaduus luurast	Final Pl	at Recorded Between: 9/1/	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	t Recorded Between: 12/1	/20 - Present*
chedule 1 Table B, Actual Roadway Impact Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Development Ur
Land Use					PORT AND TERMI	NAI		·	·			
Truck Terminal	Acre	\$22,266	\$3,140	Acre	\$14,895	\$3,140	Acre	\$11,971	\$3,140	1,000 SF GFA	\$3,141	\$3,140
General Light Industrial	1,000 SF GFA	\$3,333	\$1,057	1,000 SF GFA	\$2,230	\$1,057	1,000 SF GFA	\$1,772	\$1,057	1,000 SF GFA	\$1,058	\$1,057
General Heavy Industrial  Industrial Park	1,000 SF GFA 1,000 SF GFA	\$2,310 \$3,129	\$2,309 \$671	1,000 SF GFA 1,000 SF GFA	\$1,545 \$1,956	\$342 \$671	1,000 SF GFA 1,000 SF GFA	\$1,242 \$1,552	\$342 \$671	1,000 SF GFA	N/A \$671	\$671
Warehousing	1,000 SF GFA	\$2,076	\$317	1,000 SF GFA	\$1,340	\$317	1,000 SF GFA	\$586	\$317	1,000 SF GFA	\$318	\$317
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$987 \$3,333	\$285 \$3,333	1,000 SF GFA	\$592 N/A	\$285	1,000 SF GFA	\$476 N/A	\$285	1,000 SF GFA	\$285 N/A	\$285
		40.405			RESIDENTIAL	Å4.650	- H: 11 11	44.007	44.550	6 III II II	44.554	44.650
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit Dwelling Unit	\$3,436 \$2,105	\$1,660 \$740	Dwelling Unit Dwelling Unit	\$2,298 \$1,408	\$1,660 \$740	Dwelling Unit Dwelling Unit	\$1,827 \$1,132	\$1,660 \$740	Dwelling Unit Dwelling Unit	\$1,661 \$740	\$1,660 \$740
Multifamily Housing (High-Rise)	5 11: 11:	N/A	4000	5 11: 11:	N/A	4000	5 11: 11:	N/A	4000	Dwelling Unit	\$603	\$602
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$1,835 N/A	\$938	Dwelling Unit	\$1,183 N/A	\$938	Dwelling Unit	\$951 N/A	\$938	Dwelling Unit Dwelling Unit	\$939 \$603	\$938 \$602
Mobile Home Park	Dwelling Unit	\$1,901	\$772	Dwelling Unit	\$1,340	\$772		N/A		Dwelling Unit	\$773	\$772
Retirement Community Others Not Specified	Dwelling Unit  Dwelling Unit	\$921 \$3,436	\$921 \$3,435		N/A N/A		<u> </u>	N/A N/A			N/A N/A	
Assisted Living		N/A		Bed	\$499	\$436	Bed	\$401	\$400	Beds	\$437	\$436
Senior Adult Housing Congregate Care Facility		N/A N/A			N/A N/A		Dwelling Unit  Dwelling Unit	\$456 \$310	\$436 \$303	Dwelling Unit Dwelling Unit	\$437 \$303	\$436 \$303
		A4 400	4600		LODGING	4522		A750	de a a		4507	
Hotel  Motel/Other Lodging Facilities	Room Room	\$1,433 \$1,104	\$633 \$440	Room Room	\$929 \$738	\$633 \$440	Room Room	\$758 \$593	\$633 \$440	Rooms Rooms	\$697 \$440	\$633 \$440
					RECREATIONA							·
Arena Bowling Alley	Acre 1,000 SF GFA	\$78,327 \$8,319	\$78,326 \$8,318		N/A N/A			N/A N/A			N/A N/A	
Driving Range	Tee	\$2,939	\$1,393	Tee	\$1,966	\$1,393	Tee	\$1,584	\$1,393	Driving Positions	\$1,773	\$1,393
Golf Course  Health/Recreational Clubs and Facilities	Acre 1,000 SF GFA	\$914 \$4,116	\$448 \$1,499	Acre 1,000 SF GFA	\$469 \$2,577	\$448 \$1,499	Acre 1,000 SF GFA	\$381 \$3,466	\$381 \$1,499	Holes 1,000 SF GFA	\$4,130 \$3,278	\$448 \$1,499
Ice Rink	1,000 SF GFA	\$5,548	\$1,556	1,000 SF GFA	\$3,712	\$1,556	1,000 SF GFA	\$2,987	\$1,556	1,000 SF GFA	\$1,888	\$1,556
Live Theater  Miniature Golf	Seat Hole	\$44 \$775	\$43 \$365	Hole	N/A \$518	\$365	Hole	N/A \$417	\$365	Holes	N/A \$469	\$365
Multiplex Movie Theater	Seat	\$329	\$328	Screen	\$21,443	\$5,643	Screen	\$17,261	\$5,643	Screens	\$23,046	\$5,643
Tennis Courts	Court	\$9,116	\$1,244	Court	\$5,267 INSTITUTIONA	\$1,244 L	Court	\$4,240	\$1,244	Courts	\$5,419	\$1,244
Church	1,000 SF GFA	\$1,016	\$425	1,000 SF GFA	\$680	\$425	1,000 SF GFA	\$456	\$425	1,000 SF GFA	\$736	\$425
Day Care Center  Primary/Middle School (1-8)	1,000 SF GFA Student	\$20,263 \$249	\$2,135 \$74	1,000 SF GFA Student	\$13,536 \$156	\$2,135 \$74	1,000 SF GFA Student	\$5,702 \$134	\$2,135 \$74	1,000 SF GFA Student	\$3,935 \$108	\$2,135 \$74
High School (9-12)	Student	\$234	\$80	Student	\$142	\$80	Student	\$106	\$80	Students	\$90	\$80
Jr/Community College University/College	Student Student	\$263 \$322	\$84 \$127	Student Student	\$122 \$215	\$84 \$127	Student Student	\$98 \$141	\$84 \$127	Students Students	\$184 \$253	\$84 \$127
Oniversity/ conege	Student	<b>7322</b>		Student	MEDICAL	ŢIZ1	Student			Stadents		
Clinic  Hospital	1,000 SF GFA Bed	\$14,291 \$3,370	\$3,860 \$1,497	1,000 SF GFA Bed	\$9,560 \$2,401	\$3,860 \$1,497	1,000 SF GFA Bed	\$7,695 \$2,110	\$3,860 \$1,497	1,000 SF GFA Beds	\$5,505 \$3,173	\$3,860 \$1,497
Nursing Home	Bed	\$468	\$251	Bed	\$406	\$251	Bed	\$326	\$251	Beds	\$368	\$251
Animal Hospital/Veterinary Clinic		N/A			N/A OFFICE		1,000 SF GFA	\$4,901	\$3,860	1,000 SF GFA	\$4,148	\$3,860
Corporate Headquarters Building	1,000 SF GFA	\$4,722	\$1,007	1,000 SF GFA	\$3,183	\$1,007	1,000 SF GFA	\$2,578	\$1,007	1,000 SF GFA	\$1,007	\$1,007
General Office Building  Medical/Dental Office	1,000 SF GFA 1,000 SF GFA	\$5,066 \$12,442	\$1,931 \$3,870	1,000 SF GFA 1,000 SF GFA	\$3,389 \$8,460	\$1,931 \$3,870	1,000 SF GFA 1,000 SF GFA	\$2,723 \$6,524	\$1,931 \$3,870	1,000 SF GFA 1,000 SF GFA	\$1,931 \$5,808	\$1,931 \$3,870
Single Tenant Office Building	1,000 SF GFA	\$5,848	\$2,512	1,000 SF GFA	\$3,932	\$2,512	1,000 SF GFA	\$3,179	\$2,512	1,000 SF GFA	\$2,870	\$2,512
Office Park Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$5,102 \$5,066	\$1,797 \$5,065	1,000 SF GFA	\$3,413 N/A	\$1,797	1,000 SF GFA	\$2,704 N/A	\$1,797	1,000 SF GFA	\$1,798 N/A	\$1,797
others Not Specifica	1,000 31 0171	<del>+3,000</del>	<del> </del>		COMMERCIAL			1477			14/1	
Automobile Care Center	1,000 SF GFA	\$4,766	\$1,505	1,000 SF GFA	Automobile Rela \$3,193	\$1,505	1,000 SF GFA	\$2,366	\$1,505	1,000 SF GLA	\$1,505	\$1,505
Automobile Parts Sales	1,000 SF GFA	\$8,012	\$2,252	1,000 SF GFA	\$5,359	\$2,252	1,000 SF GFA	\$4,315	\$2,252	1,000 SF GFA	\$2,253	\$2,252
Gasoline/Service Station w/ Convenience Market Convenience Market with 12 or More Fueling Positions	Fueling Position Fueling Position	\$3,706 \$2,544	\$902 \$2,543	Fueling Position	\$1,726 N/A	\$902	Fueling Position	\$1,399 N/A	\$902	ehicle Fueling Position	\$1,336 N/A	\$902
Convenience Market with Less than 12 Fueling Positions	1,000 SF GFA	\$2,580	\$2,580		N/A			N/A			N/A	
New and Used Car Sales  Quick Lubrication Vehicle Center	1,000 SF GFA	\$5,263 \$7,317	\$1,960 \$796	1,000 SF GFA Service Position	\$3,315 \$4,890	\$1,960 \$796	1,000 SF GFA	\$2,657 \$3,934	\$1,960 \$796	1,000 SF GFA	\$1,960	\$1,960 \$796
Self-Service Car Wash	Service Position Stall	\$1,520	\$495	Stall	\$4,890	\$495	Service Position Stall	\$3,934	\$495	Servicing Positions Stalls	\$2,343 \$718	\$495
Automated Car Wash  Tire Store	1,000 SF GFA	N/A \$6,974	\$2,310	1,000 SF GFA 1,000 SF GFA	\$2,049 \$5,692	\$303 \$2,310	1,000 SF GFA	N/A \$3,785	\$2,310	1,000 SF GFA	N/A \$2,310	\$2,310
THE Store	1,000 31 GFA	\$0,574	\$2,310	1,000 31 GFA	Dining	\$2,310	1,000 SI GIA	\$3,765	\$2,310	1,000 31 GFA	\$2,310	\$2,310
Fast Food Restaurant	1,000 SF GFA	\$29,306	\$3,584	1,000 SF GFA	\$20,284 N/A	\$3,584	1,000 SF GFA	\$15,402	\$3,584	1,000 SF GFA	\$16,635 3140.7	\$3,584
Fast Food Restaurant without Drive-Thru High Turnover (Sit-down) Restaurant	1,000 SF GFA 1,000 SF GFA	\$22,888 \$10,841	\$22,887 \$2,526	1,000 SF GFA	N/A \$7,286	\$2,526	1,000 SF GFA	N/A \$5,290	\$2,526	1,000 SF GFA	3140.7 \$5,671	\$2,526
Sit-Down Restaurant	1,000 SF GFA	\$7,347	\$1,892	1,000 SF GFA	\$4,910	\$1,892	1,000 SF GFA	\$3,954	\$1,892	1,000 SF GFA	\$4,448	\$1,892
Coffee / Donut Shop		N/A		1	N/A Other Retail		<u> </u>	N/A		1,000 SF GFA	\$13,245	\$2,526
Free-Standing Retail Store	1,000 SF GFA	\$6,974	\$2,201	1,000 SF GFA	\$5,565	\$2,201	1,000 SF GFA	\$4,417	\$2,201	1,000 SF GFA	\$3,415	\$2,201
Garden Center (Nursery)  Home Improvement Superstore		N/A N/A		1,000 SF GFA 1,000 SF GFA	\$4,181 \$2,704	\$2,588 \$1,364	1,000 SF GFA 1,000 SF GFA	\$6,150 \$1,533	\$2,588 \$1,364	1,000 SF GFA 1,000 SF GFA	\$4,913 \$1,365	\$2,588 \$1,364
Pharmacy/Drugstore	1,000 SF GFA	\$12,464	\$2,996	1,000 SF GFA	\$6,919	\$2,996	1,000 SF GFA	\$6,390	\$2,996	1,000 SF GFA	\$5,307	\$2,996
Shopping Center Supermarket	1,000 SF GFA 1,000 SF GFA	\$5,804 \$17,310	\$2,537 \$4,930	1,000 SF GFA 1,000 SF GFA	\$3,897 \$10,518	\$2,537 \$4,930	1,000 SF GFA 1,000 SF GFA	\$3,101 \$7,683	\$2,537 \$4,930	1,000 SF GLA 1,000 SF GFA	\$2,538 \$5,975	\$2,537 \$4,930
Video Arcade	1,000 SF GFA	\$12,500	\$12,500	2,000 SI GIA	N/A	1 77,550	2,000 SI GI A	N/A	1 77,550	2,000 SF GFA	N/A	I 77,330
Video Rental Store Toy/Children's Superstore	1,000 SF GFA	\$15,980 N/A	\$15,979	1,000 SF GFA	N/A \$5,487	\$2,159	1,000 SF GFA	N/A \$4,417	\$2,159	1,000 SF GFA	N/A \$3,538	\$2,159
				2,000 01 01 A	Wholesale	, Y2,133	2,000 01 01 A		1 42,133	2,000 JF GFA		72,133
Wholesale Market	1,000 SF GFA	\$497	\$497		N/A SERVICES			N/A			N/A	
Bank (Walk-In)	1,000 SF GFA	\$24,642	\$2,937	1,000 SF GFA	\$16,484	\$2,937	1,000 SF GFA	\$4,865	\$2,937	1,000 SF GFA	\$5,859	\$2,937
Bank (Drive-In)	Drive-in Lane	\$35,965	\$4,659	Drive-in Lane	\$20,093	\$4,659	Drive-in Lane	\$11,770	\$4,659	Drive-in Lanes	\$14,209	\$4,659
Personal Service		N/A			N/A			N/A		1,000 SF GFA	\$1,180	\$1,180

				Servi	ce Area 'I'	Combined						
shedule 1 Table D. Astual Deadurer Immed	Final Pla	at Recorded Between: 9/1/0	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	t Recorded Between: 12/1	/20 - Present*
chedule 1 Table B, Actual Roadway Impact Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	e Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Development Un
Land Use					PORT AND TERMI	NΔI						
Truck Terminal	Acre	\$19,085	\$11,449	Acre	\$21,038 INDUSTRIAL	\$11,449	Acre	\$24,779	\$11,449	1,000 SF GFA	\$11,853	\$11,449
General Light Industrial	1,000 SF GFA	\$2,855	\$1,428	1,000 SF GFA	\$3,147	\$1,428	1,000 SF GFA	\$3,669	\$1,428	1,000 SF GFA	\$3,997	\$1,428
General Heavy Industrial Industrial Park	1,000 SF GFA 1,000 SF GFA	\$1,983 \$2,681	\$1,982 \$1,785	1,000 SF GFA 1,000 SF GFA	\$2,186 \$2,763	\$419 \$1,785	1,000 SF GFA 1,000 SF GFA	\$2,575 \$3,216	\$419 \$1,785	1,000 SF GFA	N/A \$2,530	\$1,785
Warehousing	1,000 SF GFA	\$1,919	\$1,201	1,000 SF GFA	\$2,045	\$1,201	1,000 SF GFA	\$1,306	\$1,201	1,000 SF GFA	\$1,202	\$1,201
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$913 \$2,855	\$574 \$2,855	1,000 SF GFA	\$904 N/A	\$574	1,000 SF GFA	\$1,065 N/A	\$574	1,000 SF GFA	\$1,075 N/A	\$574
				- H: 11:1	RESIDENTIAL	42.004	5 III II II	44.500	44.404	5 W 11 W	45.425	44.404
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit  Dwelling Unit	\$3,524 \$2,163	\$3,523 \$2,163	Dwelling Unit Dwelling Unit	\$3,884 \$2,385	\$3,884 \$2,384	Dwelling Unit Dwelling Unit	\$4,530 \$2,809	\$4,484 \$2,732	Dwelling Unit Dwelling Unit	\$6,135 \$2,732	\$4,484 \$2,732
Multifamily Housing (High-Rise)	Dwelling Unit	N/A	¢1 00 <i>1</i>	Duralling Unit	N/A	¢1 000	Dwelling Unit	N/A	¢2.255	Dwelling Unit	\$2,226	\$2,226
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$1,884 N/A	\$1,884	Dwelling Unit	\$2,000 N/A	\$1,999	Dwelling Unit	\$2,356 N/A	\$2,355	Dwelling Unit  Dwelling Unit	\$3,466 \$2,226	\$2,558 \$2,226
Mobile Home Park	Dwelling Unit	\$1,954	\$1,953	Dwelling Unit	\$2,269	\$2,269		N/A		Dwelling Unit	\$2,846	\$2,846
Retirement Community Others Not Specified	Dwelling Unit  Dwelling Unit	\$942 \$3,524	\$942 \$3,523		N/A N/A			N/A N/A			N/A N/A	
Assisted Living		N/A		Bed	\$846	\$846	Bed	\$997	\$996	Beds	\$1,607	\$1,082
Senior Adult Housing Congregate Care Facility		N/A N/A			N/A N/A		Dwelling Unit  Dwelling Unit	\$1,133 \$770	\$1,132 \$770	Dwelling Unit Dwelling Unit	\$1,607 \$1,113	\$1,230 \$907
	P	Ć4.440	6704	D	LODGING	6704	2	64.457	6704	P	Ć2 444	
Hotel  Motel/Other Lodging Facilities	Room Room	\$1,140 \$878	\$791 \$659	Room Room	\$1,218 \$968	\$791 \$659	Room Room	\$1,457 \$1,140	\$791 \$659	Rooms Rooms	\$2,441 \$1,543	\$791 \$659
Anna	Anna	ĆC2 24.4	ĆC2 242		RECREATIONA	L		NI/A			NI/A	
Arena  Bowling Alley	Acre 1,000 SF GFA	\$62,314 \$6,617	\$62,313 \$6,617		N/A N/A			N/A N/A			N/A N/A	
Driving Range	Tee	\$2,338	\$1,741	Tee	\$2,577	\$1,741	Tee	\$3,043	\$1,741	Driving Positions	\$6,211	\$1,741
Golf Course  Health/Recreational Clubs and Facilities	Acre 1,000 SF GFA	\$727 \$3,274	\$674 \$1,390	Acre 1,000 SF GFA	\$615 \$3,378	\$615 \$1,390	Acre 1,000 SF GFA	\$732 \$6,659	\$674 \$1,390	Holes 1,000 SF GFA	\$14,472 \$11,486	\$674 \$1,390
Ice Rink	1,000 SF GFA	\$4,414	\$1,969	1,000 SF GFA	\$4,865	\$1,969	1,000 SF GFA	\$5,738	\$1,969	1,000 SF GFA	\$6,616	\$1,969
Live Theater  Miniature Golf	Seat Hole	\$35 \$616	\$34 \$457	Hole	N/A \$679	\$457	Hole	N/A \$800	\$457	Holes	N/A \$1,645	\$457
Multiplex Movie Theater	Seat	\$262	\$261	Screen	\$28,108	\$6,954	Screen	\$33,160	\$6,954	Screens	\$104,211	\$6,954
Tennis Courts	Court	\$7,251	\$1,784	Court	\$6,904 INSTITUTIONA	\$1,784 L	Court	\$8,146	\$1,784	Courts	\$18,988	\$1,784
Church	1,000 SF GFA	\$808	\$538	1,000 SF GFA	\$891	\$538	1,000 SF GFA	\$876	\$538	1,000 SF GFA	\$2,581	\$538
Day Care Center Primary/Middle School (1-8)	1,000 SF GFA Student	\$16,119 \$198	\$2,791 \$95	1,000 SF GFA Student	\$17,743 \$205	\$2,791 \$95	1,000 SF GFA Student	\$10,955 \$257	\$2,791 \$95	1,000 SF GFA Student	\$13,789 \$380	\$2,791 \$95
High School (9-12)	Student	\$186	\$102	Student	\$186	\$102	Student	\$204	\$102	Students	\$316	\$102
Jr/Community College University/College	Student Student	\$209 \$256	\$106 \$162	Student Student	\$160 \$282	\$106 \$162	Student Student	\$189 \$272	\$106 \$162	Students Students	\$645 \$987	\$106 \$162
					MEDICAL				1		100.000	
Clinic Hospital	1,000 SF GFA Bed	\$11,368 \$2,681	\$4,902 \$1,886	1,000 SF GFA Bed	\$12,532 \$3,147	\$4,902 \$1,886	1,000 SF GFA Bed	\$14,783 \$4,054	\$4,902 \$1,886	1,000 SF GFA Beds	\$20,455 \$11,790	\$4,902 \$1,886
Nursing Home	Bed	\$372	\$318	Bed	\$532	\$318	Bed	\$627	\$318	Beds	\$1,366	\$318
Animal Hospital/Veterinary Clinic		N/A			N/A OFFICE		1,000 SF GFA	\$9,415	\$4,902	1,000 SF GFA	\$15,408	\$4,902
Corporate Headquarters Building	1,000 SF GFA	\$4,414	\$2,155	1,000 SF GFA	\$4,897	\$2,155	1,000 SF GFA	\$5,814	\$2,155	1,000 SF GFA	\$4,554	\$2,155
General Office Building  Medical/Dental Office	1,000 SF GFA 1,000 SF GFA	\$4,733 \$11,618	\$2,302 \$5,579	1,000 SF GFA 1,000 SF GFA	\$5,218 \$13,019	\$2,302 \$5,579	1,000 SF GFA 1,000 SF GFA	\$6,146 \$14,715	\$2,302 \$5,579	1,000 SF GFA 1,000 SF GFA	\$8,729 \$21,581	\$2,302 \$5,579
Single Tenant Office Building	1,000 SF GFA	\$5,460	\$2,664	1,000 SF GFA	\$6,057	\$2,664	1,000 SF GFA	\$7,173	\$2,664	1,000 SF GFA	\$12,979	\$2,664
Office Park Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$4,762 \$4,733	\$2,311 \$4,733	1,000 SF GFA	\$5,250 N/A	\$2,311	1,000 SF GFA	\$6,100 N/A	\$2,311	1,000 SF GFA	\$8,121 N/A	\$2,311
					COMMERCIAL							
Automobile Care Center	1,000 SF GFA	\$3,791	\$2,862	1,000 SF GFA	Automobile Rela \$4,186	<b>ted</b> \$2,862	1,000 SF GFA	\$4,545	\$2,862	1,000 SF GLA	\$5,275	\$2,862
Automobile Parts Sales	1,000 SF GFA	\$6,373	\$3,354	1,000 SF GFA	\$7,025	\$3,354	1,000 SF GFA	\$8,290	\$3,354	1,000 SF GFA	\$7,894	\$3,354
Gasoline/Service Station w/ Convenience Market Convenience Market with 12 or More Fueling Positions	Fueling Position Fueling Position	\$2,948 \$2,024	\$1,165 \$2,023	Fueling Position	\$2,263 N/A	\$1,165	Fueling Position	\$2,688 N/A	\$1,165	ehicle Fueling Positior	\$4,681 N/A	\$1,165
Convenience Market with Less than 12 Fueling Positions	1,000 SF GFA	\$2,053	\$2,052		N/A	4	4 6 5 5 -	N/A	1		N/A	1.
New and Used Car Sales  Quick Lubrication Vehicle Center	1,000 SF GFA Service Position	\$4,187 \$5,821	\$1,897 \$1,036	1,000 SF GFA Service Position	\$4,346 \$6,410	\$1,897 \$1,036	1,000 SF GFA Service Position	\$5,104 \$7,558	\$1,897 \$1,036	1,000 SF GFA Servicing Positions	\$6,869 \$8,210	\$1,897 \$1,036
Self-Service Car Wash	Stall	\$1,210	\$641	Stall	\$1,276	\$641	Stall	\$1,502	\$641	Stalls	\$2,517	\$641
Automated Car Wash  Tire Store	1,000 SF GFA	N/A \$5,548	\$3,280	1,000 SF GFA 1,000 SF GFA	\$2,686 \$7,461	\$397 \$3,280	1,000 SF GFA	N/A \$7,271	\$3,280	1,000 SF GFA	N/A \$8,096	\$3,280
	·				Dining							
Fast Food Restaurant Fast Food Restaurant without Drive-Thru	1,000 SF GFA 1,000 SF GFA	\$23,312 \$18,207	\$4,622 \$18,206	1,000 SF GFA	\$26,589 N/A	\$4,622	1,000 SF GFA	\$29,588 N/A	\$4,622	1,000 SF GFA	\$58,291 N/A	\$4,622
High Turnover (Sit-down) Restaurant	1,000 SF GFA	\$8,624	\$3,245	1,000 SF GFA	\$9,551	\$3,245	1,000 SF GFA	\$10,162	\$3,245	1,000 SF GFA	\$19,873	\$3,245
Sit-Down Restaurant Coffee / Donut Shop	1,000 SF GFA	\$5,844 N/A	\$2,402	1,000 SF GFA	\$6,436 N/A	\$2,402	1,000 SF GFA	\$7,595 N/A	\$2,402	1,000 SF GFA 1,000 SF GFA	\$15,585 \$46,413	\$2,402 \$3,245
					Other Retail							
Free-Standing Retail Store Garden Center (Nursery)	1,000 SF GFA	\$5,548 N/A	\$2,803	1,000 SF GFA 1,000 SF GFA	\$7,295 \$5,481	\$2,803 \$3,394	1,000 SF GFA 1,000 SF GFA	\$8,486 \$11,816	\$2,803 \$3,394	1,000 SF GFA 1,000 SF GFA	\$11,967 \$17,217	\$2,803 \$3,394
Home Improvement Superstore		N/A		1,000 SF GFA 1,000 SF GFA	\$3,481	\$2,194	1,000 SF GFA 1,000 SF GFA	\$2,945	\$3,394	1,000 SF GFA	\$4,782	\$2,194
Pharmacy/Drugstore Shopping Center	1,000 SF GFA 1,000 SF GFA	\$9,915 \$4,617	\$3,778 \$3,747	1,000 SF GFA 1,000 SF GFA	\$9,070 \$5,109	\$3,778 \$3,747	1,000 SF GFA 1,000 SF GFA	\$12,276 \$5,957	\$3,778 \$3,747	1,000 SF GFA 1,000 SF GLA	\$18,596 \$8,893	\$3,778 \$3,747
Supermarket	1,000 SF GFA	\$13,770	\$6,143	1,000 SF GFA 1,000 SF GFA	\$13,788	\$6,143	1,000 SF GFA 1,000 SF GFA	\$14,760	\$6,143	1,000 SF GFA	\$20,936	\$3,747
Video Arcade Video Rental Store	1,000 SF GFA 1,000 SF GFA	\$9,944 \$12,712	\$9,943 \$12,711		N/A N/A			N/A N/A			N/A N/A	
Toy/Children's Superstore	1,000 SF GFA	\$12,/12 N/A	γ12,/11	1,000 SF GFA	\$7,192	\$3,215	1,000 SF GFA	\$8,486	\$3,215	1,000 SF GFA	\$12,397	\$3,215
	1,000 05 054	6205	6205		Wholesale N/A			N1 / A			N1/A	
Wholesale Market	1,000 SF GFA	\$395	\$395		N/A SERVICES			N/A			N/A	
	1,000 SF GFA	\$19,602	\$3,781	1,000 SF GFA	\$21,608	\$3,781	1,000 SF GFA	\$9,347	\$3,781	1,000 SF GFA	\$20,531	\$3,781
Bank (Walk-In) Bank (Drive-In)	Drive-in Lane	\$28,610	\$6,019	Drive-in Lane	\$26,339	\$6,019	Drive-in Lane	\$22,612	\$6,019	Drive-in Lanes	\$49,790	\$6,019

				Servi	ce Area 'J'	Combined						
Schodulo 1 Table D. Actual Deadway Impact	Final Pl	at Recorded Between: 9/1/0	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	/08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	t Recorded Between: 12/1	/20 - Present*
chedule 1 Table B, Actual Roadway Impact Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged
Land Use					PORT AND TERMI	NΔI						
Truck Terminal	Acre	\$27,257	\$3,251	Acre	\$23,598 INDUSTRIAL	\$3,251	Acre	\$27,044	\$3,251	1,000 SF GFA	\$3,251	\$3,251
General Light Industrial	1,000 SF GFA	\$4,078	\$922	1,000 SF GFA	\$3,530	\$922	1,000 SF GFA	\$4,005	\$922	1,000 SF GFA	\$1,097	\$922
General Heavy Industrial  Industrial Park	1,000 SF GFA 1,000 SF GFA	\$2,832 \$3,829	\$2,832 \$694	1,000 SF GFA 1,000 SF GFA	\$2,452 \$3,099	\$473 \$694	1,000 SF GFA 1,000 SF GFA	\$2,810 \$3,510	\$473 \$694	1,000 SF GFA	N/A \$694	\$694
Warehousing	1,000 SF GFA	\$2,741	\$329	1,000 SF GFA	\$2,294	\$329	1,000 SF GFA	\$1,426	\$329	1,000 SF GFA	\$330	\$329
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$1,304 \$4,078	\$294 \$4,077	1,000 SF GFA	\$1,014 N/A	\$294	1,000 SF GFA	\$1,162 N/A	\$294	1,000 SF GFA	\$295 N/A	\$294
				- H: 11:1	RESIDENTIAL		- H: 11 11	T 44.044	44.500	6 III II II	44.500	44.600
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit Dwelling Unit	\$5,033 \$3,089	\$1,682 \$749	Dwelling Unit Dwelling Unit	\$4,357 \$2,675	\$1,682 \$749	Dwelling Unit Dwelling Unit	\$4,944 \$3,065	\$1,682 \$749	Dwelling Unit Dwelling Unit	\$1,683 \$750	\$1,682 \$749
Multifamily Housing (High-Rise)	Duralling Unit	N/A	ĆOFO	Duralling Unit	N/A	\$950	Duralling Unit	N/A	\$950	Dwelling Unit	\$611	\$610 \$950
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$2,691 N/A	\$950	Dwelling Unit	\$2,243 N/A	\$950	Dwelling Unit	\$2,571 N/A	\$950	Dwelling Unit  Dwelling Unit	\$951 \$611	\$610
Mobile Home Park Retirement Community	Dwelling Unit Dwelling Unit	\$2,790 \$1,345	\$780 \$1,345	Dwelling Unit	\$2,545 N/A	\$780		N/A N/A		Dwelling Unit	\$781 N/A	\$780
Others Not Specified	Dwelling Unit	\$5,033	\$5,032		N/A			N/A N/A			N/A N/A	
Assisted Living Senior Adult Housing		N/A N/A		Bed	\$949 N/A	\$440	Bed Dwelling Unit	\$1,088 \$1,236	\$440 \$440	Beds Dwelling Unit	\$441 \$441	\$440 \$440
Congregate Care Facility		N/A			N/A		Dwelling Unit	\$840	\$305	Dwelling Unit	\$305	\$305
Hotel	Room	\$1,628	\$669	Room	<b>LODGING</b> \$1,366	\$669	Room	\$1,590	\$669	Rooms	\$670	\$669
Hotel  Motel/Other Lodging Facilities	коот Room	\$1,628 \$1,254	\$669 \$423	Room Room	\$1,086	\$423	Room Room	\$1,590 \$1,244	\$423	Rooms Rooms	\$423	\$669
Arena	Acre	\$88,996	\$88,996		RECREATIONA N/A	L		N/A			N/A	
Bowling Alley	1,000 SF GFA	\$9,451	\$9,451		N/A			N/A			N/A	
Driving Range Golf Course	Tee Acre	\$3,339 \$1,038	\$1,703 \$764	Tee Acre	\$2,890 \$690	\$1,703 \$690	Tee Acre	\$3,321 \$799	\$1,703 \$764	Driving Positions Holes	\$1,704 \$3,970	\$1,703 \$764
Health/Recreational Clubs and Facilities	1,000 SF GFA	\$4,676	\$1,568	1,000 SF GFA	\$3,789	\$1,568	1,000 SF GFA	\$7,268	\$1,568	1,000 SF GFA	\$3,151	\$1,568
Ice Rink Live Theater	1,000 SF GFA Seat	\$6,303 \$50	\$1,814 \$49	1,000 SF GFA	\$5,457 N/A	\$1,814	1,000 SF GFA	\$6,262 N/A	\$1,814	1,000 SF GFA	\$1,815 N/A	\$1,814
Miniature Golf	Hole	\$880	\$451	Hole	\$762	\$451	Hole	\$873	\$451	Holes	\$451	\$451
Multiplex Movie Theater Tennis Courts	Seat Court	\$374 \$10,356	\$373 \$1,464	Screen Court	\$31,528 \$7,744	\$7,948 \$1,464	Screen Court	\$36,190 \$8,891	\$7,948 \$1,464	Screens Courts	\$28,586 \$5,208	\$7,948 \$1,464
Terrins courts	Court	710,330	Ş1, <del>404</del>	Court	INSTITUTIONA		Court	70,031	<b>71,404</b>	Courts	73,200	71,404
Church  Day Care Center	1,000 SF GFA 1,000 SF GFA	\$1,154 \$23,021	\$607 \$3,132	1,000 SF GFA 1,000 SF GFA	\$999 \$19,902	\$607 \$3,132	1,000 SF GFA 1,000 SF GFA	\$956 \$11,956	\$607 \$3,132	1,000 SF GFA 1,000 SF GFA	\$708 \$3,782	\$607 \$3,132
Primary/Middle School (1-8)	Student	\$282	\$104	Student	\$230	\$104	Student	\$280	\$104	Student	\$104	\$104
High School (9-12)  Jr/Community College	Student Student	\$266 \$299	\$86 \$119	Student Student	\$209 \$180	\$86 \$119	Student Student	\$222 \$206	\$86 \$119	Students Students	\$87 \$198	\$86 \$119
University/College	Student	\$365	\$182	Student	\$316	\$182	Student	\$297	\$182	Students	\$271	\$182
Clinic	1,000 SF GFA	\$16,236	\$5,529	1,000 SF GFA	\$14,056	\$5,529	1,000 SF GFA	\$16,134	\$5,529	1,000 SF GFA	\$5,611	\$5,529
Hospital	Bed	\$3,829	\$2,131	Bed	\$3,530	\$2,131	Bed	\$4,425	\$2,131	Beds	\$3,234	\$2,131
Nursing Home Animal Hospital/Veterinary Clinic	Bed	\$532 N/A	\$359	Bed	\$597 N/A	\$359	Bed 1,000 SF GFA	\$684 \$10,275	\$359 \$4,226	Beds 1,000 SF GFA	\$375 \$4,226	\$359 \$4,226
					OFFICE					·		
Corporate Headquarters Building General Office Building	1,000 SF GFA 1,000 SF GFA	\$6,303 \$6,760	\$1,249 \$2,394	1,000 SF GFA 1,000 SF GFA	\$5,493 \$5,853	\$1,249 \$2,394	1,000 SF GFA 1,000 SF GFA	\$6,345 \$6,707	\$1,249 \$2,394	1,000 SF GFA 1,000 SF GFA	\$1,249 \$2,394	\$1,249 \$2,394
Medical/Dental Office	1,000 SF GFA	\$16,593	\$5,919	1,000 SF GFA	\$14,603	\$5,919	1,000 SF GFA	\$16,060	\$5,919	1,000 SF GFA	\$5,920	\$5,919
Single Tenant Office Building Office Park	1,000 SF GFA 1,000 SF GFA	\$7,798 \$6,802	\$3,012 \$2,227	1,000 SF GFA 1,000 SF GFA	\$6,795 \$5,889	\$3,012 \$2,227	1,000 SF GFA 1,000 SF GFA	\$7,828 \$6,658	\$3,012 \$2,227	1,000 SF GFA 1,000 SF GFA	\$3,560 \$2,228	\$3,012 \$2,227
Others Not Specified	1,000 SF GFA	\$6,760	\$6,760	,	N/A		,	N/A	, ,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	N/A	, ,
					COMMERCIAL Automobile Rela							
Automobile Care Center	1,000 SF GFA	\$5,415	\$1,446	1,000 SF GFA	\$4,695	\$1,446	1,000 SF GFA	\$4,960	\$1,446	1,000 SF GLA	\$1,447	\$1,446
Automobile Parts Sales Gasoline/Service Station w/ Convenience Market	1,000 SF GFA Fueling Position	\$9,102 \$4,211	\$2,165 \$918	1,000 SF GFA Fueling Position	\$7,880 \$2,538	\$2,165 \$918	1,000 SF GFA Fueling Position	\$9,048 \$2,933	\$2,165 \$918	1,000 SF GFA /ehicle Fueling Position	\$2,165 \$1,284	\$2,165 \$918
Convenience Market with 12 or More Fueling Positions	Fueling Position	\$2,890	\$2,890	Çşı	N/A		<u> </u>	N/A		0 23.031	N/A	, , , , ,
Convenience Market with Less than 12 Fueling Positions  New and Used Car Sales	1,000 SF GFA 1,000 SF GFA	\$2,932 \$5,980	\$2,931 \$1,884	1,000 SF GFA	N/A \$4,875	\$1,884	1,000 SF GFA	N/A \$5,570	\$1,884	1,000 SF GFA	N/A \$1,884	\$1,884
Quick Lubrication Vehicle Center	Service Position	\$8,313	\$1,164	Service Position	\$7,190	\$1,164	Service Position	\$8,248	\$1,164	Servicing Positions	\$2,252	\$1,164
Self-Service Car Wash Automated Car Wash	Stall	\$1,727 N/A	\$690	Stall 1,000 SF GFA	\$1,431 \$3,013	\$690 \$297	Stall	\$1,640 N/A	\$690	Stalls	\$691 N/A	\$690
Tire Store	1,000 SF GFA	\$7,923	\$2,220	1,000 SF GFA	\$8,369 <b>Dining</b>	\$2,220	1,000 SF GFA	\$7,935	\$2,220	1,000 SF GFA	\$2,221	\$2,220
Fast Food Restaurant	1,000 SF GFA	\$33,295	\$5,197	1,000 SF GFA	\$29,824	\$5,197	1,000 SF GFA	\$32,293	\$5,197	1,000 SF GFA	\$15,990	\$5,197
Fast Food Restaurant without Drive-Thru	1,000 SF GFA	\$26,003	\$26,002	1,000 SF GFA	N/A	\$3,652	1,000 SF GFA	N/A \$11,091	\$3,652	1,000 SF GFA	N/A	\$3,652
High Turnover (Sit-down) Restaurant Sit-Down Restaurant	1,000 SF GFA 1,000 SF GFA	\$12,316 \$8,347	\$3,652 \$2,709	1,000 SF GFA 1,000 SF GFA	\$10,713 \$7,219	\$3,652	1,000 SF GFA 1,000 SF GFA	\$11,091	\$3,652	1,000 SF GFA 1,000 SF GFA	\$5,451 \$4,275	\$2,709
Coffee / Donut Shop		N/A			N/A Other Retail			N/A		1,000 SF GFA	\$12,731	\$3,652
Free-Standing Retail Store	1,000 SF GFA	\$7,923	\$3,160	1,000 SF GFA	\$8,182	\$3,160	1,000 SF GFA	\$9,262	\$3,160	1,000 SF GFA	\$3,283	\$3,160
Garden Center (Nursery) Home Improvement Superstore		N/A N/A		1,000 SF GFA 1,000 SF GFA	\$6,147 \$3,976	\$3,806 \$1,311	1,000 SF GFA 1,000 SF GFA	\$12,896 \$3,214	\$3,806 \$1,311	1,000 SF GFA 1,000 SF GFA	\$4,723 \$1,312	\$3,806 \$1,311
Pharmacy/Drugstore	1,000 SF GFA	\$14,160	\$4,265	1,000 SF GFA	\$10,174	\$4,265	1,000 SF GFA	\$13,398	\$4,265	1,000 SF GFA	\$5,101	\$4,265
Shopping Center Supermarket	1,000 SF GFA 1,000 SF GFA	\$6,594 \$19,666	\$2,439 \$5,742	1,000 SF GFA 1,000 SF GFA	\$5,730 \$15,466	\$2,439 \$5,742	1,000 SF GFA 1,000 SF GFA	\$6,501 \$16,109	\$2,439 \$5,742	1,000 SF GLA 1,000 SF GFA	\$2,439 \$5,743	\$2,439 \$5,742
Video Arcade	1,000 SF GFA	\$14,202	\$14,201	1,000 JI GFA	N/A	γJ,/42	1,000 JI GFA	N/A	۷۶,۱۴۷	1,000 SI GFA	N/A	J.,/42
Video Rental Store Toy/Children's Superstore	1,000 SF GFA	\$18,155 N/A	\$18,154	1,000 SF GFA	N/A \$8,067	\$3,137	1,000 SF GFA	N/A \$9,262	\$3,137	1,000 SF GFA	N/A \$3,401	\$3,137
				1,000 31 GIA	Wholesale	1 73,137	1,000 JI UIA		1 75,157	1,000 JI GIA		, ,,±3/
Wholesale Market	1,000 SF GFA	\$565	\$564		N/A SERVICES			N/A			N/A	
Bank (Walk-In)	1,000 SF GFA	\$27,996	\$4,255	1,000 SF GFA	\$24,237	\$4,255	1,000 SF GFA	\$10,201	\$4,255	1,000 SF GFA	\$5,632	\$4,255
Bank (Drive-In)	Drive-in Lane	\$40,861 N/A	\$6,767	Drive-in Lane	\$29,544 N/A	\$6,767	Drive-in Lane	\$24,679 N/A	\$6,767	Drive-in Lanes	\$13,658	\$6,767 \$1,124
Personal Service		IN/A			IV/A		<u> </u>	N/A		1,000 SF GFA	\$1,135	\$1,134

				Servi	ce Area 'K'	Combined						
Schedule 1 Table B, Actual Roadway Impact	Final Pla	at Recorded Between: 9/1/	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	at Recorded Between: 12/1	/20 - Present*
Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Development Uni
Land Use					PORT AND TERMI	NAL						
Truck Terminal	Acre	\$26,043	\$11,215	Acre	\$37,841 INDUSTRIAL	\$11,215	Acre	\$38,793	\$11,215	1,000 SF GFA	\$11,216	\$11,215
General Light Industrial	1,000 SF GFA	\$3,896	\$1,642	1,000 SF GFA	\$5,661	\$1,642	1,000 SF GFA	\$5,745	\$1,642	1,000 SF GFA	\$3,783	\$1,642
General Heavy Industrial  Industrial Park	1,000 SF GFA 1,000 SF GFA	\$2,706 \$3,658	\$2,705 \$2,053	1,000 SF GFA 1,000 SF GFA	\$3,932 \$4,969	\$481 \$2,053	1,000 SF GFA 1,000 SF GFA	\$4,031 \$5,035	\$481 \$2,053	1,000 SF GFA	N/A \$2,394	\$2,053
Warehousing	1,000 SF GFA	\$2,619	\$1,137	1,000 SF GFA	\$3,609	\$1,137	1,000 SF GFA	\$2,009	\$1,137	1,000 SF GFA	\$1,137	\$1,137
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$1,246 \$3,896	\$897 \$3,896	1,000 SF GFA	\$1,591 N/A	\$897	1,000 SF GFA	\$1,631 N/A	\$897	1,000 SF GFA	\$1,017 N/A	\$897
		1		- "	RESIDENTIAL	4		1 40.000	1 4		45.000	1
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit Dwelling Unit	\$4,809 \$2,952	\$4,484 \$2,585	Dwelling Unit Dwelling Unit	\$6,169 \$3,793	\$4,484 \$2,585	Dwelling Unit Dwelling Unit	\$6,265 \$3,889	\$4,484 \$2,585	Dwelling Unit Dwelling Unit	\$5,805 \$2,586	\$4,484 \$2,585
Multifamily Housing (High-Rise)		N/A			N/A		Ü	N/A		Dwelling Unit	\$2,107	\$2,106
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$2,571 N/A	\$2,570	Dwelling Unit	\$3,182 N/A	\$3,182	Dwelling Unit	\$3,262 N/A	\$3,262	Dwelling Unit Dwelling Unit	\$3,280 \$2,107	\$3,279 \$2,106
Mobile Home Park	Dwelling Unit	\$2,666	\$2,666	Dwelling Unit	\$3,609	\$2,693		N/A		Dwelling Unit	\$2,693	\$2,693
Retirement Community Others Not Specified	Dwelling Unit Dwelling Unit	\$1,285 \$4,809	\$1,285 \$4,808		N/A N/A			N/A N/A			N/A N/A	
Assisted Living	0 1	N/A	, , , , , ,	Bed	\$1,349	\$1,349	Bed	\$1,383	\$1,382	Beds	\$1,520	\$1,520
Senior Adult Housing Congregate Care Facility		N/A N/A			N/A N/A		Dwelling Unit Dwelling Unit	\$1,572 \$1,064	\$1,520 \$1,053	Dwelling Unit Dwelling Unit	\$1,520 \$1,053	\$1,520 \$1,053
			·		LODGING	·						
Hotel  Motel/Other Lodging Facilities	Room Room	\$1,555 \$1,198	\$1,228 \$1,024	Room Room	\$2,191 \$1,741	\$1,228 \$1,024	Room Room	\$2,281 \$1,785	\$1,228 \$1,024	Rooms Rooms	\$2,310 \$1,460	\$1,228 \$1,024
					RECREATIONA				¥-7			13/22
Arena Bowling Alley	Acre 1,000 SF GFA	\$85,031 \$9,030	\$85,031 \$9,030		N/A N/A			N/A N/A			N/A N/A	
Driving Range	Tee	\$3,190	\$1,994	Tee	\$4,635	\$1,994	Tee	\$4,763	\$1,994	Driving Positions	\$5,877	\$1,994
Golf Course  Health/Recreational Clubs and Facilities	Acre 1,000 SF GFA	\$992 \$4,467	\$814 \$1,615	Acre 1,000 SF GFA	\$1,107 \$6,076	\$814 \$1,615	Acre 1,000 SF GFA	\$1,147 \$10,425	\$814 \$1,615	Holes 1,000 SF GFA	\$13,694 \$10,869	\$814 \$1,615
Ice Rink	1,000 SF GFA	\$6,023	\$1,947	1,000 SF GFA	\$8,751	\$1,947	1,000 SF GFA	\$8,983	\$1,947	1,000 SF GFA	\$6,260	\$1,947
Live Theater  Miniature Golf	Seat Hole	\$48 \$841	\$47 \$713	Hole	N/A \$1,222	\$713	Hole	N/A \$1,253	\$713	Holes	N/A \$1,556	\$713
Multiplex Movie Theater	Seat	\$357	\$357	Screen	\$50,559	\$10,524	Screen	\$51,913	\$10,524	Screens	\$87,106	\$10,524
Tennis Courts	Court	\$9,895	\$1,575	Court	\$12,418 INSTITUTIONA	\$1,575	Court	\$12,754	\$1,575	Courts	\$17,967	\$1,575
Church	1,000 SF GFA	\$1,103	\$872	1,000 SF GFA	\$1,603	\$872	1,000 SF GFA	\$1,371	\$872	1,000 SF GFA	\$2,442	\$872
Day Care Center	1,000 SF GFA	\$21,996	\$4,987	1,000 SF GFA	\$31,915	\$4,987	1,000 SF GFA	\$17,151	\$4,987	1,000 SF GFA	\$13,047	\$4,987
Primary/Middle School (1-8) High School (9-12)	Student Student	\$270 \$254	\$173 \$171	Student Student	\$369 \$334	\$173 \$171	Student Student	\$402 \$319	\$173 \$171	Student Students	\$359 \$299	\$173 \$171
Jr/Community College	Student	\$286	\$166	Student	\$288	\$166	Student	\$296	\$166	Students	\$682	\$166
University/College	Student	\$349	\$267	Student	\$507 MEDICAL	\$267	Student	\$426	\$267	Students	\$934	\$267
Clinic	1,000 SF GFA	\$15,513	\$5,553	1,000 SF GFA	\$22,541	\$5,553	1,000 SF GFA	\$23,144	\$5,553	1,000 SF GFA	\$19,355	\$5,553
Hospital Nursing Home	Bed Bed	\$3,658 \$508	\$2,177 \$507	Bed Bed	\$5,661 \$957	\$2,177 \$518	Bed Bed	\$6,347 \$981	\$2,177 \$518	Beds Beds	\$11,156 \$1,293	\$2,177 \$518
Animal Hospital/Veterinary Clinic		N/A	·		N/A	·	1,000 SF GFA	\$14,740	\$5,553	1,000 SF GFA	\$14,579	\$5,553
Corporate Headquarters Building	1,000 SF GFA	\$5,848	\$3,253	1,000 SF GFA	<b>OFFICE</b> \$8,555	\$3,253	1,000 SF GFA	\$8,830	\$3,253	1,000 SF GFA	\$3,806	\$3,253
General Office Building	1,000 SF GFA	\$6,269	\$3,469	1,000 SF GFA	\$9,109	\$3,469	1,000 SF GFA	\$9,338	\$3,469	1,000 SF GFA	\$7,302	\$3,469
Medical/Dental Office Single Tenant Office Building	1,000 SF GFA 1,000 SF GFA	\$15,394 \$7,237	\$5,949 \$4,019	1,000 SF GFA 1,000 SF GFA	\$22,737 \$10,573	\$5,949 \$4,019	1,000 SF GFA 1,000 SF GFA	\$22,363 \$10,898	\$5,949 \$4,019	1,000 SF GFA 1,000 SF GFA	\$20,421 \$10,845	\$5,949 \$4,019
Office Park	1,000 SF GFA	\$6,308	\$3,486	1,000 SF GFA	\$9,166	\$3,486	1,000 SF GFA	\$9,267	\$3,486	1,000 SF GFA	\$6,787	\$3,486
Others Not Specified	1,000 SF GFA	\$6,269	\$6,268		N/A COMMERCIAL			N/A			N/A	
					Automobile Rela	ted						
Automobile Care Center  Automobile Parts Sales	1,000 SF GFA 1,000 SF GFA	\$5,174 \$8,697	\$3,274 \$4,504	1,000 SF GFA 1,000 SF GFA	\$7,529 \$12,637	\$3,274 \$4,504	1,000 SF GFA 1,000 SF GFA	\$7,116 \$12,978	\$3,274 \$4,504	1,000 SF GLA 1,000 SF GFA	\$4,991 \$7,469	\$3,274 \$4,504
Gasoline/Service Station w/ Convenience Market	Fueling Position	\$4,023	\$748	Fueling Position	\$4,070	\$748	Fueling Position	\$4,208	\$748	ehicle Fueling Position		\$748
Convenience Market with 12 or More Fueling Positions	Fueling Position	\$2,761	\$2,761		N/A N/A			N/A N/A			N/A N/A	
Convenience Market with Less than 12 Fueling Positions  New and Used Car Sales	1,000 SF GFA 1,000 SF GFA	\$2,801 \$5,713	\$2,801 \$2,986	1,000 SF GFA	\$7,817	\$2,986	1,000 SF GFA	\$7,990	\$2,986	1,000 SF GFA	\$6,500	\$2,986
Quick Lubrication Vehicle Center	Service Position	\$7,943	\$1,830	Service Position	\$11,530	\$1,830	Service Position	\$11,832	\$1,830	Servicing Positions	\$7,769	\$1,830
Self-Service Car Wash Automated Car Wash	Stall	\$1,650 N/A	\$405	Stall 1,000 SF GFA	\$2,294 \$4,831	\$405 \$271	Stall	\$2,352 N/A	\$405	Stalls	\$2,382 N/A	\$405
Tire Store	1,000 SF GFA	\$7,570	\$4,531	1,000 SF GFA	\$13,421	\$4,531	1,000 SF GFA	\$11,383	\$4,531	1,000 SF GFA	\$7,661	\$4,531
Fast Food Restaurant	1,000 SF GFA	\$31,811	\$7,923	1,000 SF GFA	\$47,826	\$7,923	1,000 SF GFA	\$46,323	\$7,923	1,000 SF GFA	\$55,158	\$7,923
Fast Food Restaurant without Drive-Thru	1,000 SF GFA	\$24,844	\$24,844		N/A			N/A			N/A	
High Turnover (Sit-down) Restaurant Sit-Down Restaurant	1,000 SF GFA 1,000 SF GFA	\$11,768 \$7,975	\$2,972 \$3,931	1,000 SF GFA 1,000 SF GFA	\$17,180 \$11,576	\$2,972 \$3,931	1,000 SF GFA 1,000 SF GFA	\$15,910 \$11,891	\$2,972 \$3,931	1,000 SF GFA 1,000 SF GFA	\$18,805 \$14,747	\$2,972 \$3,931
Coffee / Donut Shop	,::::: 3	N/A	, , , , , , , ,	,	N/A		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	N/A	, , , , , , , , , , , , , , , , , , , ,	1,000 SF GFA	\$43,918	\$2,972
Free-Standing Retail Store	1,000 SF GFA	\$7,570	\$4,622	1,000 SF GFA	Other Retail \$13,121	\$4,622	1,000 SF GFA	\$13,286	\$4,622	1,000 SF GFA	\$11,324	\$4,622
Garden Center (Nursery)	1,000 SF GFA	\$7,570 N/A	<u> </u>	1,000 SF GFA 1,000 SF GFA	\$13,121	\$4,622 \$6,106	1,000 SF GFA 1,000 SF GFA	\$13,286	\$4,622	1,000 SF GFA 1,000 SF GFA	\$11,324	\$4,622
Home Improvement Superstore	1 000 05 050	N/A	ć4 400	1,000 SF GFA	\$6,376	\$3,949	1,000 SF GFA	\$4,610 \$10,210	\$3,949	1,000 SF GFA	\$4,525	\$3,949
Pharmacy/Drugstore Shopping Center	1,000 SF GFA 1,000 SF GFA	\$13,529 \$6,300	\$4,190 \$4,236	1,000 SF GFA 1,000 SF GFA	\$16,315 \$9,189	\$4,190 \$4,236	1,000 SF GFA 1,000 SF GFA	\$19,219 \$9,326	\$4,190 \$4,236	1,000 SF GFA 1,000 SF GLA	\$17,596 \$8,415	\$4,190 \$4,236
Supermarket	1,000 SF GFA	\$18,790	\$6,903	1,000 SF GFA	\$24,801	\$6,903	1,000 SF GFA	\$23,108	\$6,903	1,000 SF GFA	\$19,810	\$6,903
Video Arcade Video Rental Store	1,000 SF GFA 1,000 SF GFA	\$13,569 \$17,346	\$13,568 \$17,345		N/A N/A			N/A N/A			N/A N/A	
Toy/Children's Superstore		N/A		1,000 SF GFA	\$12,937	\$4,006	1,000 SF GFA	\$13,286	\$4,006	1,000 SF GFA	\$11,731	\$4,006
Wholesale Market	1,000 SF GFA	\$540	\$539		Wholesale N/A		I	N/A		I	N/A	
					SERVICES							
Bank (Walk-In)	1,000 SF GFA Drive-in Lane	\$26,749 \$39,040	\$6,467 \$10,376	1,000 SF GFA Drive-in Lane	\$38,868 \$47,377	\$6,467 \$10,376	1,000 SF GFA Drive-in Lane	\$14,633 \$35,401	\$6,467 \$10,376	1,000 SF GFA Drive-in Lanes	\$19,427 \$47,114	\$6,467 \$10,376
Bank (Drive-In)					\$47377	5111376		333411.				. JIU.J/U

				Servi	ce Area 'L'	Combined						
	Final Di	at Pacardad Ratuaan: 0/1/	11/0/09*					Pacardod Ratusani 11/20	/12 11/20/20*	Final Dia	at Recorded Retween: 12/1	/20 Procent*
Schedule 1 Table B, Actual Roadway Impact	Final Pi	at Recorded Between: 9/1/0	)3 - 11/9/08* 	Final Plat	Recorded Between: 11/10/	08 - 11/19/13*	Final Plat	Recorded Between: 11/20/	/13 - 11/30/20*	Finai Pia	t Recorded Between: 12/1	/20 - Present*
Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee		Development Unit	Maximum Assessable Fee		Development Unit	Maximum Assessable Fee		Development Unit	Maximum Assessable Fee	
Land Use	·	Per Development Unit	Development Unit	·	Per Development Unit	Development Unit	·	Per Development Unit	Development Unit	·	Per Development Unit	Development Unit
Truck Terminal	Acre	\$19,513	\$12,043	Acre	<b>PORT AND TERMI</b> \$29,373	<b>NAL</b> \$12,043	Acre	\$30,268	\$12,043	1,000 SF GFA	\$13,388	\$12,043
General Light Industrial	1,000 SF GFA	\$2,919	\$1,597	1,000 SF GFA	\$4,394	\$1,597	1,000 SF GFA	\$4,488	\$1,597	1,000 SF GFA	\$4,517	\$1,597
General Heavy Industrial Industrial Park	1,000 SF GFA 1,000 SF GFA	\$2,025 \$2,740	\$2,025 \$1,465	1,000 SF GFA 1,000 SF GFA	\$3,049 \$3,856	\$671 \$1,465	1,000 SF GFA 1,000 SF GFA	\$3,142 \$3,934	\$671 \$1,465	1,000 SF GFA	N/A	Ć1 4CF
Warehousing	1,000 SF GFA 1,000 SF GFA	\$1,821	\$1,465	1,000 SF GFA	\$3,836	\$1,465	1,000 SF GFA 1,000 SF GFA	\$1,478	\$1,465	1,000 SF GFA 1,000 SF GFA	\$2,862 \$1,369	\$1,465 \$1,369
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$868 \$2,919	\$607 \$2,918	1,000 SF GFA	\$1,166 N/A	\$607	1,000 SF GFA	\$1,201 N/A	\$607	1,000 SF GFA	\$1,226 N/A	\$607
	·				RESIDENTIAL							
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit  Dwelling Unit	\$3,013 \$1,847	\$3,012 \$1,846	Dwelling Unit Dwelling Unit	\$4,535 \$2,780	\$4,484 \$2,779	Dwelling Unit Dwelling Unit	\$4,620 \$2,864	\$4,484 \$2,864	Dwelling Unit Dwelling Unit	\$7,093 \$3,148	\$4,484 \$3,147
Multifamily Housing (High-Rise)	Durallia a Unit	N/A	Ć1 COO	Duralling Unit	N/A	¢2.224	Devolling Unit	N/A		Dwelling Unit	\$2,575	\$2,575
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$1,608 N/A	\$1,608	Dwelling Unit	\$2,331 N/A	\$2,331	Dwelling Unit	\$2,402 N/A	\$2,402	Dwelling Unit  Dwelling Unit	\$4,006 \$2,575	\$2,832 \$2,575
Mobile Home Park  Retirement Community	Dwelling Unit  Dwelling Unit	\$1,668 \$808	\$1,667 \$808	Dwelling Unit	\$2,652 N/A	\$2,651		N/A N/A		Dwelling Unit	\$3,291 N/A	\$3,290
Others Not Specified	Dwelling Unit	\$3,013	\$3,012		N/A			N/A			N/A	
Assisted Living Senior Adult Housing	-	N/A N/A		Bed	\$986 N/A	\$986	Bed Dwelling Unit	\$1,016 \$1,162	\$1,016 \$1,161	Beds Dwelling Unit	\$1,860 \$1,860	\$1,198 \$1,369
Congregate Care Facility		N/A			N/A		Dwelling Unit	\$792	\$792	Dwelling Unit	\$1,288	\$933
Hotel	Room	\$1,668	\$1,167	Room	<b>LODGING</b> \$2,434	\$1,167	Room	\$2,548	\$1,167	Rooms	\$3,945	\$1,167
Motel/Other Lodging Facilities	Room	\$1,285	\$972	Room	\$1,934 RECREATIONA	\$972	Room	\$1,993	\$972	Rooms	\$2,494	\$972
Arena	Acre	\$91,193	\$91,193		N/A			N/A			N/A	
Bowling Alley Driving Range	1,000 SF GFA Tee	\$9,684 \$3,421	\$9,684 \$1,860	Tee	N/A \$5,150	\$1,860	Tee	N/A \$5,320	\$1,860	Driving Positions	N/A \$8,953	\$1,860
Golf Course	Acre	\$1,064	\$743	Acre	\$1,230	\$743	Acre	\$1,280	\$743	Holes	\$20,828	\$743
Health/Recreational Clubs and Facilities  Ice Rink	1,000 SF GFA 1,000 SF GFA	\$4,791 \$6,459	\$1,591 \$1,956	1,000 SF GFA 1,000 SF GFA	\$6,751 \$9,723	\$1,591 \$1,956	1,000 SF GFA 1,000 SF GFA	\$11,642 \$10,032	\$1,591 \$1,956	1,000 SF GFA 1,000 SF GFA	\$16,536 \$9,525	\$1,591 \$1,956
Live Theater	Seat	\$51	\$51	Hala	N/A		Hala	N/A		Halaa	N/A	
Miniature Golf  Multiplex Movie Theater	Hole Seat	\$902 \$383	\$678 \$382	Hole Screen	\$1,358 \$56,172	\$678 \$9,920	Hole Screen	\$1,399 \$57,974	\$678 \$9,920	Holes Screens	\$2,371 \$98,235	\$678 \$9,920
Tennis Courts	Court	\$10,612	\$1,014	Court	\$13,796 INSTITUTIONA	\$1,014	Court	\$14,243	\$1,014	Courts	\$27,328	\$1,014
Church	1,000 SF GFA	\$1,183	\$841	1,000 SF GFA	\$1,781	\$841	1,000 SF GFA	\$1,531	\$841	1,000 SF GFA	\$3,516	\$841
Day Care Center Primary/Middle School (1-8)	1,000 SF GFA Student	\$23,590 \$289	\$4,976 \$172	1,000 SF GFA Student	\$35,458 \$410	\$4,976 \$172	1,000 SF GFA Student	\$19,153 \$449	\$4,976 \$172	1,000 SF GFA Student	\$22,280 \$613	\$4,976 \$172
High School (9-12)	Student	\$272	\$167	Student	\$371	\$167	Student	\$356	\$167	Students	\$511	\$167
Jr/Community College University/College	Student Student	\$306 \$374	\$158 \$260	Student Student	\$320 \$564	\$158 \$260	Student Student	\$330 \$475	\$158 \$260	Students Students	\$797 \$1,083	\$158 \$260
Clinic	1,000 SF GFA	\$15,429	\$5,043	1,000 SF GFA	<b>MEDICAL</b> \$23,225	\$5,043	1,000 SF GFA	\$23,932	\$5,043	1,000 SF GFA	\$23,465	\$5,043
Hospital	Bed	\$3,634	\$1,932	Bed	\$5,829	\$1,932	Bed	\$6,560	\$1,932	Beds	\$13,531	\$1,932
Nursing Home  Animal Hospital/Veterinary Clinic	Bed	\$511 N/A	\$469	Bed	\$986 N/A	\$469	Bed 1,000 SF GFA	\$1,016 \$15,246	\$469 \$5,043	Beds 1,000 SF GFA	\$1,574 \$17,681	\$469 \$5,043
			40.000		OFFICE	40.000	,					
Corporate Headquarters Building General Office Building	1,000 SF GFA 1,000 SF GFA	\$4,144 \$4,442	\$2,220 \$2,370	1,000 SF GFA 1,000 SF GFA	\$6,277 \$6,687	\$2,220 \$2,370	1,000 SF GFA 1,000 SF GFA	\$6,521 \$6,890	\$2,220 \$2,370	1,000 SF GFA 1,000 SF GFA	\$4,292 \$8,237	\$2,220 \$2,370
Medical/Dental Office	1,000 SF GFA	\$10,901	\$5,117	1,000 SF GFA	\$16,679	\$5,117	1,000 SF GFA	\$16,500	\$5,117	1,000 SF GFA	\$24,753	\$5,117
Single Tenant Office Building Office Park	1,000 SF GFA 1,000 SF GFA	\$5,123 \$4,468	\$2,745 \$2,380	1,000 SF GFA 1,000 SF GFA	\$7,763 \$6,725	\$2,745 \$2,380	1,000 SF GFA 1,000 SF GFA	\$8,039 \$6,838	\$2,745 \$2,380	1,000 SF GFA 1,000 SF GFA	\$12,244 \$7,665	\$2,745 \$2,380
Others Not Specified	1,000 SF GFA	\$4,442	\$4,442		N/A COMMERCIAL			N/A			N/A	
					Automobile Rela	ted			1			
Automobile Care Center  Automobile Parts Sales	1,000 SF GFA 1,000 SF GFA	\$5,549 \$9,327	\$3,049 \$3,719	1,000 SF GFA 1,000 SF GFA	\$8,365 \$14,040	\$3,049 \$3,719	1,000 SF GFA 1,000 SF GFA	\$7,946 \$14,494	\$3,049 \$3,719	1,000 SF GLA 1,000 SF GFA	\$8,523 \$12,755	\$3,049 \$3,719
Gasoline/Service Station w/ Convenience Market	Fueling Position	\$4,315	\$719	Fueling Position	\$4,522	\$719	Fueling Position	\$4,699	\$719	ehicle Fueling Position	n \$7,563	\$719
Convenience Market with 12 or More Fueling Positions Convenience Market with Less than 12 Fueling Positions	Fueling Position 1,000 SF GFA	\$2,961 \$3,004	\$2,961 \$3,004		N/A N/A			N/A N/A	•		N/A N/A	
New and Used Car Sales  Quick Lubrication Vehicle Center	1,000 SF GFA Service Position	\$6,127 \$8,519	\$2,852 \$1,819	1,000 SF GFA Service Position	\$8,685 \$12,810	\$2,852 \$1,819	1,000 SF GFA Service Position	\$8,923 \$13,213	\$2,852 \$1,819	1,000 SF GFA Servicing Positions	\$11,099 \$13,266	\$2,852 \$1,819
Self-Service Car Wash	Stall	\$1,770	\$394	Stall	\$2,549	\$394	Stall	\$2,627	\$394	Stalls	\$4,068	\$394
Automated Car Wash Tire Store	1,000 SF GFA	N/A \$8,119	\$3,798	1,000 SF GFA 1,000 SF GFA	\$5,367 \$14,911	\$315 \$3,798	1,000 SF GFA	N/A \$12,712	\$3,798	1,000 SF GFA	N/A \$13,082	\$3,798
	·				Dining							
Fast Food Restaurant Fast Food Restaurant without Drive-Thru	1,000 SF GFA 1,000 SF GFA	\$34,117 \$26,645	\$7,799 \$26,644	1,000 SF GFA	\$53,136 N/A	\$7,799	1,000 SF GFA	\$51,731 N/A	\$7,799	1,000 SF GFA	\$94,188 N/A	\$7,799
High Turnover (Sit-down) Restaurant Sit-Down Restaurant	1,000 SF GFA 1,000 SF GFA	\$12,620 \$8,553	\$2,867 \$3,807	1,000 SF GFA 1,000 SF GFA	\$19,087 \$12,861	\$2,867 \$3,807	1,000 SF GFA 1,000 SF GFA	\$17,767 \$13,279	\$2,867 \$3,807	1,000 SF GFA 1,000 SF GFA	\$32,111 \$25,182	\$2,867 \$3,807
Coffee / Donut Shop	1,000 SF GFA	N/A	J γ3,007	1,000 SF GFA	N/A	/ ۶۵٫۵۷	1,000 JF GFA	\$13,279 N/A	ر ۵٫٫۰∪ر	1,000 SF GFA 1,000 SF GFA	\$74,994	\$3,807
Free-Standing Retail Store	1,000 SF GFA	\$8,119	\$2,456	1,000 SF GFA	Other Retail \$14,578	\$2,456	1,000 SF GFA	\$14,837	\$2,456	1,000 SF GFA	\$19,336	\$2,456
Garden Center (Nursery)	_,000 01 01 A	N/A	1 72,130	1,000 SF GFA	\$10,953	\$3,052	1,000 SF GFA	\$20,658	\$3,052	1,000 SF GFA	\$27,819	\$3,052
Home Improvement Superstore  Pharmacy/Drugstore	1,000 SF GFA	N/A \$14,510	\$3,580	1,000 SF GFA 1,000 SF GFA	\$7,084 \$18,126	\$3,948 \$3,580	1,000 SF GFA 1,000 SF GFA	\$5,148 \$21,463	\$3,948 \$3,580	1,000 SF GFA 1,000 SF GFA	\$7,726 \$30,047	\$3,948 \$3,580
Shopping Center	1,000 SF GFA	\$6,757	\$3,872	1,000 SF GFA	\$10,210	\$3,872	1,000 SF GFA	\$10,415	\$3,872	1,000 SF GLA	\$14,369	\$3,872
Supermarket Video Arcade	1,000 SF GFA 1,000 SF GFA	\$20,152 \$14,552	\$5,279 \$14,552	1,000 SF GFA	\$27,554 N/A	\$5,279	1,000 SF GFA	\$25,806 N/A	\$5,279	1,000 SF GFA	\$33,828 N/A	\$5,279
Video Rental Store	1,000 SF GFA	\$18,603 N/A	\$18,602	1,000 SF GFA	N/A \$14,373	\$2,891	1,000 SF GFA	N/A \$14,837	\$2,891	1,000 SF GFA	N/A \$20,031	\$2,891
Toy/Children's Superstore				1,000 SF GFA	\$14,373 Wholesale	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	1,000 SF GFA	•	J 92,091	1,000 SF GFA	•	32,831
Wholesale Market	1,000 SF GFA	\$579	\$578		N/A SERVICES			N/A			N/A	
Bank (Walk-In)	1,000 SF GFA	\$28,687	\$6,360	1,000 SF GFA	\$43,183	\$6,360	1,000 SF GFA	\$16,342	\$6,360	1,000 SF GFA	\$33,174	\$6,360
Bank (Drive-In) Personal Service	Drive-in Lane	\$41,869 N/A	\$10,232	Drive-in Lane	\$52,636 N/A	\$10,232	Drive-in Lane	\$39,534 N/A	\$10,232	Drive-in Lanes 1,000 SF GFA	\$80,452 \$6,684	\$10,232 \$3,580
I GIOGIAI SCIANA	-						_	,			50.0	

				Servi	ce Area 'M'	Combined						
Cabadula 4 Tabla D. Astual Danduus Juuraat	Final Pl	at Recorded Between: 9/1/	03 - 11/9/08*	Final Plat	Recorded Between: 11/10/	08 - 11/19/13*	Final Plat	Recorded Between: 11/20	/13 - 11/30/20*	Final Pla	t Recorded Between: 12/1,	/20 - Present*
Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee Per Development Unit	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Per Development Unit	Development Unit	Maximum Assessable Fee	Actual Fee Charged Development Un
Land Use					PORT AND TERMI							
Truck Terminal	Acre	\$0	\$0	Acre	\$0	\$0	Acre	\$0	\$0	1,000 SF GFA	\$6,761	\$0
General Light Industrial	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$2,286	\$0
General Heavy Industrial Industrial Park	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$1,444	\$0
Warehousing	1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$698	\$0
Mini-Warehouse Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$626 N/A	\$0
Others Not Specified	1,000 St Gt A	ΨŪ	<u> </u>		RESIDENTIAL			NyA			14/73	
Single Family Detached Housing  Apartment/Multi-family	Dwelling Unit  Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit  Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit  Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit Dwelling Unit	\$3,585 \$1,588	\$0 \$0
Multifamily Housing (High-Rise)		N/A			N/A	,		N/A		Dwelling Unit	\$1,299	\$0
Residential Condominium/Townhouse  Mid-Rise Residential with 1st Floor Commercial	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit	\$0 N/A	\$0	Dwelling Unit Dwelling Unit	\$2,021 \$1,299	\$0 \$0
Mobile Home Park	Dwelling Unit	\$0	\$0	Dwelling Unit	\$0	\$0		N/A		Dwelling Unit	\$1,660	\$0
Retirement Community Others Not Specified	Dwelling Unit  Dwelling Unit	\$0 \$0	\$0 \$0		N/A N/A			N/A N/A			N/A N/A	
Assisted Living	Dwelling Offic	N/A	1 70	Bed	\$0	\$0	Bed	\$0	\$0	Beds	\$938	\$0
Senior Adult Housing Congregate Care Facility		N/A N/A			N/A N/A		Dwelling Unit  Dwelling Unit	\$0 \$0	\$0 \$0	Dwelling Unit Dwelling Unit	\$938 \$650	\$0 \$0
					LODGING							
Hotel  Motel/Other Lodging Facilities	Room Room	\$0 \$0	\$0 \$0	Room Room	\$0 \$0	\$0 \$0	Room Room	\$0 \$0	\$0 \$0	Rooms Rooms	\$2,165 \$1,371	\$0 \$0
				Acom	RECREATIONA	· ·	NOOH!		, , , , , , , , , , , , , , , , , , ,	1.001113		, JO
Arena Bowling Alley	Acre 1,000 SF GFA	\$0 \$0	\$0 \$0		N/A N/A			N/A N/A			N/A N/A	
Driving Range	Tee	\$0	\$0	Tee	\$0	\$0	Tee	\$0	\$0	Driving Positions	\$4,523	\$0
Golf Course  Health/Recreational Clubs and Facilities	Acre 1,000 SF GFA	\$0 \$0	\$0 \$0	Acre 1,000 SF GFA	\$0 \$0	\$0 \$0	Acre 1,000 SF GFA	\$0 \$0	\$0 \$0	Holes 1,000 SF GFA	\$10,514 \$8,349	\$0 \$0
Ice Rink	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$4,812	\$0
Live Theater  Miniature Golf	Seat Hole	\$0 \$0	\$0 \$0	Hole	N/A \$0	\$0	Hole	N/A \$0	\$0	Holes	N/A \$1,203	\$0
Multiplex Movie Theater	Seat	\$0	\$0	Screen	\$0	\$0	Screen	\$0	\$0	Screens	\$49,564	\$0
Tennis Courts	Court	\$0	\$0	Court	\$0 INSTITUTIONA	\$0	Court	\$0	\$0	Courts	\$13,786	\$0
Church	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$1,780	\$0
Day Care Center	1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0	\$0 \$0	1,000 SF GFA Student	\$22,496	\$0
Primary/Middle School (1-8) High School (9-12)	Student Student	\$0 \$0	\$0 \$0	Student Student	\$0 \$0	\$0 \$0	Student Student	\$0 \$0	\$0 \$0	Students	\$626 \$505	\$0 \$0
Jr/Community College University/College	Student Student	\$0 \$0	\$0 \$0	Student Student	\$0 \$0	\$0 \$0	Student Student	\$0 \$0	\$0 \$0	Students Students	\$409 \$553	\$0 \$0
Offiver sity/ Coffege	Student	Ş0	Ş0 	Student	MEDICAL	ŞU	Student	, Ş0	, şu	Students	\$333	30
Clinic Hospital	1,000 SF GFA Bed	\$0 \$0	\$0 \$0	1,000 SF GFA Bed	\$0 \$0	\$0 \$0	1,000 SF GFA Bed	\$0 \$0	\$0 \$0	1,000 SF GFA Beds	\$11,838 \$6,833	\$0 \$0
Nursing Home	Bed	\$0	\$0	Bed	\$0	\$0	Bed	\$0	\$0	Beds	\$794	\$0
Animal Hospital/Veterinary Clinic		N/A			N/A OFFICE		1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$8,926	\$0
Corporate Headquarters Building	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$2,165	\$0
General Office Building  Medical/Dental Office	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$4,162 \$12,487	\$0 \$0
Single Tenant Office Building	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$6,183	\$0
Office Park Others Not Specified	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	\$3,874 N/A	\$0
Others Not Specified	1,000 3F GFA	, Ş0	, Ş0		COMMERCIAL			NYA			N/A	
Automobile Care Center	1,000 SF GFA	\$0	\$0	1,000 SF GFA	Automobile Rela \$0	<b>ted</b> \$0	1,000 SF GFA	\$0	\$0	1,000 SF GLA	\$6,761	\$0
Automobile Parts Sales	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$10,105	\$0
Gasoline/Service Station w/ Convenience Market Convenience Market with 12 or More Fueling Positions	Fueling Position Fueling Position	\$0 \$0	\$0 \$0	Fueling Position	\$0 N/A	\$0	Fueling Position	\$0 N/A	\$0	ehicle Fueling Position	\$8,902 N/A	\$0
Convenience Market with Less than 12 Fueling Positions	1,000 SF GFA	\$0	\$0 \$0		N/A			N/A			N/A	
New and Used Car Sales  Quick Lubrication Vehicle Center	1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	\$7,001 \$10,514	\$0 \$0
Self-Service Car Wash	Service Position Stall	\$0	\$0 \$0	Service Position Stall	\$0	\$0 \$0	Service Position Stall	\$0	\$0	Servicing Positions Stalls	\$10,514	\$0
Automated Car Wash	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$10,370	\$0
Tire Store	1,000 SF GFA	J \$U	J \$U	1,000 SF GFA	\$0 Dining	<b>)</b>	1,000 SF GFA	J \$U	l ⇒∩	1,000 SF GFA	) \$10,37U	<u></u> \$0
Fast Food Restaurant	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$58,971	\$0
Fast Food Restaurant without Drive-Thru High Turnover (Sit-down) Restaurant	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$20,114	\$0
Sit-Down Restaurant	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$15,783	\$0
Coffee / Donut Shop		N/A			N/A Other Retail			N/A		1,000 SF GFA	\$46,965	\$0
Free-Standing Retail Store	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$12,198	\$0
Garden Center (Nursery)  Home Improvement Superstore		N/A N/A		1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$17,540 \$4,884	\$0 \$0
Pharmacy/Drugstore	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$18,959	\$0
Shopping Center Supermarket	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GFA 1,000 SF GFA	\$0 \$0	\$0 \$0	1,000 SF GLA 1,000 SF GFA	\$9,071 \$21,341	\$0 \$0
Video Arcade	1,000 SF GFA	\$0	\$0	1,000 3F GFA	N/A	<b>Ι</b> Ψ	1,000 3F GFA	N/A	ا ب ا	1,000 SF GFA	N/A	J 30
Video Rental Store Toy/Children's Superstore	1,000 SF GFA	\$0 N/A	\$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$0	\$0	1,000 SF GFA	N/A \$12,632	\$0
roy/ Ciliuren 3 Juperstore	<u> </u>	IV/A		1,000 3F GFA	Wholesale	٠	1,000 JF UFA	<u>υ</u> , υ	. →∪	1,000 OF GFA	γ12,U32	<u></u>
Wholesale Market	1,000 SF GFA	\$0	\$0		N/A SERVICES			N/A			N/A	
Bank (Walk-In)	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$ERVICES	\$0	1,000 SF GFA	\$0	\$0	1,000 SF GFA	\$26,274	\$0
Bank (Drive-In)	Drive-in Lane	\$0 N/A	\$0	Drive-in Lane	\$0 N/A	\$0	Drive-in Lane	\$0 N/A	\$0	Drive-in Lanes 1,000 SF GFA	\$63,711 \$3,681	\$0 \$0
Personal Service	_	N/Λ		_	-1/4		_	BI / A		1 000 CE CEA		

# **SCHEDULE 1**

Maximum assessable utility fee based on date of final plat recordation.

**TABLE A.**Maximum assessable utility impact fee if date of final plat recordation is prior to September 1, 2003 for which no replatting is necessary.

Meter Size	eter Size WATER					WASTE	WATE	R
		Maximum Fee		Maximum Fee		Maximum Fee		Maximum Fee
(inches )		(pre-credit)		(post-credit)		(pre-credit)		(post-credit)
3/4	\$	640.00	\$	320.00	\$	725.00	\$	362.50
1	\$	1,120.00	\$	560.00	\$	1,268.75	\$	634.38
1 1/2	\$	2,560.00	\$	1,280.00	\$	2,900.00	\$	1,450.00
2	\$	4,480.00	\$	2,240.00	\$	5,075.00	\$	2,537.50
3	\$	10,240.00	\$	5,120.00	\$	11,600.00	\$	5,800.00
4	\$	17,920.00	\$	8,960.00	\$	20,300.00	\$	10,150.00
6	\$	40,960.00	\$	20,480.00	\$	46,400.00	\$	23,200.00
8	\$	64,000.00	\$	32,000.00	\$	72,500.00	\$	36,250.00
10	\$	96,000.00	\$	48,000.00	\$	108,750.00	\$	54,375.00

Maximum Assessable Fee (post-credit) is 50% of the Maximum Fee (pre-credit).

**TABLE B.**Maximum assessable utility impact fee if date of final plat recordation is between September 1, 2003 and November 9, 2008 for which no replatting is necessary.

Meter Size	V	VATER	WASTE	WATER
(inches)	Maximum Fee	Maximum Fee	Maximum Fee	Maximum Fee
(mes)	(pre-credit)	(post-credit)	(pre-credit)	(post-credit)
3/4	\$ 2,832.97	\$ 1,416.49	\$ 1,412.18	\$ 706.09
1	\$ 4,816.04	\$ 2,408.02	\$ 2,400.70	\$ 1,200.35
1 1/2	\$ 9,348.76	\$ 4,674.38	\$ 4,660.16	\$ 2,330.08
2	\$ 15,014.68	\$ 7,507.34	\$ 7,484.40	\$ 3,742.20
3	\$ 30,312.68	\$ 15,156.34	\$ 15,110.24	\$ 7,555.12
4	\$ 47,310.44	\$ 23,655.22	\$ 23,512.65	\$ 11,756.33
6	\$ 94,337.56	\$ 47,168.78	\$ 47,025.30	\$ 23,512.65
8	\$ 151,087.76	\$ 75,543.88	\$ 75,268.72	\$ 37,634.36
10	\$ 434,292.76	\$ 217,146.38	\$ 216,485.84	\$ 108,242.92

Maximum Assessable Fee (post-credit) is 50% of the Maximum Fee (pre-credit).

**TABLE C.**Maximum assessable utility impact fee if date of final plat recordation is between November 10, 2008 and November 19, 2013 for which no replatting is necessary.

Meter Size	Meter Type	WATE	R		WASTE	WAT	ER
(inches)	ivietei Type	Maximum Fee (pre-credit)	Maximum Fee (post-credit)		Maximum Fee (pre-credit)		Maximum Fee (post-credit)
3/4	Simple	\$ 3,255.36	\$ 1,627	7.68	\$ 411.04	\$	205.52
1	Simple	\$ 5,534.12	\$ 2,767	7.06	\$ 698.76	\$	349.38
1 1/2	Simple	\$ 10,742.68	\$ 5,371	1.34	\$ 1,356.44	\$	678.22
2	Simple	\$ 17,253.40	\$ 8,626	5.70	\$ 2,178.52	\$	1,089.26
2	Compound	\$ 17,253.40	\$ 8,626	6.70	\$ 2,178.52	\$	1,089.26
2	Turbine	\$ 21,810.92	\$ 10,905	5.46	\$ 2,753.96	\$	1,376.98
3	Compound	\$ 34,832.36	\$ 17,416	5.18	\$ 4,398.12	\$	2,199.06
3	Turbine	\$ 52,085.76	\$ 26,042	2.88	\$ 6,576.64	\$	3,288.32
4	Compound	\$ 54,364.52	\$ 27,182	2.26	\$ 6,864.36	\$	3,432.18
4	Turbine	\$ 91,150.08	\$ 45,575	5.04	\$ 11,509.12	\$	5,754.56
6	Compound	\$ 108,403.48	\$ 54,201	1.74	\$ 13,687.64	\$	6,843.82
6	Turbine	\$ 199,553.56	\$ 99,776	6.78	\$ 25,196.76	\$	12,598.38
8	Compound	\$ 173,510.68	\$ 86,755	5.34	\$ 21,908.44	\$	10,954.22
8	Turbine	\$ 347,346.92	\$ 173,673	3.46	\$ 43,857.96	\$	21,928.98
10	Compound	\$ 499,046.68	\$ 249,523	3.34	\$ 63,012.44	\$	31,506.22
10	Turbine	\$ 542,668.52	\$ 271,334	4.26	\$ 68,520.36	\$	34,260.18
12	Turbine	\$ 716,179.20	\$ 358,089	9.60	\$ 90,428.80	\$	45,214.40

Maximum Assessable Fee (post-credit) is 50% of the Maximum Fee (pre-credit).

**TABLE D.**Maximum assessable utility impact fee if date of final plat recordation is between November 20, 2013 and November 30, 2020 for which no replatting is necessary.

Meter Size	Meter Type	WATE	R	WASTE	WATER
(inches)	ivietei Type	Maximum Fee (pre-credit)	Maximum Fee (post-credit)	Maximum Fee (pre-credit)	Maximum Fee (post-credit)
3/4	Multi-Jet (Simple)	\$ 2,589.39	\$ 1,294.70	\$ 324.28	\$ 162.14
1	Multi-Jet (Simple)	\$ 4,401.96	\$ 2,200.99	\$ 551.28	\$ 275.64
2	Ultrasonic	\$ 21,491.94	\$ 10,746.01	\$ 2,691.52	\$ 1,345.76
3	Ultrasonic	\$ 43,242.81	\$ 21,621.49	\$ 5,415.48	\$ 2,707.74
4	Ultrasonic	\$ 86,226.69	\$ 43,113.51	\$ 10,798.52	\$ 5,399.26
6	Ultrasonic	\$ 138,014.49	\$ 69,007.51	\$ 17,284.12	\$ 8,642.06
8	Ultrasonic	\$ 241,590.09	\$ 120,795.51	\$ 30,255.32	\$ 15,127.66
10-12	Ultrasonic	\$ 474,635.19	\$ 237,318.51	\$ 59,440.52	\$ 29,720.26

Maximum Assessable Fee (post-credit) is 50% of the Maximum Fee (pre-credit).

**TABLE E.**Maximum assessable utility impact fee if date of final plat recordation is on or after December 1, 2020 for which no replatting is necessary.

Meter Size	Meter Type		WATER	WASTEWATER
(inches)	Wieter Type		Maximum Fee	Maximum Fee
3/4	Multijet	\$	1,754.00	\$ 2,899.00
1	Multijet	\$	2,929.18	\$ 4,841.33
1 1/2	Multijet	\$	5,840.82	\$ 9,653.67
2	Ultrasonic	\$	14,610.82	\$ 24,148.67
3	Ultrasonic	\$	29,239.18	\$ 48,326.33
4	Ultrasonic	\$	58,460.82	\$ 96,623.67
6	Ultrasonic	<b>\$</b> •	93,540.82	\$ 154,603.67
8	Ultrasonic	\$	163,700.82	\$ 270,563.67
12	Ultrasonic	\$	321,560.82	\$ 531,473.67

# **SCHEDULE 2**

Actual water and wastewater impact fees charged based on date of final plat recordation.

## TABLE A.

Actual water and wastewater impact fees charged if date of final plat recordation is prior to September 1, 2003 for which no replatting is necessary.

Meter Size (inches)	WATER	WASTEWATER
3/4	\$ 320	\$ 362
1	\$ 560	\$ 634
1 1/2	\$ 1,280	\$ 1,450
2	\$ 2,240	\$ 2,537
3	\$ 5,120	\$ 5,800
4	\$ 8,960	\$ 10,150
6	\$ 20,480	\$ 23,200
8	\$ 32,000	\$ 36,250
10	\$ 48,000	\$ 54,375

### TABLE B.

Actual water and wastewater impact fees charged if date of final plat recordation is between September 1, 2003 and November 9, 2008 for which no replatting is necessary.

Meter Size (inches)	WATER	WASTEWATER
3/4	\$ 1,416	\$ 706
1	\$ 2,408	\$ 1,200
1 1/2	\$ 4,674	\$ 2,330
2	\$ 7,507	\$ 3,742
3	\$ 15,156	\$ 7,555
4	\$ 23,655	\$ 11,756
6	\$ 47,168	\$ 23,512
8	\$ 75,543	\$ 37,634
10	\$ 217,146	\$ 108,242

#### TABLE C.

Actual water and wastewater impact fees charged if date of final plat recordation is between November 9, 2008 and November 19, 2013 for which no replatting is necessary.

Meter Size (inches)	Meter Type	WATER	WASTEWATER
3/4	Simple	\$ 1,627	\$ 205
1	Simple	\$ 2,767	\$ 349
1 1/2	Simple	\$ 5,371	\$ 678
2	Simple	\$ 8,626	\$ 1,089
2	Compound	\$ 8,626	\$ 1,089
2	Turbine	\$ 10,905	\$ 1,376
3	Compound	\$ 17,416	\$ 2,199
3	Turbine	\$ 26,042	\$ 3,288
4	Compound	\$ 27,182	\$ 3,432
4	Turbine	\$ 45,575	\$ 5,754
6	Compound	\$ 54,201	\$ 6,843
6	Turbine	\$ 99,776	\$ 12,598
8	Compound	\$ 86,755	\$ 10,954
8	Turbine	\$ 173,673	\$ 21,928
10	Compound	\$ 249,523	\$ 31,506
10	Turbine	\$ 271,334	\$ 34,260
12	Turbine	\$ 358,089	\$ 45,214

## TABLE D.

Actual water and wastewater impact fees charged if date of final plat recordation is between November 20, 2013 and November 30, 2020 for which no replatting is necessary.

Meter Size (inches)	Meter Type	WATER	WASTEWATER
3/4	Multi-Jet (Simple)	\$ 1,294	\$ 162
1	Multi-Jet (Simple)	\$ 2,200	\$ 275
2	Ultrasonic	\$ 10,746	\$ 1,345
3	Ultrasonic	\$ 21,621	\$ 2,707
4	Ultrasonic	\$ 43,113	\$ 5,399
6	Ultrasonic	\$ 69,007	\$ 8,642
8	Ultrasonic	\$ 120,795	\$ 15,127
10-12	Ultrasonic	\$ 237,318	\$ 29,720

## TABLE E.

Actual water and wastewater impact fees charged if date of final plat recordation is on or after December 1, 2020 for which no replatting is

Meter Size (inches)	Meter Type	WATER	WASTEWATER
3/4	Multijet	\$ 1,754	\$ 1,643
1	Multijet	\$ 2,929	\$ 2,744
1 1/2	Multijet	\$ 5,840	\$ 5,472
2	Ultrasonic	\$ 14,610	\$ 13,690
3	Ultrasonic	\$ 29,239	\$ 27,397
4	Ultrasonic	\$ 58,460	\$ 54,777
6	Ultrasonic	\$ 93,540	\$ 87,647
8	Ultrasonic	\$ 163,700	\$ 153,387
12	Ultrasonic	\$ 321,560	\$ 301,302