

ESTIMATE



Jimmy Don Burris
707 Lamar St
McKinney, Tx 75059
(972) 569-0410

Double R Renovations

1103 Fitzhugh St
McKinney, Tx 75069

Phone: (214) 491-2987

Email: doublerrenovations@gmail.com

Estimate #

000292

Date

10/28/2019

Description

Total

Demo,saw cutting and grinding	\$1,500.00
Demo 300 existing SQF of brick tile on front porch	
Grind existing damage sidewalk to be flush on both ends	
Grind three feet from city sidewalk to property for new brick tile to sit flush with city sidewalk	
Saw cut, jackhammer and remove concrete landing and steps by back door	
Saw cut, jackhammer and remove landing and steps by French patio door	
Concrete work	\$4,500.00
Grade, form and pour a 6'x4' landing and two steps by back door	
Grade, form and pour a 8'x5' landing and two steps by French patio door	
Grade, form and pour a 80'x1'of concrete around perimeter of sidewalk 3/4 down from existing sidewalk for brick to sit flush	
Grade, form and pour 15 SQF of concrete where side walk is uneven	
Materials \$1,500 Labor cost \$3,000	
Install brick tile	\$9,664.67
Prep and install 550 SQF of Brickckweb Boston Think Brick Panel	
300 SQF in front of the house	
80 SQF around perimeter of sidewalks in the back of the house	
170 SQF on landings and steps	
Install with flex bond thins set	

Grout with sanded grout

Materials cost \$5,664.67
Labor \$4,000

Subtotal	\$15,664.67
Total	\$15,664.67