VINYL GRAPHICS COLORS		
ITEM	#	COLOR
BLUE IN LOGO & COPY 'CAR WASH'	#97	ARLON BRISTOL BLUE
LIGHT BLUE IN LOGO	#57	ARLON OLYMPIC BLUE
BLACK COPY IN LOGO	#22	ARLON BLACK

REINFORCEMENT OF BUILDING, PHYSICAL CONDITIONS: If installation is a part of this Agreement, Buyer shall be responsible and pay for all necessary reinforcements to the building or any other structures on which Display is installed, for relocating power lines or other obstacles, and for any additional installation costs incurred by Seller due to adverse soil conditions, underground or other obstructions including but not limited to drilling for excavation or removal of any rock. Unless notified of sprinkler lines or private utility lines prior to drilling Seller is not responsible for damage caused and shall be indemnified against claims, losses or proceeding arising by replacement, repair or diversion of such services. When pier drilling is necessary, Seller will contact Dig Tess or other agents for location of all public utilities. Location of private utilities is the sole responsibility of the Buyer. In the event rock or adverse soil conditions are encountered in the drilling process, additional monies will be requested by the Seller.

Customer Signature:

Since 1956
StarliteSign.LP
www.starlitesign.com
7923 E. McKinney St., Denton, TX 76208
(940) 382-8850 Fax: (940) 387-0429

CUSTOMER: Masters Car Wash
LOCATION: 7249 S. Custer Rd.
CITY, ST: McKinney, TX 75070
ACCT. EXEC: Shannon Cash
PRJ. MGR:

Bids are good if accepted within 30 days of proposal. This drawing is the property of Starlite Sign, LP which reserves all rights to its reproduction and display.

DESIGNER	BID# JOB	DRWG. DATE	DWG.#	PAGE
K.Hufnagle	71691	11-02-16	1611-003	01 of 04

REVISIONS

#	DATE	BY	DESCRIPTION
1	11-18-16	KH	ADD DETAIL TO MONUMENT
2	11-21-16	KH	MOVE SIGN TO NEW LOCATION
3	01-06-17	KH	ADD STONE TO BACK OF SIGN
4	01-16-17	KH	MOVE EMC TO TOP OF CABINET
5	07-18-17	KH	INCREASE SIZE OF MONUMENT AND EMC UNITS
6	07-19-17	KH	REDUCE CABINETS TO 7'x 8'
7	07-27-17	KH	INCREASE SIZE OF EMC TO 89" x 99"

L.E.D. POWER SUPPLY PRIMARY WIRING CONNECTORS CONNECTED TO LINE VOLTAGE IN ACCORDANCE WITH NEC ARTICLE 600.

Construct & Install Using Only U.L. Listed Components & In Accordance w/Art. 600 of the N.E.C. & any Applicable Local Code.
U/L LABELS REQUIRED
(1) 20amp
120V DEDICATED CIRCUIT(S) REQ'D

DOUBLE-FACE (V-SHAPED) INTERNALLY ILLUMINATED MONUMENT SIGN
SCALE: ½" = 1'-0"

217.77 SQ.FT.

NOTE TO FABRICATORS: ANY CHANGES MADE TO CUSTOMER SPECS MUST BE PRE APPROVED BY PROJECT MANAGER PRIOR TO MANUFACTURING.

SCALE CHECK — WHITE BAR SHOULD MEASURE 1" LONG

ALTECOR ENGINEERING

SIGNS STRUCTURES
DESIGN & ANALYSIS

3617 FLAMINGO AVE
MCALLEN, TX 78504
P: (956) 687-7389
F: (956) 687-7390
EMAIL: INFO@ALTECOR.US
WEB: WWW . ALTECOR.US

PROJECT TITLE:

MASTERS CAR WASH

MONUMENT SIGN,
ILLUMINATED

INSEPARABLE ASSEMBLY
OUTLINE DRAWING

THE DRAWING COMPRISES EVALUATION OF SUPPORTS AND FOOTING. NO CABINET ENGINEERING IS INCLUDED

DESIGNED FOR:

STARLITE SIGN, LP.
7923 E. MCKINNEY ST.
DENTON, TX 76208
P: (940) 382-8850
F: (940) 387-0429

SITE LOCATION:

7249 S. CUSTER RD.
MCKINNEY, TX 75070

STATE OF TEXAS
T. G. ALTECOR
100306
LICENSED
PROFESSIONAL ENGINEER

TEXAS FIRM #: F-10807
TDLR MSE #: 95180

THIS SEAL IS AUTHORIZED BY
T. G. ALTECOR, P.E., 08 / 16 / 2017

DRAWING #: 001370
REVISION #: 0
PAGE #: 1 OF 3

CODE: IBC - 2015 / ICC
STANDARD: ASCE / SEI-7
SPECIFICATION: ANSI/ASTM