

ESTIMATE



Jimmy Don Burris
707 Lamar St
McKinney, Tx 75059
(972) 569-0410

Double R Renovations

1103 Fitzhugh St
McKinney, Tx 75069

Phone: (214) 491-2987

Email: doublerrenovations@gmail.com

Estimate #

000280

Date

08/12/2019

Description

Total

Entire exterior replacement	\$33,997.00
-----------------------------	-------------

Remove and replace 400 pieces of 1x8 beveled cedar siding 8x16'
Material \$6,722

Remove and replace all 1"x6" around windows total of 510' LF of pine primed smooth
Remove and replace all fascia 300' LF with 1x6 pine primed product
Remove and replace all corners of house with 1"x6" total of 100 pieces
Material \$2,600

Remove and replace all crown mold above windows and perimeter soffit total of 450' LF
Material \$1,125

Remove and replace all soffit 300' LF with #1 grade CDX product
Materials \$1,000

Remove and replace 400' LF of 2"x2" with cedar on front porch and rear deck
Material \$800

Remove and replace 300' LF of 1"x12" band around perimeter
Material \$1,500

Demo and trash haul off
Total \$1,500

Install Tyveck on entire house
\$500

Labor for all carpentry \$11,350

Painting
Power wash all exterior
Caulk and putty all holes and wood intersections
Apply Locks on Primer from Sherwin Williams
Apply Super Paint from Sherwin Williams

Material cost \$1,800
Labor \$3,600

Remove and replace gutters
\$1,500

total for all exterior be new with labor and materials \$33,997

I can give you guys a 5 year warranty on paint with everything being new

Subtotal	\$33,997.00
Total	\$33,997.00
Deposit Due	\$16,998.50