


L0.00





SEE SHEET L4.05 FOR LANDSCAPE NOTES & LEGEND

- RESTRICTIONS WITHIN THE CITY OF McKINNEY AT TIME OF PLANTING. SHOULD WATER RESTRICTIONS NOT ALLOW HYDROMULCH, HYDRO-SEEDING OR SPRIGGING (STAGE 3 AND STAGE 5 WATER RESTRICTIONS), AN APPROPRIATE ALTERNATIVE FOR GRASSING SHALL BE INSTALLED.
- 2. ALL PLANT MATERIAL LOCATIONS SHALL BE STAKED IN FIELD BY CONTRACTOR AND APPROVED BY THE LANDSCAPE ARCHITECT OR OWNER PRIOR TO
- DRAINAGE AWAY FROM ALL SITE FEATURES.
- CONSTRUCTION SHALL BE HYDROMULCHED WITH A NATIVE SEED MIX USING HYDRAULICALLY—APPLIED HIGH PERFORMANCE FLEXIBLE GROWTH MEDIUM, AS DESCRIBED IN THE SPECIFICATIONS.
- SEE SPECIFICATIONS FOR SEED MIX PLANTING DATES. THESE DATES CANNOT CHANGE.
- CONTRACTOR IS RESPONSIBLE FOR ALL AREAS
- TO BE SEEDED. FINE GRADING SHALL INCLUDE THE REMOVAL OF DEBRIS, ROCKS, ETC. FROM THE SITE.
- PROTECT ALL UTILITIES IN THE FIELD PRIOR TO
- OF MCKINNEY LANDSCAPE REQUIREMENTS LIST.
- 10. SEE SHEET L4.06 FOR PLANTING DETAILS.
- HEALTHY, VIGOROUS, WELL ROOTED, AND ESTABLISHED IN THE CONTAINER IN WHICH IT IS GROWING. CONTAINER GROWN NURSERY STOCK SHALL HAVE A WELL-ESTABLISHED ROOT SYSTEM REACHING THE SIDES OF THE CONTAINER TO MAINTAIN A FIRM BALL WHEN THE CONTAINER IS REMOVED, BUT SHALL NOT HAVE EXCESSIVE ROOT GROWTH ENCIRCLING THE INSIDE OF THE CONTAINER.

 \triangleleft

ARE

CARMAX

B002187.001 DRAWN BY: DESIGNED BY: CHECKED BY: 07-29-2016

L4.01

FILENAME: LANDSCAPE PLAN.dwg PLOTTED BY: Schwarz, Jacob PLOTTED ON: Friday, July 29, 2016

LEGEND

EXISTING TREE CANOPY



SEE SHEET L4.05 FOR LANDSCAPE NOTES & LEGEND

NOTES

- IN FIELD BY CONTRACTOR AND APPROVED BY THE LANDSCAPE ARCHITECT OR OWNER PRIOR TO INSTALLATION.
- CONSTRUCTION SHALL BE HYDROMULCHED WITH A NATIVE SEED MIX USING HYDRAULICALLY-APPLIED HIGH PERFORMANCE FLEXIBLE GROWTH MEDIUM, AS DESCRIBED IN THE SPECIFICATIONS.
- SEE SPECIFICATIONS FOR SEED MIX PLANTING
- GRASSING QUANTITIES ARE APPROXIMATE AND CONTRACTOR IS RESPONSIBLE FOR ALL AREAS DESIGNATED ON PLANS.
- TO BE SEEDED. FINE GRADING SHALL INCLUDE THE REMOVAL OF DEBRIS, ROCKS, ETC. FROM THE SITE.
- PROTECT ALL UTILITIES IN THE FIELD PRIOR TO COMMENCEMENT OF WORK.
- 10. SEE SHEET L4.06 FOR PLANTING DETAILS.

- THE CONTRACTOR SHALL VERIFY WATER RESTRICTIONS WITHIN THE CITY OF McKINNEY AT TIME OF PLANTING. SHOULD WATER RESTRICTIONS NOT ALLOW HYDROMULCH, HYDRO-SEEDING OR SPRIGGING (STAGE 3 AND STAGE 5 WATER RESTRICTIONS), AN APPROPRIATE ALTERNATIVE FOR GRASSING SHALL BE INSTALLED.
- ALL PLANT MATERIAL LOCATIONS SHALL BE STAKED
- THE CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM ALL SITE FEATURES.
- ALL DISTURBED AREAS WITHIN THE LIMITS OF
- DATES. THESE DATES CANNOT CHANGE.
- FINE GRADING SHALL BE PERFORMED IN ALL AREAS THE CONTRACTOR SHALL VERIFY LOCATIONS OF AND
- SEE SHEET L4.05 FOR PLANT SCHEDULE AND CITY OF MCKINNEY LANDSCAPE REQUIREMENTS LIST.
- 11. ALL CONTAINER GROWN NURSERY STOCK SHALL BE HEALTHY, VIGOROUS, WELL ROOTED, AND ESTABLISHED IN THE CONTAINER IN WHICH IT IS GROWING. CONTAINER GROWN NURSERY STOCK SHALL HAVE A WELL-ESTABLISHED ROOT SYSTEM REACHING THE SIDES OF THE CONTAINER TO MAINTAIN A FIRM BALL WHEN THE CONTAINER IS REMOVED, BUT SHALL NOT HAVE EXCESSIVE ROOT GROWTH ENCIRCLING THE INSIDE OF THE CONTAINER.


AREA


2

CARMAX

B002187.001 DRAWN BY: 07-29-2016

L4.02





FILENAME: IANDSCAPE PIAN.dwg PLOTTED BY: Schwarz, Jacob PLOTTED ON: Friday, July 29, 2016

SHEET: **I.4 O**

B002187.001

07-29-2016

6088

CARMAX



EXISTING TREE CANOPY



SEE SHEET L4.05 FOR LANDSCAPE NOTES & LEGEND

NOTES

- 1. THE CONTRACTOR SHALL VERIFY WATER
 RESTRICTIONS WITHIN THE CITY OF McKINNEY AT
 TIME OF PLANTING. SHOULD WATER RESTRICTIONS
 NOT ALLOW HYDROMULCH, HYDRO—SEEDING OR
 SPRIGGING (STAGE 3 AND STAGE 5 WATER
 RESTRICTIONS), AN APPROPRIATE ALTERNATIVE FOR
 GRASSING SHALL BE INSTALLED.
- 2. ALL PLANT MATERIAL LOCATIONS SHALL BE STAKED IN FIELD BY CONTRACTOR AND APPROVED BY THE LANDSCAPE ARCHITECT OR OWNER PRIOR TO INSTALLATION.
- 3. THE CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM ALL SITE FEATURES.
- 4. ALL DISTURBED AREAS WITHIN THE LIMITS OF CONSTRUCTION SHALL BE HYDROMULCHED WITH A NATIVE SEED MIX USING HYDRAULICALLY—APPLIED HIGH PERFORMANCE FLEXIBLE GROWTH MEDIUM, AS DESCRIBED IN THE SPECIFICATIONS.
- 5. SEE SPECIFICATIONS FOR SEED MIX PLANTING DATES. THESE DATES CANNOT CHANGE.
- 6. GRASSING QUANTITIES ARE APPROXIMATE AND CONTRACTOR IS RESPONSIBLE FOR ALL AREAS DESIGNATED ON PLANS.
- 7. FINE GRADING SHALL BE PERFORMED IN ALL AREAS TO BE SEEDED. FINE GRADING SHALL INCLUDE THE REMOVAL OF DEBRIS, ROCKS, ETC. FROM THE SITE.
- 8. THE CONTRACTOR SHALL VERIFY LOCATIONS OF AND PROTECT ALL UTILITIES IN THE FIELD PRIOR TO COMMENCEMENT OF WORK.
- 9. SEE SHEET L4.05 FOR PLANT SCHEDULE AND CITY OF MCKINNEY LANDSCAPE REQUIREMENTS LIST.
- 10. SEE SHEET L4.06 FOR PLANTING DETAILS.
- 11. ALL CONTAINER GROWN NURSERY STOCK SHALL BE HEALTHY, VIGOROUS, WELL ROOTED, AND ESTABLISHED IN THE CONTAINER IN WHICH IT IS GROWING. CONTAINER GROWN NURSERY STOCK SHALL HAVE A WELL—ESTABLISHED ROOT SYSTEM REACHING THE SIDES OF THE CONTAINER TO MAINTAIN A FIRM BALL WHEN THE CONTAINER IS REMOVED, BUT SHALL NOT HAVE EXCESSIVE ROOT GROWTH ENCIRCLING THE INSIDE OF THE CONTAINER.

CAPE PLAN AREA 4

CARMAX # 6089
116 NORTH CENTRAL EXPRESSV

JOB NO.

B002187.001

DRAWN BY:

TDD

DESIGNED BY:


TDD

CHECKED BY:

LPO

07-29-2016

HEET:



SITE DATA

55 SITE TREES X 50%

	575,705 SF. / 13.22 AC.		
		REQUIRED	PROVIDED
10% OF ENTIRE SITE	SHALL BE LANDSCAPED		
575,705 X 10%		57,571 SF	158,212 SF (27%)
15% OF STREET YAR	D SHALL BE LANDSCAPED		
70,319 X 15%		10,548 SF	21,093 SF (30%)
1 CANOPY TREE PER	40 LF OF STREET FRONTAGE		
W WHITE AVE- 720	' FRONTAGE / 40	18 TREES	18 TREES
US 75 - 572' FRONT	AGE / 40	15 TREES	15 TREES
1 CANOPY TREE FOR	R EVER 40LF	26 TREES	VARIANCE HAS BEEN REQUESTED
OF RESIDENTIAL ADJACENCY			EXISTING HEAVILY WOODED AREA
1 CANOPY TREE PER	10 PARKING SPACES		
580 SPACES / 10		58 TREES	89 TREES
1 CANOPY TREE AT	END OF ALL PARKING	YES	YES
ALL PARKING SPACES SHALL BE WITHIN 65' OF CANOPY TREE		YES	YES
75% OF FRONTAGE	PARKING SHALL BE SCREENED		
W WHITE AVE - 357	' X 75%	268'	350'
US 75 - 555' X 75%		417'	555'
LANDSCAPE SETBAC	KK .		
W WHITE AVE		20'	20'
US 75		20'	20'

30 CANOPY TREES


114 CANOPY TREES

NOTES

- 1. THE CONTRACTOR SHALL VERIFY WATER RESTRICTIONS WITHIN THE CITY OF McKINNEY AT TIME OF PLANTING. SHOULD WATER RESTRICTIONS NOT ALLOW HYDROMULCH, HYDRO-SEEDING OR SPRIGGING (STAGE 3 AND STAGE 5 WATER RESTRICTIONS), AN APPROPRIATE ALTERNATIVE FOR GRASSING SHALL BE INSTALLED.
- 2. ALL PLANT MATERIAL LOCATIONS SHALL BE STAKED IN FIELD BY CONTRACTOR AND APPROVED BY THE LANDSCAPE ARCHITECT OR OWNER PRIOR TO INSTALLATION.
- 3. THE CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM ALL SITE FEATURES.
- 4. ALL DISTURBED AREAS WITHIN THE LIMITS OF CONSTRUCTION SHALL BE HYDROMULCHED WITH A NATIVE SEED MIX USING HYDRAULICALLY-APPLIED HIGH PERFORMANCE FLEXIBLE GROWTH MEDIUM, AS DESCRIBED IN THE SPECIFICATIONS.
- 5. SEE SPECIFICATIONS FOR SEED MIX PLANTING DATES. THESE DATES CANNOT CHANGE.
- GRASSING QUANTITIES ARE APPROXIMATE AND CONTRACTOR IS RESPONSIBLE FOR ALL AREAS DESIGNATED ON PLANS.
- 7. FINE GRADING SHALL BE PERFORMED IN ALL AREAS TO BE SEEDED. FINE GRADING SHALL INCLUDE THE REMOVAL OF DEBRIS, ROCKS, ETC. FROM THE SITE.
- 8. THE CONTRACTOR SHALL VERIFY LOCATIONS OF AND PROTECT ALL UTILITIES IN THE FIELD PRIOR TO COMMENCEMENT OF WORK.
- 9. SEE SHEET L4.05 FOR PLANT SCHEDULE AND CITY OF MCKINNEY LANDSCAPE REQUIREMENTS LIST.
- 10. SEE SHEET L4.06 FOR PLANTING DETAILS.
- 11. ALL CONTAINER GROWN NURSERY STOCK SHALL BE HEALTHY, VIGOROUS, WELL ROOTED, AND ESTABLISHED IN THE CONTAINER IN WHICH IT IS GROWING. CONTAINER GROWN NURSERY STOCK SHALL HAVE A WELL-ESTABLISHED ROOT SYSTEM REACHING THE SIDES OF THE CONTAINER TO MAINTAIN A FIRM BALL WHEN THE CONTAINER IS REMOVED, BUT SHALL NOT HAVE EXCESSIVE ROOT GROWTH ENCIRCLING THE INSIDE OF THE CONTAINER.

LEGEND

EXISTING TREE CANOPY



SEE SHEET L4.05 FOR LANDSCAPE NOTES & LEGEND


ARE/

B002187.001

PLANT SCHEDULE <u>TREES</u>

____ STEEL EDGING


TREES	QTY	COMMON NAME	BOTANICAL NAME	SIZE	CONT.	HEIGHT	SPREAD
	13	CATHEDRAL LIVE OAK	QUERCUS VIRGINIANA `CATHEDRAL`	4"	65 GAL	12`-14`	5`-7`
£ • 3	9	CEDAR ELM	ULMUS CRASSIFOLIA	4"	65 GAL	12`-14`	5`-7`
yuru •	15	CHINESE PISTACHE	PISTACIA CHINENSIS	4"	65 GAL	12`-14`	5`-7`
and a few many	35	DRAKE ELM	ULMUS PARVIFOLIA 'DRAKE'	4"	65 GAL	12`-14`	5`-7`
* {* • * }	19	SHUMARD RED OAK	QUERCUS SHUMARDII	4"	65 GAL	12`-14`	5`-7`
SHRUBS	QTY	COMMON NAME	BOTANICAL NAME	CONT.	<u>HEIGHT</u>	SPREAD	SPACING
\odot	162	ABELIA	ABELIA X GRANDIFLORA 'EDWARD GOUCHER'	5 GAL	24"	20"	36" OC.
3 · · · · · · · · · · · · · · · · · · ·	167	DWARF BURFORD HOLLY	ILEX CORNUTA 'BURFORDII NANA'	5 GAL	24"	3,	36" OC
\odot	59	DWARF INDIAN HAWTHORN	RHAPHIOLEPIS INDICA NANA	3 GAL	12" - 18"		36" OC.
6 - 5 - 5 - 5 - 5 - 5 - 5 - 5 - 5 - 5 -	13	FOSTER'S HOLLY	ILEX X ATTENUATA `FOSTERI`	5 GAL	36"-48"	36"-48"	4` OC.
\odot	176	GULF COAST MUHLY	MUHLENBERGIA CAPILLARIS 'GULF COAST'	3 GAL	12"-14"	12"-14"	36" OC.
₹•¢	96	RED YUCCA	HESPERALOE PARVIFLORA	1 GAL			36" OC.
\odot	44	YELLOW YUCCA	HESPERALOE PARVIFLORA 'YELLOW'	1 GAL			36" OC.
SHRUB AREAS	QTY	COMMON NAME	BOTANICAL NAME	CONT.	<u>HEIGHT</u>	SPREAD	SPACING
	145	AUTUMN SAGE	SALVIA GREGGII	3 GAL	10`-12`	24"-36"	36"OC
	159	BIG BLUE LILYTURF	LIRIOPE MUSCARI 'BIG BLUE'	1GAL	8"-12"	8"-12"	18"OC
	3,811	MEXICAN FEATHERGRASS	NASSELLA TENUISSIMA 'PONY TAILS'	1GAL	9"	9"	18"OC
GROUND COVERS	COMMON NAME	BOTANICAL NAME	CONT.	<u>HEIGHT</u>	SPREAD	SPACING	
	ARIZONA COBBLE	DECORATIVE STONE COBBLE	NA	NA	NA	4"-6" STONES	
	BERMUDA GRASS	CYNODON DACTYLON	HYDROMULCH	NA	NA	NA	
	BERMUDA GRASS	CYNODON DACTYLON	SOLID SOD	NA	NA	NA	
	MULCH	MULCH	NA	NA	NA	3" THICK LAYER	




FILENAME: LANDSCAPE PIAN.dwg PLOTTED BY: Schwarz, Jacob PLOTTED ON: Friday, July 29, 2016


- 2. ALL PLANTS MUST BE CONTAINER GROWN OR BALLED AND BURLAPPED AS INDICATED IN THE PLANT LIST.
- 3. ALL TREES MUST BE STRAIGHT TRUNKED, FULL HEADED AND MEET ALL REQUIREMENTS SPECIFIED.
- 4. ALL PLANTS ARE SUBJECT TO THE APPROVAL OF THE OWNER'S REPRESENTATIVE BEFORE, DURING AND AFTER INSTALLATION.
- 5. ALL TREES MUST BE GUYED OR STAKED AS SHOWN IN THE DETAILS.
- 6. ALL PLANTING AREAS MUST BE COMPLETELY MULCHED AS SPECIFIED.
- 7. LOCATIONS OF EXISTING BURIED UTILITY LINES SHOWN ON THE PLANS ARE BASED UPON BEST AVAILABLE INFORMATION AND ARE TO BE CONSIDERED APPROXIMATE.
- PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES AND SHALL AVOID DAMAGE TO ALL NULLITIES DURING THE COURSE OF THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY AND ALL DAMAGE TO THE NULLITIES, STRUCTURES, SITE APPURTENANCES, ETC., WHICH OCCURS AS A RESULT OF THE LANDSCAPE CONSTRUCTION.
- 9. ALL PLANT MATERIAL QUANTITIES SHOWN ARE APPROXIMATE. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETE COVERAGE OF ALL PLANTING BEDS AT SPACING SHOWN.
- 10. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL QUANTITIES SHOWN ON THESE PLANS BEFORE PRICING THE WORK.
- 11. THE CONTRACTOR IS RESPONSIBLE FOR FULLY MAINTAINING ALL PLANTING, INCLUDING BUT NOT LIMITED TO: WATERING, MOWING, EDGING, SPRAYING, MULCHING, WEEDING, FERTILIZING, ETC. OF THE PLANTING AREAS AND LAWN UNTIL THE WORK IS ACCEPTED IN TOTAL BY THE OWNER.
- 12. THE CONTRACTOR SHALL COMPLETELY GUARANTEE ALL PLANT MATERIAL FOR A PERIOD OF TWO (2) YEARS BEGINNING ON THE DATE OF TOTAL ACCEPTANCE. THE CONTRACTOR SHALL PROMPTLY MAKE ALL REPLACEMENTS BEFORE OR AT THE END OF THE GUARANTEE PERIOD.
- 13. THE CONTRACTOR SHALL STAKE THE PROPOSED LOCATION OF ALL TREES AND PLANTING BEDS AND RECEIVE APPROVAL OF THE OWNER PRIOR TO INSTALLATION.
- 14. AFTER BEING DUG AT HE NURSERY SOURCE, ALL TREES IN LEAF SHALL BE ACCLIMATED FOR TWO WEEKS UNDER A MIST SYSTEM PRIOR TO INSTALLATION.
- 15. ANY PLANT MATERIAL WHICH DIES, TURNS BROWN, OR DEFOLIATES PRIOR TO TOTAL ACCEPTANCE OF THE WORK SHALL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED WITH MATERIAL OF THE SAME SPECIES, QUAINTLY, AND SIZE. THE REPLACEMENT MATERIAL SHALL MEET ALL PLANT LIST SPECIFICATIONS.
- 16. STANDARDS SET FORTH IN THE "AMERICAN STANDARD FOR NURSERY STOCK" REPRESENT GUIDELINE SPECIFICATIONS ONLY AND SHALL CONSTITUTE MINIMUM QUALITY REQUIREMENTS FOR PLANT MATERIAL.
- 17. SAFE, CLEARLY MARKED PEDESTRIAN AND VEHICULAR ACCESS TO ALL ADJACENT PROPERTIES MUST BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROCESS.
- 18. DURING THE GROWING SEASON ALL ANNUALS SHALL REMAIN IN HEALTHY, VITAL CONDITION THROUGHOUT THE CONSTRUCTION PERIOD.
- 19. THE CONTRACTOR I S CAUTIONED THAT LOCAL CITY STANDARDS MAY DIFFER FROM THOSE SHOWN HEREIN. CONSTRUCTION IS TO BE PERFORMED IN ACCORDANCE WITH LOCAL, CITY, STATE OR FEDERAL SPECIFICATIONS AND DETAILS SHOULD BE MORE STRINGENT THAN THOSE REPRESENTED HEREIN.
- 20. ALL SHRUB, GROUND COVER AND SEASONAL COLOR AND ANNUAL PLANTING BEDS ARE TO BE COMPLETELY COVERED WITH MULCH TO A MINIMUM DEPTH OF THREE INCHES.
- 22. IF LANDSCAPE CONTRACTOR DEMONSTRATES THAT ALL KNOWN RESOURCES HAVE BEEN EXHAUSTED FOR SPECIFIED PLANT MATERIAL AND AVAILABILITY OR QUALITY DOES NOT MEET OR EXCEED CRITERIA, CONTACT OWNER'S REPRESENTATIVE FOR ALTERNATIVE PLANT MATERIAL POSSIBILITIES.
- 23. PLANT MATERIALS
- "ACID GRO READY-TO-PLANT" BY SOIL BUILDING SYSTEMS, INC.
- (214)239-4777 OR APPROVED EQUAL. -MYCORRHIZAL SUPPLEMENT
- "DIEHARD-TRANSPLANT," BY HORTICULTURAL ALLIANCE, INC.
- (800)628-6377, WWW.HORTICULTURALALLIANCE.COM. APPLY TO ALL PLANTINGS DURING THE PLANTING OPERATION AT THE RATES SPECIFIED BY THE MANUFACTURER. THE CONTRACTOR SHALL CALCULATE THE REQUIRED AMOUNT OF "DIEHARD TRANSPLANT," FOR THE PROJECT USING THE MANUFACTURER'S SPREADSHEET AND SUBMIT THE SPREADSHEET WITH THE PROJECT SUBMITTALS. THE CONTRACTOR SHALL SUBMIT RECEIPTS OF THE ACTUAL PURCHASE OF THE "DIEHARD TRANSPLANT," MATERIAL AT TIME OF PROJECT PURCHASE.
- "FINE CUT HARDWOOD MULCH" BY SOIL BUILDING SYSTEMS, INC. (214)239-4777
- OR APPROVED EQUAL

GNAME: LANDSCAPE PLAN.dwg TTED BY: Schwarz, Jacob TTED ON: Friday, July 29, 2016



SHRUB PLANTING DETAIL AND SPACING DIAGRAM





GRASS AND PERENNIAL SPACING AND DETAIL

GRASS SODDING/SEEDING NOTES:

- 1. ALL SOD SHALL BE COMMON BERMUDA. CYNODON DACTYLON.
- 2. ALL UNSURFACED AREAS ARE TO RECEIVE FOUR INCHES OF TOPSOIL, SOD/SEED, MULCH, AND WATERED UNTIL HEALTHY STAND OF GRASS IS
- 3. PROVIDE TEMPORARY IRRIGATION AS NEEDED UNTIL A HEALTHY STAND OF GRASS IS ESTABLISHED OR UNTIL PERMANENT IRRIGATION IS FUNCTIONAL.

IRRIGATION NOTES:


- 1. ALL PLANTED AREAS SHALL BE WATERED WITH AN UNDERGROUND IRRIGATION SYSTEM. THE IRRIGATION SYSTEM SHALL BE AUTOMATICALLY CONTROLLED WITH A FULLY PROGRAMMABLE ET BASED CONTROLLER WITH RAIN AND FREEZE SENSORS.
- 2. THE IRRIGATION SYSTEM AND INSTALLATION SHALL MEET ALL OF THE APPROPRIATE REQUIREMENTS OF THE LOCAL MUNICIPALITY.

30 BG-NS #4 RE-BAR

- 13" DIAMETER SINGLE ROOTBALL ANCHOR RING TO ACCOMMODATE 22" ROOTBALL
- 6" U BRACKET (3) SEPARATE 36" NAIL STAKES WITH ANGLED TIP AT BOTTOM FOR EASY INSTALL

<u>45 BG-NS</u> #4 RE-BAR

- 15" & 18" DIAMETER DOUBLE ROOTBALL ANCHOR RING TO ACCOMMODATE 27" ROOTBALL
- 6" U BRACKET (3) SEPARATE 36" NAIL STAKES WITH ANGLED TIP AT BOTTOM FOR EASY INSTALL



65 BG-NS

#4 RE-BAR ROOTBALL ANCHOR RINGS


18" & 21" DIAMETER DOUBLE ROOTBALL ANCHOR RING TO ACCOMMODATE 30" ROOTBALL 6" U BRACKET

(3) SEPARATE 36" NAIL STAKES WITH ANGLED TIP AT BOTTOM FOR EASY INSTALL

100 BG-NS

#4 RE-BAR 21" & 24" DIAMETER DOUBLE ROOTBALL ANCHOR RING TO ACCOMMODATE 36" ROOTBALL

6" U BRACKET (3) SEPARATE 36" NAIL STAKES WITH ANGLED TIP AT BOTTOM FOR EASY INSTALL






B002187.001 DRAWN BY: DESIGNED BY: CHECKED BY: 07-29-2016

NORTH CENTR/ McKINNEY,

CARMAX

L4.06



NORTH CENTRAL EXPRESSW McKINNEY, TEXAS 6809 # CARMAX

PRELIMINARY FOR REVIEW ONLY These documents are for Design Review and not intended for Construction, Bidding or Permit Purposes. They were prepared by, or under the supervision of: Larry P. O'Flinn L.A.#696

JOB NO.	B002187.001
DRAWN BY:	JMM
DESIGNED BY:	TD
CHECKED BY:	LPO
DATE:	07-29-2016
SHEET.	