

PLAN	ITIN	NG SCHEDULE				
CANOP	Y ANI	D ORNAMENTAL TREES				
QTY.	UNIT	COMMON NAME	BOTANICAL NAME	SIZE	SPACING	REMARKS
8	ΕA	SHUMARD RED OAK	QUERCUS SHUMARDII	4" CAL., B¢B	PER PLAN	SINGLE, STRAIGHT LEADER,
5	ΕA	SOUTHERN LIVE OAK	QUERCUS VIRGINIANA	4" CAL., B¢B	PER PLAN	SINGLE, STRAIGHT LEADER,
5	ΕA	CEDAR ELM	ULMUS CRASSIFOLIA	4" CAL., B ₿	PER PLAN	SINGLE, STRAIGHT LEADER,
GROUN	DCO	VER & TURF GRASS				
QTY.	UNIT	COMMON NAME	BOTANICAL NAME	CONTAINER	SPACING	REMARKS
QTY. 4,787	UNIT EA	COMMON NAME ASIAN JASMINE	BOTANICAL NAME TRACHELOSPERMUM ASIATICUM	CONTAINER #1 GAL.	SPACING	REMARKS FULL, MATCHING
_,					12" O.C.	FULL, MATCHING
4,787	EA SF	ASIAN JASMINE	TRACHELOSPERMUM ASIATICUM	# GAL.	12" O.C.	FULL, MATCHING
4,787	EA SF ALS	ASIAN JASMINE	TRACHELOSPERMUM ASIATICUM	# GAL.	12" O.C.	


D JOINTS, 100% WEED AND DISEASE FREE

ED TO PLATE. APPLY TOUCH-UP PAINT.

PLANTING GENERAL NOTES

- I. ALL PLANTS SHALL BE SET OUT FOR APPROVAL BY THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.
- 2. FINE GRADING SHALL BE PERFORMED IN ALL AREAS TO BE LANDSCAPED. FINE GRADING SHALL INCLUDE THE REMOVAL OF DEBRIS, ROCKS, ETC. FROM THE SITE AND ENSURE POSITIVE DRAINAGE IN ALL AREAS.
- 3. THE CONTRACTOR SHALL LOCATE ALL UTILITIES AND EASEMENTS IN THE FIELD PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO UTILITIES DURING THE COURSE OF CONSTRUCTION.
- 4. WRITTEN DIMENSIONS SHALL GOVERN OVER SCALED DIMENSIONS.
- 5. IT IS PREFERABLE THAT NO TREE BE STAKED. HOWEVER, CONDITIONS AND PLANT MATERIAL SIZE MAY NECESSITATE STAKING. THE OWNER'S REP SHALL DETERMINE IF SUPPORT IS NEEDED AND SHALL DIRECT THE CONTRACTOR ACCORDINGLY.
- 6. THE CONTRACTOR SHALL REFER TO THE SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS ASSOCIATED WITH THE LANDSCAPE AND ACCESSORIES.
- 7. ALL PLANT MATERIALS SHALL MEET ANSI Z60.1 STANDARDS FOR CALIPER, HEIGHT AND ROOT BALL SIZE. ANY MATERIALS THAT DO NOT MEET OR EXCEED SUCH STANDARDS SHALL BE REJECTED AND REPLACED AT THE CONTRACTOR'S EXPENSE.
- 8. BALLED AND BURLAPPED TREES SHALL HAVE THE TOP HALF OF THE WIRE BASKET REMOVED. THE BURLAP SHALL BE REMOVED TO THE GREATEST EXTENT POSSIBLE, USING A KNIFE TO CUT AND REMOVE THE BOTTOM HALF UNDER THE WIRE BASKET THAT REMAINS.
- 9. QUANTITIES ARE SHOWN FOR CONVENIENCE ONLY. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL QUANTITIES
- 10. THE CONTRACTOR SHALL VERIFY WATER RESTRICTIONS WITHIN THE CITY OF MCKINNEY AT TIME OF PLANTING. SHOULD WATER RESTRICTIONS NOT ALLOW HYDRO-MULCH, HYDRO-SEEDING, OR SPRIGGING (STAGE 3 AND STAGE 4 WATER RESTRICTIONS), AN APPROVED ALTERNATIVE FOR GRASSING SHALL BE INSTALLED.

PLANT LEGEND



Have a minimum of one tree planted in the parking area for every 10 parking spaces within parking Y Y lots with more than 20 spaces. Landscaping, except required grass and low ground cover, shall not be located closer than three feet Y Y from the edge of any parking space.



12/30/2016