

December 17, 2018

Attn: Patricia Jackson, Facilities Construction Manager

Re: Extension of City WAN fiber to Trinity Falls Fire Station 10

This proposal covers the extension of the City WAN fiber to the new Trinity Falls Fire Station 10.

An exhibit is attached showing the extent of the WAN Extension. The new fiber extension will extend from the existing County fiber at Myers Park to the new Fire Station 10 and the Weston Rd Water Tower. The scope of work for the new facility is shown below:

New Trinity Falls Fire Station 10

The scope of work includes the installation of a 48 count singlemode cable extending from Myers Park to both the Weston Rd Water Tower and Fire Station 10. The scope of work includes installation of approximately 3.75 miles of new aerial fiber and 1 mile of underground duct installation. Fiber terminations will include installation of two new fiber adapter panels with SC connectors.

Total Project Cost	319 099 34
Contigency (City Approved)\$	29,009.03
Permitting Costs for GCEC poles\$	5,000.00
The total construction cost of this project including splicing will\$	285,090.31

Thank you for the opportunity to provide this proposal.

