McKinney Fire Station No. Guaranteed Maximum Price Proposal October 9, 2020





FIRE STATION

THRE

TWO

ONE

CROSSLAND CONSTRUCTION COMPANY, INC. 861 N. Coleman, Suite 100 Prosper, Texas 75078 tel 972.347.5659 fax 972.347.5684

October 9, 2020

Ms. Patricia L. Jackson, PE, RAS City of McKinney, Facilities Construction Manager 222 N. Tennessee St. McKinney, Texas 75069

RE: Guaranteed Maximum Price Proposal McKinney Fire Station No. 11

Dear Ms. Jackson:

Crossland Construction Company, Inc. ("CROSSLAND") is pleased to submit our Guaranteed Maximum Price ("GMP") Proposal for the McKinney Fire Station No. 11 ("Project"). This proposal is based on the AIA A133 Standard Form of Agreement Between Owner and Contractor and AIA A201 General Conditions of the Contract for Construction dated May 15, 2020 executed by the City of McKinney. ("Owner") and CROSSLAND and the design documents issued Conduit Architecture + Design and their consultants ("Architect") as outlined in the enclosed Document Log.

We appreciate being part of your project team and helping make your project successful. If you have any questions regarding our proposal or need additional information, please do not hesitate to call.

Best regards,

Rocky Hussman Division Manager rhussman@crossland.com

AIA[°] Document A133[°] – 2009 Exhibit A

Guaranteed Maximum Price Amendment

for the following PROJECT:

(Name and address or location)

McKinney Fire Station No. 11 6260 Rundell Way McKinney, TX 75069

THE OWNER:

(Name, legal status and address)

City of McKinney 222 N. Tennessee St McKinney, TX 75069

THE CONSTRUCTION MANAGER:

(Name, legal status and address)

Crossland Construction Company, Inc. 861 N. Coleman, Suite 100 Prosper, TX 75078

ARTICLE A.1

§ A.1.1 Guaranteed Maximum Price

Pursuant to Section 2.2.6 of the Agreement, the Owner and Construction Manager hereby amend the Agreement to establish a Guaranteed Maximum Price. As agreed by the Owner and Construction Manager, the Guaranteed Maximum Price is an amount that the Contract Sum shall not exceed. The Contract Sum consists of the Construction Manager's Fee plus the Cost of the Work, as that term is defined in Article 6 of this Agreement.

§ A.1.1 The Contract Sum is guaranteed by the Construction Manager not to exceed Eight Million One Hundred Eighty-One Thousand Four Hundred Fifty-Nine Dollars (\$ 8,181,459.00), subject to additions and deductions by Change Order as provided in the Contract Documents.

§ A.1.1.2 Itemized Statement of the Guaranteed Maximum Price. Provided below is an itemized statement of the Guaranteed Maximum Price organized by trade categories, allowances, contingencies, alternates, the Construction Manager's Fee, and other items that comprise the Guaranteed Maximum Price. (Provide below or reference an attachment.)

See Guaranteed Maximum Price Proposal dated October 9, 2020

§ A.1.1.3 The Guaranteed Maximum Price is based on the following alternates, if any, which are described in the Contract Documents and are hereby accepted by the Owner: (State the numbers or other identification of accepted alternates. If the Contract Documents permit the Owner to accept other alternates subsequent to the execution of this Amendment, attach a schedule of such other alternates showing the amount for each and the date when the amount expires.)

N/A

Init.

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Advillions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

AIA Document A201[™]-2007, General Conditions of the Contract for Construction, is adopted in this document by reference. Do not use with other general conditions unless this document is modified.

1

§ A.1.1.4 Allowances included in the Guaranteed Maximum Price, if any: (Identify allowance and state exclusions, if any, from the allowance price.)

Item	Price (\$0.00)
Exposed Aggregate in Apparatus Bay	\$18,000.00
Final Electrical System Design	\$7,500.00
Temporary Casing of Drilled Piers	\$50,000.00
Infrastructure Rough-in for the FARS	\$25,000.00

§ A.1.1.5 Assumptions, if any, on which the Guaranteed Maximum Price is based:

See Guaranteed Maximum Price Proposal dated October 9, 2020

§ A.1.1.6 The Guaranteed Maximum Price is based upon the following Supplementary and other Conditions of the Contract:

Document	Title	Date	Pages
•		ed upon the following Specifi exhibit attached to this Agree	
Refer to Document Log inclu	aded in the Guarante	eed Maximum Price Proposal	dated October 9, 2020
Section	Title	Date	Pages
•		ed upon the following Drawin ibit attached to this Agreemen	÷
Refer to Document Log inclu-	ided in the Guarante	ed Maximum Price Proposal	dated October 9, 2020
Number		Title	Date
(List any other documents or Refer to Document Log inch ARTICLE A.2	information here, o	ed upon the following other d or refer to an exhibit attached eed Maximum Price Proposal pletion established by this Am	to this Agreement.) dated October 9, 2020
OWNER (Signature)		CONSTRUCTI	ON MANAGER (Signature)

Rocky Hussman, Division Manager (Printed name and title)

(Printed name and title)

2

Init.



Table of Contents

1

Section One – Proposal Summary

- Executive Summary
- Cost Summary

Section Two – Basis of Proposal

- General Qualifications
- Package Specific Qualifications
- Allowances
- Unit Prices
- Staff Hourly Rates

Section Three - Appendices

- Document Log
- Logistics Plan
- Project Schedule



3



Section One – Proposal Summary

Executive Summary

This Guaranteed Maximum Price Proposal ("GMP") is based upon the documents prepared by Conduit Architecture + Design which are itemized in the Document Log of this proposal. Further project scope definition has been developed by **CROSSLAND**, and various qualifications that are included in this proposal.

From this data, which is summarized in the "Basis of GMP" section of this proposal, and our current understanding of the schedule and logistics involved with the project, we hereby propose a Guaranteed Maximum Price of <u>Eight Million One Hundred Eighty-One</u> <u>Thousand Four Hundred Fifty-Nine Dollars (\$8,181,459.00)</u> to complete the McKinney Fire Station No. 11 project.

We have developed and enclosed a Project Schedule, which indicates the agreed upon schedule objectives for the project.

- City Council Approval of GMP
- Issue Building Permit
- Notice to Proceed ("NTP") for Construction
- Substantial Completion

October 20, 2020 October 30, 2020 October 30, 2020 November 17, 2021

CROSSLAND recommends that the attached documents be carefully reviewed; questions and comments be referred back to us for resolution; and the overall project be approved for further progress.

Guaranteed Maximum Price ProposalProject:McKinney Fire Station No. 11

Date:

October 9, 2020



Bid Package	Description	Subcontractor/ Supplier	TOTAL	GBSF 15,950 \$/SF
01A	General Requirements	CROSSLAND	\$ 123,017	\$ 7.71
31A	Earthwork		\$ 317,180	\$ 19.89
31A 31B	Termite Treatment	Select		
		Pest Force		
32A	Landscaping & Irrigation	Superscapes	\$ 157,671	
32B	Fencing	Titan	\$ 12,227	\$ 0.77
32C	Unit Pavers	AIM	\$ 8,800	\$ 0.55
32D	Pavement Markings	Mel's	\$ 11,210	\$ 0.70
33A	Site Utilities	CalHar	\$ 271,869	\$ 17.05
03A	Concrete	Redden	\$ 947,833	\$ 59.43
04A	Masonry	GG&S	\$ 698,700	\$ 43.81
05A	Structural & Miscellaneous Steel	Tippen	\$ 545,449	\$ 34.20
06A	Woods and Plastics	Allan	\$ 177,097	\$ 11.10
07A	Roofing	Greystone	\$ 229,880	\$ 14.41
07B	Waterproofing	SCS	\$ 106,700	\$ 6.69
07C	Metal Wall Panels	Greystone	\$ 105,120	\$ 6.59
07D	Fireproofing	TBD	\$ 30,000	\$ 1.88
08A	Doors & Hardware	Commercial Hardware	\$ 163,986	\$ 10.28
08B	Glass & Glazing	Country Glass	\$ 179,041	\$ 11.23
08C	Overhead Doors	OHD of Dallas	\$ 138,699	\$ 8.70
09A	Drywall & Acoustical	Trinity	\$ 451,528	\$ 28.31
09B	Flooring	PDL/Hot Shot	\$ 130,685	\$ 8.19
09C	Painting	Taylor Made	\$ 80,904	\$ 5.07
10A	Miscellaneous Specialties	M4	\$ 85,762	\$ 5.38
10/T	Signage	Sign International	\$ 27,921	\$ 1.75
10D	Wood Lockers	Hollman	\$ 27,569	\$ 1.73
10C 10D	Gear Grid	Gear Grid	· · · · ·	\$ 0.91
				Q 0.91
10E	Cylinder Rack/Hose Rack	Safeware	\$ 4,396	Q 0.20
11A	Residential Appliances	Zetley	\$ 24,659	\$ 1.55
11D	Air Charge Station	Hoyt	\$ 60,657	\$ 3.80
11E	Laundry Equipment	Commercial Equipment	\$ 20,599	\$ 1.29
12A	Entrance Mats	TBD	\$ 3,720	\$ 0.23
12B	Window Treatments	Eastcreek	\$ 3,357	\$ 0.21
13A	Special Construction	N/A	\$-	\$-
14A	Conveying Equipment	N/A	\$-	\$ -
21A	Fire Sprinkler	Excel	\$ 47,058	\$ 2.95
22A	Plumbing	Prime	\$ 457,725	\$ 28.70
23A	HVAC	Bill Joplin	\$ 385,741	\$ 24.18
23B	Vehicle Exhaust System	Clean Air Solutions	\$ 64,069	\$ 4.02
26A	Electrical	Intex	\$ 795,797	\$ 49.89
27A	Communications	Superior	\$ 48,868	\$ 3.06
27B	Audio Visual	Superior	\$ 69,902	\$ 4.38
27B 27C	Security Systems	Allied Universal	\$ 166,945	\$ 10.47
270 28A	Fire Alarm	Johnson Controls	\$ 28,395	-
20A				\$ 1.78
		SUBTOTAL DIRECT COST	\$ 7,226,321	\$ 453.06
	Construction Contingency	CROSSLAND	\$ 150,000	\$ 9.40
	Owner's Contingency	City of McKinney	\$ 150,000	\$ 9.40
	Building Permit	City of McKinney	By Owner	\$ -
	General Liability Insurance	CROSSLAND	\$ 24,544	\$ 1.54
	Builder's Risk Insurance	CROSSLAND	\$ 8,181	\$ 0.5
	Payment & Performance Bond	OROSSLAND	\$ 73,633	\$ 4.62
	General Conditions	CROSSLAND	\$ 236,975	\$ 14.80
	Preconstruction Phase Fee	CROSSLAND	\$ 5,000	\$ 0.3
			2,500	-10
	Construction Phase Fee	CROSSLAND	\$ 306,805	\$ 19.24



2 Section Two – Basis of Proposal

Introduction

This section of Guaranteed Maximum Price (GMP) Proposal describes clarifications, qualifications, assumptions, and exclusions from which our proposal is based.

For those items that are identified as **excluded**, no cost or time has been accounted for in the GMP Proposal to address the issue. For those items that are **clarified**, **qualified** or based on an **assumption**, the GMP proposal reflects only the cost and time of the element as assumed or clarified.

Any modifications to the following clarifications, qualifications, assumptions, and exclusions will result in a change to the GMP and the Project Schedule.

Cost Basis of GMP

CROSSLAND's Guaranteed Maximum Price (GMP) Proposal is based upon the following:

- 1. Drawings and Specifications per the attached Document Log
- 2. **CROSSLAND's** estimate
- 3. The Agreement between Owner and Contractor
- 4. These Clarifications, Qualifications, Assumptions, and Exclusions
- 5. **CROSSLAND's** Construction Schedule
- 6. Site Logistics Plan

Changes or revisions to the foregoing information could result in a modification to the GMP price and Project Schedule. Documents, communications and information not included in the foregoing list, including for instance, any Third-Party agreements are not accounted for in the GMP Proposal. As such, the Owner must carefully review all the criteria used to develop this GMP Proposal and request any revisions to the same, so that a modified GMP Proposal can be prepared.

Start of Work

Due to continuing inflationary pressures on the cost of good and services, if Owner does not accept this proposal on or before November 1, 2020, **CROSSLAND** reserves the right to adjust the GMP based on market conditions in effect at the time of final acceptance.

The GMP Proposal and Project Schedule is based on a Notice to Proceed ("NTP") for Construction, with all conditions precedent met, to be issued on October 30, 2020 ("Notice to Proceed Date") and that Substantial Completion will be achieved by or before November 17, 2021 as may be modified in accordance with the Agreement. Current subcontractor bids and accepted proposals reflect an anticipated start date in accordance with the time periods set forth in this proposal.

The Notice to Proceed ("NTP") date included in the schedule is based on having the



following conditions precedent fully executed/completed/evidenced and returned to CROSSLAND:

- 1. Fully executed Agreement and GMP Amendment
- 2. Approval of CROSSLAND's General Liability Insurance and Builder's Risk Insurance
- 3. Issuance of the Building Permit
- 4. Issuance of the "For Construction" Documents (in part or in whole so as not to delay the Work)

Should any or all of these items fail to be provided by the date of NTP shown in the Project Schedule, **CROSSLAND** will be due a subsequent time extension for the amount of time between the NTP date shown in the Project Schedule and the date when all items are completed.

Bonds and Insurance

- 1. Payment and Performance Bonds for CROSSLAND are included in the GMP.
- 2. GMP includes General Liability Insurance and Builder's Risk Insurance.

Permits and Fees

- 1. The cost for the Building Permit has been **excluded** from the GMP.
- 2. Impact and/or Tap Fees for water and sanitary sewer are **excluded**.
- 3. GMP excludes any and all Fees for Franchise Utilities (ie. Atmos, Oncor, AT&T, etc...)
- 4. GMP excludes TXDOT permits

Contingency

The GMP estimate includes the following contingencies:

- A. Construction Contingency
- B. Owner's Contingency
- C. Design Contingency is **excluded**
- A. The Construction Contingency shall be available for the exclusive use of CROSSLAND with approval by the Owner to provide funds to address items such as, by way of example: (1) estimating, coordination and/or procurement errors and/or omissions, (2) overtime and other costs of accelerating and/or recovering for time lost related to the Work (which are not otherwise the basis of entitlement to a Change Order), (3) interfacing omissions between and from the various categories of work, (4) additional costs incurred due to the withdrawal or disqualification of a subcontractor bid forming the basis for the GMP prior to execution of a written subcontract, (5) cost increases due to unanticipated local labor and material market conditions, selective overtime, or the like. Construction Contingency is NOT intended to provide for costs associated with Owner initiated changes, design changes, unknown, unforeseen, concealed or unrevealed physical conditions, force majeure events or other items for which CROSSLAND may be entitled to a Change Order in accordance with the Agreement. The Construction Contingency shall be increased by any savings as a result of the buyout process.



B. Owner Contingency has been included in the GMP Proposal to address issues such as enlarging the size of the project, level of service of the components, modifications or acceleration of project schedule or additional quality to project components not currently reflected in the Drawings or Specifications.

Coordination with other Contractors

This GMP is based on the understanding that the Owner's Architect, its contractors and all other parties performing work at the Project site NOT under direct contract with **CROSSLAND** will:

- 1. Comply with **CROSSLAND's** site specific safety program and maintain an injury free environment.
- 2. Perform work according to **CROSSLAND's** project schedule, and achieve system and area completion dates according to that schedule
- 3. Perform work so as to not impact **CROSSLAND's** ability to perform its work in accordance with its project logistics plan
- 4. Perform work so as to not impact **CROSSLAND's** ability to maintain or accelerate its project schedule
- 5. Provide detailed schedule, logistics, and technical information, when and as requested by **CROSSLAND** so as to enable **CROSSLAND** to maintain or accelerate elements of its schedule so as to maintain its overall schedule and achieve necessary milestone completion dates in accordance with the Contract Documents.

CROSSLAND agrees to coordinate its work with all separate contractors hired by the Owner.



General Qualifications

- 1. The only price guaranteed within this GMP Proposal is that of the proposed GMP Amount. There are no individual line item guarantees within the GMO. Individual line item savings within the GMP shall be addressed in accordance with the Agreement.
- 2. The GMP Proposal is based on the AIA A133-2009 Standard Form of Agreement between Owner and Construction Manager and the AIA A201 General Conditions of the Contract for Construction dated May 15, 2020.
- 3. The GMO Proposal is based on CROSSLAND being granted unfettered, legal access to the Project Site at all times. The GMP Proposal does not anticipate any stoppage or interruption of Work as a result of existing Owner operations or other site restrictions or interferences except as restricted by the City of McKinney.
- 4. The only spare parts, maintenance training and manufacturer service support included in the GMP Proposal is that which is reasonably specified in the Project Manual.
- All Franchise Utilities will be provided by Owner and in accordance with the CROSSLAND Project Schedule and Site Logistics Plan. The GMP Proposal excludes any costs for tap fees, impact fees or other costs required by utility company(s) to connect services.
- 6. All utility service will be provided without interruption, that any utility work performed by others will be coordinated so as to not interfere with the Work of **CROSSLAND** and that **CROSSLAND** will not have to re-perform or correct any Work disturbed by Owner's utility contractor.
- 7. **CROSSLAND** shall reasonably assist the Owner and Architect in obtaining the Building Permit. The GMP **excludes** any costs for the Building Permit and Plan Review Fees.
- 8. Public Agency reviews or approvals and associated fees are **excluded**.
- No costs have been included for obtaining any Temporary Certificate(s) of Occupancy permits or any type of intermediary inspections prior to the final Certificate of Occupancy.
- 10. All Work associated with hazardous materials including, but not limited to asbestos, lead, petrochemicals, arsenic (beyond what has been explicitly identified on the Contract Documents), or any other hazardous material abatement, handling and/or remediation is **excluded**.
- 11. Property taxes, business operations taxes and other taxes related to the Property and the operation of the project are **excluded**.
- 12. GMP **excludes** sales tax on material and labor which become part of the real property.
- 13. 3rd party and Agency testing and inspection services are **excluded** from the GMP and



such services shall be performed by the Owner with the energy inspection which is included in the GMP.

- 14. GMP **excludes** any off-site improvements other than those indicated on the Contract Documents.
- 15. All extended warranties included in the specifications, including the material/labor warranties, shall be assigned to Owner following **CROSSLAND's** one-year repair/replacement obligation under the Contract. Thereafter, **CROSSLAMD** shall only be responsible for reasonably assisting the Owner in enforcing those warranties provided by the manufacturers, suppliers and subcontractors.



Package Specific Clarifications, Qualifications, Assumptions & Exclusions

The following definition represents the basis of our estimate and serves as the GMP Proposal for the project. The estimated costs were developed based upon the project documents listed in the appendices and schedule data described elsewhere in this report, and the assumptions, clarifications and design criteria presented under this section. The following clarifications, qualifications, assumptions and exclusions represent the basis of our GMP proposal.

01A – General Requirements

- 1. Division 01 Specifications have not been received at this time. Nothing contained in the Division 01 Specifications shall supersede the terms and conditions as set forth in the Agreement between Owner and Contractor.
- 2. In establishing the price for the GMP, **CROSSLAND** understands that reasonable substitutions may be made to specified materials except where otherwise noted. Substitution Requests shall be submitted and approved in accordance with the Contract Documents.

31A – Earthwork

- 1. GMP included 6" of lime at 8% as required by the City of McKinney Standard for all pavement subgrade prep.
- 2. GMP includes 5' of moisture conditioned soil below 5' of a select fill cap extending 5' beyond building lines with a 2' clay cap along the perimeter of the building.

31B – Termite Treatment

1. Bayer Corporation Premise Pro with a 5-year warranty has been included.

32A – Landscaping & Irrigation

1. Plants labelled as DYH but not shown on the Plant list is bid as 5-gallon Dwarf Yaupon Holly.

32B – Fencing

1. GMP includes 6' tall Ameristar Echelon Plus, black finish, three rail ornamental fence with 1 - double swing gate with heavy duty fork latch and drop rod.

32C – Unit Pavers

1. GMP includes Surebond SB1300 joint stabilizing sealer at all unit pavers.

32D – Pavement Markings

1. No comments.

33A – Site Utilities

- 1. GMP excludes public inspection fees.
- 2. GMP excludes relocation or modification of the existing Franchise Utilities
- 3. Installing of site gas distribution piping and gas meters are **excluded** from the GMP and shall be installed by others.



03A – Cast-In-Place Concrete

- 1. Site Paving thicknesses shall be per Sheet C3-01 and the Geotechnical Report as follows:
 - a. Public Sidewalks 4" 4000 PSI
 - b. Private Sidewalks 4" 4000 PSI
 - c. Light Duty Paving, head end parking 5" 4000 PSI
 - d. Fire Lane 6" 4000 PSI with bakers broom finish
 - e. Heavy Duty, dumpster enclosure 7" 4000 PSI
 - f. Tinley Lane Paving 8" 5000 PSI
 - g. Sidewalks 4" 4000 PSI
- 2. GMP includes the concrete foundations for the knee walls and monument signs per Detail 4/A1.02 and specifically **excludes** drilled piers (nothing shown on structural).
- 3. GMP includes the concrete foundation for the mailbox per Detail 9/A1.01 (nothing shown on structural).
- 4. GMP includes a \$50,000 Allowance for temporary casing of drilled piers in the event excessive ground water is encountered as determined by Fugro. In the event casing is required, actual quantities shall be confirmed by Fugro and costs will then be determined by applying the Unit Prices identified at the end of this section and funded from this Allowance.
- 5. GMP includes the dumpster foundation per the details and notes on the structural details as 10" Slab on Grade with #5 @ 10" O.C. with lime stabilized subgrade.

04A – Masonry

- 1. E-ST1 is included as chopped stone and not honed stone.
- 2. E-ST2 is included as honed stone
- 3. Mock-up for the Storm Shelter shall be built in-place due to the limited quantity required.
- 4. Interior CMU block shall have rounded/bullnose outside corners.

05A – Structural & Miscellaneous Steel

- 1. GMP includes 16 bollards 12 in the apparatus bay and 4 at the dumpster enclosure.
- 2. Interior and exterior training tower railing is to be galvanized all other mezzanine railing is to be shop primer and field painted.
- 3. Includes four (4) pipe bollards at the FDC

06A – Woods and Plastics

 Upper and lower base Millwork to be clear stained grade including base, chair railing, cased openings at Dorm Rooms, stainless steel Kitchen countertop with integral single bowl sink, vanity steel countertop supports, stainless steel table at Decon Room.

07A – Roofing

- 1. Roofing system includes R-25 ISO, ½" coverboard and 60-mil TPO membrane mechanically-fastened
- 2. 20-YEAR NDL warranty included.
- 3. Roofing includes gutters, downspouts and downspout boots
- 4. GMP includes all roof to wall flashings to complete the roof system. GMP includes the roof hatch, roof walk pads and shop drawings, submittal samples and NDL roof certifications per plans and specs.

07B – Waterproofing

- 1. GMP includes fluid-applied air barrier
- 2. GMP includes water-repellent on the stone veneer. Water-repellent on brick veneer is **excluded**.

07C – Metal Panels

- 1. GMP includes the exterior 24-gauge metal panels in metallic champagne color as PAC Clad as specified, with trim. We will submit the metal shop drawings and color samples for approval.
- 2. GMP includes the metal walls around generator enclosure at 12'H and HVAC Screen around RTU's at 10'H.
- 3. GMP includes metal panel ceiling/soffit at Outdoor Kitchen in lieu of the originally designed wood ceiling/soffit.
- 4. We have included the 10ga Galvanized coping apron at Training Tower as this metal must be rolled and the gauge is not identified in the Contract Documents.

07D – Fireproofing

- 1. GMP includes intumescent paint on the columns and beams beneath the Mezzanine.
- 2. GMP **excludes** spray-applied fire proofing

07E – EIFS

1. GMP excludes EIFS

08A – Doors & Hardware

- 1. GMP includes the interior stain grade wood doors, frames and hardware and locks.
- 2. City of McKinney to provide the correct key way for coordination.
- 3. GMP includes the Hollow Metal doors, frames and locks, and panic hardware. All Bronze hardware is included for panic hardware, closures at all exterior/interior doors.
- 4. GMP includes the Storm Shelter door as specified. Bathroom doors are included and stain grade with louvers and dark bronze hardware.
- 5. GMP includes level II ballistic doors and hardware in locations indicated on the Documents.



08B – Glass & Glazing

- 1. Storefronts and sidelights included as champagne Aluminum.
- 2. All vanity mirrors, Fitness mirror and stained art glass with #11 signage is included.
- 3. Bronze type color finish on the Hardware is included.
- 4. GMP includes bulletproof and ballistics level 2 in locations shown on the drawings.
- 5. Includes frosted/opaque glass at showers with occupancy latches and pulls

08C – Overhead Doors

- 1. Six (6) Bay doors with vision glass panel powder coated red and motor operater are included.
- 2. Six (6) rolling steel grilles with motor supports/brackets are included.

09A – Drywall & Acoustical

- GMP includes the drywall partitions, ACT #1 & #2 Armstrong ceilings 2x2 with 15/16" grid, Metal look Armstrong ceilings, CFMF engineered drawings and design calculation. Mezzanine framing, rigid Insulation board with 1.5" thickness at exterior metal framed wall assemblies, Rigid Insulation to be Foamular 250 by Owens Corning or equal, in wall fire treated blocking for specialties, tv locations, Gypsum board sheathing at exterior face of exterior walls. Gypsum glass mat sheathing with thickness of 5/8".
- 2. GMP includes the FRP at Janitorial closet location.
- 3. GMP includes Armorcore Level 2 ballistic fiberglass panels installed at Lobby partition walls as shown.

09B – Flooring

- 1. GMP includes the flooring material and labor install for all LVT, VCT, Carpet tiles, Ceramic wall tile and ceramic floor tile with Accent color at Bathroom walls, rubber fitness flooring and rubber base is included.
- 2. Waterproofing at showers is included.
- 3. Bullnose ceramic tile or Schluters are included at bathroom walls is included.
- 4. Grout is included- color TBD and shall be selected from manufacturer's full range of colors.
- 5. Marble niche at showers is included.
- 6. Waxing of floor is **excluded**.
- 7. Resinous flooring is included at adjacent rooms of the Apparatus Bay. Resinous flooring color TBD and shall be selected from manufacturer's standard colors.
- 8. Includes an \$18,000 Allowance for exposed aggregate finish in the Apparatus Bay. Final determination on the specification/process is TBD due to the fiber mesh reinforcing in the mix design.

09C - Painting

- 1. Painting exposed structure and all MEP conduits/fire sprinkler piping at Apparatus Bay with Dryfall paint is included.
- 2. Painting of CMU walls, prime and paint Mezzanine railings is included. Bollards prime and paint, interior partitions paint to 6" above ceilings is included with (2) coats.
- 3. Painting of all Hollow Metal doors and frames is included.

09D – Plaster

1. No comments

10A – Specialties

1. GMP includes the specialties per accessory schedule on sheet A0.09 and the Specifications.

10B – Signage

- 1. Monument Signs with dimensional lettering and signage is included
- 2. Building Signs and City of McKinney signage is included. All 18"H, 9"H, 12" 10" Aerial building dimensional lettering signage as dark bronze in color, bronze plaques and corner stone plaques are included, ¼" steel panel hero signage is included- verbiage from city will be required at later date for hero signage.
- 3. Storm Shelter plaque is included.

10C - Wood Lockers

1. Hollman stain grade lockers are included with lockable hardware, shelving and matching edge banding.

10D – Gear Lockers

1. GMP includes Gear Grid lockers red in color and to be mobile units and surface mounted.

10E – Cylinder Rack/Hose Rack/Hose Reels

Cylinder Rack storage and Hose Rack mobile units & Surface Mounted Hose Reels
(2) are included. All hose reels, rack storage are red in color.

11A – Equipment

- 1. Residential Appliances with gas connections is included.
- 2. Sauna
- 3. Pot Rack
- 4. The specified Air Charge Station has been discontinued, therefore, GMP includes an or equal product by Hush.
- 5. Laundry Equipment Washer and Dryer Speed Queen Manufacturer is included.
- 6. Laundry and drying rack is included.



- 7. Stainless Steel Shelving
- 8. Nexel shelving
- 9. AED defibrillator equipment/cabinet at Lobby is included.
- 10. GMP specifically **excludes** the furnish and installation of the FARS system.

12A – Furnishings

- 1. Entrance Mats
- 2. Window Treatments
- 3. Dorm Curtains and wood curtain rods

13A – Special Construction

1. NOT USED

14A – Conveying Equipment

1. NOT USED

21A - Fire Protection

- 1. State assumed flow at street for basis of design
- 2. GMP excludes a Fire Pump, Jockey Pump and associated controllers.
- 3. GMP includes a Dry-pipe system at the Outdoor Kitchen

22A – Plumbing

- 1. GMP includes cast-in-place terrazzo shower pans
- 2. Trench Drains in the Apparatus Bay shall be manufactured by DeadLevel DX
- 3. GMP includes cast iron downspout boots
- 4. Includes natural gas piping downstream from the meter

23A - HVAC

- 1. GMP includes HVAC equipment and Controls by Trane
- 2. Kitchen Hood package shall be by Captiveaire
- 3. GMP includes Magnegrip Vehicle Exhaust System as installed by Clear Air Solutions
- 4. GMP includes Re-Verber-Ray radiant heaters in the Apparatus Bay

26A – Electrical

- 1. GMP includes two (2) 4" empty conduits for primary electrical service. Primary conductors are **excluded**.
- 2. GMP includes five (5) empty 4" conduits for communication service.
- 3. GMP includes 175 kW diesel generator and 600A transfer switch
- 4. GMP includes lighting control system
- 5. Lightning Protection and grounding are included
- 6. Includes a \$7,500 Allowance per Specification Section 26 05 73 1.2C to accommodate potential adjustments require to final electrical design requirements based on the outcome of the coordination study.



7. Includes a \$25,000 Allowance infrastructure rough-in for the FARS system as this information is not currently included on the documents.

27A – Communications

1. GMP includes the required Superior Fiber install.

27B – Audio Visual

- 1. GMP includes the required Superior Fiber install with A/V equipment and Projection screen.
- 2. GMP includes CAT6A cabling.

27C – Security

1. GMP includes the required Securadyne dba Allied Universal install.

28A – Fire Alarm

1. GMP includes the Johnson Controls install.



Allowances

The estimate in this GMP Proposal was developed based upon, among other things, inprogress Construction Documents. Therefore, **CROSSLAND's** estimating team could not establish quantity survey-based pricing for certain portions of the work. In order to provide this GMP proposal per Owner's requested delivery date, a number of cost Allowances had to be established. These Allowances are intended to provide for all direct and indirect construction costs associated with each of these items.

Upon final determination of the actual cost, the GMP Allowance shall be revised by replacing the Allowance amount with the actual cost of the item or scope. In the event the actual cost is less than the specified Allowance, the cost savings shall be reallocated to the Construction Contingency. In the event the actual cost exceeds that of the Allowance, **CROSSLAND** shall be entitled to additional compensation via a Change Order to increase the GMP or such overrun shall be funded using the Owner's Contingency.

Lump Sum Allowances

1.	Exposed Aggregate in Apparatus Bay	\$´	18,000
2.	Final Electrical System Design per 26 05 73 1.2C	\$	7,500
3.	Temporary Casing of Drilled Piers	\$ 5	50,000
4.	Infrastructure rough-in for the FARS system	\$2	25,000

Unit Prices

The following Unit Prices represent the direct cost only:

Unit Price No. 1 Soil Excavation						
Unit Price No. 2 Structural Fill and Cor	nit Price No. 2 Structural Fill and Compaction					
Unit Price No. 3 Drilled Pier 18"	ADD	\$35.00/LF		DEDUCT	\$5.00/LF	
Unit Price No. 3 Drilled Pier 24"	ADD	\$65.00/LF		DEDUCT	\$7.00/LF	
Unit Price No. 4 Reinforcing Steel and	Dowels	3	ADD	\$1.00/LB		
Unit Price No. 5 Cast-in-Place Concret	e		ADD	\$300.00/0	Y	
Unit Price No. 6 Temporary Casing 18	" Drilled	l Pier	ADD	\$45.00/LF		
Unit Price No. 6 Temporary Casing 24	" Drilled	l Pier	ADD	\$50.00/LF		
Unit Price No. 7 Shade Trees			ADD	\$900/EA		
Unit Price No. 8 Grass			ADD	\$5.00/SY		
Unit Price No. 9 Data Outlets			ADD	\$150.00/E	A	
Unit Price No. 10 Power Outlets			ADD	\$250.00/E	A	



Project Staff Hourly Rates

Project Manager	\$65.00/hour
Superintendent	\$75.00/hour
Project Engineer	\$55.00/hour
Field Engineer	\$45.00/hour
General Superintendent	\$100.00/hour







Appendix – Document Log

The subsequent pages contain the Document Log.

Do Not Write Over									
DOCU	MENT LOG								
Project:	McKinney Fire Station #11		SET	SET	50	۲ ₂		lical	
Owner:	CITY OF MCKINNEY		95% 5	%	.29.	UN H	£	CHN	
Contractor:	Crossland Construction		6 0	SEI	M #1 09	#1 H NNS NNS	₩ſ	GEOTE	
Architect:	CONDUIT ARCHITECTURE + DESIGN		UN UN	UNG NIT		UM ∉ ATIC /ISIC	NDN:		
DATE:	10.09.30		GMP DRAWINGS	GMP DRAWINGS 100% SET PERMIT SET	ADDENDUM #1 09.29.20	ADDENDUM #1 REV#2 SPECIFICATIONS ONLY REVISIONS	ADDENDUM #2	ADDENDUM GEOTECHNICAL REPORT	
Sheet No.	Sheet Title	Date Issued	08.10.2020	09.04.20	09.29.20	09.30.20			
REPORT									
GEO-TECH	GEO-TECH REPORT		12.17.19					10.07.20	
SPECS	SPECIFICATIONS		08.10.20	09.04.20	09.29.20	09.30.20	10.02.20		
GENERAL									
G0.00	COVER SHEET		08.10.20	09.04.20					
G0.01	DRAWING INDEX & LOCATION INFO		08.10.20	09.04.20	09.29.20				
CIVIL C0-00	CIVIL COVER		08.07.20	08.07.20					
C0-00 C1-1	DEMOLITION PLAN		08.07.20	08.07.20					
C2-1	DIMENSION CONTROL PLAN		08.07.20	08.07.20					
C3-1	PAVING PLAN		08.07.20	08.07.20					
C4-1	GRADING PLAN		08.07.20	08.07.20					
C4-2	GRADING PLAN		08.07.20	08.07.20					
C5-1	DRAINAGE AREA MAP		08.07.20	08.07.20					
C5-2	DRAINAGE CALCULATIONS		08.07.20	08.07.20					
C5-3	STORM SEWER PLAN		08.07.20	08.07.20					
C5-4	STORM SEWER PROFILES		08.07.20	08.07.20					
C5-5	STORM SEWER PROFILES		08.07.20	08.07.20					
C6-1	WATER & SEWER PLAN		08.07.20	08.07.20					
C7-1	EROSION CONTROL PLAN		08.07.20	08.07.20					
C8-1	POST CONSTRUCTION STORM WATER QUALITY PLAN		08.07.20	08.07.20					
C9-1	TRAFFIC CONTROL PLAN		08.07.20	08.07.20					
C10-1	CONSTRUCTION DETAILS		08.07.20	08.07.20					
C10-2	CITY STANDARD DETAILS		08.07.20	08.07.20					
C10-3	CITY STANDARD DETAILS		08.07.20	08.07.20					
C10-4	CITY STANDARD DETAILS		08.07.20	08.07.20					
C10-5	CITY STANDARD DETAILS		08.07.20	08.07.20		1			
C10-6	CITY STANDARD DETAILS		08.07.20	08.07.20		1			
C10-7	CITY STANDARD DETAILS		08.07.20	08.07.20		1	1		
C10-8	CITY STANDARD DETAILS		08.07.20	08.07.20		1			
CPDP	PRELIMINARY UTILITY PLAN		00101120			1			
CPUP	PRELIMINARY DRAINAGE PLAN					1			
CSP	SITE PLAN		08.07.20	08.07.20		1	1		
СТОРО	TOPOGRAPHIC SURVEY		08.07.20	08.07.20		1	1		
GN-1	GENERAL CONSTRUCTION NOTES		08.07.20	10.01.19					

DOCUMENT LOG									
Project:	McKinney Fire Station #11		SET	jer 1	0			ICAL	
Owner:	CITY OF MCKINNEY		S %	S %C	29.2		N	NH NH	
Contractor:	Crossland Construction		S 95	\$ 100 SET	1 09.	NS NS	IM #2	₹ LEC	
Architect:	CONDUIT ARCHITECTURE + DESIGN		Ŭ	NGS AIT 8	₩ ₩		NDN	РОЙ С НОЧ	
DATE:	10.09.30		GMP DRAWINGS 95%	GMP DRAWINGS 100% SET PERMIT SET	ADDENDUM #1 09.29.20	ADDENDUM #1 REV#2 SPECIFICATIONS ONLY REVISIONS	ADDENDUM	ADDENDUM GEOTECHNICAL REPORT	
Sheet No.	Sheet Title	Date Issued	08.10.2020	09.04.20	09.29.20	09.30.20			
GN-2	GENERAL CONSTRUCTION NOTES		08.07.20	10.01.19					
LANDSCAPE									
L1.1	LANDSCAPE PLAN		06.11.20	06.11.20					
L1.2	LANDSCAPE NOTES AND DETAILS		06.11.20	06.11.20					
L1.4.1	IRRIGATION PLAN			06.11.20					
LI 4.2	IRRIGATION TREE PLAN			06.11.20					
LI 4.3	IRRIGATION PLAN			09.09.20					
ARCHITECTURA									
A0.02	GRAPHIC SYMBOLS & ABBREVIATIONS		08.07.20	09.04.20					
A0.03	CODE ANALYSIS		08.07.20	09.04.20					
A0.04	LIFE SAFETY PLAN		08.07.20	09.04.20					
A0.05	LIFE SAFETY PLAN		08.07.20	09.04.20					
A0.06	U.L. ASSEMBLY DESIGN SHEET		08.07.20	09.04.20					
A0.07	PARTITION TYPES		08.07.20	09.04.20					
A0.08	MOUNTING LOCATIONS		08.07.20	09.04.20					
A0.09	ACCESSORY SCHEDULE		08.07.20	09.04.20					
A0.10	TEXAS ACCESSIBILITY STANDARDS		08.07.20	09.04.20					
A0.11	TEXAS ACCESSIBILITY STANDARDS		08.07.20	09.04.20					
A0.12	TEXAS ACCESSIBILITY STANDARDS		08.07.20	09.04.20					
A0.13	TEXAS ACCESSIBILITY STANDARDS		08.07.20	09.04.20					
A0.14	TEXAS ACCESSIBILITY STANDARDS		08.07.20	09.04.20					
A0.15	TEXAS ACCESSIBILITY STANDARDS		08.07.20	09.04.20					
A1.00	SITE PLAN		08.07.20	09.04.20					
A1.01	SITE DETAILS		08.07.20	09.04.20					
A1.02	SITE DETAILS		08.07.20	09.04.20	09.29.20				
A2.00	FLOOR PLAN		08.07.20	09.04.20					
A2.01	FLOOR PLAN- MEZZANINE		08.07.20	09.04.20					
A2.02	DIMENSIONAL FLOOR PLAN		08.07.20	09.04.20		I			
A2.03	ENLARGED PLANS		08.07.20	09.04.20		1			
A2.04	ENLARGED PLANS		08.07.20	09.04.20	09.29.20				
A2.05	FINISH PLAN		08.07.20	09.04.20		1			
A2.06	EQUIPMENT PLAN		08.07.20	09.04.20	09.29.20				
A2.07	EQUIPMENT SCHEDULE		08.07.20	09.04.20	09.29.20				
A2.08	ENLARGED PLAN DETAILS		08.07.20	09.04.20					
A2.09	ENLARGED PLAN DETAILS		08.07.20	09.04.20					<u> </u>

DOCU	MENT LOG								
Project:	McKinney Fire Station #11		SET SET	L				CAL	
Owner:	CITY OF MCKINNEY		S %	S %C	29.2		N	N N N	
Contractor:	Crossland Construction		S 95	3ET	00	NS NS	₩ ₩	JEOTEC PORT	
Architect:	CONDUIT ARCHITECTURE + DESIGN		Ŭ	NGS NT (,# ₩				
Architect.			DRAWINGS 95%	A WII	Ind		ADDENDUM #2	MU O MU	
DATE:	10.09.30		GMP DR	GMP DRAWINGS 100% SET PERMIT SET	ADDENDUM #1 09.29.20	ADDENDUM #1 REV#2 SPECIFICATIONS ONLY REVISIONS	AC	ADDENDUM GEOTECHNICAL REPORT	
Sheet No.	Sheet Title	Date Issued	08.10.2020	09.04.20	09.29.20	09.30.20			
A2.10	TRAINING STAIR		08.07.20	09.04.20					
A2.11	STORM SHELTER		08.07.20	09.04.20					
A3.00	REFLECTED CEILING PLAN		08.07.20	09.04.20					
A3.01	REFLECTED CEILING PLAN- MEZZANINE		08.07.20	09.04.20					
A4.00	ROOF PLAN		08.07.20	09.04.20					
A5.00	EXTERIOR ELEVATIONS		08.07.20	09.04.20					
A5.01	EXTERIOR ELEVATIONS		08.07.20	09.04.20					
A5.02	MASONRY DETAILS		08.07.20	09.04.20					
A5.03	MASONRY DETAILS			09.04.20					
A6.00	BUILDING SECTIONS		08.07.20	09.04.20					
A6.01	BUILDING SECTIONS		08.07.20	09.04.20					
A6.02	BUILDING SECTIONS		08.07.20	09.04.20					
A6.03	WALL SECTIONS		08.07.20	09.04.20					
A6.04	WALL SECTIONS		08.07.20	09.04.20					
A6.05	WALL SECTIONS		08.07.20	09.04.20					
A6.06	WALL SECTIONS		08.07.20	09.04.20	09.29.20				
A6.07	WALL SECTIONS		08.07.20	09.04.20					
A6.08	SECTION DETAILS		08.07.20	09.04.20					
A6.09	SECTION DETAILS		08.07.20	09.04.20					
A6.10	SECTION DETAILS		08.07.20	09.04.20					
A6.11	MISCELLANEOUS DETAILS		08.07.20	09.04.20	09.29.20				
A7.00	INTERIOR ELEVATIONS		08.07.20	09.04.20					
A7.01	INTERIOR ELEVATIONS		08.07.20	09.04.20					
A7.02	INTERIOR ELEVATIONS		08.07.20	09.04.20					
A7.03	INTERIOR ELEVATIONS		08.07.20	09.04.20					
A7.04	INTERIOR ELEVATIONS		08.07.20	09.04.20					
A7.05	INTERIOR ELEVATIONS		08.07.20	09.04.20	<u> </u>	1			+
A7.06			08.07.20	09.04.20	09.29.20	1			+
A7.07	INTERIOR ELEVATIONS		08.07.20	09.04.20	00.20.20	1			+
A7.08	INTERIOR ELEVATIONS		08.07.20	09.04.20					
A7.09	MILLWORK DETAILS		00.07.20	09.04.20		+			+
A7.10	MILLWORK DETAILS			09.04.20					+
A7.10 A7.11	MILLWORK DETAILS		08.07.20	09.04.20					+
A7.12	MILLWORK DETAILS		08.07.20	09.04.20					+
A7.12 A7.13	MILLWORK DETAILS		08.07.20	03.04.20		+			
AL 10		Į	00.07.20	<u> </u>			<u> </u>	<u> </u>	

DOCU	MENT LOG								
Project:	McKinney Fire Station #11	SE T		SET	50	~~		ICAL	
Owner:	CITY OF MCKINNEY			% %	.29.	ONI #	S ²	NHO NHO	
Contractor:	Crossland Construction		. <u>6</u>	SET SET	1 09	#1 R NNS NNS	₩ M	GEOTE	
Architect:	CONDUIT ARCHITECTURE + DESIGN		U N	MIT G	# ≥	UM ∉ ATIC /ISIC	NDC		
DATE:	10.09.30		GMP DRAWINGS 95%	GMP DRAWINGS 100% PERMIT SET	ADDENDUM #1 09.29.20	ADDENDUM #1 REV#2 SPECIFICATIONS ONLY REVISIONS	ADDENDUM #2	ADDENDUM GEOTECHNICAL REPORT	
Sheet No.	Sheet Title	Date Issued	08.10.2020	09.04.20	09.29.20	09.30.20			
A7.14	MILLWORK DETAILS		08.07.20						
A8.00	DOOR TYPE & SCHEDULE		08.07.20	09.04.20					
A8.01	WINDOW SCHEDULE		08.07.20	09.04.20					
A8.02	DOOR & WINDOW DETAILS		08.07.20	09.04.20					
A8.03	DOOR & WINDOW DETAILS		08.07.20	09.04.20					
A8.04	DOOR & WINDOW DETAILS		08.07.20	09.04.20					
A8.05	DOOR & WINDOW DETAILS		08.07.20	09.04.20					
A8.06	CAST STONE DETAILS		08.07.20	09.04.20					
A8.07	CAST STONE DETAILS		08.07.20	09.04.20					
A8.08	FINISH SCHEDULE		08.07.20	09.04.20	09.29.20				
A8.09	FINISH SCHEDULE CONTINUED		08.07.20	09.04.20	09.29.20				
STRUCTURALS									
S1.01	STRUCTURAL NOTES		08.07.20	09.04.20	09.21.20				
S1.02	NOTES, ABBREVVIATIONS, & SYMBOLS		08.07.20	09.04.20					
S1.03	SPECIAL INSPECTIONS		08.07.20	09.04.20					
S1.04	SPECIAL INSPECTIONS		08.07.20	09.04.20					
S1.05	STORM SHELTER NOTES AND INSPECTIONS		08.07.20	09.04.20					
S2.01	FOUNDATION PLAN		08.07.20	09.04.20	09.21.20				
S2.02	MEZZANINE AND LOW ROOF FRAMING PLAN		08.07.20	09.04.20	09.21.20				
S2.03	HIGH ROOF FRAMING PLAN		08.07.20	09.04.20	09.21.20				
S2.04	TRAINING TOWER FRAMING PLANS		08.07.20	09.04.20					
S3.01	TYPICAL CONCRETE DETAILS		08.07.20	09.04.20					
S3.02	TYPICAL CONCRETE DETAILS		08.07.20	09.04.20					
S3.03	TYPICAL CONCRETE DETAILS		08.07.20	09.04.20	09.21.20				
S3.04	CONCRETE DETAILS		08.07.20	09.04.20	09.21.20				
S4.01	TYPICAL MASONRY DETAILS		08.07.20	09.04.20	09.21.20				
S4.02	TYPICAL MASONRY DETAILS		08.07.20	09.04.20	09.21.20				
S4.11	STORM SHELTER DETAILS		08.07.20	09.04.20					
S4.12	STORM SHELTER DETAILS		08.07.20	09.04.20					
S4.13	STORM SHELTER DETAILS		08.07.20	09.04.20					
S5.01	TYPICAL STEEL DETAILS		08.07.20	09.04.20	09.21.20				
S5.02	TYPICAL STEEL DETAILS		08.07.20	09.04.20					
S5.03	TYPICAL STEEL DETAILS		08.07.20	09.04.20					
S5.04	TYPICAL STEEL DETAILS		08.07.20	09.04.20					
S5.05	TYPICAL STEEL DETAILS		08.07.20	09.04.20	09.21.20				


DOCU	MENT LOG								
Project:	McKinney Fire Station #11	<u> </u>		SET		<u>ح ک</u>		ICAL	
Owner:	CITY OF MCKINNEY			%0.	.29.2	ONI EV#	ß	NHS	
Contractor:	Crossland Construction		0 76	S 10 SET	1 09	#1 R DNS	₩ ₩	ОТЕС	
Architect:	CONDUIT ARCHITECTURE + DESIGN		UN UN	UN NIL	.# ⊻	ATIC ISIC	ND(GEC	
DATE:	10.09.30		GMP DRAWINGS 95%	GMP DRAWINGS 100% PERMIT SET	ADDENDUM #1 09.29.20	ADDENDUM #1 REV#2 SPECIFICATIONS ONLY REVISIONS	ADDENDUM #2	ADDENDUM GEOTECHNICAL REPORT	
Sheet No.	Sheet Title	Date Issued	08.10.2020	09.04.20	09.29.20	09.30.20			
S5.06	STEEL DETAILS- LOW ROOF/MEZZ		08.07.20	09.04.20	09.21.20				
S5.07	STEEL DETAILS- LOW ROOF/MEZZ		08.07.20	09.04.20	09.21.20				
S5.08	STEEL DETAIL- HIGH ROOF		08.07.20	09.04.20	09.21.20				
S5.09	STEEL DETAILS -SCREEN WALL		08.07.20	09.04.20	09.21.20				
S5.10	APPARATUS BAY CMU WALL ELEVATIONS		08.07.20	09.04.20	09.21.20				
S5.51	BRACE ELEVATIONS		08.07.20	09.04.20	09.21.20				
S5.52	TYPICAL BRACE DETAILS		08.07.20	09.04.20	09.21.20				
S6.01	STORM SHELTER PLANS AND ELEVATIONS		08.07.20	09.04.20	09.21.20				
MECHANICAL MEP2.00	SITE PLAN-MEP		08.07.20	09.04.20			10.02.20		
MEP2.01	ROOF PLAN-MEP		08.07.20	09.04.20			10.02.20		
M0.00	HVAC LEGENDS AND ABBREVIATIONS		08.07.20	09.04.20					
M1.00	FLOOR PLAN- FIRST LEVEL - HVAC		08.07.20	09.04.20					
M2.00	FLOOR PLAN - FIRST LEVEL - HVAC		08.07.20	09.04.20					
M2.01	FLOOR PLAN - MEZZANINE - HVAC		08.07.20	09.04.20					
M4.00	DETAILS - HVAC		08.07.20	09.04.20					
M4.01	DETAILS - HVAC		08.07.20	09.04.20			10.02.20		
M5.00	SCHEDULES - HVAC		08.07.20	09.04.20			10.02.20		
PLUMBING									
P0.00	PLUMBING LEGENDS AND ABBREVIATIONS		08.07.20	09.04.20					
P2.00	UNDERFLOOR PLAN - FIRST LEVEL - PLUMBING		08.07.20	09.04.20					
P2.01	FLOOR PLAN-FIRST LEVEL - PLUMBING		08.07.20	09.04.20					
P2.02	FLOOR PLAN- MEZZANINE- PLUMBING		08.07.20	09.04.20					
P3.00	DETAILS - PLUMBING		08.07.20	09.04.20					
P3.01	DETAILS - PLUMBING		08.07.20	09.04.20					
P3.02	DETAILS & RISERS - PLUMBING		08.07.20	09.04.20					
P3.03	RISERS - PLUMBING		08.07.20	09.04.20					
	SCHEDULES - PLUMBING		08.07.20	09.04.20					
ELECTRICAL E0.00	ELECTRICAL LEGENDS AND ABBREVIATIONS		08.07.20	09.04.20					

DOCU	MENT LOG								
Project:	McKinney Fire Station #11		SET	SET	50	۲۲ 17		AICA	
Owner:	CITY OF MCKINNEY		5%	۲ ۲	9.29	N N N	#2	H H H	
Contractor:	Crossland Construction		6 8	S 1(#1 0č	H H H SNC	N N N N N N N N N N N N N N N N N N N	DTE RT	
Architect:	CONDUIT ARCHITECTURE + DESIGN		UN ON		₩ M			GEG	
DATE:	10.09.30		GMP DRAWINGS 95% SET	GMP DRAWINGS 100% PERMIT SET	ADDENDUM #1 09.29.20	ADDENDUM #1 REV#2 SPECIFICATIONS ONLY REVISIONS	ADDENDUM #2	ADDENDUM GEOTECHNICAL REPORT	
Sheet No.	Sheet Title	Date Issued	08.10.2020	09.04.20	09.29.20	09.30.20			
E0.01	PHOTOMETRIC LIGHTING SITE PLAN		08.07.20	09.04.20					
E2.00	FLOOR PLAN- FIRST LEVEL-POWER		08.07.20	09.04.20			10.02.20		
E2.01	FLOOR PLAN -MEZZANINE- POWER & FIRE ALARM		08.07.20	09.04.20					
E3.00	FLOOR PLAN- FIRST LEVEL- LIGHTING		08.07.20	09.04.20					
E3.01	FLOOR PLAN- MEZZANINE- LIGHTING		08.07.20	09.04.20					
E4.00	FLOOR PLAN-FIRST LEVEL -FIRE ALARM		08.07.20	09.04.20					
E5.00	ONE LINE DIAGRAM - ELECTRICAL		08.07.20	09.04.20					
E6.00	SCHEDULES- ELECTRICAL		08.07.20	09.04.20					
E6.01	SCHEDULES- ELECTRICAL		08.07.20	09.04.20					
E6.02	SCHEDULES- ELECTRICAL			09.04.20					
E6.03	DETAILS- ELECTRICAL			09.04.20					
TECHNOLOGY									
T0.00	TECHNOLOGY SYMBOLS, NOTES & INDEX OF DRAWINGS		08.10.20	09.04.20					
T0.01	AUDIOVISUAL SYMBOL & NOTES		08.10.20	09.04.20					
T1.00	SITE PLAN TECHNOLOGY		08.10.20	09.04.20					
T2.00	FLOOR PLAN IT AND SECURITY		08.10.20	09.04.20					
T2.01	FLOOR PLAN MEZZANINE TECHNOLOGY		08.10.20	09.04.20					
T2.10	FLOOR PLAN AUDIOVISUAL		08.10.20	09.04.20					
T3.00	REFLECTED CEILING PLAN AUDIOVISUAL		08.10.20	09.04.20					
T3.01	REFLECTED CEILING PLAN- MEZZANINE- AUDIOVISUAL		08.10.20	09.04.20					
T4.01	TELECOM EQUIPMENT ROOM DETAILS		08.10.20	09.04.20					
T4.02	TELECOM EQUIPMENT ROOM DETAILS		08.10.20	09.04.20					1
T5.01	AUDIOVISUAL GROUNDING SCHEMATIC		08.10.20	09.04.20					
T5.02	AUDIOVISUAL GENERAL RACK & ELECTRICAL CONFIGURATION DETAIL		08.10.20	09.04.20					
T5.03	SECTION AUDIOVISUAL		08.10.20	09.04.20					
T5.04	AUDIOVISUAL DETAILS		08.10.20	09.04.20		1	1		1
T5.05	AUDIOVISUAL DETAILS		08.10.20	09.04.20		1			1
T5.06	AUDIOVISUAL DETAILS		08.10.20	09.04.20					
T5.07	AUDIOVISUAL ROOM MATRIX		08.10.20				İ		

DOCUM	IENT LOG								
Project:	McKinney Fire Station #11		SET	SET	20	_{دا} ۲		IICAL	
Owner:	CITY OF MCKINNEY	95% (ло% 10%	09.29.20	NON S	#2	CH2		
Contractor:	Crossland Construction		NGS 9	S 1(S E	#1 00	UM #1 F ATIONS /ISIONS	WNQN	ENDUM GEOTECHN REPORT	
Architect:	CONDUIT ARCHITECTURE + DESIGN		ŬN		Σ				
DATE:	10.09.30		GMP DRAM	GMP DRAWINGS 100% PERMIT SET	ADDENDUM	ADDENDUM #1 REV#2 SPECIFICATIONS ONLY REVISIONS	ADDE	ADDENDUM RE	
Sheet No.	Sheet Title	Date Issued	08.10.2020	09.04.20	09.29.20	09.30.20			
T6.01	SECURITY DETAILS		08.10.20	09.04.20					
T6.02	SECURITY DETAILS		08.10.20	09.04.20					



Appendix – Site Logistics Plan





Appendix – Schedule

The subsequent pages contain the detailed project schedule.

					2020 2021 2022			
Line	Name	Duration	Start	Finish	Cotober November December January February March April May June July August September October November December January February February March Apr 128, 12, 126, 19, 123, 17, 121, 14, 118, 11, 115, 12, 126, 110, 124, 17, 121, 15, 19, 12, 116, 130, 113, 127, 11, 125, 18, 22, 16, 120, 13, 117, 131, 114, 128, 114, 128, 111,	ril May 25 9		
	MAJOR MILESTONES	296d	9/25/2020	11/23/2021	MAJOR MILESTONES			
2	Signed GMP Amendment	11d	9/25/2020	10/9/2020	Signed GMP Amendment			
3	NTP	1d	10/30/2020	10/30/2020	I TP			
4	Building Slab	1d	3/12/2021	3/12/2021	Building Slab			
5	Building Dry in	1d	8/20/2021	8/20/2021	Building Dry in			
6	Condition Space	1d	8/13/2021	8/13/2021	Condition Space			
7	Permanent Power	1d	8/13/2021	8/13/2021	Permanent Power			
8	со	1d	11/23/2021	11/23/2021				
9	Substantial Completion	1d	11/17/2021	11/17/2021	Substantial Completion			
10	Final Completion	1d	11/23/2021	11/23/2021	Final Completion			
	PRECONSTRUCTION	71d	9/25/2020	1/7/2021	PRECONSTRUCTION			
	PERMITTING & APPROVALS	25d	9/25/2020	10/30/2020	PERMITTING & APPROVALS			
13	CIVIL PERMIT SUBMITTED	1d	9/25/2020	9/25/2020				
14	CIVIL PERMIT APPROVED	25d	9/25/2020	10/29/2020	CIVIL PERMIT APPROVED			
15	BUILDING PERMIT SUBMITTED	7d	9/25/2020	10/5/2020	BUILDING PERMIT SUBMITTED			
16	BUILDING PERMIT REVIEW	15d	10/6/2020	10/26/2020	BUILDING PERMIT REVIEW			
17	BUILDING PERMIT APPROVED		10/30/2020	10/30/2020	BUILDING PERMIT APPROVED			
	BIDDING & AWARD	71d	9/25/2020	1/7/2021	BIDDING & AWARD			
19	LONG LEAD ITEMS BUILDING SUBS NEGOTIATION	5d	10/12/2020	10/16/2020	LONG LEAD ITEMS BUILDING SUBS NEGOTIATION			
20	CIVIL SUBS NEGOTIATION	5d	9/25/2020	10/1/2020	CIVIL SUBS NEGOTIATION			
21	CIVIL SUBS AWARD	5d	10/12/2020	10/16/2020	CIVIL SUBS AWARD			
22	FRANCHISE UTILITIES (POWER,GAS)	60d	10/12/2020	1/7/2021	FRANCHISE UTILITIES (POWER,GAS)			
23	GAS DESIGN FINALIZE	45d	10/12/2020	12/15/2020	GAS DESIGN FINALIZE			
24	LONG LEAD BUILDING ITEMS AWARDED	5d	10/19/2020	10/23/2020	LONG LEAD BUILDING ITEMS AWARDED			
	KEY CONTRACTS AWARDED	10d	10/19/2020	10/30/2020				
26	Earthwork	1d	10/19/2020	10/19/2020	Earthwork			
27	Pier Drilling	1d	10/19/2020	10/19/2020	Pier Drilling			
28	Utilities	1d	10/19/2020	10/19/2020				
29	Underground Plumbing	1d	10/19/2020	10/19/2020	Underground Plumbing			
30	Underground Electrical	1d	10/19/2020	10/19/2020	Underground Electrical			
31	Concrete	1d	10/19/2020	10/19/2020	Concrete			
32	Steel	1d	10/19/2020	10/19/2020	Steel			
33	Doors & Hardware	1d	10/30/2020	10/30/2020	Doors & Hardware			
34	Fire Sprinkler	1d	10/30/2020	10/30/2020	Fire Sprinkler			
GMP McKinney Fire Station Job #: Job Number Print Date: 9/25/2020 10:41:07 AM View: Bar Chart View Print Date: 9/25/2020 Index of:: 9/25/2020 Index of:: 9/25/2020 Index of:: 9/25/2020 Index of:: 9/25/2020								
CONS	STRUCTION COMPANY, INC.	_			Start Date: 9/25/2020 Page 1 of 4	Page 1 of 4		

Line	Name	Duration	Start	Finish	2020 1 2021 2021 2021 2022 2023 2033 2033 2033 2033 2033 20	ch April May
	SUBMITTALS/PROCUREMENT	15d	10/30/2020	11/19/2020		
	CONSTRUCTION	291d	9/25/2020	11/16/2021		
	EARTHWORK/UTILITIES	94d	11/6/2020	3/23/2021	Easthwork/utilities	
38	MOBILIZATION/ SET TRAILER/ EROSION CONTROL	1d	11/6/2020	11/6/2020	MOBILIZATION/ SET TRAILER/ EROSION CONTROL	
39	CLEAR & GRUB	2d	11/6/2020	11/9/2020	CLEAR & GRUB	
40	GROUND BREAKING	1d	11/12/2020	11/12/2020	GROUND BREAKING	
41	TEMP TRAILER POWER	1d	11/13/2020	11/13/2020	TEMP TRAILER POWER	1
42	MASS GRADE SITE	8d	11/16/2020	11/25/2020	MASS GRADE SITE	1
43	MOISTURE CONDITION AND SELECT AT BUILDING PAD	10d	11/30/2020	12/11/2020	MOISTURE CONDITION AND SELECT AT BUILDING PAD	
44	SITE UTILITIES "STORM"	10d	11/30/2020	12/11/2020	SITE UTILITIES "STORM"	
45	SITE UTILITIES "SANITARY"	4d	12/14/2020	12/17/2020	SITE UTILITIES "SANITARY"	
46	SITE UTILITIES "WATER" FIRE LINE INSTALL	8d	12/21/2020	12/31/2020	SITE UTILITIES "WATER" FIRE LINE INSTALL	
47	GAS INSTALLATION	10d	1/8/2021	1/21/2021	GAS INSTALLATION	
48	PAVEMENT SLEEVES	2d	1/22/2021	1/25/2021	PAVEMENT SLEEVES	
49	LIME STABILIZATION	10d	1/26/2021	2/8/2021	LIME STABILIZATION	
50	FRANCHISE ELECTRICAL	5d	1/8/2021	1/14/2021	FRANCHISE ELECTRICAL	
51	TRANSFORMER SET	3d	3/19/2021	3/23/2021	TRANSFORMER SET	
	FOUNDATION/STRUCTURE	181d	12/14/2020	8/30/2021	FOUNDATION/STRUCTURE	
53	DRILL/PREP POUR PIERS	15d	12/14/2020	1/5/2021	DRILL/PREP POUR PIERS	
54	FORM/PREP POUR GRADE BEAMS, PITS, PIER CAPS	20d	1/15/2021	2/11/2021	FORM/PREP POUR GRADE BEAMS, PITS, PIER CAPS	
55	MEP UNDERSLAB ROUGH	10d	1/15/2021	1/28/2021	MEP UNDERSLAB ROUGH	
56	FORM PREP POUR SLAB	10d	2/15/2021	2/26/2021	FORM PREP POUR SLAB	
57	CURE TIME FOR SLAB	7d	3/1/2021	3/9/2021	CURE TIME FOR SLAB	
58	STRIPE TO GO VERTICAL	1d	3/10/2021	3/10/2021	STRIPE TO GO VERTICAL	
59	INSTALL STRUCTURAL STEEL FRAMING	25d	3/9/2021	4/12/2021	INSTALL STRUCTURAL STEEL FRAMING	
60	EXTERIOR COLD METAL FRAMING	20d	3/10/2021	4/6/2021	EXTERIOR COLD METAL FRAMING	
61	EXTERIOR SHEATHING	15d	4/13/2021	5/3/2021	EXTERIOR SHEATHING	
62	CMU AT APPARATUS BAY	25d	3/19/2021	4/22/2021	CMU AT APPARATUS BAY	
63	INSTALL JOIST AND DECKING	15d	5/4/2021	5/24/2021	INSTALL JOIST AND DECKING	
64	WATERPROOFING	12d	5/4/2021	5/19/2021	WATERPROOFING	
65	MASONRY BRICK & STONE	40d	5/20/2021	7/16/2021	MASONRY BRICK & STONE	
66	INSTALL ROOFING	20d	7/12/2021	8/6/2021	INSTALL ROOFING	1
67	INSTALL METAL SIDING	15d	7/2/2021	7/23/2021	INSTALL METAL SIDING	
68	INSTALL STOREFRONT & GLASS	10d	7/26/2021	8/6/2021	INSTALL STOREFRONT & GLASS	
	ROSSLAND	tion Job #: Job Number Print Date: 9/25/2020 10:41:07 AM Update as of:: 9/25/2020 10:41:07 AM Filter: None Filter: None Page 2 of 4				
					raye 2 01 4	

Line	Name	Duration	Start	Finish	2020 October November December	I January February March	2 AprilMayJune	1021 July August September	October November December J; 11, 125, 18, 122, 16, 120, 13,	2022 Ianuary February March	April May
69	BUILDING DRY IN		8/30/2021	8/30/2021	128, 112, 126, 19, 123, 17, 121,	<u> 4 18, 1 15, 1 15, </u>	129, 112, 126, 110, 124, 17, 121,	15, 19, 12, 16, 130, 13, 127, ♦ BUILDING DR		<u>17, 131, 14, 128, 14, 128</u>	11, 25, 9
	EXTERIORS	166d	2/5/2021	9/29/2021	1		8	1	EXTERIORS	1	
71	PREP POUR FOUNDATIONS FOR GENERATOR & MONUMENT SIGN	5d	5/13/2021	5/19/2021	-	1	PREP POUR FOUNE	DATIONS FOR GENERATOR & MONUMENT SIGN	1	1	
72	FORM PREP POUR FIRELANE	20d	2/5/2021	3/4/2021		FORM PR	EP POUR FIRELANE				
73	Form Prep Pour Parking	15d	3/1/2021	3/19/2021		FO	DRM PREP POUR PARKING				
74	SITE MASONRY FOR DUMPSTER ENCLOSURE, MONUMENT SIGN	5d	5/20/2021	5/26/2021			SITE MASONRY	FOR DUMPSTER ENCLOSURE, MONUMENT SIG	5N		
75	PREP POUR SIDEWALKS	5d	8/23/2021	8/27/2021				PREP POUR SID	EWALKS		
76	FINE GRADE TOP SOIL	5d	8/30/2021	9/3/2021				FINE GRADE	TOP SOIL		
77	INSTALL IRRIGATION	5d	9/7/2021	9/13/2021			1	INSTALL	IRRIGATION		
78	INSTALL LANDSCAPING & SOD	10d	9/13/2021	9/24/2021				IN	STALL LANDSCAPING & SOD		
79	SET GEAR, PULL SECONDARY, MAKE HOT	50d	6/4/2021	8/13/2021		1		SET GEAR, PULL SECO	NDARY, MAKE HOT		
80	SET LIGHT POLES	3d	8/16/2021	8/18/2021				SET LIGHT POLES			
81	SET GENERATOR & START UP GENERATOR	7d	8/16/2021	8/24/2021	-			SET GENERATOR	& START UP GENERATOR		
82	INSTALL EXTERIOR BUILDING LIGHTING	3d	8/19/2021	8/23/2021	-			INSTALL EXTERIOR	R BUILDING LIGHTING	-	
83	INSTALL FLAG POLES/ & BIKE RACK	2d	9/27/2021	9/28/2021		1	1		NSTALL FLAG POLES/ & BIKE RACK		
84	STRIPING	1d	9/29/2021	9/29/2021				0	STRIPING		
	INTERIORS	291d	9/25/2020	11/16/2021			- -	· · · · · ·	INTERIORS		
86	INTERIOR FRAMING	15d	5/25/2021	6/15/2021			INTER	RIOR FRAMING			
87	MEP OVERHEAD ROUGH IN	20d	5/25/2021	6/22/2021			ME	EP OVERHEAD ROUGH IN			
88	FIRE SPRINKLER ROUGH IN	10d	6/23/2021	7/7/2021				FIRE SPRINKLER ROUGH IN			
89	INSTALL MEZZANINE FRAMING	8d	7/8/2021	7/19/2021	-	1	1	INSTALL MEZZANINE FRAMING			
90	INTERIOR MEP WALL ROUGH-IN	10d	8/24/2021	9/7/2021	-			INTERIOR	MEP WALL ROUGH-IN		
91	DRYWALL ONE SIDE	7d	8/24/2021	9/1/2021	-			DRYWALL ON	E SIDE		
92	INTERIOR MEP WALL ROUGH IN	12d	8/26/2021	9/13/2021			1	INTERIO	R MEP WALL ROUGH IN		
93	TWO SIDE DRYWALL	7d	8/30/2021	9/8/2021	-	-	1	TWO SIDE	DRYWALL		
94	TAPE/BED PAINT	15d	9/7/2021	9/27/2021			1	т.	APE/BED PAINT		
95	INSTALL MILLWORK	15d	9/8/2021	9/28/2021			1	I	NSTALL MILLWORK		
96	INSTALL ACCOUSTICAL CEILING GRID	8d	9/17/2021	9/28/2021				I	NSTALL ACCOUSTICAL CEILING GRID		
97	INSTALL ACCOUSTICAL CEILING TILES	5d	9/15/2021	9/21/2021				TRNI	TALL ACCOUSTICAL CEILING TILES		
98	MEP TRIM OUT WALLS & LIGHTING, FIRE SPRINKLER	15d	9/22/2021	10/12/2021					MEP TRIM OUT WALLS & LIGHTING, FIRE S	SPRINKLER	
99	INSTALL CERAMIC TILE & WALL TILE	18d	9/22/2021	10/15/2021	-		-		INSTALL CERAMIC TILE & WALL TILE		
100	INSTALL BATHROOM ACCESSORIES	5d	10/18/2021	10/22/2021			1		INSTALL BATHROOM ACCESSORIES		
101	INSTALL VCT/ CARPET FLOORING	5d	10/25/2021	10/29/2021	1	1	1	· · ·	INSTALL VCT/ CARPET FLOORING	; 	
102	MEP TRIM OUT CEILINGS	10d	11/1/2021	11/12/2021					MEP TRIM OUT CEILINGS	1	
					-		1	· · · ·			
	ROSSLAND #1	MP N 1 Sc	lcKinney hedule	Fire Stat	Start Date: 9/2	mber 5/2020	Print Date: 9/25/2020 10 Update as of:: 9/25/2020		View: Bar Chart V	View	
0043	THOUTION COMPANY, INC.				Finish Date: 12	2/1/2021			Page 3 of 4		

[1						
Line	Name	Duration	Start	Finish	2020 October November December 28, 12, 26, 9, 23, 7, 21,	January February March	2 April May June 129, 12, 126, 10, 124, 17, 121,	2021 July August September 1 5, 19, 12, 16, 30, 13, 127,	October November December 11, 25, 8, 22, 6, 20,	2022 January February March April Ma 3 , 17, 31, 14, 28, 14, 28, 11, 25, 9
103	HVAC START UP	3d	9/10/2021	9/14/2021				HVAC S		
104	SET PLUMBING FIXTURES	3d	10/12/2021	10/14/2021					SET PLUMBING FIXTURES	
105	INSTALL DOORS & HARDWARE	5d	10/14/2021	10/20/2021		1			INSTALL DOORS & HARDWARE	
106	INSTALL GEAR GRID LOCKERS	3d	9/28/2021	9/30/2021		1		۵	INSTALL GEAR GRID LOCKERS	
107	INSTALL TRUCK EXHAUST SYSTEM	5d	9/25/2020	10/1/2020	INSTALL TRUCK EXHAUST SYSTEM					
108	SEAL APPARATUS BAY	2d	10/21/2021	10/22/2021		1 1			SEAL APPARATUS BAY	
109	INSTALL RESIDENTIAL APPLIANCES	2d	11/15/2021	11/16/2021					INSTALL RESIDENTIA	L APPLIANCES
110	FINAL CLEAN	5d	11/10/2021	11/16/2021				I	FINAL CLEAN	
	OWNER PROVIDED EQUIPMENT	3d	9/9/2021	9/13/2021	i I	I		OWNER	PROVIDED EQUIPMENT	
112	INSTALL RADIO ALERT SYSTEM	3d	9/9/2021	9/13/2021				INSTALL	RADIO ALERT SYSTEM	
•	CLOSEOUT	300d	9/25/2020	12/1/2021		1		· · · · · · · · · · · · · · · · · · ·	CLOSEOUT	
	COMMISSIONING	292d	9/25/2020	11/17/2021		1		1	COMMISSIONING	
115	COMMISSIONING REPORT STARTUP	1d	9/25/2020	9/25/2020	COMMISSIONING REPORT STARTUP	1		 		
116	TEST & BALANCE	3d	11/12/2021	11/16/2021					TEST & BALANCE	
117	FINAL COMMISSIONG REPORT	1d	11/17/2021	11/17/2021					FINAL COMMISSION	REPORT
	PUNCHLIST		11/16/2021	12/1/2021	1	1 1		I I I I I I I I I I I I I I I I I I I		
110	SUBSTANTIAL COMPLETION	14				 	1	· · · · · · · · · · · · · · · · · · ·		
119		10	11/17/2021	11/17/2021	:			· · · · · · · · · · · · · · · · · · ·	SUBSTANTIAL COMP	
120	OWNER DESIGN & TEAM PUNCHLIST	2d	11/17/2021	11/18/2021	:			<u> </u>		
121 122		10d	11/16/2021	12/1/2021	: 					COMPLETION OF PUNCHLIST
122	FINAL CO OWNER TRAININGS & VIDEOS FOR CLOSEOUTS	1d	11/18/2021 11/17/2021	11/18/2021 11/23/2021	-			· · · · · · · · · · · · · · · · · · ·		S & VIDEOS FOR CLOSEOUTS
125		JU 47.1			-					
	FINAL INSPECTIONS	47d		11/29/2021		1			FINAL INSPECT	
125	FINAL PLAT RECORDED FOR COUNTY	40d	9/22/2021	11/16/2021		1			FINAL PLAT RECORDS	
126	COMMUNITY DEVELOPMENT ENGINEERING FIELD SIGNOFF	5d	11/17/2021	11/23/2021		1			COMMUNITY DEVE	
127	(UTILITIES,PAVING)	5d	11/19/2021	11/29/2021				<u> </u>		FIELD SIGNOFF (UTILITIES,PAVING)
128	ENGINEERING ADMIN (BONDS, ASBUILTS)	5d	11/17/2021	11/23/2021				· · · · · ·		MIN (BONDS, ASBUILTS)
129	PUBLIC WORKS UTILITIES FIRE DEPT (FIRE ALARM, FIRE SPRINKLER, LIFE	5d	11/17/2021	11/23/2021	1	1	1	<u> </u>	PUBLIC WORKS U	
130	SAFETY) BUILDING INSPECTIONS (BLDG SIGNS,	50	10/29/2021	11/2/2021	1	1	1	<u> </u>	FIRE DEPT (FIRE ALARM, FI	
131	DUMPSTER, SCREEN, EXT LIGHTING ETC)	5d	11/19/2021	11/29/2021	-	1	1	 	BUILDING INSP	ECTIONS (BLDG SIGNS, DUMPSTER, SCREEN, EXT LIGHTING ET
						I				
						I 				
						-		 		
CI			/IcKinney	Fire Stat	tion Job #: Job Nu	mber	Print Date: 9/25/2020 10 Update as of:: 9/25/2020		View: Bar Char	t View
		1 50	hedule		Start Data: 0/0/	5/2020			Filter: None	
CONS	TRUCTION COMPANY, INC.				Start Date: 9/2 Finish Date: 12	/1/2021			Page 4 of 4	